

अधीक्षण अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, मुजफ्फरपुर

पत्रांक :- 01 गै.स्य परना अनु०

/मुज० /दिनांक :- 23/1/21

प्रेषक,

अधीक्षण अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, मुजफ्फरपुर।

सेवा में,

मुख्य अभियंता- 04
ग्रामीण कार्य विभाग,
बिहार, पटना।

भा.अ.अ.अ.
15/1/21

विषय :-
प्रसंग :-

GTSNY योजनान्तर्गत 01 (एक) पथ का पुनरीक्षित तकनीकी अनुमोदन के संबंध में।
कार्य प्रमण्डल, महनार का पत्रांक- 68/ दिनांक :- 15.01.2021

महाशय,

उपर्युक्त विषयक GTSNY योजनान्तर्गत ग्रामीण कार्य विभाग, कार्य प्रमण्डल, महनार से प्राप्त निम्नवत 01 (एक) पथ का पुनरीक्षित प्राक्कलन तकनीकी स्वीकृति के पश्चात् तकनीकी अनुमोदन हेतु समर्पित की जा रही है :-

क्र० सं०	प्रखण्ड	योजना का नाम	लम्बाई (कि०मी० में)	निर्माण की राशि (लाख में)	पंचवर्षीय अनुरक्षण की राशि (लाख में)	सतत लीज की राशि (लाख में)	प्राक्कलित राशि (लाख में)
1	Raghopur	PMGSY Road L029 to Mahadalit Tola Rustampur	0.575	37.811	1.114	34.035	72.960



25.1.21
342
25.1.21
श्री. वि. क. सिंह

विश्वासभाजन

अधीक्षण अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, मुजफ्फरपुर।

Tender Inviting Authority: Executive Engineer, R.W.D. Works Division, Mahanar					
Name of Work:			PMGSY Road L029 To Mahadalit Tola Rustampur		
BLOCK Raghopur			DISTRICT - Vaishali		
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate Figure	AMOUNT Rs. P
1	Construction of Benchmark and Reference Pillars as per specification and drawing 200.1 & 200.2	0.09	Km	9 079.65	817.17
2	(ii) Construction of Reference Pillars/Burjees	0.09	Km	7 760.74	698.47
3	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top fertile soil not exceeding	0.05	Ha.	48 296.75	2414.84
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per	6.75	Cum	142.87	964.37
5	Construction of subgrade & earthen shoulders with approved material obtained from borrow pits with all lifts and lead, transporting to site, spreading, grading to required slope and compacted to meet requirement of Tables 300.2 with lead upto 1000m as per Technical Specification Clause 301.4.1	185.71	Cum	157.26	29204.75
6	Construction of granular sub-base by providing well graded material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401	42.19	Cum	1 918.25	80930.97
7	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M25 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork, spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding	53.44	Cum	6 662.60	356049.34
Cost of Construction (Rs.) :-					471079.91

(Chk) 10/- 47108-

423972-

220 Kumar Ray

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
MAHANAR
28/5/24