



GOVERNMENT OF BIHAR

RURAL WORKS DEPARTMENT

BIHAR RURAL ROAD PROJECT

BIHAR RURAL ROAD DEVELOPMENT AGENCY (BRRDA)

HEAD:- F.D.R.

FINANCIAL YEAR-2021-2022

STATE BIHAR
DISTRICT SUPAUL
BLOCK Raghapur
DIVISION BIRPUR

BIHAR RURAL ROAD DEVELOPMENT AGENCY (BRRDA)

NAME OF WORK :- RESTORATION WORK OF SITUHAR TO BAISI
BOARDER (2021-22)

Actual Length of Road	=	2.360 km
Flood Affected Length of Road	=	0.110 km
Flood Affected Length of Cost	Rs	3353740.00


Submitted By:
By: EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT
WORK DIVISION, BIRPUR


Prepared
EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT
WORK DIVISION, BIRPUR


Index of Road

Name of Work:- Name of Work : - Restoration Work of Situhar to Baisi Boarder (2021-22)

DIVISION		Birpur
Block		Raghopur
Actual Length of Road		2.360 km
Flood affected length of Road		0.110 km
Sr. No.	Description	Page No.
1	Prativedan	07
2	MIS Report	10
3	Joint Inspection committee Report	17
4	Summary of Road	12
5	Estimate of Road	16
6	Carriage of Road	09
7	Basic Rate of Labour Material & Machinery	22
8	Analysis of Rate	28
9	Photograph of Pre & Post Cutting / Ditches	34-37


 Junior Engineer
 RWD, W Sub-Div, Raghopur


 Assistant Engineer
 RWD, Wsub-Div, Raghopur


 Executive Engineer
 Rural Work Department
 Work's Division, Birpur

**ग्रामीण कार्य विभाग
बिहार, सरकार**

पत्रांक - मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

पटना, दिनांक 07/07/2021

प्रेषक,

पंकज कुमार पाल (भा0प्र0से0)
सचिव

सेवा में,

सभी कार्यपालक अभियंता
ग्रामीण कार्य विभाग,

विषय- बाढ़ अतिवृष्टि से क्षतिग्रस्त पथों/पुलियों को यातयात लायक (Motorable) करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में निदेश दिया जाता है कि प्रमंडल अन्तर्गत सभी अभियंता बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों का शत प्रतिशत निरीक्षण करेंगे। पथों/पुलियों के क्षतिग्रस्त भाग से पानी उतरते ही उसे यातायात लायक बनाने की कारवाई एवं Motorable किये जाने से पहले तथा Motorable कार्य के बाद का Real time, Geo tagged photographs को MIS पर तत्क्षण अपलोड किया जाना सुनिश्चित करेंगे। इन कार्यों को कराने हेतु कार्यपालक अभियंता पूर्ण रूप से जिम्मेवार होंगे। कार्य न कराने की स्थिति में उनके विरुद्ध अनुशासनिक कार्रवाई की बाध्यता होगी।

विश्वासभाजन
(पंकज कुमार पाल)
सचिव

ज्ञापांक- मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी अधीक्षण अभियंता को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। साथ ही उन्हें निदेश दिया जाता है कि वे लगातार अनुश्रवण एवं निरीक्षण करते हुए क्षतिग्रस्त भाग को अतिशीघ्र यातायात लायक बनवाने की कारवाई सुनिश्चित करेंगे।

सचिव

ज्ञापांक-मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी मुख्य अभियंता, ग्रामीण कार्य विभाग को सूचनार्थ एवं लगातार अनुश्रवण करने हेतु प्रेषित।

सचिव

(3)

**अभियंता प्रमुख का कार्यालय
ग्रामीण कार्य विभाग, बिहार, पटना।**

पत्रांक:- मु0अ0-4(मु0)विविध(कार्य)-23-66/2020-1890⁽²⁵⁾ दिनांक- 22/04/2022

प्रेषक-

अशोक कुमार मिश्रा,
अभियंता अभियंता।

सेवा में,

अधीक्षण अभियंता,
कार्य अंचल- मधेपुरा,
ग्रामीण कार्य विभाग।

विषय:- वर्ष 2021-22 की बाढ़/अतिवृष्टि से क्षतिग्रस्त मोटरबुल कार्यों के प्राक्कलन की जाँच के संबंध में।

महाशय,

उपरोक्त विषय के संबंध में निर्देशानुसार कहना है कि अपने अंचल अंतर्गत सुपौल, वीरपुर एवं त्रिवेणीगंज कार्य प्रमंडलों के वर्ष 2021-22 में बाढ़/अतिवृष्टि से क्षतिग्रस्त सभी पथों के मोटरबुल कार्य के कृत कार्य मदों की मात्रा का स्थलीय जाँच किया जाना है। इस कार्य के लिए आपकी अध्यक्षता में जाँच टीम गठित की जाती है, जिसमें सभी कार्यों के लिए कार्यपालक अभियंता, कार्य प्रमंडल- सुपौल, वीरपुर एवं त्रिवेणीगंज सदस्य होंगे।

जाँच प्रतिवेदन एवं सभी आवश्यक अभिलेख यथा स्वीकृत प्राक्कलन, मापीपुस्त, Geotag फोटोग्राफ इत्यादि पाँच दिनों के अंदर FDR MIS पर अपलोड किया जाना सुनिश्चित करेंगे।

विश्वासभाजन

अभियंता प्रमुख

ज्ञापांक:- मु0अ0-4(मु0)विविध(कार्य)-23-66/2020/1890 दिनांक- 22/04/2022

प्रतिलिपि:- कार्यपालक अभियंता कार्य प्रमंडल-सुपौल, वीरपुर एवं त्रिवेणीगंज को सूचनार्थ एवं अक्षरशः अनुपालनार्थ प्रेषित।

ज्ञापांक 503 /

मधेपुरा, दिनांक 22.04.22 /

प्रतिलिपि : कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सुपौल/वीरपुर एवं त्रिवेणीगंज को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। साथ ही निर्देश दिया जाता है कि जाँच के क्रम में आवश्यक सभी वॉछित अभिलेख के साथ उपस्थित रहेंगे।

अधीक्षण अभियंता,

ग्रामीण कार्य विभाग, कार्य अंचल,
मधेपुरा।

**अभियंता प्रमुख का कार्यालय
ग्रामीण कार्य विभाग, बिहार, पटना।**

पत्रांक:- मु0अ0-4(मु0)विविध(कार्य)23-291/2019-4849 दिनांक- 07/12/2021

प्रेषक- अशोक कुमार मिश्रा,
अभियंता प्रमुख

सेवा में,

सभी कार्यपालक अभियंता, कार्य प्रमंडल, ग्रामीण कार्य विभाग
सभी अधीक्षण अभियंता, कार्य अंचल, ग्रामीण कार्य विभाग

विषय:- वर्ष 2021-22 में बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों के पुनर्स्थापन कार्य के संबंध में।

महाशय,

वर्ष 2020-21 में बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों का पुनर्स्थापन कार्य युद्ध स्तर पर किया जाना है। इस संबंध में पूर्व निर्गत निदेशों का अनुपालन सुनिश्चित किया जाए। पुनर्स्थापन के संबंध में कार्य प्रक्रिया पुनः अंकित किए जा रहे हैं।

(A) अस्थायी पुनर्स्थापन (Motorable) कार्य:-

वर्ष 2021-22 में बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों के अस्थायी पुनर्स्थापन कार्य की स्वीकृति एवं उनके भुगतान की प्रक्रिया विभागीय पत्रों एवं VC के माध्यम से अनेक बार स्पष्ट की जा चुकी है फिर भी कार्य प्रमंडल से प्राप्त प्राक्कलनों में कतिपय त्रुटियाँ दृष्टिगोचर हो रही हैं जिसके कारण उनकी स्वीकृति में विलंब हो रहा है। इस मामले में स्थिति पुनः स्पष्ट की जा रही है:-

- (1) बाढ़/अतिवृष्टि से क्षतिग्रस्त सभी पथों की प्रारंभिक प्रविष्टि MIS के FDR module में की जानी है। बाढ़ अवधि समाप्त हो चुकी है और यह अपेक्षा की जाती है कि अब बाढ़/अतिवृष्टि से क्षतिग्रस्त कोई भी पथ प्रारंभिक प्रविष्टि हेतु शेष नहीं है।
- (2) बाढ़ का प्रभाव खत्म होने पर उन पथों के क्षति का वास्तविक आकलन कर प्रारंभिक प्रविष्टि किए गए पथों का FDR module से पथों की क्षति की वास्तविक लम्बाई एवं संभावित व्यय की प्रविष्टि की जानी है।
- (3) तत्पश्चात मरम्मत कार्य पूर्ण कर वास्तविक व्यय के आधार पर प्राक्कलन तैयार किया जाना है जिसकी जाँच कार्य अंचल द्वारा निर्धारित असंबद्ध कार्य प्रमंडलों द्वारा की जानी है।
- (4) जाँचित प्राक्कलनों को जाँच प्रतिवेदन, अधीक्षण अभियंता की तकनीकी स्वीकृति (TS) एवं MB की छायाप्रति के साथ प्रशासनिक अनुमोदन हेतु विभाग को समर्पित किया जाना है।

९

अ

(5) प्रशासनिक अनुमोदन प्राप्त होने के उपरांत पथों की प्रविष्टि FDR module के ATR module में करने के पश्चात आवंटन की मांग की जा सकती है।

(6) Upload किए जाने वाले सभी फोटोग्राफ Geotagged होना चाहिए।

(B) स्थायी पुनर्स्थापन कार्य:-

(क) स्थायी पुनर्स्थापन कार्य में पथ में संवेदक बहाल होने पर अर्थात् पथ एकरारित अवधि में होने पर :-

(1) यदि बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ एकरारित अवधि में है तब उक्त पथ के क्षतिग्रस्त भाग का मद विचलन हेतु नियमानुसार पुनरीक्षित प्राक्कलन का प्रस्ताव उसी शीर्ष से दिया जाए जिस योजना में पथ एकरारित अवधि में है। नियमानुसार पूरक एकरारनामा कर उसी संवेदक से पुनर्स्थापन कार्य करा लिया जाए। उक्त अंश के कार्यों का भुगतान गैर योजना शीर्ष 3054/FDR से किया जाएगा। पुनर्स्थापन कार्य के पुनरीक्षित प्राक्कलन में इस आशय का प्रमाण पत्र अंकित किया जाए कि अस्थायी पुनर्स्थापन कार्य में उपयोग किए गए आवश्यक अवयवों का समुचित समायोजन कर लिया गया है एवं पुनरीक्षित प्राक्कलन सिर्फ बाढ़ से क्षतिग्रस्त भाग का ही बनाया गया है एवं संवेदक की लापरवाही से कोई क्षति नहीं हुयी है।

(ख) यदि बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ एकरारित अवधि के बाहर है:-

(i) बाढ़ से क्षतिग्रस्त वैसे पथ जो एकरारित अवधि के बाहर है अर्थात् जिनपर कोई संवेदक बहाल नहीं है, का प्राक्कलन निम्नवत् बनाया जाए:-

(1) यदि बाढ़ से क्षतिग्रस्त पथांश 50 % या उससे अधिक है तब पूरे पथ की मरम्मत का प्रस्ताव बिहार ग्रामीण पथ अनुरक्षण नीति 2018 के अनुसार समर्पित किया जाए।

(2) यदि बाढ़ से क्षतिग्रस्त पथांश 50 % से कम है तब पथ के क्षतिग्रस्त भाग की मरम्मत का प्राक्कलन विभाग को समर्पित किया जाए। साथ ही साथ निविदा का प्रकाशन भी कर दिया जाए किन्तु निविदा का निस्तार प्रशासनिक अनुमोदन प्राप्त होने के उपरांत किया जाए।

अतिआवश्यक होने पर अधीक्षण अभियंता की अनुमति से Short Tender Notice जारी किया जा सकता है।




(C) पुल-पुलियों का पुनर्स्थापन:-

(1) बाढ़ से क्षतिग्रस्त पथों में अवस्थित पुल-पुलिया के एप्रोच के पुनर्स्थापन का कार्य भी पथों के पुनर्स्थापन कार्य के अनुरूप किया जाए।

(2) बाढ़ के कारण जिन पुल/पुलियों में structural damage हुआ है, उनके पुनर्स्थापन का कार्य हेतु मूल योजना से पुनरीक्षित प्राक्कलन का गठन किया जाए यदि वे एकरारित अवधि के अन्दर हों। एकरारित अवधि से बाहर हो चुके पुल/पुलियों की लम्बाई यदि 15 मीटर तक है तो उसके पुनर्स्थापन हेतु प्राक्कलन का गठन गैर योजना शीर्ष 3054 से किया जाए। 15 मीटर से अधिक लम्बाई वाले पुल/पुलियों के प्राक्कलन का गठन कर स्वीकृति हेतु विभाग को भेजी जाय ताकि निधि की उपलब्धता के अनुरूप समुचित शीर्ष से उसकी स्वीकृति दी जा सके।

इसे अतिआवश्यक समझा जाय।

विश्वासभाजन

7/11/21
(अशोक कुमार मिश्रा)
अभिधन्ता प्रमुख

तकनीकी प्रतिवेदन


पथ का नाम : सिवुहर से वायसी बॉर्डर ।
 पथ की लंबाई : 2.360 कि०मी०
 प्राक्कलित राशि : 3353740.00
 प्रमंडल का नाम : वीरपुर
 अंचल का नाम : मधोपुरा
 योजना शीर्ष : F.D.R
 योजना वर्ष : 2021-22


प्रस्तुत प्राक्कलन विभागीय पत्रांक 1934 दिनांक 04-04-2021
 के आदेशानुसार पथ में कराये गये यातायात पुनर्स्थापना कार्य के निमित्त तैयार की गयी है ।


यह प्राक्कलन अस्थायी यातायात पुनर्स्थापना कार्य के लिए तैयार की गई है । वर्ष 2021 में आयी प्रलयंकारी बाढ़/अतिवृष्टि के कारण पथ कई जगहों पर क्षतिग्रस्त हो गया था जिसके कारण आवागमन अवरुद्ध हो गई थी जिसमें अस्थायी यातायात पुनर्स्थापन कार्य किया गया है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर, जो संवेदक लामांश को छोड़कर था, उसे प्राक्धान करते हुए तैयार किया गया है ।

अतः किये गये कार्यों के भुगतान हेतु प्राक्कलन की तकनीकी स्वीकृति अपेक्षित है ।


 कनीय अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रसाखा- राधोपुर


 सहायक अभियंता
 ग्रामीण कार्य विभाग
 कार्य अवर प्रमंडल - राधोपुर


 कार्यपालक अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल-वीरपुर

Summary of Carriage Cost			
Sl. No.	Particulars	Unit	Amount
1	Gr-III/GSB		
2	Stone Metal Below 40 mm	Cum	1637.73
3	Stone Chips	Cum	1637.73
4	Screening Materials	Cum	1637.73
5	Gr-II	Cum	1637.73
6	Stone Metal above 40 mm	Cum	1747.91
7	Binding Material/Moorum	Cum	1747.91
8	a)Course Sand	Cum	393.72
9	b)Course Sand at site	Cum	2033.01
10	c)Local Sand	Cum	2183.81
11	d)Local Sand at site	Cum	157.4
12	Boulder	Cum	274.25
13	a)Cement	Cum	1687.77
14	a)Cement at site	Ton	560.83
15	Bitumen (S-90)(FROM MUZAFFARPUR	Ton	5716.83
16	Bitumen Emulsion SS & RS (FROM BARAUNI)	Ton	1674.16
17	a)Hume Pipe NP 3 (600 MM DIA)	Ton	1987.9
18	b)Hume Pipe (600 MM DIA)at site	m	284.8
19	a)Hume Pipe NP 3 (1000 MM DIA)	m	1053.33
20	b)Hume Pipe NP 3 (1000 MM DIA)at site	m	706.78
21	Steel	m	3481.28
22	Brick	Ton	579.45
23	Brick Bats/Jhama metal	per 1000	698.98
		Cum	444.76

Amir Koope
12/5/22
Junior Engineer
R.W.D. Works Division, Virpur

Amir Koope
Asstt. Engineer
R.W.D. Works Division, Virpur

Amir Koope
Executive Engineer
R.W.D. Works Division, Virpur

Analysis for Carriage by Road & Rail
MADHYA VIDHAYLAY TEGRAHA TO CHILHAWA NAHAR TAK

NAME OF ROAD:-

District:- SUPAUL

Block:- RAGHOPUR

Sl No	Item with Source	Unit	Source	Pucka / Surface		Katcha		Loading & Unloading Cost	Carriage Cost by Rail Head	Total	Min Total
1	Stone Metal Gr-I & Gr-II	Cum	Shekhpura	8.00	x 820	x 29.00 Km = Rs 414.47	8.00	x 19.80	x 0.00 Km = Rs 0.00	89.90	Rs 1747.91
2	Stone Metal Gr-III/CSB	Cum	Shekhpura	4.59	x 820	x 29.00 Km = Rs 381.24	4.59	x 19.80	x 0.00 Km = Rs 0.00	1243.54	Rs 1637.73
3	Stone Aggregate / Chips	Cum	Mirzachowid	8.00	x 820	x 29.00 Km = Rs 381.24	8.00	x 19.80	x 0.00 Km = Rs 0.00	1166.59	Rs 1637.73
4	Stone Boulder	Cum	Shekhpura	4.59	x 820	x 29.00 Km = Rs 381.24	4.59	x 19.80	x 0.00 Km = Rs 0.00	1166.59	Rs 1637.73
5	Course Sand	Cum	Jagdishpur	8.00	x 747	x 161.00 Km = Rs 1928.13	8.00	x 18.09	x 0.00 Km = Rs 0.00	1201.54	Rs 1687.77
6	Binding Material/Moorum	Cum	Shekhpura	4.99	x 747	x 29.00 Km = Rs 288.84	4.99	x 19.80	x 0.00 Km = Rs 0.00	104.88	Rs 2033.01
7	Local Sand	Cum	Local	8.00	x 747	x 2.00 Km = Rs 23.95	8.00	x 17.82	x 1.00 Km = Rs 28.57	104.88	Rs 393.72
8	Brick	1000 Nos	Local	4.99	x 747	x 7.00 Km = Rs 209.16	4.99	x 18.09	x 1.00 Km = Rs 72.36	104.88	Rs 157.40
9	Cement	MT	Local	8.00	x 747	x 35.00 Km = Rs 261.45	8.00	x 18.09	x 0.00 Km = Rs 0.00	417.46	Rs 698.98
10	Steel	MT	Local	8.00	x 747	x 35.00 Km = Rs 261.45	8.00	x 18.09	x 0.00 Km = Rs 0.00	299.38	Rs 560.83
11	Bitumen Emulsion	MT	Barauni	8.00	x 747	x 220.00 Km = Rs 1643.40	8.00	x 18.09	x 0.00 Km = Rs 0.00	318.00	Rs 579.45
12	Bitumen	MT	Muzaffarpur	8.00	x 747	x 178.00 Km = Rs 1329.66	8.00	x 18.09	x 0.00 Km = Rs 0.00	344.50	Rs 1987.90
13	Hume Pipe (1000 mm)	M	Local	8.00	x 747	x 106.00 Km = Rs 633.46	8.00	x 18.09	x 0.00 Km = Rs 0.00	344.50	Rs 1674.16
14	Hume Pipe (600 mm)	M	Local	10.00	x 747	x 106.00 Km = Rs 253.38	10.00	x 18.09	x 0.00 Km = Rs 0.00	73.32	Rs 706.78
15	Hume Pipe (300 mm)	M	Local	8.00	x 747	x 106.00 Km = Rs 105.58	8.00	x 18.09	x 0.00 Km = Rs 0.00	31.42	Rs 284.80
16	Brick Bats	Nos	Local	60.00	x 747	x 106.00 Km = Rs 105.58	60.00	x 18.09	x 0.00 Km = Rs 0.00	31.42	Rs 137.00
Cost of Haulage Excluding Loading & Unloading as per SOR				3.60	x 19.63	x 5.00 Km = Rs 157.04	3.60	x 29.03	x 2.00 Km = Rs 92.90	194.82	Rs 444.76
Subjected to Verification of Load				2.25			2.25				

Type of Road	Per Ton. Km by Tipper	Per Ton. Km by Truck
For Surface Road	8.20	7.47
Unsurface Gravel Road	9.90	8.99
Kachha Road	19.80	18.09

Type of Road	Per Ton. Km by	Per Ton. Km by Truck
For Surface Road		19.63
Unsurface Gravel Road		24.53
Kachha Road		29.03

Handwritten signature
12/5/22
JE

Handwritten signature
12/5/22
ATC

FDR Road List of RWD, Works Division, Virpur

Sl. No.	Block	Road Name	Scheme	Road Status	Is Maintenance (Y/N)	Is Agreement (Y/N)	Length (In Km.)	Length of Damage Part Due to Flood	Tentative Restoration Amount (In Lac)	Actual Restoration Amount (In Lac)	Remarks	FDR Year	Start Latitude	Start Longitude	Mid Latitude	Mid Longitude	End Latitude	End Longitude
1	Basantpur	Balibhadrapur Bazar to Badhiva Chowk.	MMGSY(Gen)	On Going	No	Yes	3.145	0.15	20	0	Partially damaged at different places due to heavy rain.	2021-22	26.45364	87.02653	26.46165	87.039184	26.461914	87.035676
2	Basantpur	LJ40 House of Malendra Mehta To Arna Block Border via Shankarpur Madarsa (VRLB)	PMGSY	Completed	Yes	Yes	3.907	0.2	30	0	Damaged due to heavy rain and flood.	2021-22	26.474815	87.050716	26.477478	87.054776	26.473534	87.060084
3	Basantpur	SH 91 Barpur Bilpur to Airport Via Basantpur Block Rudhayaia Patil	MR	Completed	Yes	Yes	1.875	0.5	30	0	Road Damage different places.	2021-22	26.504124	87.015566	26.497943	87.013967	26.497413	87.01147
4	Basantpur	NH 106 to NH 10 Main Road	MMGSY NDB(BRICS)-I	On Going	No	Yes	1.28	0.2	17.35	0	Water flow on the Road	2021-22	26.507976	86.970029	26.507942	86.96996	26.508161	86.970419
5	Basantpur	Patra Kamal Gaoi Ne REO Sadak to Muslimani Tola - 2 Tak	MMGSY(SCI)	Completed	Yes	Yes	3.495	0.11	41	0	Bridge Damage.	2021-22	26.456575	87.041658	26.452385	87.052902	26.456633	87.04447
6	Basantpur	House Of Chandra Deo to BRICS YODHA Road (Canal Bridge)	GTSNY	Completed	Yes	Yes	1.05	0.35	18	0	Damaged due to heavy rain and flood.	2021-22	26.465422	87.059954	26.465413	87.059959	26.464572	87.062801
7	Basantpur	Vithwa Bank Road to Mehta Tola (Boathillapali)	MMGSY(SCI)	On Going	No	Yes	2.99	0.31	32.5	0	Road cut at different places.	2021-22	26.510222	87.051972	26.510245	87.051968	26.510129	87.051923
8	Basantpur	FATEHPUR NOKI WARD NO. 2 to NEPAL BORDER SSB CAMP TAK	MMGSY NDB(BRICS)-I	On Going	No	No	2.885	0.075	15	0	Road damage in three parts due to heavy rain.	2021-22	26.515702	86.998953	26.516904	86.99685	26.516945	86.996809
9	Basantpur	Koshi Bendi Nepalakatti Bathumia ur Sillapatti	New MR	On Going	No	Yes	6.39	0.155	15	0	Road Damaged due to heavy rain.	2021-22	26.399827	86.897224	26.40294	86.884126	26.407292	86.884126
10	Pratapgarh	House Of Ganeshi Ram to NH 57	GTSNY	On Going	No	Yes	1.485	0.06	5.5	0	water flow on the Road.	2021-22	26.321265	86.930108	26.321243	86.930301	26.3211	86.93142
11	Pratapgarh	House of Badri Mehta to PMGSY Road (MBC)	MMGSY(SCI)	On Going	No	Yes	0.95	0.52	48.5	0	Road cut different places by flood.	2021-22	26.232291	86.945354	26.258197	86.967298	26.251162	86.95234
12	Rajbhour	Repair of road from Stuhar to Bansi Border	MR	Completed	Yes	Yes	2.36	0.1	16	0	Partially Damaged due to rain.	2021-22	26.38655	86.92985	26.386416	86.929928	26.386388	86.929938
13	Rajbhour	Harekha Pachayot Se Durga Singh Gaoi Tola Hote Huye to Stapur Chok Tak	NABARD	On Going	No	Yes	2.889	0.24	15	0	Bank damage in more places due to heavy rain. No Need of temporary restoration	2021-22	26.357468	86.852363	26.357413	86.852394	26.357465	86.85317
14	Rajbhour	Karain Pandharat Ne Shvath Tak	GTSNY	Completed	Yes	Yes	1.6	0.08	15	0	No Need of temporary restoration. Required of RCC Box Culvert.	2021-22	26.41124	86.844387	26.411247	86.84414	26.411246	86.84419
15	Sarangarh Bhajiyahi	RWD Path to Shaludev Gori Ke Char Va Mahan Tola Nam Prasad Tak	MMGSY(Gen)	Completed	Yes	Yes	5.45	0.075	20	0	Road damaged.	2021-22	26.312365	86.755386	26.312258	86.756542	26.312127	86.757388
16	Sarangarh Bhajiyahi	Repair of road from Supaul Bhajiyahi to Puri Koshi (atbandh)	MR	Completed	Yes	Yes	2.85	0.04	3	0	Road damaged at different places or rain cut.	2021-22	26.269193	86.701712	26.273695	86.72181	26.273714	86.72176
17	Sarangarh Bhajiyahi	Mukhya mantri Sadak Vianpur to Kojwe Hote Huye Devra Singh Kanaal Tak	MMGSY(SCI)	Completed	Yes	Yes	1.65	0.11	20	0	cutting different places by flood	2021-22	26.336653	86.791593	26.336624	86.791871	26.336582	86.791775
18	Sarangarh Bhajiyahi	Madhe School Tengaraha to Chhwa Nalla	GTSNY	Completed	Yes	Yes	2	0.135	15	0	Damaged due to flood.	2021-22	26.25846	86.751696	26.257723	86.752557	26.257315	86.752339
19	Sarangarh Bhajiyahi	Mukhyamantri Gamin Sadak Nonkar Ram Tola Hote Hue Brahman Tola to Nonkar Tola Supaul up Sakha Nahar tak	MMGSY(WB)	On Going	No	Yes	1.925	0.26	35	0	Partially damaged at different places due to heavy rain. No Need of temporary restoration	2021-22	26.351528	86.801428	26.352464	86.801548	26.351679	86.801404
Total:							50.176	3.67	411.85	0								

12/5/22
A.E

12/5/22
A.E

12/5/22
A.E

FDR RESTORATION WORK
YEAR (2021-22)

GENERAL ABSTRACT OF COST

BLOCK :-	Raghopur	DISTRICT	SUPAUL
Name of Road	Restoration Work of Situhar to Baisi Boarder.		

S.No.	Description of Items		Amounts
A	TOTAL COST OF RESTORATION	Rs.	2814461.00
B	Seigniorage Fees	Rs.	173399.00
C	Add @12% GST	Rs.	337735.00
D	Add @1% Labour Cess	Rs.	28145.00
	Total (A+B+C+D)	Rs.	3353740.00
	Say	Rs.	3353740.00

Muram
12/5/22
Junior Engineer
RWD, W Sub-Division, Raghopur

Swati
12/5/22
Assistant Engineer
RWD, W Sub-Division, Raghopur

Swati
12/5/22
Executive Engineer
RWD Works Division Birpur

T.S NO - 604 dt - 17/05/2022

पत्रांक :- मु. अ. वि. - 04 (मु.) रा. वि. (अ. वि.) 23-29/1/2019-4849, दिनांक 07/12/2021

Technically sanctioned for Rs - 33,53,740.00 (Rupees thirty three Lacs fifty three thousand seven hundred forty) only.


Swati
17/05/22
Superintending Engineer
Rural Works Department
Works Circle Madhepura


SUMMARY OF COST ESTIMATE FOR THE PROJECT


Name of Work:- Name of Work : - Restoration Work of Situhar to Baisi Boarder (2021-22)

DIVISION		Birpur
Block		Raghopur
Actual Length of Road		2.360 km
Flood affected length of Road		0.110 km
Sr. No.	Item	Amount
1	Geo Bag	979046
2	Bamboo Piles	71069
3	Bamboo Runner	5280
4	Bamboo	67577
5	Brick Bat's	1691489
Total		2814461
Add @1% L.Cess		28145
Add @12% GST		337735
Add @10% S.Fee		173399
Add @2.25% Contingency		0.00
Total		3353740

Rupees Thirty Three Lakh Fifty Three Thousand Seven Hundred Forty Only


 Junior Engineer
 RWD,W Sub-Div,Raghopur


 Assistant Engineer
 RWD,W Sub-Div,Raghopur



 Executive Engineer
 RWD,WD Birpur


Office of the, Executive Engineer, Rural Work Department, Work's Division, Birpur
BOO


(Annexure-A)

Name of Work :- Restoration Work of Situhar to Baisi Boarder (2021-22)

Sr. No.	Item	Total Quantity	Unit	Rate (Rs.)	Total
1	2	3	4	5	6
1	Providing, laying & filling Geo Bags of size 1 m x 0.70 m, (Type A 300 GSM nonwoven) weight of bags 420 gm, volume of filled bag 0.07 cum, weight of filled geo bag 126 kg. with a local sand including stitching in four Lines by approved nylon thread with stitching machine and generator, stacking and placing after loading unloading and carriage with the help of trolley within 150 m lead .all complete as per specification and direction of E.I.(S.O.R.of W.R.D.5.7.54)	5193.88	Each	188.5	979046
2	Labour for cutting 62 mm to 75 mm dia bamboo piles t size and making shoes and driving etc. complete job as per specification and direction of E/I.	2214	M	32.1	71069
3	Labour for fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wir or nails complete job as per approved design, specification and direction of E/I.	880	M	6	5280
4	Supply 62 mm to 75 mm dia bamboo as per specification and direction of E.I.	369	Nos	183.3	67577
5	Providing and laying of Brick bats obtained from chimney with machnical means with all spreading grading to required slope compacted at OMC to achieve required density with all compacted as per specification and direction of E/I.	879.67	M ³	1922.87	1691489
Total					2814461
Add @1% L.Cess		Total S. Fee	Add @1% L.Cess	28145	
Add @12% GST					337735
Add @10% S.Fee					173399
Gross Total					3353740


 Junior Engineer
 RWD,W Sub-Div,Raghopur


 Assistant Engineer
 RWD,W Sub-Div,Raghopur


 Executive Engineer
 RWD,WD,Birpur

Office of the Executive Engineer, Rural Work Department, Work's Division, Birnur
Calculation Sheet
(Annexure-A)

Name of Work :- Restoration Work of Situhar to Baisi Boarder (2021-22)

Sr. No	Item	Sides	Nos	Length (m)	Width (m)		Depth (m)		Total Area/ Total Quantity/Total Length/Total No.	Unit	Total Quantity	Unit	Remark	
					W1	W2	D1	D2						
1	2	3	4	5	6	7	8	9	10	11	12	13	16	
1	Providing,laying & filling Geo Bags of size 1 m x 0.70 m, (Type A 300 GSM nonwoven) weight of bags 420 gm, volume of filled bag 0.07 cum, weight of filled geo bag 126 kg. with a local sand including stitching in four Lines by approved nylon thread with stitching machine and generator, stacking and placing after loading unloading and carriage with the help of trolley within 150 m lead ,all complete as per specification and direction of E.L.(S.O.R.of W.R.D.5.7.54)	1	1	25	0.7		2.5		89.29	nos				
		1	1	75	0.7		2.2		235.71	nos				
		1	1	10	0.7		2.7		38.57	nos	5194	Each		
		Total Quantity								363.57	nos			
Total no. of GEO bag Say (Volume of each geo bag-0.07 cum)										5194	nos			
2	Labour for cutting 62 mm to 75 mm dia bamboo piles (size and making shoes and driving etc. complete job as per specification and direction of E/L)		369	6					2214	m	2214	M		
3	Labour for fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.L. wire or nails complete job as per approved design,specification and direction of E/L.	2	4	110					880	m	880	M		
				Total					880	m				
4	Supply 62 mm to 75 mm dia bamboo as per specification and direction of E.L.								369	nos	369	Nos		
5	Providing and laying of Brick bats obtained from chimney with mechanical means with all spreading grading to required slope compacted at OMC to achieve required density with all compacted as per specification and direction of E/L.		1	25	2.85	2.5	0.9	0.8	56.84					
			1	75	7.5	5.65	0.9	2.3	789.00					
			1	10	3.95	2.65	1.2	0.85	33.825		879.67	M ³		
		Total								879.67				
										Total				
										Material Statement				
				Item	Quantity			Base Rate	Unit		Total	Total S. Fee		
				Sand	363.5714			116.90	cum		42502			
				brick bat	879.67			1922.87	cum		1691489	173399		
											1733990			

(Signature)
Junior Engineer
RWD, W Sub-Div, Raghapur

(Signature)
Assistant Engineer
RWD, W Sub-Div, Raghapur

(Signature)
Executive Engineer
RWD, W.D, Birnur

Office of the Executive Engineer, Rural Work Department, Work's Division, Birpur
Calculation Sheet
 (Annexure-A)

Name of Work :- Restoration Work of Situhar to Baisi Boarder (2021-22)

Name of Work :- Restoration Work of Situhar to Baisi Boarder (2021-22)																	
Sr. No	Item	Sides	Nos	Length (m)	Width (m)			Depth (m)		Total Area/Total Quantity/Total Length/Total No.	Unit		Total Quantity	Unit	Rate (Rs.)	Total	Remarks
					W1	W2	D1	D2	Nos/M ² /M ³								
1	2	3	4	5	6	7	9	10	12	13	14	15	16	17	18		
1	Providing,laying & filling Geo Bags of size 1 m x 0.70 m, (Type A 300 GSM nonwoven) weight of bags 420 gm, volume of filled bag 0.07 cum, weight of filled geo bag 126 kg. with a local sand including stitching in four Lines by approved nylon thread with stitching machine and generator, stacking and placing after loading unloading and carriage with the help of trolley within 150 m lead ,all complete as per specification and direction of E.I.(S.O.R.of W.R.D.5.7.54)	1	1	25	0.7		2.5		89.29	cum							
		1	1	75	0.7		2.2		235.71	cum							
		1	1	10	0.7		2.7		38.57	cum							
		Total Quantity							363.57	cum							
		Total no. of GEO bag Say (Volume of each geo bag-0.07 cum)															
2	Labour for cutting 62 mm to 75 mm dia bamboo piles t size and making shoes and driving etc. complete job as per specification and direction of E.I.		369	6					2214.00			2214.00	M		32.1	71069	
3	Labour for fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wir or nails complete job as per approved design,specification and direction of E/I.	2	4	110					880			880	M		6	5280	
					Total				880								
4	Supply 62 mm to 75 mm dia bamboo as per specification and direction of E.I.								369			369	Nos		183.3	67577	
5	Providing and laying of Brick bats obtained from chimney with machnical means with all spreading grading to required slope compacted at OMC to achieve required density with all compacted as	1	25	2.85	2.5	0.9	0.8		56.84								
		1	75	7.5	5.65	0.9	2.3		789.00								
		1	10	3.95	2.65	1.2	0.85		33.825								
		Total							879.67								
Material Statement											Total		2814461.00				
		Item	Quantity				Base Rate		Unit		Total	Total S. Fee	Add @1% L.Cess	28145			

Office of the Executive Engineer, Rural Work Department, Work's Division, Birpur

Calculation Sheet
(Annexure-A)

Name of Work : - Restoration Work of Situhar to Baisi Boarder (2021-22)

Sr. No.	Item	Sides	Nos	Length (m)	Width (m)	Depth (m)	Total Area/Total Quantity/Total Length/Total No.	Unit	Total Quantity	Unit	Rate (Rs.)	Total	Remarks
	Sand			363.5714		116.90	cum		42502		Add @12% GST	337735	
	E/w			879.67		1032	cum		907818	95032	Add @10% S.Fee	95032	
									950320		Gross Total	3275373.00	

[Signature]
12/5/22
Junior Engineer
RWD,W Sub-Div, Raigopur

[Signature]
Assistant Engineer
RWD,W Sub-Div, Raigopur

[Signature]
12/5/22
Executive Engineer
RWD,W,D, Birpur

जॉच प्रतिवेदन

अभिषेक प्रमुख, ग्रामीण कार्य विभाग, विहार, पटना के पत्रांक-1890 दिनांक-22.04.2022 द्वारा अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मधेपुरा की अध्यक्षता में गठित चार सदस्यीय समिती द्वारा कार्य प्रमंडल, मीरपुर के अंतर्गत वर्ष 2021-22 में बाढ़/अतिवृष्टि से क्षतिग्रस्त यहाँ के मोटरघर कार्य के कूत कार्य मर्दों की मात्रा का स्थलीय जॉच संबंधित सहायक अभियंता एवं कनीय अभियंता के साथ मापी लिया गया जो निम्न है :-

क्र.सं.	प्रखंड	कार्य का नाम	किये गये कार्य का नाम	स्थल पर किये गये कार्य की मापी										Unit	Remarks
				Sides	Nos	Lengt h (m)	Width (m)		Depth (m)		Total Area/ Total Quantity/Total Length/Total No.	Unit			
							W1	W2	D1	D2		Nos/M ² /M ³			
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
1			Providing,laying & filling Geo Bags of size 1 m x 0.70 m, (Type A 300 GSM nonwoven) weight of bags 420 gm, volume of filled bag 0.07 cum, weight of filled geo bag 126 kg, with a local sand including stitching in four Lines by approved nylon thread with stitching machine and generator, stacking and placing after loading unloading and carriage with the help of trolley within 150 m lead ,all complete as per specification and direction of E.L.(S.O.R.of W.R.D.5.7.54)	1	1	25	0.7		2.5		89.29	cum			
				1	1	75	0.7		2.2		235.71	cum			Each
				1	1	10	0.7		2.7		38.57	cum			
				Total Quantity			Total no. of GEO bag, Say (Volume of each geo bag=0.07 cum)			363.57	5194				
2	Raghopur	Restoration Work of Situhar to Basai Boarder (2021-22)	Labour for cutting 62 mm to 75 mm dia bamboo piles t size and making shoes and driving etc. complete job as per specification and direction of E/L.		369	6					2214	m	2214	M	
Labour for fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wir or nails complete job as per approved design,specification and direction of E/L.			2	4	110				880	M	880	M			
Supply 62 mm to 75 mm dia bamboo as per specification and direction of E.L.									369	nos	369	Nos			
4			Providing and laying of Brick bats obtained from chimney with machanical means with all spreading grading to required slope compacted at OMC to achieve required density with all compacted as per specification and direction of E/L.		1	25	2.85	2.5	0.9	0.8	56.84				
5					1	75	7.5	5.65	0.9	2.3	789.00				
					1	10	3.95	2.65	1.2	0.85	33.825			879.67	M ³
					Total						879.67				

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

G.P.S. 22

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, त्रिवेणीगंज

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सुपौल

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मीरपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

कार्यपालक अभियंता ग्रामीण कार्य विभाग कार्य प्रमंडल, मीरपुर समिति के जॉच प्रतिवेदन अनुसार post facto M.B. & post facto प्राक्कलन तैयार कर स्वसम प्रतिकाप को अप्रतार कार्यवेध हेतु शीघ्र भेजे

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

Name Of Road :- Situhar To Baisi Boarder (MR)

Block-Raghopur

Distt. Supaul

Length- 2.360 KM



Murarto
12/5/22
JE

Sv
12/5/22
AC

12/5/22
EE

Name Of Road :- Situhar To Baisi Boarder (MR)

Block-Raghopur

Distt. Supaul

Length- 2.360 KM



Situhar
12/11/22
JE

AB
12/11/22
AB

EE
12/11/22
EE

Name Of Road :- Situhar To Baisi Boarder (MR)

Block-Raghopur

Distt. Supaul

Length- 2.360 KM



Murad
12/5/22
JE

Ju
12/5/22
AE

GA
12/5/22
EE

Name Of Road :- Situhar To Baisi Boarder (MR)

Block-Raghopur

Distt. Supaul

Length- 2.360 KM



Shweta
 12/5/22
 JE

Sh
 12/5/22
 AE

Sh
 12/5/22
 EE