

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

बिहार BIHAR

19 FEB 2020

Agreement No.

Name of Works

AGREEMENT

51 MBD/2020-21 (2020-21)

Construction of Road With 5 years
Maintenance of Package No.-MR-N/19-20
Belsand/06 Under 3054 M/R Scheme.

Name of Agency

Alok Kumar Singh
Vill+Po- Madanpur,
Ps- Parsauni, Dist.- Sitamarhi.

Date of Start:-

18/05/2020.

Date of Completion:-

17/02/2020 (2021)

E.M. Deposit

Rs. 663,000/-

This Agreement Made on 18/05/2020 between Executive Engineer, Rural Work Department, Works Division, Belsand of the one part and Alok Kumar Singh, Vill+Po- Madanpur, Ps- Parsauni, Dist.- Sitamarhi. Whereas the Employer is desirous that the contractor execute the Work under 3054 M/R Scheme.

Alok Kumar Singh

Executive Engineer

RWD Works Division

Belsand

18/05/2020

Construction of Road With 5 years maintenance of **Package No.-MR-N/19-20 Belsand/06 Under 3054 M/R Scheme**. And the Employer has accepted the Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein at a cost of rupees 2,58,57,263.00 (Two Crore Fifty Eight Lakhs Fifty Seven Thousand Two Hundred Sixty Three only).

NOW THIS AGREEMENT WITNESSETH as follows :

1. In the Agreement, works and expressions shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
 - i) Letter of Acceptance;
 - ii) Notice to proceed with the work;
 - iii) Contractor's Bid;
 - iv) Contract Data;
 - v) Special Conditions of contract and General Conditions of Contract;
 - vi) Specifications;
 - vii) Drawings;
 - viii) Bill of Quantities; and
 - ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written,

The Common Seal of

Was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said

In the presence of :

Binding Signature of Employer

Binding Signature of Contractor

Alak Kumar Singh

[Signature]
Executive Engineer
R.W.D. Works Division
Belsand
18/10/2020
[Signature]
18/10/2020

AGREEMENT

1. Agreement No. :- S1 ^{MBD} SBD / 2020 (2020-21)
2. Name of Work :- Construction of Road With 5 years Maintenance of Package No.-MR-N/19-20 Belsand/06 Under 3054 M/R Scheme.
3. Name of Agency :- Alok Kumar Singh
Vill+Po- Madanpur,
Ps- Parsauni, Dist- Sitamarhi.
4. Constructions Cost :- 1,94,32,563 = 00
5. Maintenance Cost :- 64,24,694 = 00
6. Performance Security Deposit :- BG- 2,58,57,263 = 00
7. B.G. No. / Bank
8. Work Allotted rate :- (-) 1.99% Below
9. The Employer shall retain security deposit of 5% (five percent) and performance security of 2.5% (Two and half percent) of the amount from each payment due to the Contractor until completion of the whole of the Construction Work. No security deposit / retention shall be retained from the payments for routine maintenance works (As per SBD Clause 43).
10. Date of written order to commence :- 18/05/2020
11. Time required for the work from date of written order to commence :- 09 months
12. Total No. of Items :- 192

Note : SBD Rules Terms and condition will be applicable.

Alok Kumar Singh
Contractor


18/05/2020
Executive Engineer
R.W.D., Work Division
Belsand
18/05/2020

Tender Inviting Authority: Engg-in Chief RWD Patna			
Name of Work: =		Dhanger B Enar To PWD Dema Chowk	
Name Of Block =		Parsauni	
Contract No: Civil Works/			
Bidder Name		Excess (+)	%

SCHEDULE OF WORKS						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.28	ha	49496.70	Rupees Forty Nine Thousand Four Hundred Ninety Six And Paise Seventy Only	13859.08
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 300.2	588.00	Cum	176.75	Rupees One Hundred Seventy Six And Paise Seventy Five Only	103929.00
3.00	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	41.13	Cum	2083.43	Rupees Two Thousand Eighty Three And Paise Forty Three Only	85691.48
4.00	WBM Grading 2 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 401.	35.05	Cum	3739.16	Rupees Three Thousand Seven Hundred Thirty Nine And Paise Sixteen Only	131057.56

Atoll (un) Sub

801-
P. P. P. P. P.
P. P. P. P. P.
P. P. P. P. P.

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
5.00	WBM Grading 3 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical	48.26	Cum	3458.01	Rupees Three Thousand Four Hundred Fifty Eight And Paise One Only	166883.56
6.00	Prime Coat (Low porosity) :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	643.47	Sqm	41.38	Rupees Forty One And Paise Thirty Six Only	26613.92
7.00	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503.	671.60	Sqm	14.03	Rupees Fourteen And Paise Three Only	9422.55
8.00	Patch work over WBM using Mix seal surface With Waste Plastic for bituminous and Existing CC Pavement :- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 With waste plastic	671.60	Sqm	204.27	Rupees Two Hundred Four And Paise Twenty Seven Only	137187.73
9.00	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503.	5250.00	Sqm	11.76	Rupees Eleven And Paise Seventy Six Only	61740.00

Atul Kumar Singh

841-
Executive Engineer
R.W.D. Works Division
Bansari

Sl. No.	Description of work	No. of Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
10.00	Semi-Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects	131.25	Cum	10221.76	Rupees Ten Thousand Two Hundred Twenty One And Paise Seventy Six Only	1341606.00
11.00	Kilometre stone :- Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing etc as per drawing and technical specification clause 1703. i) 5th km Stone	0.00	nos	4517.86	Rupees Four Thousand Five Hundred Seventeen And Paise Eighty Six Only	0.00
12.00	ii) km stone	2.00	nos	2426.75	Rupees Two Thousand Four Hundred Twenty Six And Paise Seventy Five	4853.50
13.00	ii) 200 m Stone	6.00	nos	653.00	Rupees Six Hundred Fifty Three Only	3918.00
14.00	Direction and Place Identification signs with size more than 0.9 sqm size board :- Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per	0.00	Sqm	12440.62	Rupees Twelve Thousand Four Hundred Forty And Paise Sixty Two Only	0.00
15.00	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 i) 600 mm equilateral & triangle	12.00	nos	3721.22	Rupees Three Thousand Seven Hundred Twenty One And Paise Twenty Two Only	44654.64
16.00	600 mm circular	8.00	nos	3820.57	Rupees Three Thousand Eight Hundred Twenty And Paise Fifty Seven Only	30564.56
17.00	600 mm x 450 mm rectangular	10.00	nos	3691.45	Rupees Three Thousand Six Hundred Ninety One And Paise Forty Five Only	36914.50

Alok Kumar Singh

Sr

Executive Engineer
R.W.D. Works Dept.
Bhopal

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
18.00	Boundary Pillar/Gaurd Post :- Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	36.00	nos	515.08	Rupees Five Hundred Fifteen And Paise Eight Only	18542.88
19.00	Printing New Letters and Figures of any Shade :- Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	0.00	per cm height per letter	0.51	Rupees And Paise Fifty Only	0.00
20.00	Planting of Trees and their Maintenance for one Year :- Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard	63.00	Each	800.30	Rupees Eight Hundred And Paise Thirty Only	50418.90
21.00	Road Marking with Hot Applied Thermoplastic :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35 The finished surface to be level, uniform and free from streaks and holes	280.00	Sqm	735.40	Rupees Seven Hundred Thirty Five And Paise Forty Only	205912.00
22.00	Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 16 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause	2.00	nos	9470.76	Rupees Nine Thousand Four Hundred Seventy And Paise Seventy Six Only	18941.52
23.00	Brick Masonry in C.M.(1:3) in parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	8.64	Cum	5266.93	Rupees Five Thousand Two Hundred Sixty Six And Paise Ninety Three Only	45506.28

Alok Kumar Singh

881-
Executive Engineer
P.W.D. District
Bhuj

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
24.00	Plastering with cement mortar (1:4):- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	60.48	Sqm	191.56	Rupees One Hundred Ninety One And Paise Fifty Six Only	11585.55
25.00	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	175.68	Sqm	95.63	Rupees Ninety Five And Paise Sixty Three Only	16800.28
26.00	Maintenance for 1st year	1.00	Year	41056.00	Rupees Forty One Thousand Fifty Six Only	41056.00
27.00	Maintenance for 2nd year	1.00	Year	131527.00	Rupees One Lakh(s) Thirty One Thousand Five Hundred Twenty Seven Only	131527.00
28.00	Maintenance for 3rd year	1.00	Year	145234.00	Rupees One Lakh(s) Forty Five Thousand Two Hundred Thirty Four Only	145234.00
29.00	Maintenance for 4th year	1.00	Year	160958.00	Rupees One Lakh(s) Sixty Thousand Nine Hundred Fifty Eight Only	160958.00
30.00	Maintenance for 5th year	1.00	Year	364972.00	Rupees Three Lakh(s) Sixty Four Thousand Nine Hundred Seventy Two Only	364972.00
* Total Estimated Cost in Figures						34,10,350.49
31	1% Labour					34,103.50
32	12% GST					4,09,242.06
Quoted Amount					38,53,696.05	38,53,696.00
Quoted Rate in Words		Rupees Thirty Eight Lakh(s) Fifty Three Thousand Six Hundred Ninety Six Only				

[Signature]
28

Approved32.....(thirty two) items
 Valuing Rs. 38,53,696.00 (Rs. Thirty eight five
 fifty three thousand six hundred ninety six) only
 as Corrected

S. E.

R W D WORKS CIRCLE
 SITAMARHI

Alok Kumar Singh

81-