

कार्यपालक अभियंता का कार्यालय  
ग्रामीण कार्य विभाग, कार्य प्रमंडल, हाजीपुर

पत्रांक:- 1027 अनु  
हाजीपुर / दिनांक:- 27-4-23

प्रेषक,  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, हाजीपुर।

सेवा में,

IT NODAL (MIS)  
BRRDA, Patna

विषय :- State MIS के शीर्ष New Maintenance Policy Sanction Year ( 2022-23 के अंतर्गत पथ – Batch no- RM/VA/HAJ/23/0001 CHAK SARUPAN - MASTAFAPUR (Project Id - 31507502054) Agreement De-finalized करने के संबंध में।

महाशय,

उपर्युक्त विषयक के संबंध में सूचित करना है कि State MIS के शीर्ष New Maintenance Policy Sanction Year ( 2022-23 के अंतर्गत पथ – Batch no- RM/VA/HAJ/23/0001 CHAK SARUPAN - MASTAFAPUR (Project Id - 31507502054) Agreement Length - 850 Mt था परन्तु जगह उपलब्ध नहीं होने के कारण 800 मीटर की कार्य हुआ है जिसके कारण पथ की लंबाई 850 मीटर के बदले 800 मीटर करने की आवश्यकता है, इस पथ का Agreement Finalized हो चुका है और यहाँ से सुधार नहीं हो रहा है।

अतः अनुरोध है कि विषयांकित पथ का Agreement De-finalized करने की कृपा की जाये ताकि विषयांकित पथ Agreement Length को सुधार किया जा सके।

अनु0 – Agreement की छाया प्रति।

विश्वासभाजन

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग, कार्य प्रमंडल,  
हाजीपुर।

## 3054 MR (New Maintenance Policy) Yojana

Name of Road

1. Bhagwanpur Prakhand Ke Akbar Malahi Panchayat Anfragat Gram Mansurpur NH77 Petrol Pump ke Bagal to Mangal Singh Ke Ghar Railway Gumti Gram Shembhopur Berai Belkunda Road Tak Sadak Nirman Length- 1.5 K.M

2. Bhagwanpur Rasulpur to Husena Ghat Length - 2.50 K.M

3. ChakSherpur to Mustaphapur Length - 0.850 K.M

4. Husena Khurd Panchayat Avasthit Utkarmit Madhaya Middle School Husena Buzurg to Mevalal Singh ke Makan Se hote hue Mahadalit Tola Hote hue Jogi Asthan tak Length - 1.10 K.M

Total Length :- 5.95

Name of Division :- R.W.D Wokrs Division, Hajipur.

Name of Block :- Bhagwanpur 34/MRD/2022-23

Agreement No & Date :- 22/12/2022

Name and Address of Agency :- Basant Kumar At- Barahrup, P.O- Warishpur, Bhagwanpur, Vaishali.

As per BOQ

As per Agreement Less 23.55 Amount.

Construction Cost :- 197.65597 lac

151.10799 lac

Maintenance Cost :- 62.62014 lac

47.87310

Total :- 260.27611 lac

198.98109 Lac

Agreement Value :- 198.98109 Lac

Performance Security Deposit :-

Addl. Performance Grantee :-

Time required for Work :- 9 Month

Date of Start :-

Date of Completion :-

Total No. of Item :-

244

Basant Kumar

Agency

Division Accounts Officer

R.W.D (W) Div Hajipur

Executive Engineer

R.W.D(W) Div, Hajipur

Basant Kumar

Executive Engineer  
R.W.D. Works Division

22/12/22

22/12/22



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : Chaksherpur To Mustaphapur

Length of Road : 0.85

L / TR No. : 0

District : VAISHALI

Block : BHAGWANPUR

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
<b>(A) PREPARATORY WORK &amp; SITE CLEARANCE</b>						
1	2.2	<b>Clearing and Grubbing Road Land</b> Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I				
	(I)	<b>By Manual Means</b>				
	(A)	In area of non-thorny jungle	Hect.	0.170	62032.43	10545.51
2	3.14	<b>Construction of Subgrade and Earthen Shoulders</b> Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	Cum	357.000	254.19	90745.83
<b>Sub Head : PAVEMENT LAYERS - GSB &amp; WBM ITEMS</b>						
3	4.1	<b>Granular Sub-base with Well Graded Material (Table 400.1)</b> (By mix in place method) For Grading II Material				
		Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	Cum	16.300	2578-61 2710.89	42031.34 44187.51
4	4.7	<b>Water Bound Macadam with Stone Screening Gr-II</b> WBM Grading 2 (By Mechanical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	Cum	21.570	5361.71	115652.08

Executive Engineer

R.W.D. Works Division

22/11/2019



Name of Work—  
 Situation of Work—  
 Agency by which work is executed—  
 Date of Measurement—  
 No. and date of agreement

(These four lines should be repeated at the commencement of the measurement relating to each work)

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
1st on A/c & Final Bill					
Name of work: - Construction of Road					
from Chaksterpur to					
Mustaphapur under					
3054 m (1 ha maintenance					
policy) Varanasi					
Agency: - Basant Kumar At. Barakpur,					
P.O. Warishpur, Bhagwanpur					

Varanasi

Agreement no. - 34/EN/32/2022-23

Rate Approved - 23.55% Below

Date of Work order - 22/2/2022

Date of Completion - 21/9/2023

Actual date of Completion - 10/4/23

Date of measurement -

Work done

Gravel Grubbing

1st lot - 1000

2nd lot - 1000

3rd lot - 1000

4th lot - 1000

5th lot - 1000



Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
					Rs 13,15,08,739.00
Less 23.55% below as per agreement (-) Rs 5,90,808.00					
					Rs 19,17,931.00
Sabita 10/04/23 JE				18/4/23 AE	
Work has been done as per Specification in the length of 800 m				18/4/23 AE	
Sabita 10/04/23 JE					