



बिहार BIHAR

अमरपुर कंस्ट्रक्शन प्राइवेट लिमिटेड कम्पनी अमरपुर
कोटा AS 583606

1099
28-3-23

कार्य प्रारंभ की तिथि - 25-07-2023
कार्य समाप्ति की तिथि - 24-04-2024

1000x121000260 नीति निगम का
स्थायी धन, बाका का
बिल नं. 15/190

Agreement No - 03 MB7/2023-24

This agreement, made the day of between The Executive Engineer, Rural Work Department (Works) Division, Banka-1 (hereinafter called "the Employer") of the one part, and Amarpur Construction Co.(P) Ltd, Amarpur, Dist- Banka 813101 (hereinafter called "the Contractor") of the other part.

Whereas the Employer is desirous that the Contractor execute the Construction of Road & CD Works with maintenance under Road name Package No.- MR-N/22-23 Banka-1/24 (Tender ID- 124602, Bid ID- 540914) Year 2022-23 under M/R (3054) Yojna, Block- Amarpur, District- Banka, Bihar (hereinafter called the contract) Chief Engineer-4 Rural work department, Bihar Patna, Vide Letter No-3901 Enc / Patna, Dated- 25.07.2023 and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the Routine maintenance of works for Five Years of the Contract Price remedying of any defects therein, at a Construction of cost of Rs. 374.66477 (Rupees Three Crore Seventy Four Lakh Sixty Six Thousand Four Hundred Seventy Seven Only) & Maintenance of cost Rs. 136.23344 (Rupees One Crore Thirty Six Lakh Twenty Three Thousand Three Hundred Fourty Four Only) with a Total Amount of Rs. 510.89821 (Rupees Five Crore Ten Lakh Eighty Nine Thousand Eight Hundred Twenty One Only) at bidder rate quoted 10.00 % below the estimated cost. Amarpur Construction Co.(P) Ltd the contractor has deposited (i) BG No.- 4317NDLG00004024 Amount Rs. 1135000.00 (ii) BG No.- 4317NDLG00011324 Amount Rs. 2554500.00 & (iii) BG No.- 4317NDLG00011224 Amount Rs. 1000000.00.

[Signature]
Divisional Account Officer
R.W.D. (W) Div. Banka-1

[Signature] 21/8/23
Executive Engineer
R.W.D. Works Division
BANKA-1

Amarpur Cons. Co. (P) Ltd
[Signature]
Director

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the Contract and undertaking routine maintenance for five years.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the works and the remedying the defects wherein and undertaking routine maintenance for five years, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and be read and construed as part of this Agreement, viz:
 - i) Letter of Acceptance :
 - ii) Notice to proceed with the works;
 - iii) Contractor's Bid;
 - iv) Contract Data;
 - v) Special Conditions of Contract;
 - vi) General Conditions of Contract;
 - vii) Specifications;
 - viii) Drawings;
 - ix) Bill of Quantities; and
 - x) Any other documents listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day any year first before written.

The Common Seal of _____
Divisional Account Officer
R.W.D. (W) Div. Banka-1

Executive Engineer
R.W.D. Works Division
BANKA-1
21/8/23

Was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said _____

In the presence of:

Binding Signature of Employer _____
Divisional Account Officer
R.W.D. (W) Div. Banka-1

Executive Engineer
R.W.D. Works Division
BANKA-1
21/8/23

Binding Signature of Contractor _____

Amropur Cons. Co. (P) Ltd.

Director

Executive Engineer
R.W.D. Works Division
BANKA-1

BIHAR RURAL ROADS DEVELOPMENT AGENCY
(GOVERNMENT OF BIHAR)

BID DOCUMENT

FOR

CONSTRUCTION AND MAINTENANCE OF RURAL
ROADS

DISTRICT: Banka

BLOCK: Amarpur

Sl. No.	Name of Road	Length In Km	Cost of Const. (Rs. In Lakhs)	Maintenance Cost (Rs. In Lakhs)	Total Cost (Rs. In Lakhs)
Package No.- MR-N/22-23 Banka-1/24					
1.	English More Shambhuganj Road Shobhanpur to Janakpur Tak	2.590	92.59994	31.84855	124.44849
2.	Mahadeopur Kaswa PMGSY Road to Chakasia	1.500	49.94404	19.92255	69.86659
3.	L081 Mahadeopur Kaswa Road to Laguniya Via Chandpur	4.100	148.76556	58.15619	206.92175
4.	Amarpur Shahkund Path Medhiyanath School To kamdeopur Koritola Via Bhaluar	1.853	83.35523	26.30615	109.66138
Total-		10.043	374.66477	136.23344	510.89821

Financial Bid
Year 2023-24

Under
M/R Head 3054
MINISTRY OF RURAL DEVELOPMENT
GOVERNMENT OF BIHAR

Divisional Account Officer
R.W.D. (W) Div. Banka-1

Executive Engineer
R.W.D. Works Division
BANKA-1

Contractor's Detail

Agreement No. -

Name of Work - Package No.- MR-N/22-23 Banka-1/24

Name of Contractor - Amarpur Construction Co.(P) Ltd

Address - Amarpur,
Dist- Banka 813101

Registration No. - 1210024

Pan - AADCA4194K

GST - 10AADCA4194K1ZU

Bank Account Details :-


Name of Bank -


Account No. -

IFSC Code -

Mobile No. - 9931060622

Email ID - accpl@yahoo.com

Amarpur Cons. Co. (P) Ltd.

Director


Divisional Account Officer
R.W.D.(W) Div. Banka-1


Executive Engineer
R.W.D. Works Division
21/8/23 BANKA-1

**Office of the Executive Engineer
R.W.D. Works Division, Banka-1**

Letter of Acceptance

Letter No. :- 1352

Date :- 25.07.2023

To,

Amarpur Construction Co.(P) Ltd
Amarpur, Banka, 813109
Mob.- 9931060622
Email ID - K_09@ymail.com

Ref No- C.E-4, RWD , Patna Vide Letter No- 3901 Encl. dt- 25.07.2023

Dear Sirs,

This is to notify you that your Bid dated 11.05.2023 for execution of the road construction and routine maintenance of the works for five years after completion of the construction under **Package No.- MR-N/22-23 Banka-1/24 (MR)** (Tender ID- 124602, Bid ID- 540914) for the Contract Price of **Rupees 51089821.00** (Rupees Five Crore Ten Lakh Eighty Nine Thousand Eight Hundred Twenty One Only) is hereby accepted by our Agency.

We note that as per bid, you do not intend to subcontract any component of work.

You are hereby requested to furnish Performance Security including an additional Performance Security for unbalanced bid in terms of ITB clause 27.4 in the form detailed in Para 34.1 of ITB for an amount of APG Rs. 2128750.00 & Earnest Money Rs. 2554500.00 Total Rs. **4683250.00** (Rupees Forty Six Lakh Eighty Three Thousand Two Hundred Fifty Only) and all Related documents submitted. within 21 days of the receipt of this letter of acceptance in accordance with the conditions of contract and sign the contract, failing which action as stated in Para 34.2 of ITB will be taken.

Yours faithfully,

Executive Engineer,
Rural Works Department,
Works Division, Banka-1.

Amarpur Cons. Co. (P) Ltd.
[Signature]
Director

Divisional Account Officer
R.W.D. (W) Div. Banka-1

Executive Engineer
R.W.D. Works Division
BANKA-1

UNDER MR-3054
BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : L081- Mahadeopur Kaswa Road To Laguniya via Chandpur

Block : Amarpur


District :

Banka

Length : 4.100 km

Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	Hect.	0.62	72697.96	59612.25
2	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202. (Cement Concrete)	Cum	1.62	658.99	1067.56
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202. (Stone Masonry/Brick Masonry)	Cum	61.38	314.04	19275.78
4	Removing all types of Hume pipes and stacking within a lead of 1000 m including Earthwork and Dismantling of Masonry Works as per Technical Specification Clause 202. (Above 600 mm to 900 mm dia Hume pipe)	Rm	10.00	336.35	3363.50
5	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	Cum	2388.00	264.02	630479.76
6	For Grading II Material -Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	cum	161.69	2190.08	354114.04




Director

Executive Engineer
R.W.D. Works Division
BANKA-1


Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
13	Cement Concrete Pavement -Construction of unreinforced plain cement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete of not less than 0.2cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick plythene film, wedges, steel plates including levelling the formwork as per drawing) spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/ culvert and construction joints, admixtures as approved, curing of concrete slab for 14 days curing compound (where specified) and water finishing to lines and grade as per drawing and Technical specification clause 1501.	Cum	242.40	7981.09	1934616.22
14	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703.				
	ii) Km stone	No.	6.00	2852.93	17117.58
	iii) 200 m stone	No.	16.00	819.41	13110.56
15	Direction and Place Identification signs with size more than 0.9 sqm size board- Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	Sqm	11.52	15008.60	172899.07
16	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801				
	500 mm equilateral & triangle	No.	32.00	4446.75	142296.00
	500 mm circular	No.	2.00	4295.93	8591.86
	500 mm x 450 mm rectangular	No.	8.00	4151.39	33211.12
17	Painting new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	per cm height per letter	792.00	0.73	578.16
18	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	Each	370.00	1254.41	464131.70

Sanjay K. Singh
Sanjay K. Singh

Sanjay K. Singh


Executive Engineer
R.W.D. Works Division
BANKA-1

Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
27	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.				
	Parapet	Rm	60.00	1061.15	63669.00
28	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications				
29	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	141.12	203.96	28702.84
		Sqm	141.12	135.23	19083.66
				Total =	13776256.37
				Labour cess @1% =	137762.56
				GST @18% =	2479726.15
				Add Seigniorage Fee @ 10% =	135762.73
				Total (A) =	16529507.81
30	5 YEAR ORDINARY MAINTENANCE COST	Quarterly	20	270882.13	5417642.50
				Labour cess @1% =	54176.43
				GST @18% =	975175.65
				Add Seigniorage Fee @ 10% =	14804.23
				Total (B) =	6461798.80
				Grand Total Cost (A+B) =	22991306.61



 21/4/23
 Executive Engineer
 Rural Works Department
 Works Division-Banka 1

BOQ Approved for Rs- 2,29,91,307 = 00 (Rupees Two crore twenty nine lakhs ninety one thousand three hundred seven) only -


 26.4.23
 Superintending Engineer
 Rural Works Department
 Works Circle, Bhagalpur


 26/04/23

Executive Engineer
 R.W.D. Works Division
 BANKA-1

Co. (P) L-1

 District