



बिहार BIHAR

क्रमांक २९४६ दिनांक ६.७.२४
 श्री/श्रीमती राजनीश कुमार पितृ विरूपनाथ की
 नाम/पुत्र/पुत्री गहिरो न जितपुरी बिहार मुजफ्फरपुर
 मुद्रांक किया गया
 मुद्रांकित नाम राजनीश कुमार
 राजनीश कुमार सिंह ला. नं. १००/२०२३

AR 833521

Agreement No :- 02 MBD/2023-24

Name of Works :- Construction of Road With 5 Year maintenance of Package No-MR-N/2022-23 Belsand/06 Under M/R 3054 Scheme.
 1. Gidha Ghat To Gidha Gaw Tak Path
 2. Belahi School Chowk To Khopa Path
 3. Bagahi To Dhapar path

Name of Agency :- Sri Rajnish Kumar
 Vill- Gahilo, Po-Jaitpur, PS- Saraiya
 Distt- Muzaffarpur.

Date of Start :- 31.07.2023

Date of Completion :- 30.04.2024

E.M. Deposit :- AXIS Bank (P.D) :- 4,06,519 + 255,474 + 1153100 + 762600 =

Total :- 3874,693 :-

This Agreement Made on 31.07.2023 between Executive Engineer, Rural Work Department, Works Division, Belsand of the one part and Sri Rajnish Kumar, Vill- Gahilo, Po-Jaitpur, PS- Saraiya, Distt-Muzaffarpur. Whereas the Employer is desirous that the contractor execute the Works under M/R 3054 Scheme.

राजनीश कुमार

Signature
 Executive Engineer
 R.W.D. Works Division
 Belsand

Signature
 31.07.2023

Construction of Road With 5 Year maintenance Road from Package No-MR-N/2022-23 Belsand/06 Under M/R 3054 Scheme And the employer has accepted the bid by The Contractor for the execution and completion of such works and remedying of any defects therein at a cost of rupees-4,23,00,298.00 (Four Crore Twenty Three Lakh Thirty Two Hundred Ninety Eight Only)

NOW THIS AGREEMENT WITNESSETH as follows :

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract thereafter referred to, and they shall be form and be read and constructed as part of this agreement.
2. In consideration of the payments to made by the Employer to the Contractor as herein after mentioned, the contractor hereby covenants with Employer to execute and complete the works and remedy any defects therein in conformity I all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and constructed as part of this agreement , viz.

- (i) Letter of Acceptance
- (ii) Notice to proceed with the works
- (iii) Contractor's Bid
- (iv) Contract Data
- (v) Special condition of contract and general conditions of contract.
- (vi) Specifications
- (vii) Drawings
- (viii) Bill of Quantities and

31/07/2023
Executive Engineer
R.W.D. Works Division
Belsand

राजनीश कुमार

31/07/23

- (ix) Any other document listed in the contract Data as forming part the contract

In witness, where of the parties there to have caused this Agreement to be executed the day and year first before written.

The common seal of

Was hereunto affixed in the presence of

Signed, sealed and Delivered by the said

In the presence of

Binding signature of Employer

Binding signature of contractor.

रजनीश कुमार

31/7/23
Ratna
31.07.2023
Executive Engineer
R.W.D. Works Division
Belsand
31/7/23

AGREEMENT

1. Agreement No. :- 02 MBD / 2023-24
2. Name of Work :- Construction of Road With 5 Year maintenance of Package No-MR-N/2022-23 Belsand/06 Under M/R 3054 Scheme.
3. Name of Agency :- Sri Rajnish Kumar
Vill- Gahilo, Po-Jaitpur, PS- Saraiya
Distt- Muzaffarpur.
4. Construction Cost :- RS 3,30,19,384.00
5. Maintenance Cost :- RS 9280,911.00
- Total :- RS 4,23,00,295.00
6. Performance Security Deposit :- ~~RS~~ ① 9230400814914772 11531002
② 921040051939016 = 255477
③ 921040072880326 = 7,06519.
7. B.G. No. / Bank :- APS 2. ① 9230400814916542 1762600.00
8. Work Allotted rate :- (10% Below)
9. The Employer shall retain S.D. of (5 %) of the amount from each payment due to the contractor until completion of the whole of the construction work. No security deposit / retention shall be retained from the payment for routine maintenance of work.
10. Date of written order to commence :- 31.07.2023
11. Time required for the work from date of written order to commence :- 9 Month
12. Total No. of Items :-

Note : MBD Rules Terms and condition will be applicable.

Contractor

Adman
Executive Engineer
RWD, Works Division
Belsand

Adman
31.07.23
31/7/23

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work: Belahi School Chowk To Khops Dhanuahi

Name Of Block: Runni Saidpur

Contract No: Civil Works/

Bidder Name: Excess (+) %

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.64	ha	72697.86	Rupees Seventy Two Thousand Six Hundred Ninety Seven And Paise Eighty Six Only	46526.63
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1344.00	Cum	262.96	Rupees Two Hundred Sixty Two And Paise Ninety Six Only	353418.24
3.00	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	78.98	Cum	2881.87	Rupees Two Thousand Eight Hundred Eighty One And Paise Eighty Seven Only	227602.89
4.00	WBM Grading 2 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	41.87	Cum	5598.13	Rupees Five Thousand Five Hundred Ninety Eight And Paise Thirteen Only	234407.70

Patna

27/07/2013

Patna
31/07/2013
Executive Engineer
R.W.D. Works Division
Belsand
21/8/23

Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
			Figure	Words	
5.00 WBM Grading 3 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand pecking, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, wetting and compacting to the required density Grading 3 as per Technical Specification Clause 405.	84.62	Cum	5442.09	Rupees Five Thousand Four Hundred Forty Two And Paise Nine Only	460523.26
6.00 Prime Coat (Low porosity) :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	1128.30	Sqm	59.54	Rupees Fifty Nine And Paise Fifty Four Only	67178.98
7.00 Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrioc broom as per technical specification clause 503.	1128.30	Sqm	20.49	Rupees Twenty And Paise Forty Nine Only	23118.87
8.00 Patch work over WBM using Mix seal surface With Waste Plastic for bituminous and Existing CC Pavement :- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 With waste plastic	1128.30	Sqm	293.29	Rupees Two Hundred Ninety Three And Paise Twenty Nine Only	330919.11
9.00 Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrioc broom as per technical specification clause 503	7500.00	Sqm	17.10	Rupees Seventeen And Paise Ten Only	128250.00

26/07/21

21.07.2023
Executive Engineer
R.W.D. Works Division
Belsand
31/07/23

Description of work		No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
10.00	Semi-Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	187.50	Cum	Figure	Words	2029648 13
				15624.79	Rupees Fifteen Thousand Six Hundred Twenty Four And Paise Seventy Nine Only	
	Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregate conforming to IS-383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant.	22.50	Cum	4798.09	Rupees Four Thousand Seven Hundred Ninety Eight And Paise Nine Only	107957 10
	Cement Concrete Pavement :- Construction of un-reinforced plain cement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete of not less than 0.2cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing) spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars near approaches to bridge culvert and construction joints, admixtures as approved, curing of concrete slab for 14 days curing compound (where specified) and water finishing to lines and grade as per drawing and Technical specification clause 1501.	720.00	Cum	9674.59	Rupees Nine Thousand Six Hundred Seventy Four And Paise Fifty Nine Only	6965704 80
11.00	Kilometre stone :- Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. i) km Stone	4.00	nos	3373.83	Rupees Three Thousand Three Hundred Seventy Three And Paise Eighty Three Only	13495.32
12.00	ii) 200 m Stone	13.00	nos	911.48	Rupees Nine Hundred Eleven And Paise Forty Eight Only	11849.24

Ratna
27/07/2015

Ratna
31.07.2015
Executive Engineer
R.W.D. Works Division

Ratna
31/7/15

13.00	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
	Direction and Place Identification signs with size more than 0.9 sqm size board :- Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	1.92	Sqm	15329.54	Rupees Fifteen Thousand Three Hundred Twenty Nine And Paise Fifty Four Only	29432.72
14.00	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 i) 600 mm equilateral & triangle	8.00	nos	4687.45	Rupees Four Thousand Six Hundred Eighty Seven And Paise Forty Five Only	37499.60
15.00	600 mm circular	4.00	nos	4536.63	Rupees Four Thousand Five Hundred Thirty Six And Paise Sixty Three Only	18146.52
16.00	600 mm x 450 mm rectangular	4.00	nos	4392.10	Rupees Four Thousand Three Hundred Ninety Two And Paise Ten Only	17568.40
17.00	Boundary Pillar/Guard Post :- Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	80.00	nos	833.78	Rupees Eight Hundred Thirty Three And Paise Seventy Eight Only	66702.40
18.00	Printing New Letters and Figures of any Shade :- Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	702.00	per cm height per letter	0.73	Rupees And Paise Seventy Three Only	512.46
19.00	Planting of Trees and their Maintenance for one Year :- Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	201.00	Each	1254.41	Rupees One Thousand Two Hundred Fifty Four And Paise Forty One Only	252136.41

Rabna
22/01/2019

Rabna
31.07.2019
Executive Engineer
R.W.D. Works Division
Belsand
31/7/19

No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
10.00	Road Marking with Hot Applied Thermoplastic :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area. thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35. The finished surface to be level, uniform and free from streaks and holes.	640.00	Sqm	888.39	Rupees Eight Hundred Eighty Six And Paise Thirty Nine Only	567289.60
11.00	Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos 75mm x 75 mm of 12 SWG steel tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4.00	nos	11777.58	Rupees Eleven Thousand Seven Hundred Seventy Seven And Paise Fifty Eight Only	47110.32
22.00	Brick Masonry in C.M.(1:3) in parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	11.52	Cum	9341.57	Rupees Nine Thousand Three Hundred Forty One And Paise Fifty Seven Only	107614.89
23.00	Plastering with cement mortar (1:4) :- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	0.86	Sqm	87586.18	Rupees Eighty Seven Thousand Five Hundred Eighty Six And Paise Eighteen Only	75674.46

Redon

20/12/21 GHK

Redon
31.07.2023
Executive Engineer
R.W.D. Works Division
Beland
shun
31/7/23

Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
			Figure	Words	
24.00 Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	80.64	Sqm	133.61	Rupees One Hundred Thirty Three And Paise Sixty One Only	10774.31
Total cost Of Construction					1,31,31,062.36
25.00 Maintenance for 5 year	20.00	Per 3 month	182407.60	Rupees One Lakh(s) Eighty Two Thousand Four Hundred Seven And Paise	36,48,152.00
26.00 Total Estimated Cost in Figures					1,67,79,214.36
27.00 1% Labour					1,67,792.14
28.00 18% GST					30,20,258.58
29.00 TOTAL SEIGNIORAGE FEE					1,36,980.55
30.00 Quoted Amount				2,01,04,245.63	2,01,04,246.00
Quoted Rate in Words				Rupees Two Crore One Lakh(s) Four Thousand Two Hundred Forty Six Only	

Ratna
24.04.2023

BOQ Approved for Rs. 2,01,04,246.00 (Rupees two crore one lakh four thousands two hundred forty six only).
for total 1 to 30 items only.
(thirty).

राजनीश कुमार

24/04/23
अधीक्षक अभियन्ता
सामान्य कार्य विभाग, कार्य अंचल
मीतामदी
24/04/2023 → 24/04/23

31/07/2023
Executive Engineer
R.W.D. Works Division
Belsand

31/07/23