



Prohibition Excise &
Registration Department,
Government of Bihar



INDIA NON JUDICIAL
Other



First Party Name * : ANIL KUMAR SINGH
Second Party Name * : ANIL KUMAR SINGH
Purchased By * : ANIL KUMAR SINGH
Certificate Number : BR038161381691998176473
Consideration Price : ₹0.00/-
Stamp Duty Paid : ₹1,000.00/-
Registration Fee & Other Fees : ₹0.00/-
LLR & Proc Fee : ₹0.00/-
Miscellaneous Fees : ₹0.00/-
Discore SC : ₹0.00/-
Total Amount : ₹1,000.00/- (One Thousand)




----- This stamp paper will only be valid if embossed below with special RED ink impression -----

कार्य प्राप्त की तिथि - 11-08-2023

कार्य समाप्त की तिथि - 10-05-2024

Phone No:
Sold To/Issued To:
Anil
For whom/ID Proof:
Anil



AUG-14-2023 13:00:23

₹ 0001000/-
ZERO ZERO ZERO ONE ZERO ZERO ZERO

Other
38161381652018023570-00004655
3816138 2848

Agreement No - 04/182/2023-24

This agreement, made the _____ day of _____ between The Executive Engineer, Rural Work Department (Works) Division, Banka-1 (hereinafter called "the Employer") of the one part, and Anil Kumar Singh At-Babutola, Anchal+Dist-Banka, Bihar, PIN- 813102 (hereinafter called "the Contractor") of the other part.

Whereas the Employer is desirous that the Contractor execute the Construction of Road & CD Works with maintenance under Road name Package No.- MR-N/23-24 Banka-1/01 (Tender ID-125730 & Bid ID - 547340) Year 2023-24 under M/R (3054) Yojna, Block-Shambhuganj, District- Banka, Bihar (hereinafter called the contract) Chief Engineer-2 Rural work department, Bihar Patna Vide Letter No-2456 Encl, Dated 08.08.2023 and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the Routine maintenance of works for Five Years of the Contract Price remedying of any defects therein, at a Construction of cost of Rs. 3159790.00 (Rupees One Crore Thirty One Lakh Fifty Nine Thousand Seven Hundred Ninety Only) & Maintenance of cost Rs. 3776332.00 (Rupees Thirty Seven Lakh Seventy Six Thousand Three Hundred Thirty Two Only) with a Total Amount of Rs. 16936122.00 (Rupees One Crore Sixty Nine Lakh Thirty Six Thousand One Hundred Twenty Two Only) at bidder rate quoted 10.00 % below the estimated cost. Anil Kumar Singh the contractor has deposited FD A/c No.- 17990310060490 Amount Rs. 706000.00, FD A/c No.- 17990310060483 Amount Rs. 847000.00. NOW THIS AGREEMENT WITNESSETH as follows:

महेश कुमार सिंह


Divisional Account Officer
R.W.D. (W) Div. Banka-1


Executive Engineer
R.W.D. Works Division
BANKA-1

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the Contract and undertaking routine maintenance for five years.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the works and the remedying the defects wherein and undertaking routine maintenance for five years, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and be read and construed as part of this Agreement, viz:
 - i) Letter of Acceptance;
 - ii) Notice to proceed with the works;
 - iii) Contractor's Bid;
 - iv) Contract Data;
 - v) Special Conditions of Contract;
 - vi) General Conditions of Contract;
 - vii) Specifications;
 - viii) Drawings;
 - ix) Bill of Quantities; and
 - x) Any other documents listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day any year first before written.

The Common Seal of _____


Divisional Account Officer
R.W.D. (W) Div. Banka-1



Executive Engineer
R.W.D. Works Division
BANKA-1
17/8/23


Was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said _____


In the presence of:

Binding Signature of Employer _____


Divisional Account Officer
R.W.D. (W) Div. Banka-1


Executive Engineer
R.W.D. Works Division
BANKA-1
17/8/23

Binding Signature of Contractor _____



BIHAR RURAL ROADS DEVELOPMENT AGENCY
(GOVERNMENT OF BIHAR)

BID DOCUMENT

FOR

CONSTRUCTION AND MAINTENANCE OF RURAL
ROADS

DISTRICT: Banka

BLOCK: Shambhuganj

Sl. No.	Name of Road	Length In Km	Cost of Const. (Rs. In Lakhs)	Maintenance Cost (Rs. In Lakhs)
Package No.- MR-N/23-24 Banka-1/01				
1.	Mirzapur Kiranpur Road to Patwara tak	1.490	5392292	1470409
2.	Shambhuganj Kaitha PMGSY Road to Sahadevpur	1.484	5046526	1746472
3.	Mirzapur Chutiya to Shyampur Dhaula L045 tak	0.585	2720973	559451
Total			13159790	3776332

Financial Bid
Year 2023-24

Under
M/R Head 3054
MINISTRY OF RURAL DEVELOPMENT
GOVERNMENT OF BIHAR

हमिषा झा 01/2

Divisional Account Officer
R.W.D. (W) Div. Banka-1

Executive Engineer
R.W.D. Works Division
BANKA-1

Contractor's Detail

Agreement No. -
Name of Work - MR-N/23-24 Banka-1/01
Name of Contractor - Anil Kumar Singh
Address - At-Babutola, Anchal+Dist-Banka, Bihar, PIN- 813102
Registration No. - 1190279
Pan - AISPS7033H
GST - 10AISPS7033H1Z4

Bank Account Details :-

Name of Bank -
Account No. -
IFSC Code -
Mobile No. - 7782906600
Email ID - anilkumarsingh20211@gmail.com

★
17/8/23
Executive Engineer
R.W.D. Works Division
BANKA-1

Divisional Account Officer
R.W.D.(W) Div. Banka-1

ममिअ अमय अर

UNDER MR-3054
BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : Mirjapur Kiranpur Road To Patwara Tak

Block : Shambhuganj


District :

Banka

Length : 1.490 km

Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	Hect.	0.30	75573.34	22672.00
2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	Cum	733.80	264.21	193877.30
3	For Grading II Material -Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	cum	19.69	2340.20	46078.54
4	WBM Grading 2 (By Mechanical Means) -Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	Cum	13.50	4610.97	62248.10
5	WBM Grading 3 (By Mechanical Means) -Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	25.31	4432.41	112184.30
6	Prime Coat (Low porosity) -Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	Sqm	337.47	60.80	20518.18

Divisional Account Officer
R.W.D.(W) Div. Banka-1


Executive Engineer
R.W.D. Works Division
BANKA-1


Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
16	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	Each	60.00	1288.76	77325.60
17	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads-Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.				
	At Edge for BT Portion	Sqm	120.00	886.46	106375.20
	At Edge for CC Portion	Sqm	178.00	1005.35	178952.30
18	Providing and fixing of typical MR informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	No.	5.00	11569.78	57848.90
19	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	Rm	30.00	1071.55	32146.50

Divisional Account Officer
R.W.D.(W) Div. Banka-1

[Signature]


[Signature]
Executive Engineer
R.W.D. Works Division
BANKA-1

Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Parapet				
20	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	Sqm	20.16	207.00	4173.12
21	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	20.16	137.83	2778.65
				Total =	4988264.90
				Labour cess @1% =	49882.65
				GST @18% =	897887.68
				Add Seigniorage Fee @ 10% =	55399.21
				Total (A) =	5991434.45
22	5 YEAR ORDINARY MAINTENANCE COST	Quarterly	20	68513.20	1370264.00
				Labour cess @1% =	13702.64
				GST @18% =	246647.52
				Add Seigniorage Fee @ 10% =	3173.74
				Total (B) =	1633787.90
				Grand Total Cost (A+B) =	7625222.34


 29/5/23
 Executive Engineer
 R.W.D. Works Division
 BAIKA 1

Say Rs 76,25,222=00

B.O.Q, (item no. 01 to 22) approved for Rs 76,25,222=00 (Seventy-six lakh twenty five thousand two hundred twenty two)


 31.5.23
 Superintending Engineer
 Rural Works Department
 Works Circle, Bhagalpur

अनुमोदित है