

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, सिकहरना, ढाका।

पत्रांक - 1007...../सिकहरना, ढाका, दिनांक-25.07.2023

सेवा में,

M/S Dhirendra Construction Pvt. Ltd.,
Sri Krishna Nagar, Motihari,
Dist- East Champaran


विषय :- पुनरीक्षित कार्यादेश के संबंध में।

प्रसंग :- अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल-मोतिहारी का
ज्ञापांक-803 (अनु0) दिनांक-18.07.2023

महाशय,

उपर्युक्त विषयक अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल-मोतिहारी का ज्ञापांक-520 दिनांक-31.05.2023 के द्वारा MR-3054 (New Maintenance policy-2018) योजना अन्तर्गत Package No.-MR-N/2022-23/Dhaka/01 (1) Bagha Shekhauna Tola to Lohan Tola Tak (2) GBC Road Bankatwa to Sunderpur via Baluadhanukhi (3) Sikarganj Narulapur to Bheriyahi (4) Ghorasahan Main road to Baya Muhalla under Ghorasahan block का पथ निर्माण कार्य आपको आवंटित हुआ था, जिसका एकरारनामा आपके द्वारा दिनांक-24.12.2022 को किया गया था। अधीक्षण अभियंता के प्रासंगिक पत्र के द्वारा पुनरीक्षित परिमाण विपत्र का तकनोकि स्वीकृति प्राप्त हुआ है। जिसके आलोक में किये गये एकरारनामा के राशि में आवश्यक संशोधन कर पुनरीक्षित कार्यादेश दिया जाता है।

विश्वासभाजन


25.7.23
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सिकहरना, ढाका।

SE, RWD, Motihari, Letter No.-803/ Dated -18.07.2023 MBD No.-21
MBD/2022-23 Has been revised

Name of Contractor :- **M/S Dhirendra Construction Pvt. Ltd.,
Sri Krishna Nagar, Motihari,
Dist- East Champaran**

Name of Work :- **3054(MR) New maintenance Policy-2018**
के अधीन

Sl.No.	Name of the Road
1	Bagha Shekhauna Tola to Lohan Tola Tak
2	GBC Road Bankatwa to Sunderpur via Baluadhanukhi
3	Sikarganj Narulapur to Bheriyahi
4	Ghorasahan Main road to Baya Muhalla under Ghorasahan block

Previous Agreement Value :- Rs. 4,44,59,659.00

Supplementary Agreement Value :- 23,41,117.00 (Rupees twenty Three Lac
Fourty

One Thousand One Hundred
Seventeen)

Performance Security & Add. PS. – (Required Amount)


Submitted By Contractor Rs. (Amount) –

Rate :-

Date of Work Order :-

Revised BOQ Item of Work :- GST

Contract Date of Completion :-
Dhirendra Construction Pvt. Ltd.


Director



INDIA NON JUDICIAL Government of Bihar

e-Stamp

Certificate No: IN-BR-2300516732

Certificate Issue Date: 21-Jul-2023 12:34 PM

GRN No: BHR20230700584231E

Unique Doc Reference: EST-BR-4605-2300003499

Party Name: DHIRENDRA CONSTRUCTION PVT LTD

Purchased by: DHIRENDRA CONSTRUCTION PVT LTD

Purpose: Agreement or Memorandum of an Agreement Article no (05)

Stamp Duty Paid (Rs.): 1000 (One Thousand Only)

Reg. Fee (Rs.): 0 (Zero Only)

LLR & P Fee (Rs.): 0 (Zero Only)

Miscellaneous Fee (Rs.): 0 (Zero Only)

Discore SC (Rs.): 0 (Zero Only)

Total Amount (Rs.): 1000 (One Thousand Only)

Supplementary Agreement

Agreement No..... MBD/ R.W.D. Dhaka/3054(MR)

This agreement, made the _____ day of _____ 20____,

Between Executive Engineer RWD (W) Div., Dhaka of the one part, and M/S
Dhirendra Construction Pvt. Ltd., Sri Krishna Nagar, Motihari,

Dist- East Champaran of the another part. Whereas the Employer is desirous

that the Contractor execute Construction of Package No.-MR-N/2022-

23/Dhaka/01 (1) Bagha Shekhauna Tola to Lohan Tola Tak (2) GBC Road

Bankatwa to Sunderpur via Baluadhanukhi (3) Sikarganj Narulapur to

Bheriyahi (4) Ghorasahan Main road to Baya Muhalla under Ghorasahan

block, Under Package No.-MR-N/2022-23/Dhaka/01 Tender ID:117740 and the

employer has accepted the Bid by the contractor for the execution and completion

of such works and the remedying of any defects therein at a cost of Rupees

23.41.17.00 (Rupees twenty Three Lac Fourty One Thousand One Hundred

IN 2300518883 (Rupees) Only

Statutory Alert:

1. The authenticity of this Stamp certificate should be verified at <https://enibandhan.bihar.gov.in> or using enibandhan Mobile App

Any discrepancy in the details on this Certificate and as available on the website/Mobile App renders it invalid.

2. The onus of checking the legitimacy is on the users of the certificate.

3. In case of any discrepancy please inform the Competent Authority.

Dhirendra Construction Pvt. Ltd.

Director

Executive Engineer

R. W. D. (Works)

Division Dhaka

25.7.23
2107/23

NOW THIS REVISED AGREEMENT WITNESSETH as follows:

1. In this Revised Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
 - i) Letter of Acceptance;
 - ii) Notice to proceed with the works;
 - iii) Contractor's Bid;
 - iv) Contract Data;
 - v) Special Conditions of contract and General Conditions of Contract;
 - vi) Specifications;
 - vii) Drawings;
 - viii) Bill of Quantities; and
 - ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of


_____ was hereunto affixed in the presence of:
Signed, Sealed and Delivered by the said

_____ in the presence of:
Binding Signature of Employer

_____ Binding Signature of Contractor

Dhirendra Construction Pvt. Ltd.


Director


Executive Engineer
R. W. D. (Works)
Division Dhaka
25/07/23

अधीक्षण अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, मोतिहारी

पत्रांक 803 (अनु०) मोतिहारी, दिनांक 18/07/2023

प्रेषक:-

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल मोतिहारी

सेवा में,

कार्य पालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल ढाका

विषय :-

ग्रामीण कार्य विभाग, कार्य प्रमंडल ढाका के अधीन एम0आर0-3054 अन्तर्गत जी0एस0टी0 दर 12 प्रतिशत से 18 प्रतिशत होने के कारण अद्यतन पुनरीक्षित परिमाण विपत्र अनुमोदनोपरान्त वापस करने के सम्बन्ध में।

प्रसंग :-

आपका पत्रांक-834 अनु० दिनांक- 20.06.2023

महाशय,

उपरोक्त विषयक प्रासांगिक पत्र द्वारा प्राप्त ग्रामीण कार्य विभाग, कार्य प्रमंडल ढाका के अधीन जी0एस0टी0 दर 12 प्रतिशत से 18 प्रतिशत होने के कारण अद्यतन पुनरीक्षित परिमाण विपत्र अनुमोदनोपरान्त वापस किया जाता है।

क्र.सं	पथ का नाम/पैकेज संख्या	पुनरीक्षित परिमाण विपत्र की राशि
1	MR-N/2022-23 Dhaka /01	46800776.00

अनु०- यथोक्त।


विश्वासभाजन



अधीक्षण अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, मोतिहारी

Dhirendra Construction Pvt. Ltd.


Director


Executive Engineer
R. W. D. (Works)
Division Dhaka
25/7/23

Revised Abstract of BOQ for Package No.-MR-N/2022-23/Dhaka/01

Rural Works Department, Works Division, Dhaka

49-031
330-157
47-831
34-718

~~Model~~
20.6.23

Superintending Engineer
Rural Works Department
Works Circle, Motihari

Subenzarkir
15.06.23
J.E/Ghorasahan

[Handwritten signatures and dates]

Revised B.O.R. (Due to increase in G.S.T. from 12% to 18%) is approved for Rs. 46800776.00 (Rupees four crore sixty eight lakhs seven hundred seventy six only). For further follow the instructions as per letter No-761 dt 23.03.2023.

Dhirendra Construction Pvt. Ltd.

Debra M. Miller
Director

Superintending Engineer
Rural Works Department
Works Circle, Motihari

COMPARATIVE STATEMENT OF REVISED BOQ

Name of Road- GCB Road Bankatwa To Sunderpur Via Baluadhanukhi
Block- Bankatwa

District- East Champaran

Package No.-MR-N/2022-23/Dhaka/01

Length of Road :- 5.00 KM

Sl.No.	Item Description	As Per Sanctioned Estimate / BOQ on 12 % GST				As Per Revised Estimate / BOQ on 18 % GST			Difference		% (+/-) Amount	Remarks
		Units	Quantity	Estimated Rate	Total Amount Without Taxes	Quantity	Estimated Rate	Total Amount Without Taxes	Quantity	Amount		
1	GCB Road Bankatwa To Sunderpur Via Baluadhanukhi											
2	Schedule-1 Initial Rectification including Surface Renewal:-											
3	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	Hect.	1.00	59726.13	59726.13	1.00	59726.13	59726.13	0.00	0.00	0.00%	
4	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202. (Cement Concrete)	Cum	0.81	560.39	453.92	0.81	560.39	453.92	0.00	0.00	0.00%	
5	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202. (Stone Masonary/Brick Masonary)	Cum	42.21	277.43	11710.32	42.21	277.43	11710.32	0.00	0.00	0.00%	
6	Removing all types of Hume pipes and stacking within a lead of 1000 m including Earthwork and Dismantling of Masonry Works as per Technical Specification Clause 202. (Above 600 mm to 900 mm dia Hume pipe)	Rm	5.00	275.91	1379.55	5.00	275.91	1379.55	0.00	0.00	0.00%	

Approved

[Signature]
Superintending Engineer
Rural Works Department
Works Circle, Motihari

19/06/23
S.E

19/06/23
AE

NOV
15/6/23
AE

20/6/23
EC

Dhirendra Construction Pvt. Ltd.
[Signature]
Director

7	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	Cum	2676.00	250.88	671354.88	2676.00	250.88	671354.88	0.00	0.00	0.00%
8	For Grading II Material-Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	cum	288.87	2781.69	803546.79	288.87	2781.69	803546.79	0.00	0.00	0.00%
9	WBM Grading 2 (By Mechanical Means) - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	Cum	185.76	5656.19	1050693.85	185.76	5656.19	1050693.85	0.00	0.00	0.00%
10	WBM Grading 3 (By Mechanical Means) - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	351.60	5462.45	1920597.42	351.60	5462.45	1920597.42	0.00	0.00	0.00%
11	Prime Coat (Low porosity)-Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	Sqm	3000.40	59.60	178823.84	3000.40	59.60	178823.84	0.00	0.00	0.00%

APPROVED

Superintending Engineer
Rural Works Department
Works Circle, Motihari

15/06/23
JTC

15/06/23
AB


15/06/23
AB

20.6.23
ET

Dhirendra Construction Pvt. Ltd.

Director

12	Patch work over WBM using Mix seal surface for bituminous and Existing GG Pavement- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509.	Sqm	3030.40	274.29	831208.42	3030.40	274.29	831208.42	0.00	0.00	0.00%
13	Tack Coat -Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and elened with hydrioc broom as per technical specification clause 508	Sqm	15150.40	20.28	307250.11	15150.40	20.28	307250.11	0.00	0.00	0.00%
14	Semi-Dense Bituminous Concrete -Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	Cum	303.00	14459.79	4381316.37	303.00	14459.79	4381316.37	0.00	0.00	0.00%


 Superintending Engineer
 Rural Works Department
 Works Circle, Motihari


15/06/23
 J.E

15/06/23
 J.E


15/6/23
 AB

20.6.23
 EE

Dhirendra Construction Pvt. Ltd.


 Director

15	Cement Concrete Pavement -Construction of un-reinforced plain cement thickness as per design , over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm , mixed in a concrete of not less than 0.2cum capacity and appropriate weigh batcher using approved mix design ,laid in approved fixed side formwork (steel channel ,laying and fixing of 125 micron thick plythene film ,wedges ,steel plates including levelling the formwork as per drawing) spreading the concrete with shovels , rakes , compacted using needle , screed and plate vibrators and finished in continuous operation including provision of contraction and expansion , construction joints ,applying debonding strips , primer , sealant , dowel bars , near approaches to bridge/ culvert and construction joints, admixtures as approved , curing of concrete slab for 14 days curing compound (where specified) and water finishing to lines and grade as per drawing and	Cum	1090.80	9191.53	10026120.92	1090.80	9191.53	10026120.92	0.00	0.00	0.00%
16	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing , etc as per drawing and technical specification clause 1703.								0.00	0.00	0.00%
17	i) 5th km stone	No.	1.00	5798.99	5798.99	1.00	5798.99	5798.99	0.00	0.00	0.00%
18	ii) Km stone	No.	5.00	2981.83	14909.15	5.00	2981.83	14909.15	0.00	0.00	0.00%
19	iii) 200 m stone	No.	20.00	813.40	16268.00	20.00	813.40	16268.00	0.00	0.00	0.00%
20	Direction and Place Identification signs with size more than 0.9 sqm size board- Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	Sqm	15.36	15639.44	240221.80	15.36	15639.44	240221.80	0.00	0.00	0.00%

Approved

 Superintending Engineer
 Rural Works Department
 Works Circle, Motihari

15/06/23
 JE

15/06/23
 AB

15/06/23
 AB

20.6.23
 EE

Dhirendra Construction Pvt. Ltd.


 Director

21	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801								0.00	0.00	0.00%
22	600 mm equilateral & triangle	No.	41.00	4526.63	185591.83	41.00	4526.63	185591.83	0.00	0.00	0.00%
23	600 mm circular	No.	2.00	4555.29	9110.58	2.00	4555.29	9110.58	0.00	0.00	0.00%
24	600 mm x 450 mm rectangular	No.	10.00	4402.44	44024.40	10.00	4402.44	44024.40	0.00	0.00	0.00%
25	Boundary Pillar/Guard Post-Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	Nos	96.00	754.08	72391.68	96.00	754.08	72391.68	0.00	0.00	0.00%
26	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	in height per	1056.00	0.61	644.16	1056.00	0.61	644.16	0.00	0.00	0.00%
27	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	Each	320.00	1035.01	331203.20	320.00	1035.01	331203.20	0.00	0.00	0.00%
28	Half Brick Circular Tree Guard, in 2nd Class Brick, Internal Diameter 1.25 Metres, and Height 1.2 Metres, above ground and 0.20 metre below ground, bottom two courses laid dry and top three courses in cement mortar 1:6 (1cement 6 sand) and the intermediate courses being in dry honey comb masonry, as per design complete	Each	320.00	1986.03	635529.60	320.00	1986.03	635529.60	0.00	0.00	0.00%

15/06/23
JE

15/06/23
AB


15/6/23
AB

20.6.23
EC

Dhirendra Construction Pvt. Ltd.

Director

29	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.								0.00	0.00	0.00%
30	At Edge for BT Portion	Sqm	640.00	823.74	527193.60	640.00	823.74	527193.60	0.00	0.00	0.00%
31	At Edge for CC Portion	Sqm	360.00	925.46	333165.60	360.00	925.46	333165.60	0.00	0.00	0.00%
32	Providing and fixing of typical MR informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	No.	5.00	10956.06	54780.30	5.00	10956.06	54780.30	0.00	0.00	0.00%
33	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	Cum	15.66	336.86	5275.23	15.66	336.86	5275.23	0.00	0.00	0.00%
34	Providing M15 (PCC 1:2.5:5) as levelling course in foundation :- Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	Cum	2.85	7537.75	21482.59	2.85	7537.75	21482.59	0.00	0.00	0.00%
35	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 (M20)	Cum	15.17	8472.23	128523.73	15.17	8472.23	128523.73	0.00	0.00	0.00%

Approved

 Superintending Engineer
 Rural Works Department
 Works Circle, Motihari


15/04/23
 JE

17/06/23
 JE

15/6/23
 AG

20/6/23
 EC

Dhirendra Construction Pvt. Ltd.


 Director

36	Providing and laying RCC pipe NP-3 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106 (600 mm Dia)	Rm	7.50	3141.76	23563.20	7.50	3141.76	23563.20	0.00	0.00	0.00%
37	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	12.48	114.73	1431.83	12.48	114.73	1431.83	0.00	0.00	0.00%
38	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	Rm	22.50	994.74	22381.65	22.50	994.74	22381.65	0.00	0.00	0.00%
39	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	Cum	14.40	6954.86	100149.98	14.40	6954.86	100149.98	0.00	0.00	0.00%
40	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	Sqm	100.80	225.20	22700.16	100.80	225.20	22700.16	0.00	0.00	0.00%
41	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	Sqm	120.96	225.20	27240.19	120.96	225.20	27240.19	0.00	0.00	0.00%
42	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	221.76	114.73	25442.52	221.76	114.73	25442.52	0.00	0.00	0.00%
43	Total Construction cost Excluding all Taxes				23093206.49			23093206.49	0.00	0.00	0.00%
44	Labour cess @ 1 %	RS	1.00	230932.06	230932.06	1.00	230932.06	230932.06	0.00	0.00	0.00%
45	GST @ 12 %/18%	RS	1.00	2771184.78	2771184.78	1.00		4156777.17	0.00	1385592.39	50.00%
46	Add Seigniorage Fee @ 10%	RS	1.00	247701.65	247701.65	1.00	247701.65	247701.65	0.00	0.00	0.00%

Approved

[Signature]

Superintending Engineer
Rural Works Department
Works Circle, Motihari

15/06/23
JE

15/06/23
AE

15/06/23
AE

20/6/23
EC

Dhirendra Construction Pvt. Ltd.

[Signature]
Director

47	TOTAL CONSTRUCTION COST INCLUDING ALL TAXES				26343024.98			27728617.37	8.00	1385592.39	5.26%	
48	less 0.40% Below as per Agreement (-)				105372.10			110914.47	0.00	5542.37	5.26%	
49	Total Construction				26237652.88			27617702.90	0.00	1380050.02	5.26%	
50	Schedule - 2 :-								0.00	0.00		
51	Five Year Ordinary Maintenance in GCB Road Bankatwa To Sunderpur Via Baluadhanukhi	Quarterly	20.00	249211.84	4984236.80	20.00	249211.84	4984236.80	0.00	0.00	0.00%	
52	Labour cess @1 %	RS	1.00	49842.37	49842.37	1.00	49842.37	49842.37	0.00	0.00	0.00%	
53	GST @12 %/18%	RS	1.00	598108.42	598108.42	1.00		897162.62	0.00	299054.20	50.00%	
54	Add Seigniorage Fee @ 10%	RS	1.00	14268.81	14268.81	1.00	14268.81	14268.81	0.00	0.00	0.00%	
55	TOTAL Maintenance COST INCLUDING ALL TAXES				5646456.40			5945510.60	0.00	299054.20	5.30%	
56	less 0.40% Below as per Agreement (-)							23782.04	0.00	1196.21	5.30%	
57	Total Maintenance				5623870.57			5921728.56	0.00	297857.99	5.30%	
58	COST OF PROJECT IN RS. (A+B)				31861523.45			33539431.46	0.00	1677908.01	5.27%	

Superintending Engineer
Rural Works Department
Works Circle, Motihari

15/06/23
J.E

15/06/23
A.E

15/06/23
A.B

20.6.23
E.C

Dhirendra Construction Pvt. Ltd.

Director