



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT

YEAR (2022 - 2023)

T-S COPY

|                                           |                                                |
|-------------------------------------------|------------------------------------------------|
| STATE                                     | BHAR                                           |
| DISTRICT                                  | Aurangabad                                     |
| BLOCK                                     | Nabinagar                                      |
| NAME OF ROAD                              | Akari Mahadalit Tola Ke Nala Per Puliya Nirman |
| TOTAL LENGTH OF Culvert                   | 4.00 M (1x4.0 M x 3.0 M)                       |
| TOTAL COST OF CULVERT CONSTRUCTION        | Rs. 38.557 Lacs                                |
| TOTAL COST OF APPROACH & DIVERSION        | Rs. 1.821 Lacs                                 |
| TOTAL PROJECT COST INCLUDING GST AND L.C. | Rs. 49.480 Lacs                                |

SUBMITTED BY:  
EXECUTIVE ENGINEER  
RWD (w) DIVISION, AURANGABAD  
AURANGABAD

पत्रांक- 2127

प्रेषक,

जिला पदाधिकारी,  
औरंगाबाद।

सेवा में,

सचिव,  
ग्रामीण कार्य विभाग,  
बिहार, पटना।

औरंगाबाद, दिनांक 27/6/23

विषय :- Emergent work के अन्तर्गत प्रखण्ड नवीनगर के पंचायत सोरी ग्राम अकड़ी महादलित टोला के नाला पर पुलिया निर्माण यथाशीघ्र कराने के संबंध में।


महाराज,

उपर्युक्त विषय के संबंध में कहना है कि प्रखण्ड नवीनगर के पंचायत सोरी ग्राम अकड़ी महादलित टोला के नाला पर पुलिया को आपातकालीन योजना में शामिल किया जाना अत्यावश्यक है। उक्त जर्जर पुलिया ध्वस्त हो गया है एवं आवागमन पूर्णतः बाधित है। उक्त पुलिया L028 माली चरण पथ से टोना थ को जोड़ती है। उक्त जर्जर पुलिया ध्वस्त हो जाने के कारण ग्राम टोना, खड़ग परसा, अकड़ी महादलित टोला, को प्रत्यक्ष रूप से सम्पर्कता भंग हो गयी है। तथापि ग्राम सिन्दुरिया, शाहपुर, धनहारा, गम्हारिया, रघु गहा को अप्रत्यक्ष रूप से सम्पर्कता भी काफी प्रभावित हुई है। ग्रामीणों द्वारा बार-बार मोबाईल पर उक्त लिया के बनाने के संबंध में आग्रह किया जा रहा है।

अतः उक्त पुलिया को आपातकालीन योजना में चयनित करने हेतु की कृपा की जाय।

सूचनार्थ एवं आवश्यक कार्रवाई हेतु समर्पित।

विश्वासभाजन

  
27/6/23  
कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमण्डल, औरंगाबाद।

  
जिला पदाधिकारी,  
औरंगाबाद।



DMFT

YEAR (2022 - 2023)

GENERAL ABSTRACT OF COST

Block:--Nabinagar


District:--Aurangabad


CNCPL SL No. :--0


Length of Culvert:-- 4.000 M

Name of Road:-- Akari Mahadalit Tola Ke Nala Per Puliya Nirman

| SL. No. | Item of Work                  | Amount             |
|---------|-------------------------------|--------------------|
| A       | TOTAL COST OF CONSTRUCTION    | 48.391 Lacs        |
| I       | CONTINGENCY 2.25 %            | 1.089 Lacs         |
|         | Sub Total=                    | 49.480 Lacs        |
|         | <b>TOTAL cost of project=</b> | <b>49.480 Lacs</b> |

  
18/7/23  
Junior Engineer  
RWD (w)Section ,  
Nabinagar


  
18/07/23  
Asstt. Engineer  
RWD (w)Sub Division , Nabinagar

  
18.7.23  
Executive Engineer  
RWD (w) Division,  
Aurangabad


### SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD : Akari Mahadalit Tola Ke Nala Per Puliya Nirman  
DISTRICT Aurangabad  
BLOCK Nabinagar  
LENGTH OF CULVERT (in m) 4.00 M, 2 No  
CD STRUCTURES

| Sl. No. | DESCRIPTION                                                              | AMOUNT (LACS) |
|---------|--------------------------------------------------------------------------|---------------|
| 1       | EARTHWORK                                                                | 0.342         |
| 2       | GSB                                                                      | 0.574         |
| 3       | WBM GRADE III                                                            | 0.168         |
| 4       | CC PAVEMENT                                                              | 0.582         |
| 6       | ROAD FURNITURES , KM STONES , TRAFFIC & DIRECTION SIGN, MMGSY LOGO       | 0.154         |
|         | SUB TOTAL OF PAVEMENT COST IN LACS =                                     | 1.821         |
|         | CROSS DRAINAGE STRUCTURES                                                |               |
| 7       | RCC SLAB CULVERT (1x4.0x3.0 m)                                           | 9.600         |
| 8       | RCC SLAB CULVERT (1x4.0x3.0 m)                                           | 28.957        |
|         | SUB TOTAL OF CD STRUCTURES COST IN LACS =                                | 38.557        |
|         | Sub Total :-                                                             | 40.378        |
|         | 18% GST on Total Amount :-                                               | 7.268         |
|         | 1% Lab Cess :-                                                           | 0.404         |
|         | Seigniorage Fee @ 10%                                                    | 0.341         |
|         | Total Constriction Cost (including GST and Labour Cess) (A) :-           | 48.391        |
|         | Add Contingency Charges @ 2.25 % (IN LACS) on Cont. Cost (C) :-          | 1.089         |
|         | TOTAL COST OF PROJECT IN LACS(including GST 18% & 1% Lab Cess)(A+B+C) :- | 49.480        |

  
18/7/23  
Junior Engineer  
RWD (w)Section , Nabinagar

  
18/07/23  
Assistant Engineer  
RWD (w)Sub Division , Nabinagar

  
18.7.23  
Executive Engineer  
RWD (w) Division,  
Aurangabad

Cost Estimate for Road Work

| Sl.No.                  | SDB<br>SL.NO | MORD<br>Ref.No | Description                                                                                                                                                                                                                                                                                                                                                                                                                                     |  |  |  |  | Unit             | NOS  | LENGTH | WIDTH | HEIGHT | QUANTITY | RATE   | AMOUNT<br>(In Rs.) |        |        |           |
|-------------------------|--------------|----------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|------------------|------|--------|-------|--------|----------|--------|--------------------|--------|--------|-----------|
| SUB HEAD : EARTHWORK    |              |                |                                                                                                                                                                                                                                                                                                                                                                                                                                                 |  |  |  |  |                  |      |        |       |        |          |        |                    |        |        |           |
| 1                       | 3.4          | 301.5          | Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a <u>lead upto 1000 m &amp; 100 m</u> as per Technical Specification Clause 301.5 . (Including Royalty & Labour Cess).                                                                                             |  |  |  |  |                  |      |        |       |        |          |        |                    |        |        |           |
| 2                       | 3.14         | 303.1          | For 1000 m lead (For Diversion)<br><b>Construction of Subgrade and Earthen Shoulders</b><br>Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess). |  |  |  |  |                  |      |        |       |        |          |        |                    | 120.00 | 259.42 | 31,130.40 |
|                         |              |                | ii) Earth shoulder                                                                                                                                                                                                                                                                                                                                                                                                                              |  |  |  |  |                  |      |        |       |        |          |        |                    |        |        |           |
|                         |              |                | Adjacent to PCC (PCC Portion)                                                                                                                                                                                                                                                                                                                                                                                                                   |  |  |  |  | cum              | 2.00 | 12.00  | 1.125 | 0.160  | 4.32     |        |                    |        |        |           |
|                         |              |                | Adjacent to WBM-GR III (PCC Portion)                                                                                                                                                                                                                                                                                                                                                                                                            |  |  |  |  | cum              | 2.00 | 12.00  | 1.125 | 0.075  | 2.03     |        |                    |        |        |           |
|                         |              |                | Adjacent to GSB (PCC Portion)                                                                                                                                                                                                                                                                                                                                                                                                                   |  |  |  |  | cum              | 2.00 | 12.00  | 1.125 | 0.200  | 5.40     |        |                    |        |        |           |
|                         |              |                | For 1000 m lead @ 100 %                                                                                                                                                                                                                                                                                                                                                                                                                         |  |  |  |  | Total Quantity = |      |        |       |        | 11.75    | 262.95 | 3,089.66           |        |        |           |
| B) SUB TOTAL OF CRUST = |              |                |                                                                                                                                                                                                                                                                                                                                                                                                                                                 |  |  |  |  |                  |      |        |       |        |          |        | 34,220.06          |        |        |           |



# Cost Estimate for Road Work

| Sl. No.                     | SDB<br>SL NO | MORD<br>Ref No | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Unit | NO.  | LENGTH | WIDTH | HEIGHT | QUANTITY | DATE                                 | AMOUNT<br>(Rs.)    |
|-----------------------------|--------------|----------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|--------|-------|--------|----------|--------------------------------------|--------------------|
| <b>SUB HEAD : DIVERSION</b> |              |                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      |      |        |       |        |          |                                      |                    |
| 9                           | 4.1          | 401            | Granular Sub-base with Well Graded Material (Table 400.1)<br>( By mix in place method )<br><b>For Grading I Material (With Coarse sand Screening)</b><br>Construction of granular sub base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |      |        |       |        |          |                                      |                    |
|                             |              |                | (For Diversion)<br>GSB in Approach                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Cum  | 1.00 | 12.00  | 4.00  | 0.200  | 9.60     |                                      |                    |
|                             |              |                | Net GSB Qty. Required form Grading I Material                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | cum  | 1.00 | 12.00  | 3.750 | 0.200  | 9.00     |                                      |                    |
| 10                          | 4.7<br>(3-A) | 405            | <b>Water Bound Macadam with Stone Screenings</b><br><b>WBM Grading 3 (By Mechanical Means)</b><br>Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |      |      |        |       |        | 18.60    | 3,086.81                             | 57,414.67          |
|                             |              |                | WBM Gr-III in Brick Soling / Earthen Length                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Cum  | 1.00 | 12.00  | 3.75  | 0.075  | 3.38     | 4,984.09                             | 16,846.22          |
| 11                          | 6.4          | 1500           | <b>Cement Concrete Pavement</b><br>Construction of un-reinforced expansion and contraction joint only, plain cement thickness as per design, over a prepared sub base with 4:3 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete of not less than 0.20cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork ( steel channel laying and fixing of 125 micron thick plythene film, wedges, steel plates including levelling the formwork as per drawing ) spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/ culvert and construction joints, admixtures as approved, curing of concrete slab for 14 days curing compound (where specified) and water finishing to lines and grade as per drawing and Technical specification clause 1501. |      |      |        |       |        |          |                                      |                    |
|                             |              |                | Net Qty                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | cum  | 1.00 | 12.00  | 3.75  | 0.160  | 7.20     | 8,086.53                             | 58,223.02          |
|                             |              |                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      |      |        |       |        |          | <b>E) SUB TOTAL OF CC PAVEMENT =</b> | <b>1,32,483.91</b> |



Providing and fixing of typical MMGSV informative sign board with Logo as per MORD specifications and drawing. Three MS Plates of 16 mm thick, top and middle plate duly welded with MS flat iron. 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1

|                                                |      | Providing and Fixing 'Logo' of Project As per Drawing                                                                                                                                                                                 | No.  | 1.00 |           |           |
|------------------------------------------------|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|-----------|-----------|
|                                                |      | Total=                                                                                                                                                                                                                                | 1.00 |      |           |           |
| 10                                             | 10.1 | 1700 Boundary Pillar/Guard Post                                                                                                                                                                                                       |      |      |           |           |
|                                                |      | Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704 | No   | 7.00 | 674.41    | 4720.87   |
| TOTAL COST OF PAVEMENT IN RS. (A+B+C+D+E+F+G)= |      |                                                                                                                                                                                                                                       |      |      | 10,678.12 | 15,098.99 |

18/7/23

Junior Engineer  
RWD (w)Section , Nabinagar

18/8/23

Assistant Engineer  
RWD (w)Sub Division , Nabinagar

18/8/23

Executive Engineer  
RWD (w) Division, Aurangabad

SUB TOTAL 1,82,10,296

| Sl. No.                                            | SDB Sl. No. | MORD Ref. No. | Description                                                                                                                                                                                                                                                                                                              | Unit | Quantity | Rate   | Amount (In Rs.) | Total Material Required | Material Amount | Add Seigniorage Fee 10% |
|----------------------------------------------------|-------------|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|--------|-----------------|-------------------------|-----------------|-------------------------|
| <b>EARTHWORK</b>                                   |             |               |                                                                                                                                                                                                                                                                                                                          |      |          |        |                 |                         |                 |                         |
| 1                                                  | 3.14        | 303.1         | <b>Construction of Subgrade and Earthen Shoulders</b>                                                                                                                                                                                                                                                                    |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.                 |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | <b>Unit = cum</b>                                                                                                                                                                                                                                                                                                        |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | Taking output = 100 cum                                                                                                                                                                                                                                                                                                  |      |          |        |                 |                         |                 |                         |
|                                                    |             | a)            | <b>Material</b>                                                                                                                                                                                                                                                                                                          |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | Compensation For Earth Taken From Private Land                                                                                                                                                                                                                                                                           | Cum  | 100      | 35.01  | 3,501.00        |                         |                 |                         |
|                                                    |             |               | Cost for 100 cum = a                                                                                                                                                                                                                                                                                                     |      |          |        | 3,501.00        |                         |                 |                         |
|                                                    |             |               | Rate Per Cum = (a)/100=                                                                                                                                                                                                                                                                                                  | Cum  |          |        | 35.01           |                         |                 |                         |
|                                                    |             |               | <b>Total Cost =</b>                                                                                                                                                                                                                                                                                                      | Cum  |          |        | 35.01           | 11.75                   | 411.37          | 41.14                   |
| <b>PAVEMENT LAYERS - GSB, WBM-II &amp; WBM-III</b> |             |               |                                                                                                                                                                                                                                                                                                                          |      |          |        |                 |                         |                 |                         |
| 2                                                  | 4.1         | 401           | <b>Granular Sub-base with Well Graded Material (Table 400.1)</b>                                                                                                                                                                                                                                                         |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | (By mix in place method)                                                                                                                                                                                                                                                                                                 |      |          |        |                 |                         |                 |                         |
|                                                    |             | (i)           | <b>For Grading I Material (With Coarse Sand Screening)</b>                                                                                                                                                                                                                                                               |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | <b>For Grading I Material (With Coarse Sand Screening)</b>                                                                                                                                                                                                                                                               |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | Unit = cum                                                                                                                                                                                                                                                                                                               |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | Taking output = 300 cum                                                                                                                                                                                                                                                                                                  |      |          |        |                 |                         |                 |                         |
|                                                    |             | a)            | <b>Material</b>                                                                                                                                                                                                                                                                                                          |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | Coarse graded granular sub-base material as per Table 400.2                                                                                                                                                                                                                                                              |      |          |        |                 |                         |                 |                         |
|                                                    |             |               | 53 mm to 9.5 mm @ 50 per cent                                                                                                                                                                                                                                                                                            | Cum  | 180.00   | 915.67 | 1,64,820.60     |                         |                 |                         |
|                                                    |             |               | 9.5 mm to 2.36 mm @ 20 per cent                                                                                                                                                                                                                                                                                          | Cum  | 72.00    | 424.21 | 30,543.120      |                         |                 |                         |
|                                                    |             |               | 2.36 mm below @ 30 per cent (Coarse Sand Screening)                                                                                                                                                                                                                                                                      | Cum  | 108.00   | 262.42 | 28,341.360      |                         |                 |                         |
|                                                    |             |               | Cost for 300 cum = a                                                                                                                                                                                                                                                                                                     |      |          |        | 2,23,705.08     |                         |                 |                         |
|                                                    |             |               | Rate Per Cum = (a)/300=                                                                                                                                                                                                                                                                                                  | Cum  |          |        | 745.68          |                         |                 |                         |
|                                                    |             |               | <b>Total Cost =</b>                                                                                                                                                                                                                                                                                                      | Cum  |          |        | 745.68          | 18.60                   | 13,869.71       | 1,386.97                |



| Sl. No. | SDB Sl. No. | MORD Ref. No. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Unit | Quantity | Rate     | Amount (In Rs.) | Total Material Required | Material Amount | Add. Seigniorage Fee 10% |
|---------|-------------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|----------|-----------------|-------------------------|-----------------|--------------------------|
| 3       | 4.7         | 405           | Water Bound Macadam with Stone Screening Type "B" Gr- III                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |          |                 |                         |                 |                          |
|         | (3-A)       |               | WBM Grading 3 (Mechanical means)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |      |          |          |                 |                         |                 |                          |
|         |             |               | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |          |          |                 |                         |                 |                          |
|         |             |               | <b>For WBM III Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      |          |          |                 |                         |                 |                          |
|         |             |               | Unit = cum                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |          |          |                 |                         |                 |                          |
|         |             |               | Taking output = 360 cum                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |          |          |                 |                         |                 |                          |
|         | a)          |               | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |          |                 |                         |                 |                          |
|         |             |               | <b>Aggregate</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |      |          |          |                 |                         |                 |                          |
|         |             |               | Grading 3 53 mm to 22.4 mm @ 0.91 cum per 10 sqm for compacted thickness of 75 mm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Cum  | 435.60   | 1,080.50 | 4,70,665.80     |                         |                 |                          |
|         |             |               | <b>Stone Screening</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |          |          |                 |                         |                 |                          |
|         |             |               | Type B 11.2 mm for Grading 3 @ 0.18 cum per 10 sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Cum  | 86.40    | 424.21   | 36,651.744      |                         |                 |                          |
|         |             |               | Cost for 360 cum = a                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |      |          |          | 5,07,317.54     |                         |                 |                          |
|         |             |               | Rate Per Cum = (a)/360 =                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Cum  |          |          | 1,409.22        |                         |                 |                          |
|         |             |               | <b>Total Cost =</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Cum  |          |          | 1,409.22        | 388                     | 4763.15         | 4763.15                  |
|         |             |               | <b>SUB HEAD : CC PAVEMENT</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |          |          |                 |                         |                 |                          |
| 4       | 6.4         | 1500          | Cement Concrete Pavement                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |          |          |                 |                         |                 |                          |
|         |             |               | Construction of un-reinforced expansion and construction joint only, plain cement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete of not less than 0.2cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork ( steel channel, laying and fixing of 125 micron thick plythene film, wedges, steel plates including levelling the formwork as per drawing ) spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/ culvert and construction joints, admixtures as approved, curing of concrete slab for 14 days curing compound (where specified) and water finishing to lines and grade as per drawing and Technical specification clause 1501. |      |          |          |                 |                         |                 |                          |
|         |             |               | Unit = cum                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |          |          |                 |                         |                 |                          |



| Sl. No. | SDB Sl. No | MORD Ref.No | Description                                                                                                                           | Unit | Quantity | Rate   | Amount (In Rs.) | Total Material Required | Material Amount | Add Seigniorage Fee 10% |
|---------|------------|-------------|---------------------------------------------------------------------------------------------------------------------------------------|------|----------|--------|-----------------|-------------------------|-----------------|-------------------------|
|         |            |             | Taking output = 75 cum (172.50 t)                                                                                                     |      |          |        |                 |                         |                 |                         |
|         |            | a)          | Material                                                                                                                              |      |          |        |                 |                         |                 |                         |
|         |            |             | Aggregate                                                                                                                             |      |          |        |                 |                         |                 |                         |
|         |            |             | Crushed stone coarse aggregates, grading will be as per Clause 1501.2.4.1 (Table 1500.1) of specifications @ 0.90 cum/cum of concrete | Cum  | 67.50    | 886.00 | 59,805.00       |                         |                 |                         |
|         |            |             | Sand as per IS:383 and conforming to Clause 1500.2.4.2 @ 0.45 cum/cum of concrete                                                     | Cum  | 33.75    | 494.00 | 16,672.50       |                         |                 |                         |
|         |            |             | Cost for 75 cum = a                                                                                                                   |      |          |        | 76,477.50       |                         |                 |                         |
|         |            |             | Rate Per Cum = (a)/75 =                                                                                                               | Cum  |          |        | 1,019.70        |                         |                 |                         |
|         |            |             | Total Cost =                                                                                                                          | Cum  |          |        | 1,019.70        | 7.20                    | 7,341.84        | 734.18                  |

|   |      |            |                                                                                                                                                         |     |      |          |          |        |             |           |
|---|------|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|----------|----------|--------|-------------|-----------|
|   |      |            | ANALYSIS OF CULVERT/ MINOR BRIDGES ITEMS                                                                                                                |     |      |          |          |        |             |           |
| 5 | 11.4 | 800 & 1200 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 |     |      |          |          |        |             |           |
|   |      | (ii)       | P.C.C Grade M 15 In Foundation                                                                                                                          |     |      |          |          |        |             |           |
|   |      | (i)        | Nominal mix (1:2.5:5)                                                                                                                                   |     |      |          |          |        |             |           |
|   |      |            | Unit = Cum                                                                                                                                              |     |      |          |          |        |             |           |
|   |      | a)         | Material                                                                                                                                                |     |      |          |          |        |             |           |
|   |      |            | Coarse sand                                                                                                                                             | Cum | 0.48 | 494.00   | 237.12   |        |             |           |
|   |      |            | 40 mm aggregate                                                                                                                                         | Cum | 0.48 | 975.00   | 468.00   |        |             |           |
|   |      |            | 20 mm aggregate                                                                                                                                         | Cum | 0.24 | 1,186.00 | 284.64   |        |             |           |
|   |      |            | 10 mm aggregate                                                                                                                                         | Cum | 0.08 | 586.00   | 46.88    |        |             |           |
|   |      |            | Rate Per Cum = (a) =                                                                                                                                    | Cum |      |          | 1,036.64 |        |             |           |
|   |      |            | Total Cost =                                                                                                                                            | Cum |      |          | 1,036.64 | 165.11 | 1,71,163.91 | 17,116.39 |
| 6 |      | (iii)      | P.C.C Grade M 20 In Foundation                                                                                                                          |     |      |          |          |        |             |           |
|   |      | (i)        | Nominal mix (1:2:4)                                                                                                                                     |     |      |          |          |        |             |           |
|   |      |            | Unit = Cum                                                                                                                                              |     |      |          |          |        |             |           |
|   |      | a)         | Material                                                                                                                                                |     |      |          |          |        |             |           |




| Description                                                         | Unit | Quantity | Rate    | Amount<br>(In Rs.) | Total<br>Material<br>Required | Material<br>Amount | Seigniorage |
|---------------------------------------------------------------------|------|----------|---------|--------------------|-------------------------------|--------------------|-------------|
| Concrete                                                            | Cum  | 1.45     | 154.50  | 222.93             |                               |                    |             |
| 40 mm aggregate                                                     | Cum  | 1.06     | 325.50  | 351.00             |                               |                    |             |
| 20 mm aggregate                                                     | Cum  | 2.36     | 1186.00 | 426.96             |                               |                    |             |
| 10 mm aggregate                                                     | Cum  | 1.19     | 586.00  | 105.48             |                               |                    |             |
| Rate Per Cum = (a) =                                                |      |          |         | 1105.74            |                               |                    |             |
| Total Cost =                                                        | Cum  |          |         | 1105.74            | 105.29                        | 116.47             | 105.29      |
| (ii) P.C.C Grade M 20 In Substructure                               |      |          |         |                    |                               |                    |             |
| (i) Nominal mix (1:2:4)                                             |      |          |         |                    |                               |                    |             |
| Unit = Cum                                                          |      |          |         |                    |                               |                    |             |
| a) Material                                                         |      |          |         |                    |                               |                    |             |
| Grassy sand                                                         | Cum  | 0.45     | 494.00  | 222.30             |                               |                    |             |
| 40 mm aggregate                                                     | Cum  | 0.36     | 975.00  | 351.00             |                               |                    |             |
| 20 mm aggregate                                                     | Cum  | 0.36     | 1186.00 | 426.96             |                               |                    |             |
| 10 mm aggregate                                                     | Cum  | 0.18     | 586.00  | 105.48             |                               |                    |             |
| Rate Per Cum = (a) =                                                |      |          |         | 1105.74            |                               |                    |             |
| Total Cost =                                                        | Cum  |          |         | 1105.74            | 10.43                         | 126.41             | 10.43       |
| (iv) R.C.C Grade M 25 In Substructure                               |      |          |         |                    |                               |                    |             |
| Unit = Cum                                                          |      |          |         |                    |                               |                    |             |
| a) Material                                                         |      |          |         |                    |                               |                    |             |
| Coarse sand                                                         | Cum  | 0.45     | 494.00  | 222.30             |                               |                    |             |
| 20 mm aggregate                                                     | Cum  | 0.54     | 1186.00 | 640.44             |                               |                    |             |
| 10 mm aggregate                                                     | Cum  | 0.36     | 586.00  | 210.96             |                               |                    |             |
| Rate Per Cum = (a) =                                                |      |          |         | 1073.70            |                               |                    |             |
| Total Cost =                                                        | Cum  |          |         | 1073.70            | 13.79                         | 14,808.20          | 10.43       |
| Total Construction Cost (With 10% Seigniorage Fee) :-               |      |          |         |                    |                               |                    | 36,127.92   |
| Total Construction + Maintenance Cost (With 10% Seigniorage Fee) :- |      |          |         |                    |                               |                    | 36,127.92   |

  
 Date: 18/03/23  
 By: [Signature]



18/03/23  
 Checked: [Signature]  
 By: [Signature]

**Akari Mahadalit Tola Ke Nala Per Puliya Nirman(DMFT)**  
(2022-2023)


**Quantities & Cost Estimate for R.C.C. Slab Culvert - 1 No. x 2.00 m Span x 2.50 m Vent Height**



## Sectional Elevation



**Section of Return Wall**





**Quantities & Cost Estimate for R.C.C. Slab Culvert - 1 No. x 2.00 m Span x 2.50 m Vent Height**

| Sl No | SOR No. | Description of Items                                                                                                                                                                                                                                                                                                                      | Total Qty                   | Unit              | Rate (₹)        | Amount (₹)         |
|-------|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------|-------------------|-----------------|--------------------|
| 1     | 2       | 3                                                                                                                                                                                                                                                                                                                                         | 4                           | 5                 | 6               | 7                  |
| 1     | 11.1    | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. |                             |                   |                 |                    |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                  | 2 x 7.600 x 2.467 x 1.600 = | 59.997            |                 |                    |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                               | 4 x 1.433 x 2.263 x 1.600 = | 20.754            |                 |                    |
|       |         | Floor Under Deck Slab                                                                                                                                                                                                                                                                                                                     | 1 x 6.200 x 0.400 x 0.250 = | 0.620             |                 |                    |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                              |                             | <b>81.371 cum</b> | <b>410.66</b>   | <b>33,415.81</b>   |
| 2     | 11.2    | Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108.                                                                                                                                                                                                                                               |                             |                   |                 |                    |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                  | 2 x 7.600 x 2.467 x 0.000 = | 0                 |                 |                    |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                               | 4 x 1.433 x 2.263 x 0.000 = | 0                 |                 |                    |
|       |         | Floor Under Deck Slab                                                                                                                                                                                                                                                                                                                     | 1 x 6.200 x 1.629 x 0.100 = | 1.01              |                 |                    |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                              |                             | <b>1.010 cum</b>  | <b>699.49</b>   | <b>706.48</b>      |
| 3     | 11.4    | Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations (ii) complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203                                                                                                                                                                      |                             |                   |                 |                    |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                  | 2 x 7.600 x 2.467 x 0.200 = | 7.500             |                 |                    |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                               | 4 x 1.433 x 2.263 x 0.200 = | 2.594             |                 |                    |
|       |         | Floor Under Deck Slab                                                                                                                                                                                                                                                                                                                     | 1 x 6.200 x 1.736 x 0.150 = | 1.614             |                 |                    |
|       |         | Cut Off Wall                                                                                                                                                                                                                                                                                                                              | 2 x 0.400 x 1.000 x 0.200 = | 0.16              |                 |                    |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                              |                             | <b>11.868 cum</b> | <b>6,861.10</b> | <b>81,427.53</b>   |
| 4     | 11.4    | Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations (ii) complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203                                                                                                                                                                      |                             |                   |                 |                    |
|       |         | Qty below GL :                                                                                                                                                                                                                                                                                                                            |                             |                   |                 |                    |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                  | 2 x 6.800 x 1.967 x 1.400 = | 37.452            |                 |                    |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                               | 4 x 1.433 x 1.763 x 1.400 = | 14.148            |                 |                    |
|       |         | Cut Off Wall                                                                                                                                                                                                                                                                                                                              | 2 x 1.200 x 0.588 x 1.400 = | 1.974             |                 |                    |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                              |                             | <b>53.574 cum</b> | <b>6,861.10</b> | <b>3,67,576.57</b> |
| 5     | 12.5    | Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204. ( M15 (PCC 1:2.5:5)                                                                                                                                                                 |                             |                   |                 |                    |
|       |         | Qty above GL :                                                                                                                                                                                                                                                                                                                            |                             |                   |                 |                    |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                  | 2 x 6.000 x 1.084 x 2.300 = | 29.905            |                 |                    |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                               | 4 x 1.817 x 0.332 x 2.590 = | 15.648            |                 |                    |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                              |                             | <b>45.553 cum</b> | <b>7,428.23</b> | <b>3,38,378.16</b> |
| 6     | 12.5    | Plain/Reinforced cement concrete(M-20) in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204                                                                                                                                                                                |                             |                   |                 |                    |
|       |         | Abutment Cap                                                                                                                                                                                                                                                                                                                              | 2 x 6.000 x 0.700 x 0.200 = | 1.680             |                 |                    |
|       |         | Dirt Wall                                                                                                                                                                                                                                                                                                                                 | 2 x 6.000 x 0.400 x 0.240 = | 1.152             |                 |                    |
|       |         | Parapet                                                                                                                                                                                                                                                                                                                                   | 2 x 8.000 x 0.400 x 0.600 = | 3.840             |                 |                    |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                              |                             | <b>6.672 cum</b>  | <b>7,917.49</b> | <b>52,825.49</b>   |
| 7     | 13.1    | RCC M25 in Deck Slab :- Providing and laying reinforced cement concrete in superstructure (Deck slab M25) as per drawing and technical specifications Clauses 800, 1205.4, 1205.5                                                                                                                                                         |                             |                   |                 |                    |
|       |         |                                                                                                                                                                                                                                                                                                                                           | 1 x 6.000 x 2.560 x 0.240 = | 3.6864            |                 |                    |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                              |                             | <b>3.686 cum</b>  | <b>9,107.05</b> | <b>33,568.59</b>   |

20/18/7/23  
J.E

| Sl. No. | SOR No. | Description of Items                                                                                                                                                                                                               | Quantity      | Unit   | Rate (₹) | Amount (₹)             |
|---------|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|--------|----------|------------------------|
| 8       | 13.2    | Supplying, fitting and placing HYSD bar reinforcement in super-structure complete as per drawing and technical specifications                                                                                                      |               |        |          |                        |
|         |         | Abutment Cap & Dirt Wall @ 70 Kg per Cum qty of Concrete                                                                                                                                                                           | 2.832 x 70.00 | =      | 198.240  |                        |
|         |         | Deck Slab @ 80 Kg per Cum qty of Concrete                                                                                                                                                                                          | 3.686 x 80.00 | =      | 294.880  |                        |
|         |         | Sub Total                                                                                                                                                                                                                          |               |        | 493.120  |                        |
|         |         | Total in MT                                                                                                                                                                                                                        | 493.120       | + 1000 | = 0.493  | MT 87,092.05 42,936.38 |
| 9       | 13.16   | Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 per cent bitumen by weight                                                                                        |               |        |          |                        |
|         |         | 2 x 6.000                                                                                                                                                                                                                          |               | =      | 12.000   |                        |
|         |         | Total                                                                                                                                                                                                                              |               |        | 12.000   | RM 56.56 678.72        |
| 10      | 12.9    | Providing Weepholes in brick masonry, Plain / Reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V 20H towards drawing                  |               |        |          |                        |
|         |         | 2 x 8                                                                                                                                                                                                                              |               | =      | 28       | Nos. 144.52 4,046.56   |
| 11      | 13.10   | Drainage spouts complete as per drawing and technical specifications Clause 1209.                                                                                                                                                  |               |        |          |                        |
|         |         | 1 x 2                                                                                                                                                                                                                              |               | =      | 2        | Nos. 548.41 1,096.82   |
| 12      | 10.5    | Painting on Parapet Wall Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1703 |               |        |          |                        |
|         |         | Top                                                                                                                                                                                                                                | 2 x 8.00      | x 0.40 | =        | 6.40                   |
|         |         | Side                                                                                                                                                                                                                               | 4 x 8.00      | x 0.40 | =        | 19.20                  |
|         |         | Front                                                                                                                                                                                                                              | 4 x 0.40      | x 0.40 | =        | 0.96                   |
|         |         |                                                                                                                                                                                                                                    | 26.56         | Sqm    | 126.32   | 3,355.06               |
|         |         | Total ₹                                                                                                                                                                                                                            |               |        |          | 9,60,012.17            |

Cost of 1 No SLAB CULVERT Size ( 2 m x 2.5 m ) . =

₹ 9,60,012.17

284  
18/7/23


18.7.23

कार्यपालक अभियंता  
ग्रामिण कार्य विभाग  
काच प्रमण्डल, ओरंगाबाद

**Akari Mahadalit Tola Ke Nala Per Puliya Nirman(DMFT)**  
**YEAR (2022 - 2023)**

Quantities & Cost Estimate for R.C.C. Slab Culvert -

1 No. x 4.00 m Span x 2.50 m Vent Height



Sectional Elevation





# Quantities & Cost Estimate for R.C.C. Slab Culvert

1 No. x 4.00 m Span x 2.50 m Vent Height

| Sl No | SOR No. | Item or work involved                                                                                                                                                                                                                                                                                                                                                                       | Quantity                     | Unit | Rate (₹)      | Amount (₹)                      |
|-------|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|------|---------------|---------------------------------|
| 1     | 11.1    | Earth work in excavation of foundation trenches :- Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material |                              |      |               |                                 |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                                                                    | 2 x 9.300 x 2.950 x 1.800 =  |      | 98.77         |                                 |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                                                                                 | 4 x 1.433 x 2.679 x 1.800 =  |      | 27.64         |                                 |
|       |         | Floor Under Deck Slab                                                                                                                                                                                                                                                                                                                                                                       | 1 x 8.900 x 1.434 x 0.250 =  |      | 3.19          |                                 |
|       |         | Cut off Wall                                                                                                                                                                                                                                                                                                                                                                                |                              |      |               |                                 |
|       |         | Long Walls (U/S & D/S side)                                                                                                                                                                                                                                                                                                                                                                 | 2 x 10.200 x 1.000 x 1.800 = |      | 36.72         |                                 |
|       |         | Cross Walls (U/S Side)                                                                                                                                                                                                                                                                                                                                                                      | 2 x 0.600 x 1.000 x 1.800 =  |      | 2.16          |                                 |
|       |         | Cross Walls (D/S Side)                                                                                                                                                                                                                                                                                                                                                                      | 2 x 2.100 x 1.000 x 1.800 =  |      | 7.56          |                                 |
|       |         | Flooring (U/S Side)                                                                                                                                                                                                                                                                                                                                                                         | 1 x 8.200 x 0.600 x 0.250 =  |      | 1.23          |                                 |
|       |         | Flooring (D/S Side)                                                                                                                                                                                                                                                                                                                                                                         | 1 x 8.200 x 2.100 x 0.250 =  |      | 4.31          |                                 |
|       |         | Sub Total                                                                                                                                                                                                                                                                                                                                                                                   |                              |      | 181.57        |                                 |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                |                              |      | <b>181.57</b> | <b>cum 410.66 74,563.54</b>     |
| 2     | 11.2    | Sand Filling in Foundation :- Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108.                                                                                                                                                                                                                                                                   |                              |      |               |                                 |
|       |         | Floor Under Deck Slab                                                                                                                                                                                                                                                                                                                                                                       | 1 x 8.900 x 3.625 x 0.100 =  |      | 3.23          |                                 |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                |                              |      | <b>3.23</b>   | <b>cum 699.49 2,259.35</b>      |
| 3     | 11.4    | Providing M15 (PCC 1:2.5:5) as levelling course in foundation :- Providing PCC M 10 (1:3:6) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203                                                                                                                                                              |                              |      |               |                                 |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                                                                    | 2 x 9.300 x 2.950 x 0.200 =  |      | 10.97         |                                 |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                                                                                 | 4 x 1.433 x 2.679 x 0.200 =  |      | 3.07          |                                 |
|       |         | Floor Under Deck Slab                                                                                                                                                                                                                                                                                                                                                                       | 1 x 8.900 x 3.734 x 0.150 =  |      | 4.99          |                                 |
|       |         | Cut off Wall                                                                                                                                                                                                                                                                                                                                                                                |                              |      |               |                                 |
|       |         | Long Walls (U/S & D/S side)                                                                                                                                                                                                                                                                                                                                                                 | 2 x 10.200 x 1.000 x 0.150 = |      | 3.06          |                                 |
|       |         | Cross Walls (U/S Side)                                                                                                                                                                                                                                                                                                                                                                      | 2 x 0.600 x 1.000 x 0.150 =  |      | 0.18          |                                 |
|       |         | Cross Walls (D/S Side)                                                                                                                                                                                                                                                                                                                                                                      | 2 x 2.100 x 1.000 x 0.150 =  |      | 0.63          |                                 |
|       |         | Flooring (U/S Side)                                                                                                                                                                                                                                                                                                                                                                         | 1 x 10.000 x 1.500 x 0.150 = |      | 2.25          |                                 |
|       |         | Flooring (D/S Side)                                                                                                                                                                                                                                                                                                                                                                         | 1 x 10.000 x 3.000 x 0.150 = |      | 4.50          |                                 |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                |                              |      | <b>29.65</b>  | <b>cum 6,861.10 2,01431.62</b>  |
| 4     | 11.4    | Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203                                                                                                                                                                                                                             |                              |      |               |                                 |
|       |         | Qty below GL :                                                                                                                                                                                                                                                                                                                                                                              |                              |      |               |                                 |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                                                                    | 2 x 8.400 x 2.400 x 1.600 =  |      | 64.51         |                                 |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                                                                                 | 4 x 1.433 x 2.129 x 1.600 =  |      | 19.53         |                                 |
|       |         | Cut off Wall                                                                                                                                                                                                                                                                                                                                                                                |                              |      |               |                                 |
|       |         | Long Walls (U/S & D/S side)                                                                                                                                                                                                                                                                                                                                                                 | 2 x 10.000 x 0.588 x 1.500 = |      | 17.63         |                                 |
|       |         | Cross Walls (U/S Side)                                                                                                                                                                                                                                                                                                                                                                      | 2 x 0.913 x 0.588 x 1.500 =  |      | 1.61          |                                 |
|       |         | Cross Walls (D/S Side)                                                                                                                                                                                                                                                                                                                                                                      | 2 x 2.413 x 0.588 x 1.500 =  |      | 4.25          |                                 |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                |                              |      | <b>107.52</b> | <b>cum 6,861.10 7,33,705.47</b> |
| 5     | 12.5    | Plain/reinforced cement concrete in substructure complete as per drawings and technical specification                                                                                                                                                                                                                                                                                       |                              |      |               |                                 |
|       |         | (II) Clauses 802, 804, 805, 806, 807, 1202 and 1204. (M15 (PCC 1:2.5:5))                                                                                                                                                                                                                                                                                                                    |                              |      |               |                                 |
|       |         | Qty above GL :                                                                                                                                                                                                                                                                                                                                                                              |                              |      |               |                                 |
|       |         | Abutment                                                                                                                                                                                                                                                                                                                                                                                    | 2 x 7.500 x 1.275 x 2.500 =  |      | 43.99         |                                 |
|       |         | Return Wall                                                                                                                                                                                                                                                                                                                                                                                 | 4 x 1.817 x 0.990 x 2.720 =  |      | 19.56         |                                 |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                |                              |      | <b>63.54</b>  | <b>cum 7,428.23 4,71,989.73</b> |
| 6     | 12.5 II | Plain/reinforced cement concrete(M-20) in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204                                                                                                                                                                                                                                  |                              |      |               |                                 |
|       |         | Abutment Cap                                                                                                                                                                                                                                                                                                                                                                                | 2 x 7.500 x 0.700 x 0.200 =  |      | 2.10          |                                 |
|       |         | Dirt Wall                                                                                                                                                                                                                                                                                                                                                                                   | 2 x 7.500 x 0.300 x 0.370 =  |      | 1.67          |                                 |
|       |         | Return Wall Coping                                                                                                                                                                                                                                                                                                                                                                          | 2 x 2.200 x 0.400 x 0.150 =  |      | 0.26          |                                 |
|       |         | Parapet                                                                                                                                                                                                                                                                                                                                                                                     | 2 x 10.000 x 0.400 x 0.600 = |      | 4.80          |                                 |
|       |         | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                |                              |      | <b>8.83</b>   | <b>cum 7,917.49 69,911.44</b>   |

| Sl. No.                                           |                                                         | Description                                                                                                                                                                                                                                            |  | Unit      |          | Amount   |              |
|---------------------------------------------------|---------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|-----------|----------|----------|--------------|
| 13.1                                              | Providing RCC M25 in Deck Slab :-                       | Providing and laying reinforced cement concrete in Superstructure (Deck slab M25) as per drawing and technical specifications Clauses 800, 1205.4, 1205.5                                                                                              |  |           |          |          |              |
|                                                   |                                                         | 1 x 7.500 x 4.760 x 0.370                                                                                                                                                                                                                              |  | 13.21     |          |          |              |
|                                                   | Total                                                   |                                                                                                                                                                                                                                                        |  | 13.21 cum | 9,107.05 |          | 1,20,104.13  |
| 8                                                 | 13.2                                                    | Supplying, fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specifications                                                                                                                          |  |           |          |          |              |
|                                                   | Abutment                                                | 130.000 x 70.000                                                                                                                                                                                                                                       |  | 9,100.00  |          |          |              |
|                                                   | Return Wall                                             | 43.520 x 70.000                                                                                                                                                                                                                                        |  | 3,046.40  |          |          |              |
|                                                   | Abutment Cap & Out Wall @ 70 kg per Cum qty of Concrete | 8.830 x 70.000                                                                                                                                                                                                                                         |  | 618.100   |          |          |              |
|                                                   | Deck Slab @ 80 kg per Cum qty of Concrete               | 13.210 x 80.000                                                                                                                                                                                                                                        |  | 1056.800  |          |          |              |
|                                                   | Total in Kg                                             |                                                                                                                                                                                                                                                        |  | 13821.300 | Kg       |          |              |
|                                                   | Total in MT                                             | 13821.300 ÷ 1000                                                                                                                                                                                                                                       |  | 13.821    | MT       | 87092.05 | 12,03,699.22 |
| 9                                                 | 13.16                                                   | Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 percent bitumen by weight                                                                                                             |  |           |          |          |              |
|                                                   |                                                         | 2 x 7.500                                                                                                                                                                                                                                              |  | 15.00     |          |          |              |
|                                                   | Total                                                   |                                                                                                                                                                                                                                                        |  | 15.00     | RM       | 56.56    | 848.40       |
| 10                                                | 12.9                                                    | Providing weep holes in abutment :- Providing Weepholes in brick masonry, Plain / Reinforced concrete abutment, wing wall, return wall with 100 mm dia AL pipe extending through the full width of the structure with slope of 1V: 20H towards drawing |  |           |          |          |              |
|                                                   |                                                         | 2 x 10 x 4 x 3                                                                                                                                                                                                                                         |  | 32 Nos.   | 144.52   |          | 4,624.64     |
| 11                                                | 13.19                                                   | Drainage spouts complete as per drawing and technical specifications Clause 1209                                                                                                                                                                       |  |           |          |          |              |
|                                                   |                                                         | 1 x 4                                                                                                                                                                                                                                                  |  | 4 Nos.    | 548.41   |          | 2,193.64     |
| 12                                                | 10.5                                                    | Painting on Parapet Wall Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1201                     |  |           |          |          |              |
|                                                   | Top                                                     | 2 x 10.00 x 0.40                                                                                                                                                                                                                                       |  | = 8.00    |          |          |              |
|                                                   | Side                                                    | 4 x 10.00 x 0.60                                                                                                                                                                                                                                       |  | = 24.00   |          |          |              |
|                                                   | Front                                                   | 4 x 0.40 x 0.60                                                                                                                                                                                                                                        |  | = 0.96    |          |          |              |
|                                                   |                                                         |                                                                                                                                                                                                                                                        |  | 32.96     | sqm      | 126.32   | 4,163.51     |
|                                                   | Total ₹                                                 |                                                                                                                                                                                                                                                        |  |           |          |          | 28,95,694.69 |
| Cost of 1 No SLAB CULVERT Size ( 4 m x 2.5 m ) :- |                                                         |                                                                                                                                                                                                                                                        |  | ₹         |          |          | 28,95,694.69 |

18/7/23  
J.E

18/07/23  
A.E

18.7.23  
कार्यपालक अभियंता  
ग्रामिण कार्य विभाग  
कारा प्रमण्डल, औरंगाबाद



## Analysis for Carriage by Road

Name of Road:- Akarj Mahadalit Tola Ke Nala Per Puliya Nirman

District:- Aurangabad

Block :- Nabinagar

| Sl No | Item with Source         | Unit     | Source Up to   | Pukka / Surface                      | Carriage Cost & Lead in Km       | Hardia | Leaving & Unloading Cost | Carriage Cost by Half Head | Total      |
|-------|--------------------------|----------|----------------|--------------------------------------|----------------------------------|--------|--------------------------|----------------------------|------------|
| 1     | Stone Metal Gr-I & Gr-II | Cum      | Kariara (Gaya) | 8.00 x 7.94 x 140.00 Km = Rs 1937.43 | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.59   | 210.00                   |                            | Rs 2147.43 |
| 2     | Stone Metal Gr-III / GSB | Cum      | Kariara (Gaya) | 8.00 x 7.94 x 140.00 Km = Rs 1782.12 | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 1992.12 |
| 3     | Stone Aggregate / Chips  | Cum      | Wanpur         | 8.00 x 7.94 x 130.00 Km = Rs 1454.83 | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 1864.83 |
| 4     | Stone Boulder            | Cum      | Kariara (Gaya) | 8.00 x 7.94 x 140.00 Km = Rs 1452.67 | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.80   | 210.00                   |                            | Rs 2062.67 |
| 5     | Course Sand              | Cum      | Dehri On-Son   | 8.00 x 7.94 x 25.00 Km = Rs 256.24   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 326.24  |
| 6     | Binding Material         | Cum      | Kariara (Gaya) | 8.00 x 7.94 x 140.00 Km = Rs 1482.12 | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 1692.12 |
| 7     | Local Sand               | Cum      | Local          | 8.00 x 7.94 x 100.00 Km = Rs 23.48   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 234.82  |
| 8     | Brick                    | 1000 Nos | Local          | 8.00 x 7.94 x 100.00 Km = Rs 23.48   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 234.82  |
| 9     | Cement                   | MT       | Local          | 8.00 x 7.94 x 100.00 Km = Rs 23.48   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 234.82  |
| 10    | Steel                    | MT       | Local          | 8.00 x 7.94 x 100.00 Km = Rs 23.48   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 234.82  |
| 11    | Bitumen Emulsion         | MT       | Belagani       | 8.00 x 7.94 x 100.00 Km = Rs 23.48   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 234.82  |
| 12    | Bitumen                  | MT       | Belagani       | 8.00 x 7.94 x 100.00 Km = Rs 23.48   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 234.82  |
| 13    | Humie Pipe (3000 mm)     | m        | Sinduria       | 8.00 x 7.94 x 25.00 Km = Rs 256.80   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 377.62  |
| 14    | Humie Pipe (600 mm)      | m        | Sinduria       | 8.00 x 7.94 x 25.00 Km = Rs 256.80   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 377.62  |
| 15    | Humie Pipe (300 mm)      | m        | Sinduria       | 8.00 x 7.94 x 25.00 Km = Rs 256.80   | 8.00 x 19.22 x 0.00 Km = Rs 0.00 | 4.99   | 210.00                   |                            | Rs 377.62  |

\* Subjected to Verification of Lead

Cost of Material Excluding Loading &amp; Unloading as per SOR

| Type of Road           | Per Ton. Km by | Per Ton. Km by |
|------------------------|----------------|----------------|
| For Surface Road       | 12.20          | 12.20          |
| Subsurface Gravel Road | 14.50          | 14.50          |
| Asphalt Road           | 22.50          | 22.50          |

14/09/2020  
14/09/2020

14/09/2020  
14/09/2020

**BASIC RATES  
(A) Labour**

| Sl. No. | Description of Labour  | Unit | Rate (Rs.) |
|---------|------------------------|------|------------|
| L-01    | Bhisti                 | day  | 373.00     |
| L-02    | Bitumen Sprayer        | day  | 393.00     |
| L-03    | Blacksmith             | day  | 449.00     |
| L-04    | Blaster                | day  | 619.00     |
| L-05    | Carpenter 1st Class    | day  | 503.00     |
| L-06    | Chips spreader         | day  | 449.00     |
| L-07    | Chiseller              | day  | 577.00     |
| L-08    | Dresser (Skilled)      | day  | 472.00     |
| L-09    | Driller                | day  | 449.00     |
| L-10    | Electrician            | day  | 476.00     |
| L-11    | Fitter                 | day  | 511.00     |
| L-12    | Mason (1st class)      | day  | 503.00     |
| L-13    | Mason (2nd Class)      | day  | 449.00     |
| L-14    | Mate                   | day  | 397.00     |
| L-15    | Mazdoor (Unskilled)    | day  | 373.00     |
| L-16    | Mazdoor (Semi skilled) | day  | 388.00     |
| L-17    | Mazdoor (Skilled)      | day  | 472.00     |
| L-18    | Painter (1st class)    | day  | 476.00     |
| L-19    | Plumber                | day  | 476.00     |
| L-20    | Surveyor               | day  | 454.00     |
| L-21    | White Washer           | day  | 476.00     |

**BASIC RATES  
(B) Material**

| Sl. No. | Description                                                        | Unit | Basic Rate as per<br>SOR including<br>Royalty | Final Rate<br>including Royalty |
|---------|--------------------------------------------------------------------|------|-----------------------------------------------|---------------------------------|
| M-001   | AC pipe 100 mm                                                     | m    | 44.28                                         | 44.28                           |
| M-002   | Aggregate - For 37.5 mm Maximum size - 22.4 mm to 5.6 mm           | cum  | 886.00                                        | 886.00                          |
| M-003   | Aggregate - For 37.5 mm Maximum size - 45 mm to 22.5 mm            | cum  | 1,080.50                                      | 1,080.50                        |
| M-004   | Aggregate - For 37.5 mm Maximum size - Below 5.6 mm                | cum  | 424.21                                        | 424.21                          |
| M-005   | Aggregate - For 53 mm Maximum size - 22.5 mm to 5.6 mm             | cum  | 886.00                                        | 886.00                          |
| M-006   | Aggregate - For 53 mm Maximum size - 63 mm to 45 mm                | cum  | 975.00                                        | 975.00                          |
| M-007   | Aggregate - For 53 mm Maximum size - Below 5.6 mm                  | cum  | 424.21                                        | 424.21                          |
| M-008   | Aggregate - Grading I (40 mm nominal Size) 10 mm - 5 mm            | cum  | 586.00                                        | 586.00                          |
| M-009   | Aggregate - Grading I (40 mm nominal Size) 25 mm - 10 mm           | cum  | 886.00                                        | 886.00                          |
| M-010   | Aggregate - Grading I (40 mm nominal Size) 37.25 mm - 25 mm        | cum  | 1,080.50                                      | 1,080.50                        |
| M-011   | Aggregate - Grading I (40 mm nominal Size) 5 mm and below          | cum  | 424.21                                        | 424.21                          |
| M-012   | Aggregate - Grading II (19 mm nominal Size) 10 mm - 5 mm           | cum  | 586.00                                        | 586.00                          |
| M-013   | Aggregate - Grading II (19 mm nominal Size) 25 mm - 10 mm          | cum  | 886.00                                        | 886.00                          |
| M-014   | Aggregate - Grading II (19 mm nominal Size) 5 mm and below         | cum  | 424.21                                        | 424.21                          |
|         | Aggregate-13.2 mm to 0.09 mm                                       | cum  | 515.53                                        | 515.53                          |
| M-015   | Aggregate 10 mm                                                    | cum  | 586.00                                        | 586.00                          |
| M-016   | Aggregate 20 mm                                                    | cum  | 1,186.00                                      | 1,186.00                        |
| M-017   | Aggregate 40 mm                                                    | cum  | 975.00                                        | 975.00                          |
| M-018   | Aggregate- Crushable type such as moorum or Gravel for Grading I   | cum  | 165.30                                        | 165.30                          |
| M-019   | Aggregate- Crushable type such as moorum or Gravel for Grading II  | cum  | 165.30                                        | 165.30                          |
| M-020   | Aggregate- Crushable type such as moorum or Gravel for Grading III | cum  | 165.30                                        | 165.30                          |
| M-021   | Aggregate-Grading I 90 mm to 45 mm                                 | cum  | 975.00                                        | 975.00                          |
| M-022   | Aggregate-Grading II 63 mm to 45 mm                                | cum  | 975.00                                        | 975.00                          |
| M-023   | Aggregate-Grading III 53 mm to 22.4 mm                             | cum  | 1,080.50                                      | 1,080.50                        |
| M-024   | Aggregates 22.4 mm to 2.36 mm for wet mix macadam                  | cum  | 678.14                                        | 678.14                          |
| M-025   | Aggregates 45 mm to 22.4 mm for wet mix macadam                    | cum  | 1,080.50                                      | 1,080.50                        |
| M-026   | Aluminium sheeting (1.5 mm thick)                                  | sqm  | 8,945.43                                      | 8,945.43                        |



| Sl. No. | Description                                                                                                             | Unit  | Basic Rate as per SOR including Royalty | Final Rate including Royalty |
|---------|-------------------------------------------------------------------------------------------------------------------------|-------|-----------------------------------------|------------------------------|
| M-027   | Aluminium Studs 100 mm x 100 mm fitted with lense reflectors                                                            | Nos   | 187.29                                  | 187.29                       |
| M-028   | Bamboo (1st Class) 85 mm - 100 mm dia, 2.0 m long                                                                       | No.   | 20.98                                   | 20.98                        |
| M-029   | Bamboo (1st Class) 85 mm - 100 mm dia, 2.5 m long                                                                       | No.   | 20.98                                   | 20.98                        |
| M-029   | Bamboo (1st Class) 85 mm - 100 mm dia, 3.0 m long                                                                       | No.   | 20.98                                   | 20.98                        |
| M-030   | Bamboo (1st Class) 85 mm - 100 mm dia, 4.5 m - 5.5 m long                                                               | No.   | 20.98                                   | 20.98                        |
| M-029   | Bamboo (2nd Class) 75mm dia, 1.8 m - 2.5 m long                                                                         | No.   | 19.65                                   | 19.65                        |
| M-030   | Bamboo (2nd Class) 75mm dia, 2.1 m - 3.0 m long                                                                         | No.   | 19.65                                   | 19.65                        |
| M-031   | Barbed wire                                                                                                             | kg    | 73.77                                   | 73.77                        |
| M-032   | Binding Material                                                                                                        | cum   | 160.00                                  | 160.00                       |
| M-033   | Binding wire                                                                                                            | kg    | 75.04                                   | 75.04                        |
| M-034   | Bitumen (Crumb Rubber Modified)                                                                                         | tonne |                                         |                              |
| M-035   | Bitumen (Natural Rubber Modified)                                                                                       | tonne |                                         |                              |
| M-036   | Bitumen (Polymer Modified)                                                                                              | tonne |                                         |                              |
| M-037   | Bitumen (S-65) (Fatuha) (Excluding the cost of empty drum @ Rs. 816.61 / Per MT)                                        | t     | 51,650.50                               | 51,650.50                    |
| M-038   | Bitumen (S-90) (Fatuha) (Excluding the cost of empty drum @ Rs. 816.61 / Per MT)                                        | t     | 50,930.50                               | 50,930.50                    |
| M-039   | Bitumen Emulsion (RS-1) (Patna) (Excluding the cost of empty drum @ Rs. 665.625 / Per MT)                               | t     | 48,921.50                               | 48,921.50                    |
| M-040   | Bitumen Emulsion (SS-1) (Patna) (Excluding the cost of empty drum @ Rs. 665.625 / Per MT)                               | t     | 50,361.50                               | 50,361.50                    |
| M-041   | Bituminous sealant                                                                                                      | litre | 27.24                                   | 27.24                        |
| M-042   | Blasted rubble                                                                                                          | cum   | 675.00                                  | 675.00                       |
| M-043   | Blasting material (Moorum)                                                                                              | kg    | 131.28                                  | 131.28                       |
| M-044   | Bond stone (400 mm x 150 mm x 150 mm)                                                                                   | No.   | 10.57                                   | 10.57                        |
| M-045   | Brick 1st Class                                                                                                         | No.   | 6.07                                    | 6.07                         |
| M-046   | Cement (OPC-43 Grade) (Excluding the cost of empty bag @ Rs. 8.48 / Per Bag) (OPC 43 grade)                             | t     | 5,854.90                                | 5,854.90                     |
| M-047   | Cement Primer                                                                                                           | litre | 115.16                                  | 115.16                       |
| M-048   | Chlorprene Elastomer or Closed Cell Foam Sealing Element                                                                | m     |                                         |                              |
| M-049   | Compensation for earth taken from private land (Including royalty @ Rs. 22.0 per cum & compensation @ Rs. 1.65 per cum) | cum   | 35.01                                   | 35.01                        |
| M-050   | Compressible Fibre Board                                                                                                | sqm   | 1,132.98                                | 1,132.98                     |
| M-051   | Copper plate                                                                                                            | kg    | 896.80                                  | 896.80                       |

| Sl. No. | Description                                                                     | Unit  | Basic Rate as per<br>SOR including<br>Royalty | Final Rate<br>including Royalty |
|---------|---------------------------------------------------------------------------------|-------|-----------------------------------------------|---------------------------------|
| M-052   | Corbelling Stones (300 mm x 150 mm x 150 mm)                                    | No.   |                                               |                                 |
| M-053   | Corrosion Resistant Structural Steel Grating                                    | kg    | 46.83                                         | 46.83                           |
| M-054   | Credit for excavated rock found suitable for use                                | cum   | 101.24                                        | 101.24                          |
| M-055   | Crow bars 40 mm dia (hire charges)                                              | hour  | 5.00                                          | 5.00                            |
| M-056   | Crushed Sand or Grit Passing 2.36 mm and retained on 180 micron                 | cum   | 119.10                                        | 119.10                          |
| M-057   | Crushed Slag                                                                    | cum   | 729.73                                        | 729.73                          |
| M-058   | Crushed Stone Aggregate 26.5 mm to 75 micron                                    | cum   | 657.85                                        | 657.85                          |
| M-059   | Crushed Stone chipping 13.2 mm nominal size                                     | cum   | 697.55                                        | 697.55                          |
| M-060   | Crushed Stone Chipping 6.7 mm size 100% passing 11.2 mm and retained on 2.36 mm | cum   | 514.58                                        | 514.58                          |
| M-061   | Crushed Stone Chipping 6.7 mm size 100% passing 9.5 mm and retained on 2.36 mm  | cum   | 514.58                                        | 514.58                          |
| M-062   | Crushed Stone chipping 9.5 mm nominal size                                      | cum   | 668.80                                        | 668.80                          |
| M-063   | Crushed Stone Coarse Aggregate Passing 5.3 mm and retained on 2.8 mm            | cum   | 524.27                                        | 524.27                          |
| M-064   | Curing compound                                                                 | litre | 136.22                                        | 136.22                          |
| M-065   | Debonding strips                                                                | m     | 45.00                                         | 45.00                           |
| M-066   | Edge Stone (450 mm x 350 mm x 100 mm)                                           | No.   |                                               |                                 |
| M-067   | Edge Stone (450 mm x 350 mm x 200 mm)                                           | No.   |                                               |                                 |
| M-068   | Elastomeric bearing assembly                                                    | Nos.  | 28,508.46                                     | 28,508.46                       |
| M-069   | Electric Detonator                                                              | each  | 6.19                                          | 6.19                            |
| M-070   | Epoxy Paint                                                                     | kg    | 568.30                                        | 568.30                          |
| M-071   | Epoxy Primer                                                                    | kg    | 122.02                                        | 122.02                          |
| M-072   | Farmyard manure                                                                 | cum   | 278.90                                        | 278.90                          |
| M-073   | Fevicol adhesive                                                                | kg    | 125.00                                        | 125.00                          |
| M-074   | Filter media                                                                    | cum   | 678.14                                        | 678.14                          |
| M-075   | Fine aggregate/Crushed sand 2.36 mm to 75 micron                                | cum   | 119.10                                        | 119.10                          |
| M-076   | Galvanised angle                                                                | kg    |                                               |                                 |
| M-077   | Galvanised angle Section 100 mm x 100 mm of 12 mm thickness                     | kg    | 39.25                                         | 39.25                           |
| M-078   | Gelatine 80 per cent                                                            | kg    | 976.21                                        | 976.21                          |
| M-079   | GI Pipe 100 mm dia                                                              | m     | 617.50                                        | 617.50                          |
| M-080   | GI Pipe 50 mm dia                                                               | m     | 617.50                                        | 617.50                          |

| M No. | Description                                                                                         | Unit | Basic Rate as per<br>NDR including<br>Royalty | Final Rate<br>including Royalty |
|-------|-----------------------------------------------------------------------------------------------------|------|-----------------------------------------------|---------------------------------|
| M 003 | Concrete                                                                                            | kg   | 90.20                                         | 90.20                           |
| M 004 | Graded stone aggregate                                                                              | cum  | 109.21                                        | 109.21                          |
| M 005 | Concrete material (Material for wing, end gravel pitstone / quarry waste, kankar, laterite, dhanda) | cum  | 165.26                                        | 165.26                          |
| M 006 | Cast Iron Pipe Metal 40 mm dia                                                                      | cum  | 145.22                                        | 145.22                          |
| M 007 | Bricks                                                                                              | kg   | 169.78                                        | 169.78                          |
| M 008 | Imperial King Blanks with oil from the kankar                                                       | cum  |                                               |                                 |
| M 009 | Imperial King Blanks with oil from the kankar                                                       | cum  |                                               |                                 |
| M 010 | Imperial King Blanks with oil from the kankar                                                       | cum  |                                               |                                 |
| M 011 | Imperial King Blanks with oil from the kankar                                                       | cum  |                                               |                                 |
| M 012 | Imperial King Blanks with oil from the kankar                                                       | cum  | 957.49                                        | 957.49                          |
| M 013 | Imperial King Blanks with oil from the kankar                                                       | cum  | 41.26                                         | 41.26                           |
| M 014 | Imperial King Blanks with oil from the kankar                                                       | cum  | 14.28                                         | 14.28                           |
| M 015 | Imperial King Blanks with oil from the kankar                                                       | cum  | 581.99                                        | 581.99                          |
| M 016 | Imperial King Blanks with oil from the kankar                                                       | cum  | 1871.95                                       | 1871.95                         |
| M 017 | Imperial King Blanks with oil from the kankar                                                       | cum  | 1871.95                                       | 1871.95                         |
| M 018 | Imperial King Blanks with oil from the kankar                                                       | cum  | 197.50                                        | 197.50                          |
| M 019 | Imperial King Blanks with oil from the kankar                                                       | cum  | 20775.00                                      | 20775.00                        |
| M 020 | Imperial King Blanks with oil from the kankar                                                       | cum  | 106.33                                        | 106.33                          |
| M 021 | Imperial King Blanks with oil from the kankar                                                       | cum  | 13.36                                         | 13.36                           |
| M 022 | Imperial King Blanks with oil from the kankar                                                       | cum  | 57823.00                                      | 57823.00                        |
| M 023 | Imperial King Blanks with oil from the kankar                                                       | kg   | 88.65                                         | 88.65                           |
| M 024 | Imperial King Blanks with oil from the kankar                                                       | cum  | 169.78                                        | 169.78                          |
| M 025 | Imperial King Blanks with oil from the kankar                                                       | cum  | 139.56                                        | 139.56                          |
| M 026 | Imperial King Blanks with oil from the kankar                                                       | cum  | 69.150.00                                     | 69.150.00                       |
| M 027 | Imperial King Blanks with oil from the kankar                                                       | kg   | 246.65                                        | 246.65                          |
| M 028 | Imperial King Blanks with oil from the kankar                                                       | kg   | 214.86                                        | 214.86                          |
| M 029 | Imperial King Blanks with oil from the kankar                                                       | kg   | 14.68                                         | 14.68                           |
| M 030 | Imperial King Blanks with oil from the kankar                                                       | kg   | 14.68                                         | 14.68                           |
| M 031 | Imperial King Blanks with oil from the kankar                                                       | cum  | 355.68                                        | 355.68                          |
| M 032 | Imperial King Blanks with oil from the kankar                                                       | m    | 3,921.34                                      | 3,921.34                        |
| M 033 | Imperial King Blanks with oil from the kankar                                                       | m    | 2,758.22                                      | 2,758.22                        |



| M. No. | Description                                             | Unit  | Basic Rate as per<br>SOR including<br>Royalty | Final Rate<br>including Royalty |
|--------|---------------------------------------------------------|-------|-----------------------------------------------|---------------------------------|
| M-110  | RCC Pipe NP4 (750 mm dia)                               | m     | 996.02                                        | 996.02                          |
| M-111  | RCC Pipe NP4 (600 mm dia)                               | m     | 667.90                                        | 667.90                          |
| M-112  | RCC Pipe NP4 (500 mm dia)                               | m     |                                               |                                 |
|        | RCC Pipe NP4 (300 mm dia)                               | m     | 505.12                                        | 505.12                          |
| M-113  | RCC Pipe NP4 (1200 mm dia)                              | m     | 6,510.00                                      | 6,510.00                        |
| M-114  | RCC Pipe NP4 (1000 mm dia)                              | m     | 5,570.00                                      | 5,570.00                        |
| M-115  | RCC Pipe NP4 (750 mm dia)                               | m     |                                               |                                 |
| M-116  | RCC Pipe NP4 (600 mm dia)                               | m     | 2,350.00                                      | 2,350.00                        |
| M-117  | RCC Pipe NP4 (500 mm dia)                               | m     | 532.24                                        | 532.24                          |
| M-118  | Red oxide Primer                                        | litre | 226.49                                        | 226.49                          |
| M-119  | Road marking paint                                      | litre | 246.65                                        | 246.65                          |
| M-120  | Sand (Coarse)                                           | cum   | 494.00                                        | 494.00                          |
| M-121  | Sand (Fine)                                             | cum   | 143.32                                        | 143.32                          |
| M-122  | Seeds                                                   | kg    | 38.31                                         | 38.31                           |
| M-123  | Steel Pipe 50 mm dia                                    | m     | 244.89                                        | 244.89                          |
| M-124  | Steel Reinforcement (HYSD Bars)                         | t     | 57,667.00                                     | 57,667.00                       |
| M-125  | Steel Reinforcement (MS Round Bars)                     | t     | 57,667.00                                     | 57,667.00                       |
| M-126  | Steel Reinforcement (TMT Bars)                          | t     | 57,667.00                                     | 57,667.00                       |
| M-127  | Stone Boulder of size 150 mm and below                  | cum   | 675.00                                        | 675.00                          |
| M-128  | Stone Chips 12 mm size                                  | cum   | 586.00                                        | 586.00                          |
| M-129  | Stone Chips 13.2 mm to 5.6 mm                           | cum   | 586.00                                        | 586.00                          |
| M-130  | Stone Crushed Aggregate 11.2 mm to 0.09 mm              | cum   | 600.00                                        | 600.00                          |
| M-131  | Stone for Coarse Rubble Masonry 1st Sort                | cum   | 392.53                                        | 392.53                          |
| M-132  | Stone for Coarse Rubble Masonry 2nd Sort                | cum   |                                               |                                 |
| M-133  | Stone for Random Rubble Masonry                         | cum   |                                               |                                 |
| M-134  | Stone for Stone Set Pavement (300 mm x 200 mm x 150 mm) | No    | 340.55                                        | 340.55                          |
| M-135  | Stone Screening - Type A 13.2 mm for Grading-1          | cum   | 424.21                                        | 424.21                          |
| M-136  | Stone Screening - Type A 13.2 mm for Grading-2          | cum   | 424.21                                        | 424.21                          |
| M-137  | Stone Screening - Type B 11.2 mm for Grading-2          | cum   | 424.21                                        | 424.21                          |

| Sl. No. | Description                                                         | Unit  | Basic Rate as per<br>SOR including<br>Royalty | Final Rate<br>including Royalty |
|---------|---------------------------------------------------------------------|-------|-----------------------------------------------|---------------------------------|
| M-138   | Stone Screening - Type B 11.2 mm for Grading-3                      | cum   | 424.21                                        | 424.21                          |
| M-139   | Stone spall                                                         | cum   | 351.36                                        | 351.36                          |
| M-140   | Traffic cones                                                       | No.   |                                               |                                 |
| M-141   | Water                                                               | lit   | 56.20                                         | 56.20                           |
| M-142   | Well graded Granular Base Material - Grading A 2.36 mm below        | cum   | 262.42                                        | 262.42                          |
| M-143   | Well graded Granular Base Material - Grading A 2.65 mm to 4.75 mm   | cum   | 886.00                                        | 886.00                          |
| M-144   | Well graded Granular Base Material - Grading A 5.3 mm to 26.5 mm    | cum   | 1,080.50                                      | 1,080.50                        |
| M-145   | Well graded Granular Base Material - Grading B 2.36 mm below        | cum   | 262.42                                        | 262.42                          |
| M-146   | Well graded Granular Base Material - Grading B 2.65 mm to 4.75 mm   | cum   | 886.00                                        | 886.00                          |
| M-147   | Well graded Granular Base Material - Grading F 2.36 mm below        | cum   | 262.42                                        | 262.42                          |
| M-148   | Well graded Granular Base Material - Grading C 9.5 mm to 4.75 mm    | cum   | 586.00                                        | 586.00                          |
| M-149   | Well Graded Material for Sub Base - Grading (I) 2.36 mm below       | cum   | 262.42                                        | 262.42                          |
| M-150   | Well Graded Material for Sub Base - Grading (I) 5 mm to 9.5 mm      | cum   | 915.67                                        | 915.67                          |
| M-151   | Well Graded Material for Sub Base - Grading (I) 5 mm to 2.36 mm     | cum   | 424.21                                        | 424.21                          |
| M-152   | Well Graded Material for Sub Base - Grading (I) 2.36 mm below       | cum   | 262.42                                        | 262.42                          |
| M-153   | Well Graded Material for Sub Base - Grading (I) 2.65 mm to 9.5 mm   | cum   | 886.00                                        | 886.00                          |
| M-154   | Well Graded Material for Sub Base - Grading (I) 9.5 mm to 2.36 mm   | cum   | 424.21                                        | 424.21                          |
| M-155   | Well Graded Material for Sub Base - Grading (II) 2.36 mm below      | cum   | 262.42                                        | 262.42                          |
| M-156   | Well Graded Material for Sub Base - Grading (II) 4.75 mm to 2.36 mm | cum   | 262.42                                        | 262.42                          |
| M-157   | Well Graded Material for Sub Base - Grading (II) 9.5 mm to 4.75 mm  | cum   | 586.00                                        | 586.00                          |
| M-158   | Wooden sleepers (250 mm x 250 mm x 125 mm) (hire charges)           | No.   | 5.00                                          | 5.00                            |
| BC-11   |                                                                     |       |                                               |                                 |
| M-158   | Hydrochloric acid (30% solution) (pH < 1)                           | litre | 198.46                                        | 198.46                          |
| M-159   | Hydrochloric acid (30% solution) (pH < 1)                           | kg    | 72.00                                         | 72.00                           |
| M-160   | 600 mm x 100 mm x 100 mm (marker rate)                              | lit   | 43,000.00                                     | 43,000.00                       |

**BASIC RATES**  
**(C) USAGE RATES OF PLANT & MACHINERY**

| Sr. No. | Description of                                       |                                   | Output of Machine |          | Usage Rates in Rs. |           |
|---------|------------------------------------------------------|-----------------------------------|-------------------|----------|--------------------|-----------|
|         | Machine                                              | Activity                          | Unit              | Output   | Unit               | Rate      |
| PM-001  | Air Compressor 210 cfm                               | Supplying compressed air          | cfm               | 210.00   | per hour           | 440.00    |
| PM-002  | Batch mix HMP 40-60 TPH                              | BM, DBM, SDBC, PM                 | t/h               | 50.00    | per hour           | 31,459.00 |
|         | Batch mix HMP 40-60 TPH @ 37.4 t/h Actual output     | BM, DBM, SDBC, PM                 | t/h               | 37.40    | per hour           | 31,459.00 |
| PM-003  | Batch type HMP 30/40 TPH                             | BM, DBM, SDBC, PM                 | t/h               | 35.00    | per hour           | 31,459.00 |
| PM-004  | Bitumen boiler oil fired                             | Heating of bitumen                | litre / h         | 400.00   | per hour           | 552.00    |
|         | 200 litre<br>1000 litre                              |                                   | litre / h         | 2000.00  | per hour           | 552.00    |
| PM-005  | Bitumen emulsion pressure distributor                | Applying bitumen tack coat        | sqm/h             | 1750.00  | per hour           | 1,350.00  |
| PM-006  | Concrete mixer 0.28/0.4 cum                          | Mixing of ingredients             | cum/h             | 2.50     | per hour           | 334.00    |
| PM-007  | Crane upto 3.5T                                      | Lifting of materials              |                   |          | per hour           | 831.00    |
| PM-008  | Dozer D 50                                           | Dozing cutting                    | cum/h             | 200.00   | per hour           | 5,610.00  |
|         |                                                      |                                   | cum/h             | 100.00   | per hour           | 2,997.00  |
| PM-009  | Electric generator set, 125 KVA                      | Electricity generation            | KVA               | 100.00   | per hour           | 1,642.00  |
| PM-010  | Emulsion Sprayer with Tractor                        | Spraying of Emulsion              |                   |          | per hour           | 1,350.00  |
| PM-011  | Front end-loader 1 cum bucket capacity @ 45 cum/hour | Loading Aggregates                | cum/h             | 45.00    | per hour           | 1,419.00  |
|         |                                                      | Loading Soil                      | cum/h             | 100.00   | per hour           | 1,419.00  |
| PM-012  | Hydraulic broom with tractor                         | Surface cleaning                  | sqm/h             | 1250.00  | per hour           | 794.00    |
| PM-013  | Hydraulic Excavator 0.9 cum                          | Excavation                        | cum/h             | 100.00   | per hour           | 2,272.00  |
| PM-014  | Hydraulic self propelled chip spreader               | Surface Dressing                  | sqm/h             | 1500.00  | per hour           | 1,674.00  |
| PM-015  | Jack Hammer with tractor                             | Pavement breaking & rock drilling | cum/h             | 05. to 1 | per hour           | 1,289.30  |
| PM-016  | Joint Cutting Machine with 2-3 blades                | Cutting of joints                 | h                 |          | per hour           | 342.00    |
| PM-017  | Mixall 6-10 t capacity                               | Mixing of bituminous materials    | t/h               | 8.00     | per hour           | 3,702.00  |
| PM-018  | Motor Grader                                         | Scarifier & levelling             | cum/h             | 200.00   | per hour           | 2,982.00  |
|         | Tractor Mounted Grader                               |                                   | cum/h             | 50.00    | per hour           | 646.00    |
| PM-019  | Needle vibrator                                      | Vibrating cement concrete mix     | cum/h             | 3.50     | per hour           | 386.00    |
| PM-020  | Paver finisher                                       | Laying/spreading                  | t/h               | 75.00    | per hour           | 2,141.00  |



| Sr. No. | Description of                              |                                    | Output of Machine |          | Usage Rates in Rs. |           |
|---------|---------------------------------------------|------------------------------------|-------------------|----------|--------------------|-----------|
|         | Machine                                     | Activity                           | Unit              | Output   | Unit               | Rate      |
| PM-021  | Plate compactor                             | Compaction                         | cum/h             |          | per hour           | 396.00    |
| PM-022  | Plate vibrator                              | Compaction                         | cum/h             |          | per hour           | 396.00    |
| PM-023  | Screed vibrator                             | Compaction                         | cum/h             |          | per hour           | 102.64    |
| PM-024  | Smooth wheeled 80-100 kN tandem roller      | Compaction of Sub-base/ Asphalt    | cum/h             | 30.00    | per hour           | 2,053.00  |
| PM-025  | Stone crusher (Integrated) of 200 TPH       | Crushing of Spalls                 | t/h               | 200.00   | per hour           | 13,721.00 |
| PM-026  | Three wheel 80-100 kN Static Roller         | Compaction/ Rolling                |                   |          |                    | 1,593.00  |
|         |                                             | Earth:- Embankment or sub-grade    | cum/h             | 80/70    |                    | 1,593.00  |
|         |                                             | Sub-base G-I                       | cum/h             | 10.00    |                    | 1,593.00  |
|         |                                             | Sub-base G-II/G-III                | cum/h             | 8.00     |                    | 1,593.00  |
|         |                                             | WMM                                | cum/h             | 16.00    |                    | 1,593.00  |
|         |                                             | BUSG                               | cum/h             | 10.00    | per hour           | 1,593.00  |
|         |                                             | BM 50/75 mm                        | cum/h             | 12.00    |                    | 1,593.00  |
|         |                                             | Premix 20 mm                       | sqm/h             | 250.00   |                    | 1,593.00  |
|         |                                             | Seal Coat                          | sqm/h             | 500.00   |                    | 1,593.00  |
|         |                                             | Surface Dressing 1st Coat          | sqm/h             | 400.00   |                    | 1,593.00  |
|         |                                             | Surface Dressing 2nd Coat          | sqm/h             | 500.00   |                    | 1,593.00  |
| PM-027  | Tipper 5.5 cum/10 t                         | Carriage                           | cum/trip          | 5.50     | per hour           | 1,426.00  |
| PM-028  | Tractor with Disc Harrows                   | Pulverisation of soil              | cum/h             | 80.00    | per hour           | 676.00    |
| PM-029  | Tractor with ripper @ 60 cum per hour       | Ripping Pavements, uprooting trees | cum/h             | 60.00    | per hour           | 697.00    |
| PM-030  | Tractor with trolley/with Grading equipment | Transportation of materials        | t/trip            | 3 to 5   | per hour           | 676.00    |
| PM-031  | Tractor with Rotavator                      | Scarifier                          | cum/h             | 25.00    | per hour           | 693.00    |
| PM-032  | Truck 10 t capacity                         | Carriage                           | cum/trip          | 5.50     | per hour           | 934.30    |
| PM-033  | Vibratory roller 80-100 kN                  | Compaction of soil WMM             | cum/h             | 100.00   | per hour           | 2,063.00  |
|         |                                             | Compaction of BM                   | cum/h             | 60.00    |                    | 2,063.00  |
| PM-034  | Water tanker 6 kl capacity (Truck Mounted)  | Carriage of water                  | litre / h         | 12000.00 | per hour           | 752.00    |
| PM-035  | Wet mix plant (Pug Mill)                    | Wet Mix                            | cum/h             | 25.00    | per hour           | 1,822.30  |
| RCD     |                                             |                                    |                   |          |                    |           |
| P&M-043 | Road marking machine                        | Road marking                       | Sqm/h             | 100.00   | per hour           | 1,411.00  |



# Analysis of Rates (FORMAT B)

| Sl. No.                  | Subs. No. | Item Ref. | Description                                                                                                                                                                                                                                                                                                                                                                  | Unit       | Quantity | Rate    | Amount in Rs. |
|--------------------------|-----------|-----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|----------|---------|---------------|
| <b>Haulage BY TIPPER</b> |           |           |                                                                                                                                                                                                                                                                                                                                                                              |            |          |         |               |
| 1                        | 1.10      | (i)       | <b>Haulage excluding Loading &amp; Unloading</b><br>Haulage of materials by tipper excluding cost of loading, unloading and stacking.<br>Unit = t.km<br>Taking output 10 t load and lead 10 km = 100 t.km<br><b>Case-I: Surfaced Road</b><br>Speed with load: 25 km per hour<br>Speed while returning empty: 35 km per hour                                                  |            |          |         |               |
|                          |           | a)        | <b>Machinery</b><br><b>Tipper 10 t capacity</b><br>Haulage with load                                                                                                                                                                                                                                                                                                         | hour       | 0.40     | 1426.00 | 570.40        |
|                          |           |           | Empty return trip                                                                                                                                                                                                                                                                                                                                                            | hour       | 0.29     | 1426.00 | 413.54        |
|                          |           | b)        | Overheads @ 12 % on (a)                                                                                                                                                                                                                                                                                                                                                      |            |          |         | 118.07        |
|                          |           |           | Contractor's profit @ 10% on (a+b)                                                                                                                                                                                                                                                                                                                                           |            |          |         | 110.20        |
|                          |           |           | Cost for 100 t.km = a+b                                                                                                                                                                                                                                                                                                                                                      |            |          |         | 1212.21       |
|                          |           |           | Rate per cum = (a+b) / 100                                                                                                                                                                                                                                                                                                                                                   |            |          |         | 12.12         |
|                          |           |           | <b>Rate Per Km.</b>                                                                                                                                                                                                                                                                                                                                                          | <b>Cum</b> |          |         | <b>12.10</b>  |
| 2                        | 1.10      | (ii)      | <b>Haulage excluding Loading &amp; Unloading</b><br>Haulage of materials by tipper excluding cost of loading, unloading and stacking.<br>Unit = t.km<br>Taking output 10 t load and lead 10 km = 100 t.km<br><b>Case-II: Unsurfaced Gravel Road.</b><br>Speed with load: 20 km/hour<br>Speed for empty return trip: 30 km/hour                                               |            |          |         |               |
|                          |           | a)        | <b>Machinery</b><br><b>Tipper 10 t capacity</b><br>Haulage with load                                                                                                                                                                                                                                                                                                         | hour       | 0.50     | 1426.00 | 713.00        |
|                          |           |           | Empty return trip                                                                                                                                                                                                                                                                                                                                                            | hour       | 0.33     | 1426.00 | 470.58        |
|                          |           | b)        | Overheads @ 12% on (a)                                                                                                                                                                                                                                                                                                                                                       |            |          |         | 142.03        |
|                          |           |           | Contractor's profit @ 10% on (a+b)                                                                                                                                                                                                                                                                                                                                           |            |          |         | 132.56        |
|                          |           |           | Cost for 100 t.km = a+b                                                                                                                                                                                                                                                                                                                                                      |            |          |         | 1458.17       |
|                          |           |           | Rate per cum = (a+b) / 100                                                                                                                                                                                                                                                                                                                                                   |            |          |         | 14.58         |
|                          |           |           | <b>Rate Per Km.</b>                                                                                                                                                                                                                                                                                                                                                          | <b>Cum</b> |          |         | <b>14.60</b>  |
| 3                        | 1.10      | (iii)     | <b>Haulage excluding Loading &amp; Unloading</b><br>Haulage of materials by tipper excluding cost of loading, unloading and stacking.<br>Unit = t.km<br>Taking output 10 t load and lead 10 km = 100 t.km<br><b>Case-III: Katcha Track and Track in River Bed/Nallah Bed and Choe Bed.</b><br>Speed with load: 10 km per hour<br>Speed while returning empty: 15 km per hour |            |          |         |               |
|                          |           | a)        | <b>Machinery</b><br><b>Tipper 10 t capacity</b><br>Haulage with load                                                                                                                                                                                                                                                                                                         | hour       | 1.00     | 1426.00 | 1426.00       |
|                          |           |           | Empty return trip                                                                                                                                                                                                                                                                                                                                                            | hour       | 0.67     | 1426.00 | 955.42        |
|                          |           | b)        | Overheads @ 12 % on (a)                                                                                                                                                                                                                                                                                                                                                      |            |          |         | 285.77        |
|                          |           | c)        | Contractor's profit @ 10% on (a+b)                                                                                                                                                                                                                                                                                                                                           |            |          |         | 266.72        |
|                          |           |           | Cost for 100 t.km = a+b+c                                                                                                                                                                                                                                                                                                                                                    |            |          |         | 2933.91       |
|                          |           |           | Rate per cum = (a+b+c) / 100                                                                                                                                                                                                                                                                                                                                                 |            |          |         | 29.34         |
|                          |           |           | <b>Rate Per Km.</b>                                                                                                                                                                                                                                                                                                                                                          | <b>Cum</b> |          |         | <b>29.30</b>  |
| <b>Haulage BY TRUCK</b>  |           |           |                                                                                                                                                                                                                                                                                                                                                                              |            |          |         |               |
| 4                        | 1.10      | (i)       | <b>Haulage excluding Loading &amp; Unloading</b><br>Haulage of materials by tipper excluding cost of loading, unloading and stacking.<br>Unit = t.km<br>Taking output 10 t load and lead 10 km = 100 t.km<br><b>Case-I: Surfaced Road</b>                                                                                                                                    |            |          |         |               |



| Sl. No. | SDB Sl. No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Unit         | Quantity                                                      | Rate               | Amount in R                                               |
|---------|-------------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|---------------------------------------------------------------|--------------------|-----------------------------------------------------------|
|         |             |               | Speed with load: 25 km per hour<br>Speed while returning empty: 35 km per hour<br><b>a) Machinery</b><br><b>Truck 10 t capacity</b><br>Haulage with load<br>Empty return trip<br><b>b) Overheads @ 12 % on (a)</b><br><b>(c) Contractor's profit @ 10% on (a+b)</b><br>Cost for 100 t-km = a+b+c<br><b>Rate per cum = (a+b+c) / 100</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | hour<br>hour | 0.40<br>0.29                                                  | 934.30<br>934.30   | 373.72<br>270.95<br>77.36<br>72.20<br>794.23<br>7.94      |
|         |             |               | <b>Rate Per Km.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | <b>Cum</b>   |                                                               |                    | 7.94                                                      |
| 5       | 1.10        | (ii)          | <b>Haulage excluding Loading &amp; Unloading</b><br>Haulage of materials by tipper excluding cost of loading, unloading and stacking.<br>Unit = tkm<br>Taking output 10 t load and lead 10 km = 100 t km<br><b>Case-II: Unsurfaced Gravel Road.</b><br>Speed with load: 20 km/hour<br>Speed for empty return trip: 30 km/hour<br><b>a) Machinery</b><br><b>Truck 10 t capacity</b><br>Haulage with load<br>Empty return trip<br><b>b) Overheads @ 12 % on (a)</b><br><b>(c) Contractor's profit @ 10% on (a+b)</b><br>Cost for 100 t-km = a+b+c<br><b>Rate per cum = (a+b+c) / 100</b>                                                                                                                                                                                                                                                                         | hour<br>hour | 0.50<br>0.33                                                  | 934.30<br>934.30   | 467.15<br>308.32<br>93.00<br>86.85<br>955.38<br>9.55      |
|         |             |               | <b>Rate Per Km.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | <b>Cum</b>   |                                                               |                    | 9.55                                                      |
| 6       | 1.10        | (iii)         | <b>Haulage excluding Loading &amp; Unloading</b><br>Haulage of materials by tipper excluding cost of loading, unloading and stacking.<br>Unit = t km<br>Taking output 10 t load and lead 10 km = 100 t km<br><b>Case-III: Katcha Track and Track in River Bed/Nallah Bed and Choe Bed.</b><br>Speed with load: 10 km per hour<br>Speed while returning empty: 15 km per hour<br><b>a) Machinery</b><br><b>Truck 10 t capacity</b><br>Haulage with load<br>Empty return trip<br><b>b) Overheads @ 12 % on (a)</b><br><b>(c) Contractor's profit @ 10% on (a+b)</b><br>Cost for 100 t-km = a+b+c<br><b>Rate per cum = (a+b+c) / 100</b>                                                                                                                                                                                                                          | hour<br>hour | 1.00<br>0.67                                                  | 934.30<br>934.30   | 934.30<br>625.98<br>187.23<br>174.75<br>1922.27<br>19.22  |
|         |             |               | <b>Rate Per Km.</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | <b>Cum</b>   |                                                               |                    | 19.22                                                     |
| 7       | 1.1         | RCD           | Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kanker/Moorum<br>Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and<br><b>Unit = cum</b><br><b>Taking output = 5.5 cum</b><br><b>Time required for</b><br>i) Positioning of tipper at loading point<br>ii) Loading by front end loader 1 cum bucket capacity @ 25 cum per hour<br>iii) Maneuvering, reversing, dumping and turning for return<br>iv) Waiting time, unforeseen contingencies etc<br><b>Total</b><br><b>a) Machinery</b><br>Tipper 5.5 tonnes capacity<br>Front end-loader 1 cum bucket capacity @ 25 cum/hour<br>Overheads @ 12 % on (a)<br><b>(c) Contractor's profit @ 10% on (a+b)</b><br>Cost for 5.5 cum = a+b+c<br><b>Rate per cum = (a+b+c) / 5.5</b><br><b>Unloading will be by tipping.</b> | hour<br>hour | 1 Min<br>13 Min<br>2 Min<br>4 Min<br>20 Min<br>0.330<br>0.330 | 1426.00<br>1419.00 | 470.58<br>468.27<br>112.66<br>105.15<br>1156.66<br>210.30 |
|         |             |               | <b>say</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |              |                                                               |                    | 210.00                                                    |



| Sl. No. | SBBS No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Unit | Quantity | Rate | Amount in Rs. |
|---------|----------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|------|---------------|
| 8       | 1.2      |               | <p>Loading and Unloading Lime, Aggregate, Stone Boulder, Brick Aggregate, Kankar, Building Rubbish, Crushed Slag, Stone for Masonry Work by Mechanical Means</p> <p>i Loading of Lime, Aggregate, Stone Boulder, Brick Aggregate, Kankar, Building Rubbish, Crushed Slag, Stone for Masonry Work by mechanical means including a lead upto 30 m<br/>Placing tipper at loading point, loading with front end loader excluding time for haulage and return trip.</p> <p>Unit = cum<br/>Taking output = 5.5 cum<br/>Time required for</p> <p>i Positioning of tipper at loading point Min 1.000</p> <p>ii Loading by front end loader 1 cum bucket capacity @ 45 cum per hour Min 7.330</p> <p>iii Waiting time, unforeseen contingencies, etc. Min 2.000</p> <p>Total Min 10.330</p> <p>a) Machinery hour 0.172 1426.00 245.27<br/>Tipper 10 t capacity hour 0.122 1419.00 173.12<br/>Front end-loader 1 cum bucket capacity @ 45 cum per hour 50.21</p> <p>b) Overheads @ 12 % 46.86</p> <p>c) Contractors Profit @ 10.0 % 515.46</p> <p>Cost for 5.5 cum = a+b+c 93.72</p> <p>Rate per cum = (a+b)/5.5</p> <p>Unloading of Earth, Sand, Lime, Moorum, Aggregate, Stone Boulder, Brick Aggregate, Kankar, Building Rubbish, Manure, Crushed Slag, Flyash, Stone for Masonry Work by mechanical means.</p> <p>Unit = cum<br/>Taking output = 5.5 cum<br/>Placing tipper at unloading point excluding time for haulage and return trip</p> <p>Time required for</p> <p>i Positioning of tipper at loading point Min 1.000</p> <p>ii Manoeuvring, reversing, dumping and turning for return Min 2.000</p> <p>iii Waiting time, unforeseen contingencies, etc. Min 2.000</p> <p>Total Min 5.000</p> <p>a) Machinery hour 0.080 1426.00 114.08<br/>Tipper 10 t capacity 13.69</p> <p>b) Overheads @ 12 % on (a) 12.78</p> <p>c) Contractors Profit @ 10.0 % on (b) 140.55</p> <p>Cost for 5.5 cum = a+b 25.55</p> <p>Rate per cum = (a+b)/5.5</p> <p>Total loading and unloading by mechanical means 119.27</p> |      |          |      |               |
| 8       | 1.2      | RCD           | <p>Loading and Unloading of Boulders by Manual Means</p> <p>Unit = cum<br/>Taking output = 5.5 cum</p> <p>a) Labour day 0.110 397.00 43.67<br/>Mate day 0.750 373.00 279.75<br/>Mazdoor for loading and unloading</p> <p>b) Machinery hour 0.750 1426.00 1069.50<br/>Tipper 5.5 tonne capacity 167.15<br/>Overheads @ 12% on (a+b) 156.01<br/>(d) Contractor's profit @ 10% on (a+b+c) 1716.08<br/>Cost for 5.5 cum = a+b+c+d 312.01</p> <p>Rate per cum = (a+b+c+d)/5.5</p> <p>Unloading will be by tipping. say 312.00</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |          |      |               |
| 9       | 1.3      | RCD           | <p>Loading and Unloading of Cement or Steel by Manual Means</p> <p>Unit = tonne<br/>Taking output = 10 tonnes</p> <p>a) Labour day 0.080 397.00 31.76<br/>Mate day 2.000 373.00 746.00<br/>Mazdoor for loading and unloading</p> <p>b) Machinery hour 2.000 934.30 1868.60<br/>Truck 10 tonne capacity 317.56<br/>Overheads @ 12 % on (a+b) 296.39<br/>(d) Contractor's profit @ 10% on (a+b+c)</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |      |               |



| Sl. No. | SDB No. | MORTAR Ref. No. | DESCRIPTION                                                                                                                                                                                                          | Unit | Quantity | Rate             | Amount (Rs.) |
|---------|---------|-----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|------------------|--------------|
|         |         |                 | Cost for 10 tonnes = $a+b+c+d$                                                                                                                                                                                       |      |          |                  | 1260.32      |
|         |         |                 | Rate per tonnes = $(a+b+c+d) / 10$                                                                                                                                                                                   |      |          | 126.03           | 1260.32      |
| 10      | 1.1     | (i)             | Loading of Lime, Aggregate, Stone Boulder, Brick Aggregate, Kankar, Building Rubbish, Crushed Slag, Stone for Masonry Work by manual means including a lead upto 30 m<br>Unit = cum<br>Taking output = 5.5 cum       |      |          |                  |              |
|         |         | a)              | Labour                                                                                                                                                                                                               | day  | 0.02     | 397.00           | 7.94         |
|         |         |                 | Mate                                                                                                                                                                                                                 | day  | 0.50     | 373.00           | 186.50       |
|         |         | b)              | Machinery                                                                                                                                                                                                            | hour | 0.50     | 934.30           | 467.15       |
|         |         | c)              | Overheads @ 12% on (a+b)                                                                                                                                                                                             |      |          |                  | 79.39        |
|         |         | d)              | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                 |      |          |                  | 74.10        |
|         |         |                 | Cost for 5.5 cum = $a+b+c+d$                                                                                                                                                                                         |      |          |                  | 815.09       |
|         |         |                 | Rate per cum = $(a+b+c+d) / 5.5$                                                                                                                                                                                     |      |          |                  | 148.20       |
|         |         |                 | Total Cost                                                                                                                                                                                                           | Cum  |          |                  | 148.2        |
| 11      |         | (ii)            | Loading of Earth, Sand, Moorum, Manure, Flyash by manual means including a lead upto 30 m.<br>Unit = cum<br>Taking output = 5.5 cum                                                                                  |      |          |                  |              |
|         |         | a)              | Labour                                                                                                                                                                                                               | day  | 0.01     | 397.00           | 3.97         |
|         |         |                 | Mate                                                                                                                                                                                                                 | day  | 0.25     | 373.00           | 93.25        |
|         |         | b)              | Machinery                                                                                                                                                                                                            | hour | 0.25     | 934.30           | 233.58       |
|         |         | c)              | Overheads @ 12% on (a+b)                                                                                                                                                                                             |      |          |                  | 39.70        |
|         |         | d)              | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                 |      |          |                  | 37.05        |
|         |         |                 | Cost for 5.5 cum = $a+b+c+d$                                                                                                                                                                                         |      |          |                  | 407.54       |
|         |         |                 | Rate per cum = $(a+b+c+d) / 5.5$                                                                                                                                                                                     |      |          |                  | 74.10        |
|         |         |                 | Total Cost                                                                                                                                                                                                           | Cum  |          |                  | 74.1         |
| 12      |         | (iii)           | Unloading of Lime, Aggregate, Stone Boulder, Brick Aggregate, Kankar, Building Rubbish, Crushed Slag, Stone for Masonry Work by mechanical means including a lead upto 30 m<br>Unit = cum<br>Taking output = 5.5 cum |      |          |                  |              |
|         |         | a)              | Labour                                                                                                                                                                                                               | day  | 0.01     | 397.00           | 3.97         |
|         |         |                 | Mate                                                                                                                                                                                                                 | day  | 0.25     | 373.00           | 93.25        |
|         |         | b)              | Machinery                                                                                                                                                                                                            | hour | 0.25     | 934.30           | 233.58       |
|         |         | c)              | Overheads @ 12% on (a+b)                                                                                                                                                                                             |      |          |                  | 39.70        |
|         |         | d)              | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                 |      |          |                  | 37.05        |
|         |         |                 | Cost for 5.5 cum = $a+b+c+d$                                                                                                                                                                                         |      |          |                  | 407.54       |
|         |         |                 | Rate per cum = $(a+b+c+d) / 5.5$                                                                                                                                                                                     |      |          |                  | 74.10        |
|         |         |                 | Total Cost                                                                                                                                                                                                           | Cum  |          |                  | 74.1         |
|         |         |                 | Total Loading & Unloading of Stone Aggregate                                                                                                                                                                         | Cum  |          | = 148.2 + 74.1 = | 222.30       |
| 13      |         | (iv)            | Unloading of Earth, Sand, Moorum, Manure, Flyash by manual means including a lead upto 30 m.<br>Unit = cum<br>Taking output = 5.5 cum                                                                                |      |          |                  |              |
|         |         | a)              | Labour                                                                                                                                                                                                               | day  | 0.01     | 397.00           | 1.99         |
|         |         |                 | Mate                                                                                                                                                                                                                 | day  | 0.13     | 373.00           | 46.63        |
|         |         | b)              | Machinery                                                                                                                                                                                                            | hour | 0.166    | 934.30           | 155.09       |
|         |         | c)              | Overheads @ 12% on (a+b)                                                                                                                                                                                             |      |          |                  | 24.44        |
|         |         | d)              | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                 |      |          |                  | 22.81        |
|         |         |                 | Cost for 5.5 cum = $a+b+c+d$                                                                                                                                                                                         |      |          |                  | 250.96       |
|         |         |                 | Rate per cum = $(a+b+c+d) / 5.5$                                                                                                                                                                                     |      |          |                  | 45.63        |
|         |         |                 | Total Cost                                                                                                                                                                                                           | Cum  |          |                  | 45.6         |
|         |         |                 | Total Loading & Unloading of Sand / Moorum                                                                                                                                                                           | Cum  |          | = 74.1 + 45.63 = | 119.73       |
| 14      | 1.3     | (i)             | Loading, Unloading and Stacking of Bricks by Manual Means<br>Loading of Bricks by manual means including a lead upto 30 m                                                                                            |      |          |                  |              |



| Sl. No. | SDB Sl. No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                        | Unit       | Quantity | Rate   | Amount in Rs  |
|---------|-------------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|----------|--------|---------------|
|         |             |               | Unit = 1000 Nos.<br>Taking output = 2000 Nos.                                                                                                                                                      |            |          |        |               |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                      | day        | 0.01     | 397.00 | 3.97          |
|         |             |               | Mate                                                                                                                                                                                               | day        | 0.25     | 373.00 | 93.25         |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                |            |          |        |               |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                   | hour       | 0.33     | 934.30 | 308.32        |
|         |             |               | Truck                                                                                                                                                                                              |            |          |        | 48.66         |
|         |             | c)            | Overheads @ 12 % on (a+b)                                                                                                                                                                          |            |          |        | 45.42         |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                               |            |          |        | 499.62        |
|         |             |               | Cost for 2000 Nos. = a+b+c+d                                                                                                                                                                       |            |          |        | 249.81        |
|         |             |               | Rate for 1000 bricks = (a+b+c+d)/2                                                                                                                                                                 |            |          |        | 249.81        |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                  | <b>no.</b> |          |        | 249.81        |
| 15      |             | (ii)          | Unloading and Stacking of Bricks by manual means including a<br>Unit = 1000 Nos.<br>Taking output = 2000 Nos.                                                                                      |            |          |        |               |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                      | day        | 0.01     | 397.00 | 3.97          |
|         |             |               | Mate                                                                                                                                                                                               | day        | 0.25     | 373.00 | 93.25         |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                |            |          |        |               |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                   | hour       | 0.33     | 934.30 | 308.32        |
|         |             |               | Truck                                                                                                                                                                                              |            |          |        | 48.66         |
|         |             | c)            | Overheads @ 12% on (a+b)                                                                                                                                                                           |            |          |        | 45.42         |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                               |            |          |        | 499.62        |
|         |             |               | Cost for 2000 Nos. = a+b+c+d                                                                                                                                                                       |            |          |        | 249.81        |
|         |             |               | Rate for 1000 bricks = (a+b+c+d)/2                                                                                                                                                                 |            |          |        | 249.81        |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                  | <b>no.</b> |          |        | 249.81        |
|         |             |               | <b>Total Loding &amp; Unloading of Brick Per 1000 = 249.81 + 249.81 =</b>                                                                                                                          |            |          |        | <b>499.62</b> |
| 16      |             | (i)           | Loading and Unloading of Cement by Manual Means<br>Loading of Cement by manual means including a lead upto 30 m<br>Unit = t<br>Taking output = 10 t                                                |            |          |        |               |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                      | day        | 0.06     | 397.00 | 23.82         |
|         |             |               | Mate                                                                                                                                                                                               | day        | 1.50     | 373.00 | 559.50        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                |            |          |        |               |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                   | hour       | 1.00     | 934.30 | 934.30        |
|         |             |               | Truck                                                                                                                                                                                              |            |          |        | 182.11        |
|         |             | c)            | Overheads @ 12 % on (a+b)                                                                                                                                                                          |            |          |        | 169.97        |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                               |            |          |        | 1869.71       |
|         |             |               | Cost for 10 t = a+b+c+d                                                                                                                                                                            |            |          |        | 186.97        |
|         |             |               | Rate per tonnes = (a+b+c+d)/10                                                                                                                                                                     |            |          |        | 186.97        |
|         |             |               | <b>Total Cost including</b>                                                                                                                                                                        | <b>t</b>   |          |        | 186.97        |
| 17      |             | (ii)          | Unloading of Cement by manual means including a lead upto 30 m<br>Unit = t<br>Taking output = 10 t                                                                                                 |            |          |        |               |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                      | day        | 0.06     | 397.00 | 23.82         |
|         |             |               | Mate                                                                                                                                                                                               | day        | 1.50     | 373.00 | 559.50        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                |            |          |        |               |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                   | hour       | 1.00     | 934.30 | 934.30        |
|         |             |               | Truck                                                                                                                                                                                              |            |          |        | 182.11        |
|         |             | c)            | Overheads @12 % on (a+b)                                                                                                                                                                           |            |          |        | 169.97        |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                               |            |          |        | 1869.71       |
|         |             |               | Cost for 10 t = a+b+c+d                                                                                                                                                                            |            |          |        | 186.97        |
|         |             |               | Rate per tonnes = (a+b+c+d)/10                                                                                                                                                                     |            |          |        | 186.97        |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                  | <b>t</b>   |          |        | 186.97        |
|         |             |               | <b>Total Loding &amp; Unloading of Cement = 186.97 + 186.97 =</b>                                                                                                                                  |            |          |        | <b>373.94</b> |
| 18      | 1.5         | (i)           | Loading and Unloading of Structural Steel and Steel Bars by manual means<br>Loading of Structural Steel, Steel Bars by manual means including a lead upto 30 m<br>Unit = t<br>Taking output = 10 t |            |          |        |               |



| Sl. No. | Particulars                                                                                      | Unit     | Quantity | Rate   | Amount in Rs. |
|---------|--------------------------------------------------------------------------------------------------|----------|----------|--------|---------------|
|         | <b>(i) Labour</b>                                                                                |          |          |        |               |
|         | Mate                                                                                             | day      | 0.07     | 397.00 | 27.79         |
|         | Mazdoor (Unskilled)                                                                              | day      | 1.80     | 373.00 | 671.40        |
|         | <b>(ii) Machinery</b>                                                                            |          |          |        |               |
|         | Truck                                                                                            | hour     | 1.00     | 934.30 | 934.30        |
|         | c) Overheads @ 12% on (a+b)                                                                      |          |          |        | 196.02        |
|         | d) Contractor's profit @ 10% on (a+b+c)                                                          |          |          |        | 182.95        |
|         | Cost for 10 t = a+b+c+d                                                                          |          |          |        | 2012.46       |
|         | Rate per tonnes = (a+b+c+d)/10                                                                   |          |          |        | 201.25        |
|         | <b>Total Cost</b>                                                                                | <b>t</b> |          |        | 201.25        |
| 19      | <b>(ii) Unloading of Structural Steel, Steel Bars by manual means including a lead upto 30 m</b> |          |          |        |               |
|         | Unit = t                                                                                         |          |          |        |               |
|         | Taking output = 10 t                                                                             |          |          |        |               |
|         | <b>a) Labour</b>                                                                                 |          |          |        |               |
|         | Mate                                                                                             | day      | 0.07     | 397.00 | 27.79         |
|         | Mazdoor (Unskilled)                                                                              | day      | 1.80     | 373.00 | 671.40        |
|         | <b>b) Machinery</b>                                                                              |          |          |        |               |
|         | Truck                                                                                            | hour     | 1.00     | 934.30 | 934.30        |
|         | c) Overheads @ 12% on (a+b)                                                                      |          |          |        | 196.02        |
|         | d) Contractor's profit @ 10% on (a+b+c)                                                          |          |          |        | 182.95        |
|         | Cost for 10 t = a+b+c+d                                                                          |          |          |        | 2012.46       |
|         | Rate per tonnes = (a+b+c+d)/10                                                                   |          |          |        | 201.25        |
|         | <b>Total Cost</b>                                                                                | <b>t</b> |          |        | 201.25        |
|         | <b>Total Loading &amp; Unloading of Steel</b>                                                    | <b>t</b> |          |        | 402.50        |
| 20      | <b>1.6 Loading and Unloading of Bitumen Drums by Manual Means</b>                                |          |          |        |               |
|         | <b>(i) Loading of Bitumen Drums by manual means including a lead upto 30 m</b>                   |          |          |        |               |
|         | Unit = t                                                                                         |          |          |        |               |
|         | Taking output = 10 t                                                                             |          |          |        |               |
|         | <b>a) Labour</b>                                                                                 |          |          |        |               |
|         | Mate                                                                                             | day      | 0.06     | 397.00 | 23.82         |
|         | Mazdoor (Unskilled)                                                                              | day      | 1.60     | 373.00 | 596.80        |
|         | <b>b) Machinery</b>                                                                              |          |          |        |               |
|         | Truck                                                                                            | hour     | 1.25     | 934.30 | 1167.88       |
|         | c) Overheads @ 12% on (a+b)                                                                      |          |          |        | 214.82        |
|         | d) Contractor's profit @ 10% on (a+b+c)                                                          |          |          |        | 200.31        |
|         | Cost for 10 t = a+b+c+d                                                                          |          |          |        | 2203.43       |
|         | Rate per tonnes = (a+b+c+d)/10                                                                   |          |          |        | 220.34        |
|         | <b>Total Cost</b>                                                                                | <b>t</b> |          |        | 220.34        |
| 21      | <b>(ii) Unloading of Bitumen Drums by Manual Means including a lead upto 30 m</b>                |          |          |        |               |
|         | Unit = t                                                                                         |          |          |        |               |
|         | Taking output = 10 t                                                                             |          |          |        |               |
|         | <b>a) Labour</b>                                                                                 |          |          |        |               |
|         | Mate                                                                                             | day      | 0.05     | 397.00 | 19.85         |
|         | Mazdoor (Unskilled)                                                                              | day      | 1.20     | 373.00 | 447.60        |
|         | <b>b) Machinery</b>                                                                              |          |          |        |               |
|         | Truck                                                                                            | hour     | 1.25     | 934.30 | 1167.88       |
|         | c) Overheads @ 12% on (a+b)                                                                      |          |          |        | 196.24        |
|         | d) Contractor's profit @ 10% on (a+b+c)                                                          |          |          |        | 183.16        |
|         | Cost for 10 t = a+b+c+d                                                                          |          |          |        | 2014.72       |
|         | Rate per tonnes = (a+b+c+d)/10                                                                   |          |          |        | 201.47        |
|         | Note: The rate is inclusive of the self weight of drum                                           |          |          |        |               |
|         | <b>Total Cost</b>                                                                                | <b>t</b> |          |        | 201.47        |
|         | <b>Total Loading &amp; Unloading of Bitumen Drums</b>                                            | <b>t</b> |          |        | 421.81        |
| 22      | <b>1.9 Loading and Unloading of Hume Pipes</b>                                                   |          |          |        |               |
|         | <b>(i) Loading of RCC Hume pipes by mechanical means including a lead upto 30 m</b>              |          |          |        |               |
|         | A. 1000 / 1200 mm dia Hume pipe                                                                  |          |          |        |               |
|         | Unit = per pipe                                                                                  |          |          |        |               |
|         | Taking output = 9 pipes                                                                          |          |          |        |               |
|         | <b>a) Labour</b>                                                                                 |          |          |        |               |
|         | Mate                                                                                             | day      | 0.02     | 397.00 | 7.94          |
|         | Mazdoor (Unskilled)                                                                              | day      | 0.50     | 373.00 | 186.50        |



| Sl. No. | DD Sl. No. | MORD Ref. No. | DESCRIPTION                                                                  | Unit     | Quantity | Rate               | Amount in Rs |
|---------|------------|---------------|------------------------------------------------------------------------------|----------|----------|--------------------|--------------|
|         |            | b)            | <b>Machinery</b>                                                             | hour     | 0.33     | 934.30             | 308.32       |
|         |            |               | Truck                                                                        | hour     | 0.33     | 831.00             | 274.23       |
|         |            |               | Crane                                                                        |          |          |                    | 93.24        |
|         |            | c)            | Overheads @ 12 % on (a+b)                                                    |          |          |                    | 87.02        |
|         |            | d)            | Contractor's profit @ 10% on (a+b+c)                                         |          |          |                    | 957.25       |
|         |            |               | Cost for 9 pipes = a+b+c+d                                                   |          |          |                    | 106.36       |
|         |            |               | Rate per pipe = (a+b+c+d)/9                                                  |          |          |                    | 106.36       |
|         |            |               | <b>Total Cost</b>                                                            | per p    |          |                    | 106.36       |
| 23      |            | C.            | <b>600/450 mm dia Hume pipe</b>                                              |          |          |                    |              |
|         |            |               | Unit = per pipe                                                              |          |          |                    |              |
|         |            |               | Taking output = 21 pipe                                                      |          |          |                    |              |
|         |            | a)            | <b>Labour</b>                                                                |          |          |                    |              |
|         |            |               | Mate                                                                         | day      | 0.02     | 397.00             | 7.94         |
|         |            |               | Mazdoor (Unskilled)                                                          | day      | 0.50     | 373.00             | 186.50       |
|         |            | b)            | <b>Machinery</b>                                                             |          |          |                    |              |
|         |            |               | Truck                                                                        | hour     | 0.33     | 934.30             | 308.32       |
|         |            |               | Crane                                                                        | hour     | 0.33     | 831.00             | 274.23       |
|         |            |               |                                                                              |          |          |                    | 93.24        |
|         |            | c)            | Overheads @ 12 % on (a+b)                                                    |          |          |                    | 87.02        |
|         |            | d)            | Contractor's profit @ 10% on (a+b+c)                                         |          |          |                    | 957.25       |
|         |            |               | Cost for 21 pipes = a+b+c+d                                                  |          |          |                    | 45.58        |
|         |            |               | Rate per pipe = (a+b+c+d)/21                                                 |          |          |                    | 45.58        |
|         |            |               | <b>Total Cost</b>                                                            | per p    |          |                    | 45.58        |
| 24      |            | (ii)          | Unloading of RCC Hume pipe by mechanical means including a lead upto 30 m    |          |          |                    |              |
|         |            | A.            | <b>1000/1200 mm dia RCC Hume pipes</b>                                       |          |          |                    |              |
|         |            |               | Unit = per pipe                                                              |          |          |                    |              |
|         |            |               | Taking output = 9 pipes                                                      |          |          |                    |              |
|         |            | a)            | <b>Labour</b>                                                                |          |          |                    |              |
|         |            |               | Mate                                                                         | day      | 0.02     | 397.00             | 7.94         |
|         |            |               | Mazdoor (Unskilled)                                                          | day      | 0.50     | 373.00             | 186.50       |
|         |            | b)            | <b>Machinery</b>                                                             |          |          |                    |              |
|         |            |               | Truck                                                                        | hour     | 0.20     | 934.30             | 186.86       |
|         |            |               | Crane                                                                        | hour     | 0.20     | 831.00             | 166.20       |
|         |            |               |                                                                              |          |          |                    | 65.70        |
|         |            | c)            | Overheads @ 12 % on (a+b)                                                    |          |          |                    | 61.32        |
|         |            | d)            | Contractor's profit @ 10% on (a+b+c)                                         |          |          |                    | 674.52       |
|         |            |               | Cost for 9 pipes = a+b+c+d                                                   |          |          |                    | 74.95        |
|         |            |               | Rate per pipe = (a+b+c+d)/9                                                  |          |          |                    | 74.95        |
|         |            |               | <b>Total Cost</b>                                                            | per p    |          |                    | 74.95        |
|         |            |               | <b>Total Loding &amp; Unloading of RCC Hume Pipe</b>                         | per Pipe |          | = 106.36 + 74.95 = | 181.31       |
|         |            |               | <b>Total Loding &amp; Unloading of RCC Hume Pipe</b>                         | m        |          | = 181.31 / 2.50 =  | 72.52        |
| 24      |            | C.            | <b>600/450 mm dia Hume pipe</b>                                              |          |          |                    |              |
|         |            |               | Unit = per pipe                                                              |          |          |                    |              |
|         |            |               | Taking output = 21 pipes                                                     |          |          |                    |              |
|         |            | a)            | <b>Labour</b>                                                                |          |          |                    |              |
|         |            |               | Mate                                                                         | day      | 0.02     | 397.00             | 7.94         |
|         |            |               | Mazdoor (Unskilled)                                                          | day      | 0.50     | 373.00             | 186.50       |
|         |            | b)            | <b>Machinery</b>                                                             |          |          |                    |              |
|         |            |               | Truck                                                                        | hour     | 0.20     | 934.30             | 186.86       |
|         |            |               | Crane                                                                        | hour     | 0.20     | 831.00             | 166.20       |
|         |            |               |                                                                              |          |          |                    | 65.70        |
|         |            | c)            | Overheads @ 12 % on (a+b)                                                    |          |          |                    | 61.32        |
|         |            | d)            | Contractor's profit @ 10% on (a+b+c)                                         |          |          |                    | 674.52       |
|         |            |               | Cost for 21 pipes = a+b+c+d                                                  |          |          |                    | 32.12        |
|         |            |               | Rate per pipe = (a+b+c+d)/21                                                 |          |          |                    | 32.12        |
|         |            |               | <b>Total Cost</b>                                                            | per p    |          |                    | 32.12        |
|         |            |               | <b>Total Loding &amp; Unloading of RCC Hume Pipe</b>                         | per Pipe |          | = 45.58 + 32.12 =  | 77.70        |
|         |            |               | <b>Total Loding &amp; Unloading of RCC Hume Pipe</b>                         | m        |          | = 77.7 / 2.50 =    | 31.08        |
| 1       | 1.16       | 100           | <b>Setting Out Pillars</b>                                                   |          |          |                    |              |
|         |            |               | Unit = 1 No.                                                                 |          |          |                    |              |
|         |            |               | Analysis of rates per pillar shall account for following :                   |          |          |                    |              |
|         |            |               | Typical Benchmark 1 no. as per Dwg no. 200.1 of MORD Data Book ( Page 1-18 ) |          |          |                    |              |
|         |            |               | The rate analysis for a typical benchmark as per dwg                         |          |          |                    |              |
|         |            |               | 1. Excavation                                                                | cum      | 0.325    | 410.66             | 133.46       |
|         |            |               | 2. P.C.C. grade M 10                                                         | cum      | 0.100    | 7188.28            | 718.83       |
|         |            |               | 3. Brick Masonry in CM 1:4                                                   | cum      | 0.475    | 7084.03            | 3364.91      |
|         |            |               | 4. Plastering with CM 1:4, 15 mm thick cement plaster on Brick work.         | sqm      | 2.630    | 208.74             | 549.00       |



| Sl. No. | Particulars | Description                                                                                                                                                                                                                                                                                                                                                                                                                     | Unit | Quantity | Rate    | Amount in Rs. |
|---------|-------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|---------|---------------|
|         |             | Add 5 per cent cost of items No. 1 to 4 for white washing.                                                                                                                                                                                                                                                                                                                                                                      |      |          |         | 240.51        |
|         |             | Sub Total                                                                                                                                                                                                                                                                                                                                                                                                                       | NO   |          |         | 5004.51       |
|         | A           | Total 4 Nos. of Pillars required for 1 Km.                                                                                                                                                                                                                                                                                                                                                                                      | NO   | 1        | 5004.51 | 5004.51       |
|         |             | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                      | NO   |          |         | 5004.51       |
|         |             | Unit = 1 No.                                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |         |               |
|         |             | Analysis of rates per pillar shall account for following                                                                                                                                                                                                                                                                                                                                                                        |      |          |         |               |
|         |             | Reference Pillar 1 nos. as per Diagram 200.2                                                                                                                                                                                                                                                                                                                                                                                    |      |          |         |               |
|         |             | of MORD (Data Book Page 1-18)                                                                                                                                                                                                                                                                                                                                                                                                   |      |          |         |               |
|         |             | The rate analysis for a typical benchmark as per diag                                                                                                                                                                                                                                                                                                                                                                           |      |          |         |               |
|         |             | 1. Excavation                                                                                                                                                                                                                                                                                                                                                                                                                   | cum  | 0.192    | 410.66  | 78.83         |
|         |             | 2. P.C.C. grade M 1:4                                                                                                                                                                                                                                                                                                                                                                                                           | cum  | 0.060    | 7108.28 | 431.30        |
|         |             | 3. Brick Masonry in C.M 1:4                                                                                                                                                                                                                                                                                                                                                                                                     | cum  | 0.194    | 7084.03 | 1367.21       |
|         |             | 4. Plastering with CM 1:4, 15 mm thick cement plaster on Brick work                                                                                                                                                                                                                                                                                                                                                             | sqm  | 1.500    | 200.74  | 311.12        |
|         |             | Add 5 per cent cost of items No. 1 to 4 for white washing.                                                                                                                                                                                                                                                                                                                                                                      |      |          |         | 109.52        |
|         |             | Sub Total                                                                                                                                                                                                                                                                                                                                                                                                                       | NO   |          |         | 2300.00       |
|         | B           | Total 4 Nos. of reference pillars required for 1 Km.                                                                                                                                                                                                                                                                                                                                                                            | NO   | 1        | 2300.00 | 2300.00       |
|         |             | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                      | NO   |          |         | 2300.00       |
| 3       | 2.2<br>(ii) | 201 Clearing and grubbing Road Land                                                                                                                                                                                                                                                                                                                                                                                             |      |          |         |               |
|         |             | Clearing and grubbing Road Land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 500mm, removal of stumps of such trees cut earlier and unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specifications, clause 201.11 |      |          |         |               |
|         |             | By Manual Means                                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |         |               |
|         | (A)         | In area of non thorny jungle                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |         |               |
|         | a)          | Labour                                                                                                                                                                                                                                                                                                                                                                                                                          | day  | 6.00     | 397.00  | 2382.00       |
|         |             | Mate                                                                                                                                                                                                                                                                                                                                                                                                                            | day  | 150.00   | 373.00  | 55950.00      |
|         |             | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                             |      |          |         |               |
|         | b)          | Machinery                                                                                                                                                                                                                                                                                                                                                                                                                       | hour | 1.00     | 676.00  | 676.00        |
|         |             | Tractor with trailer                                                                                                                                                                                                                                                                                                                                                                                                            |      |          |         | 7080.96       |
|         | c)          | Overheads @ 12 % on (a+b)                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |         | 6608.96       |
|         | d)          | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                            |      |          |         | 72697.86      |
|         |             | Rate per hectare = (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |         | 72697.86      |
|         |             | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                      | Ha.  |          |         |               |
|         |             | EARTHWORK                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |         |               |
| 3       | 3.3         | 301.5 Construction of embankment with material obtained from road way cutting                                                                                                                                                                                                                                                                                                                                                   |      |          |         |               |
|         |             | Construction of embankment with approved materials deposited at site and obtained from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification clause 301.5                                                                                                                                              |      |          |         |               |
|         |             | Unit = cum                                                                                                                                                                                                                                                                                                                                                                                                                      |      |          |         |               |
|         |             | Taking output = 100 cum                                                                                                                                                                                                                                                                                                                                                                                                         |      |          |         |               |
|         | a)          | Labour                                                                                                                                                                                                                                                                                                                                                                                                                          | day  | 0.02     | 397.00  | 7.94          |
|         |             | Mate                                                                                                                                                                                                                                                                                                                                                                                                                            | day  | 0.50     | 373.00  | 186.50        |
|         |             | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                             |      |          |         |               |
|         | b)          | Machinery                                                                                                                                                                                                                                                                                                                                                                                                                       | hour | 0.50     | 2992.00 | 0.00          |
|         |             | Doser D-50 for spreading @ 100 cum per hour                                                                                                                                                                                                                                                                                                                                                                                     | hour | 0.50     | 646.00  | 323.00        |
|         |             | Tractor mounted grader arrangement for grading @ 100 cum per hour                                                                                                                                                                                                                                                                                                                                                               | hour | 2.00     | 752.00  | 1504.00       |
|         |             | Water tanker 8 KL capacity                                                                                                                                                                                                                                                                                                                                                                                                      | hour | 1.25     | 1593.00 | 1991.25       |
|         |             | Three wheel 80-100 KN Static Roller                                                                                                                                                                                                                                                                                                                                                                                             |      |          |         |               |
|         | c)          | Material                                                                                                                                                                                                                                                                                                                                                                                                                        | kl   | 12.00    | 56.20   | 674.40        |
|         |             | Water                                                                                                                                                                                                                                                                                                                                                                                                                           |      |          |         | 562.45        |
|         | d)          | Overheads @ 12% on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                      |      |          |         | 524.95        |
|         | e)          | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                          |      |          |         | 5774.49       |
|         |             | Rate for 100 cum = (a+b+c+d+e)                                                                                                                                                                                                                                                                                                                                                                                                  |      |          |         | 57.74         |
|         |             | Rate per cum = (a+b+c+d+e)/100-                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |         |               |
|         |             | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                      | CUM  |          | 4       | 57.74         |
| 9       | 3.5         | (ii) Excavation in Soil with Doser with lead upto 100 m                                                                                                                                                                                                                                                                                                                                                                         |      |          |         |               |
|         |             | Excavation for roadway in soil by mechanical means including cutting and pushing the earth to site of embankment upto a distance of 100 m, including trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections.                                                                                                                                                                       |      |          |         |               |
|         |             | Unit = cum                                                                                                                                                                                                                                                                                                                                                                                                                      |      |          |         |               |
|         |             | Taking output = 180 cum                                                                                                                                                                                                                                                                                                                                                                                                         |      |          |         |               |
|         | a)          | Labour                                                                                                                                                                                                                                                                                                                                                                                                                          |      |          |         |               |
|         |             | Mate                                                                                                                                                                                                                                                                                                                                                                                                                            | day  | 0.08     | 397.00  | 31.76         |
|         |             | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                             | day  | 2.00     | 373.00  | 746.00        |
|         | b)          | Machinery                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |         |               |
|         |             | Doser D-50 @ 50 cum per hour (cutting with pushing)                                                                                                                                                                                                                                                                                                                                                                             | hour | 3.60     | 5610.00 | 20196.00      |
|         | c)          | Overheads @ 12 % on (a+b)                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |         | 2516.80       |
|         | d)          | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                            |      |          |         | 2349.06       |

| Sl. No. | SDB Sl. No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Unit | Quantity | Rate     | Amount in Rs |
|---------|-------------|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|----------|--------------|
|         |             |               | Cost for 360 cum = a+b+c+d                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |          | 25,839.67    |
|         |             |               | Rate per cum = (a+b+c+d)/180                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |          |          | 143.55       |
|         |             |               | Compensation for earth                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | cum  | 1.00     | 35.01    | 35.01        |
|         |             |               | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | CUM  |          | B        | 178.56       |
|         |             |               | Total Cost (A+B)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |          |          | 236.31       |
| 10      | 3.5         | (iii)         | <b>Excavation in Soil using Hydraulic Excavator and Tippers with disposal upto 1000 m</b><br>Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross-sections, and transporting to the embankment location with a lift upto 1.5 m and lead upto 1000 m as per Technical Specification Clause 302.3<br>Unit = cum<br>Taking output = 360 cum |      |          |          |              |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |          |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | day  | 0.08     | 397.00   | 31.76        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | day  | 2.00     | 373.00   | 746.00       |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |          |          |              |
|         |             |               | Hydraulic excavator 0.9 cum bucket capacity @ 100 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                | hour | 3.60     | 2,272.00 | 8,179.20     |
|         |             |               | Tipper 5.5 cum capacity, 4 trips per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | hour | 15.00    | 1,426.00 | 21,390.00    |
|         |             | c)            | Overheads @ 12 % on (a+b)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |      |          |          | 3641.64      |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |          |          | 3398.86      |
|         |             |               | Cost for 360 cum = a+b+c+d                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |          | 37,387.45    |
|         |             |               | Rate per cum = (a+b+c+d)/360                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |          |          | 103.85       |
|         |             |               | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | CUM  |          |          | 103.85       |
| 11      | 3.4         | 301.5 (A)     | <b>Construction of Embankment with Material Obtained from Borrow Pits</b><br>Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a <u>lead upto 1000 m</u> as per Technical Specification Clause 301.5<br>Unit = cum<br>Taking output = 100 cum                                                                                  |      |          |          |              |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |          |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | day  | 0.04     | 397.00   | 15.88        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | day  | 1.00     | 373.00   | 373.00       |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |          |          |              |
|         |             |               | Hydraulic Excavator 0.9 cum bucket capacity @ 60 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                 | hour | 1.67     | 2272.00  | 3,794.24     |
|         |             |               | Tipper 5.5 cum with 10 t capacity                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | hour | 4.50     | 1,426.00 | 6,417.00     |
|         |             |               | Add 10 % of the cost of carriage by tipper                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |          | 641.70       |
|         |             |               | Dozer D-50 for spreading @ 100 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | hour | 0.50     | 2,997.00 | 1,498.50     |
|         |             |               | Tractor mounted grader arrangement @ 200 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                         | hour | 1.00     | 646.00   | 646.00       |
|         |             |               | Water tanker 6 kl capacity                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | hour | 2.00     | 752.00   | 1,504.00     |
|         |             |               | Three wheel 80-100 kN Static Roller                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour | 1.25     | 1,593.00 | 1,991.25     |
|         |             | c)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |          |              |
|         |             |               | Water                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | kl   | 12.00    | 56.20    | 674.40       |
|         |             |               | Compensation for earth taken from private land                                                                                                                                                                                                                                                                                                                                                                                                                                                                | cum  | 100.00   | 35.01    | 3,501.00     |
|         |             | d)            | Overheads @12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |          | 2526.84      |
|         |             | e)            | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |          |          | 2358.38      |
|         |             |               | Cost for 100 cum = a+b+c+d+e                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |          |          | 25,942.19    |
|         |             |               | Rate per cum = (a+b+c+d+e)/100=                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |          | 259.42       |
|         |             |               | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | CUM  |          |          | 259.42       |
| 13      | 3.14        | 303.1         | <b>Construction of Subgrade and Earthen Shoulders</b><br>Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.<br>Unit = cum<br>Taking output = 100 cum                                                                                                    |      |          |          |              |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |          |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | day  | 0.04     | 397.00   | 15.88        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | day  | 1.00     | 373.00   | 373.00       |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |          |          |              |
|         |             |               | Hydraulic excavator 0.9 cum bucket capacity @ 100 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                | hour | 1.67     | 2272.00  | 3,794.24     |
|         |             |               | Tipper 5.5 cum capacity, 4 trips per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | hour | 4.50     | 1426.00  | 6,417.00     |
|         |             |               | Add 10 % of the cost of carriage to cover loading & unloading                                                                                                                                                                                                                                                                                                                                                                                                                                                 | cum  |          |          | 641.70       |
|         |             |               | Dozer D-50 for spreading @ 100 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | hour | 0.50     | 2997.00  | 1,498.50     |
|         |             |               | Tractor mounted grader arrangement for grading @ 100 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                                                             | hour | 1.00     | 646.00   | 646.00       |
|         |             |               | Water tanker with 6 kl capacity                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | hour | 2.00     | 752.00   | 1,504.00     |
|         |             |               | Three wheel 80-100 kN Static Roller                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour | 1.43     | 1,593.00 | 2,277.99     |
|         |             | c)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |          |              |
|         |             |               | Water                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | kl   | 12.00    | 56.20    | 674.40       |
|         |             |               | Compensation for earth taken from private land                                                                                                                                                                                                                                                                                                                                                                                                                                                                | cum  | 100.00   | 35.01    | 3,501.00     |



| Sl. No. | SDB Sl. No.  | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                              | Unit       | Quantity | Rate    | Amount in Rs.    |
|---------|--------------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|----------|---------|------------------|
|         |              | d)            | Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                              |            |          |         | 256.12           |
|         |              | e)            | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                   |            |          |         | 2390.50          |
|         |              |               | Cost for 100 cum = a+b+c+d+e                                                                                                                                                                                                                                                                                                                                                                                                                             |            |          |         | 26295.87         |
|         |              |               | Rate per cum = (a+b+c+d+e)/100                                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |         | 262.95           |
|         |              |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                        | <b>sqm</b> |          |         | <b>262.95</b>    |
|         |              |               | <b>PAVEMENT CRUST LAYERS</b>                                                                                                                                                                                                                                                                                                                                                                                                                             |            |          |         |                  |
| 14      | 4.1          | 401           | <b>Granular Sub-base with Well Graded Material (Table 400.1)</b>                                                                                                                                                                                                                                                                                                                                                                                         |            |          |         |                  |
|         |              | (A)           | <b>By Mix in Place Method</b>                                                                                                                                                                                                                                                                                                                                                                                                                            |            |          |         |                  |
|         |              |               | Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401                                                                                                                                  |            |          |         |                  |
|         |              |               | <b>For Grading I Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                            |            |          |         |                  |
|         |              |               | Unit = cum                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |          |         |                  |
|         |              |               | Taking output = 300 cum                                                                                                                                                                                                                                                                                                                                                                                                                                  |            |          |         |                  |
|         |              | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                            |            |          |         |                  |
|         |              |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                     | day        | 0.48     | 397.00  | 190.56           |
|         |              |               | Mazdoor (Skilled)                                                                                                                                                                                                                                                                                                                                                                                                                                        | day        | 2.00     | 472.00  | 944.00           |
|         |              |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                      | day        | 10.00    | 373.00  | 3730.00          |
|         |              | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |          |         |                  |
|         |              |               | Tractor Mounted Grader 110 HP @ 25 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                          | hour       | 12.00    | 646.00  | 7752.00          |
|         |              |               | Three wheel 80-100 kN Static Roller                                                                                                                                                                                                                                                                                                                                                                                                                      | hour       | 30.00    | 1593.00 | 47790.00         |
|         |              |               | Tractor with Rotavator 25 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                                   | hour       | 12.00    | 693.00  | 8316.00          |
|         |              |               | Water tanker 6 kl capacity                                                                                                                                                                                                                                                                                                                                                                                                                               | hour       | 5.00     | 752.00  | 3760.00          |
|         |              | c)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                          |            |          |         |                  |
|         |              |               | Coarse graded granular sub-base material as per Table 400.2                                                                                                                                                                                                                                                                                                                                                                                              |            |          |         |                  |
|         |              |               | 53 mm to 9.5 mm @ 50 per cent                                                                                                                                                                                                                                                                                                                                                                                                                            | cum        | 180.00   | 915.67  | 164820.60        |
|         |              |               | 9.5 mm to 2.36 mm @ 20 per cent                                                                                                                                                                                                                                                                                                                                                                                                                          | cum        | 72.00    | 424.21  | 30543.12         |
|         |              |               | 2.36 mm below @ 30 per cent (Coarse Sand Screening)                                                                                                                                                                                                                                                                                                                                                                                                      | cum        | 108.00   | 262.42  | 28341.36         |
|         |              |               | Water                                                                                                                                                                                                                                                                                                                                                                                                                                                    | kl         | 30.00    | 56.20   | 1686.00          |
|         |              |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                          |            |          |         | 35744.88         |
|         |              | d)            | Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                              |            |          |         | 3336.185         |
|         |              | e)            | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                   |            |          |         | 366980.3         |
|         |              |               | Cost for 300 cum = a+b+c+d+e                                                                                                                                                                                                                                                                                                                                                                                                                             |            |          |         | 1223.27          |
|         |              |               | Rate per cum = (a+b+c+d+e)/300                                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |         |                  |
|         |              |               | <b>Add for Carriage Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                             |            |          |         |                  |
|         |              |               | 53 mm to 9.5 mm @ 50 per cent                                                                                                                                                                                                                                                                                                                                                                                                                            |            | 0.60     | 1992.12 | 1195.272         |
|         |              |               | 9.5 mm to 2.36 mm @ 20 per cent                                                                                                                                                                                                                                                                                                                                                                                                                          |            | 0.24     | 1992.12 | 478.1088         |
|         |              |               | 2.36 mm below @ 30 per cent (Coarse Sand Screening)                                                                                                                                                                                                                                                                                                                                                                                                      |            | 0.36     | 528.24  | 190.1664         |
|         |              |               | <b>Total Cost per Cum</b>                                                                                                                                                                                                                                                                                                                                                                                                                                |            |          |         | <b>308658.81</b> |
|         |              |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                        | <b>CUM</b> |          |         | <b>3,086,581</b> |
| 15      | 4.7<br>(3-A) | 405           | <b>Water Bound Macadam with Stone Screening Type "B" Gr- III</b>                                                                                                                                                                                                                                                                                                                                                                                         |            |          |         |                  |
|         |              |               | <b>WBM Grading 3</b>                                                                                                                                                                                                                                                                                                                                                                                                                                     |            |          |         |                  |
|         |              |               | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density, Grading 3 as per Technical Specification Clause 405. |            |          |         |                  |
|         |              | (A)           | <b>By Mechanical Means</b>                                                                                                                                                                                                                                                                                                                                                                                                                               |            |          |         |                  |
|         |              |               | Unit = cum                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |          |         |                  |
|         |              |               | Taking output = 360 cum                                                                                                                                                                                                                                                                                                                                                                                                                                  |            |          |         |                  |
|         |              | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                            |            |          |         |                  |
|         |              |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                     | day        | 0.68     | 397.00  | 269.96           |
|         |              |               | Mazdoor (Skilled)                                                                                                                                                                                                                                                                                                                                                                                                                                        | day        | 2.00     | 472.00  | 944.00           |
|         |              |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                      | day        | 15.00    | 373.00  | 5595.00          |
|         |              | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |          |         |                  |
|         |              |               | Tractor Mounted grader for grading @ 25 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                     | hour       | 14.40    | 646.00  | 9302.40          |
|         |              |               | Three wheel 80-100 kN static roller @ 8 cum per hour                                                                                                                                                                                                                                                                                                                                                                                                     | hour       | 45.00    | 1593.00 | 71685.00         |
|         |              |               | Water tanker 6 kl capacity                                                                                                                                                                                                                                                                                                                                                                                                                               | hour       | 24.00    | 752.00  | 18048.00         |
|         |              | c)            | <b>Material (Refer Tables 400.7, 8, 9 and 10)</b>                                                                                                                                                                                                                                                                                                                                                                                                        |            |          |         |                  |
|         |              |               | <b>Aggregate</b>                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |          |         |                  |
|         |              |               | Grading 3 53 mm to 22.4 mm @ 0.91 cum per 10 sqm for compacted thickness of 75 mm                                                                                                                                                                                                                                                                                                                                                                        | cum        | 435.60   | 1080.50 | 470665.80        |
|         |              |               | <b>Stone Screening</b>                                                                                                                                                                                                                                                                                                                                                                                                                                   |            |          |         |                  |
|         |              |               | Type B 11.2 mm for Grading 3 @ 0.18 cum per 10 sqm                                                                                                                                                                                                                                                                                                                                                                                                       | cum        | 86.40    | 424.21  | 36651.74         |
|         |              |               | Water                                                                                                                                                                                                                                                                                                                                                                                                                                                    | kl         | 144      | 56.20   | 8092.80          |
|         |              | d)            | Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                              |            |          |         | 74550.56         |
|         |              | e)            | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                   |            |          |         | 69580.53         |
|         |              |               | Cost for 360 cum = a+b+c+d+e                                                                                                                                                                                                                                                                                                                                                                                                                             |            |          |         | 765385.80        |
|         |              |               | Rate per cum = (a+b+c+d+e)/360                                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |         | 2126.07          |
|         |              | f)            | <b>CARRIAGE</b>                                                                                                                                                                                                                                                                                                                                                                                                                                          |            |          |         |                  |
|         |              |               | Stone material Grading 3 53 mm to 22.4 mm                                                                                                                                                                                                                                                                                                                                                                                                                | Cum        | 1.21     | 1992.12 | 2410.47          |



| Sl. No. | SDB Sl. No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Unit | Quantity | Rate      | Amount in Rs |
|---------|-------------|---------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|-----------|--------------|
|         |             |               | Stone Screening                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Cum  | 0.24     | 1864.83   | 447.56       |
|         |             |               | Rate per cum with carriage                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |           | 4984.09      |
|         |             |               | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | cum  |          |           | 4984.09      |
|         |             |               | <b>BITUMINOUS ITEMS</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |      |          |           |              |
| 16      | 5.1<br>(I)  | 502           | <b>Prime Coat ( Low Porosity )</b><br>Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502                                                                                                                                                                                                                                                             |      |          |           |              |
|         |             |               | Unit = sqm<br>Taking output = 1750 sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |          |           |              |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |           |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | day  | 0.04     | 397.00    | 15.88        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | day  | 1.00     | 373.00    | 373.00       |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |          |           |              |
|         |             |               | Hydraulic broom @ 1250 sqm per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour | 1.40     | 794.00    | 1,111.60     |
|         |             |               | Air compressor 210 cfm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | hour | 1.40     | 440.00    | 616.00       |
|         |             |               | Emulsion Sprayer @ 1750 sqm per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | hour | 1.00     | 1,350.00  | 1,350.00     |
|         |             |               | Water tanker 6 kl capacity 1 trip per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | hour | 0.50     | 752.00    | 376.00       |
|         |             | c)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |           |              |
|         |             |               | Bitumen emulsion (SS-1) @ 0.85 kg per sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | t    | 1.48     | 50,361.50 | 74,535.02    |
|         |             |               | Water                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | kl   | 3.00     | 56.20     | 168.60       |
|         |             |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |           | 9425.53      |
|         |             | d)            | Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |          |           | 8797.16      |
|         |             | e)            | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |          |           | 96768.80     |
|         |             |               | Cost of 1750 sqm = a+b+c+d+e                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |          |           | 55.30        |
|         |             |               | Rate per sqm = (a+b+c+d+e)/1750                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |           |              |
|         |             | f)            | <u>Carriage Cost</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |          |           |              |
|         |             |               | Bitumen Emulsion                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | ton  | 0.00085  | 1771.61   | 1.50         |
|         |             |               | Rate per sqm with carriage                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |           | 56.79        |
|         |             |               | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | sqm  |          |           | 56.79        |
| 17      | 5.2<br>(I)  | 503           | <b>Tack Coat</b><br>Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.3 kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503                                                                                                                                                                                                                                                                                                  |      |          |           |              |
|         |             |               | Unit = sqm<br>Taking output = 1750 sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |          |           |              |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |           |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | day  | 0.04     | 397.00    | 15.88        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | day  | 1.00     | 373.00    | 373.00       |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |          |           |              |
|         |             |               | Hydraulic broom @ 1250 sqm per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour | 1.40     | 794.00    | 1,111.60     |
|         |             |               | Air compressor 210 cfm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | hour | 1.40     | 440.00    | 616.00       |
|         |             |               | Emulsion Sprayer @ 1750 sqm per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | hour | 1.00     | 1,350.00  | 1,350.00     |
|         |             | c)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |           |              |
|         |             |               | Bitumen emulsion (RS-1) @ 0.275 kg per sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | t    | 0.48     | 48,921.50 | 23,482.32    |
|         |             | d)            | Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |      |          |           | 3233.86      |
|         |             | e)            | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      |          |           | 3018.27      |
|         |             |               | Cost of 1750 sqm = a+b+c+d+e                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |          |           | 33200.92     |
|         |             |               | Rate per sqm = (a+b+c+d+e)/1750                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |           | 18.97        |
|         |             |               | <u>Carriage Cost</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |          |           |              |
|         |             |               | Bitumen Emulsion                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | ton  | 0.00027  | 1771.61   | 0.49         |
|         |             |               | Rate per sqm with carriage                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |      |          |           | 19.46        |
|         |             |               | Total Cost                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | sqm  |          |           | 19.46        |
| 19      | 5.9<br>(II) | 508           | <b>Premix Carpet</b><br>Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. |      |          |           |              |
|         |             |               | <b>Case - II By Mechanical Means</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |      |          |           |              |
|         |             | (I)           | <b>Bitumen (S-90)</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |          |           |              |
|         |             |               | Unit = sqm<br>Taking output = 4000 sqm (80 cum)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |      |          |           |              |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |      |          |           |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | day  | 0.52     | 397.00    | 206.44       |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | day  | 10.00    | 373.00    | 3,730.00     |
|         |             |               | Mazdoor (Skilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | day  | 3.00     | 472.00    | 1,416.00     |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |      |          |           |              |
|         |             |               | HMP 30/40 t per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | hour | 6.00     | 31,459.00 | 188,754.00   |
|         |             |               | Electric generator set 125 KVA                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | hour | 6.00     | 1,642.00  | 9,852.00     |
|         |             |               | Front end loader 1 cum bucket capacity                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | hour | 6.00     | 1,419.00  | 8,514.00     |
|         |             |               | Tipper 5.5 10 t capacity                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | hour | 3.64     | 1,426.00  | 5,190.64     |
|         |             |               | Paver finisher                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | hour | 6.00     | 2,141.00  | 12,846.00    |
|         |             |               | Three wheel 80-100 kN static roller                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour | 16.00    | 1,593.00  | 25,488.00    |



| Sl. No. | SDB Sl. No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Unit                                                        | Quantity                                                                | Rate                                                                                   | Amount in Rs.                                                                                       |
|---------|-------------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------|-------------------------------------------------------------------------|----------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------|
|         |             | c)            | <b>Material</b><br>Bitumen (S-90) @ 14.60 kg per 10 sqm<br>Crushed stone chipping, 13.2 mm to 5.6 mm @ 0.27 cum per 10 sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | t<br>cum                                                    | 5.84<br>108.00                                                          | 50,930.50<br>697.55                                                                    | 292,434.10<br>75,335.50                                                                             |
|         |             | d)            | Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                             |                                                                         |                                                                                        | 75,451.99                                                                                           |
|         |             | e)            | Contractor's profit @ 10% on (a+b+c+d)<br>Cost of 4000 sqm = a+b+c+d+e<br>Rate per sqm = (a+b+c+d+e)/4000                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                             |                                                                         |                                                                                        | 70,421.10<br>77,464.04<br>19.36                                                                     |
|         |             |               | <b>Carriage Cost</b><br>Bitumen (S-90)<br>Stone chips                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | ton<br>cum                                                  | 0.00146<br>0.02700                                                      | 1771.61<br>1864.83                                                                     | 2.57<br>50.35                                                                                       |
|         |             |               | Rate per sqm with carriage                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                                             |                                                                         |                                                                                        | 246.67                                                                                              |
|         |             |               | Total Cost including 1 % LABOUR CESS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | sqm                                                         |                                                                         |                                                                                        | 249.06                                                                                              |
| 20      | 5.12        | 510           | <b>Seal Coat</b><br>Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type B, as per Technical Specification Clause 510                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                             |                                                                         |                                                                                        |                                                                                                     |
|         |             | A.            | <b>By Manual Means</b><br>Case - 1 : Type B                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                             |                                                                         |                                                                                        |                                                                                                     |
|         |             | (f)           | <b>Bitumen (S-90)</b><br>Unit = sqm<br>Taking output = 1250 sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                                             |                                                                         |                                                                                        |                                                                                                     |
|         |             | a)            | <b>Labour</b><br>Mate<br>Mazdoor (Unskilled)<br>Mazdoor (Semi-Skilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | day<br>day<br>day                                           | 0.85<br>15.00<br>2.00                                                   | 397.00<br>373.00<br>388.00                                                             | 337.45<br>5595.00<br>776.00                                                                         |
|         |             | b)            | <b>Machinery</b><br>Mixer 6/10 t capacity<br>Bitumen boiler oil fired, capacity 1000 litre fitted with spray set<br>Three wheel 80-100 kN static roller                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | hour<br>hour<br>hour                                        | 2.50<br>2.50<br>2.50                                                    | 3702.00<br>552.00<br>1593.00                                                           | 9255.00<br>1380.00<br>3982.50                                                                       |
|         |             | c)            | <b>Material</b><br>Bitumen (S-90) @ 6.80 kg per 10 sqm<br>Crushed stone chipping of 6.7 mm size 100 per cent passing 11.2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | t<br>cum                                                    | 0.85<br>7.50                                                            | 50930.50<br>119.10                                                                     | 43290.93<br>893.25                                                                                  |
|         |             | d)            | Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                             |                                                                         |                                                                                        | 7861.2                                                                                              |
|         |             | e)            | Contractor's profit @ 10% on (a+b+c+d)<br>Cost of 1250 sqm = a+b+c+d<br>Rate per sqm = (a+b+c+d+e)/1250                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                                                             |                                                                         |                                                                                        | 7337.13<br>30708.17<br>64.57                                                                        |
|         |             | f)            | <b>Carriage Cost</b><br>i) Bitumen<br>ii) Crushed stone chipping                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | t<br>cum                                                    | 0.00068<br>0.00600                                                      | 1771.61<br>1864.83                                                                     | 1.20<br>11.19                                                                                       |
|         |             |               | Rate per sqm = (a+b+c+d+e+f) / 1250                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                                             |                                                                         |                                                                                        | 76.96                                                                                               |
|         |             |               | Total Cost including 1 % LABOUR CESS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | cum                                                         |                                                                         |                                                                                        | 77.73                                                                                               |
| 19      | 6.4         | 1500          | <b>CC PAVEMENT</b><br><b>Cement Concrete Pavement</b><br>Construction of un-reinforced, expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing) spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14 days using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501<br>Unit = cum<br>Taking output = 75 cum (172.50 t)<br>(100 x 3.75 x 0.200) |                                                             |                                                                         |                                                                                        |                                                                                                     |
|         |             | a)            | <b>Labour</b><br>Mate<br>Mason (1st class)<br>Mason (2nd class)<br>Mazdoor (Unskilled)<br>Mazdoor (Skilled)<br>Surveyor<br>Mazdoor (Semi-Skilled)<br>Bhisti<br>Blacksmith for cutting of dowel bars including removal of burrs, fabrications & fixing of dowel bars.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | day<br>day<br>day<br>day<br>day<br>day<br>day<br>day<br>day | 7.00<br>5.00<br>5.00<br>129.00<br>6.00<br>2.00<br>6.00<br>14.00<br>1.00 | 397.00<br>503.00<br>449.00<br>373.00<br>472.00<br>454.00<br>388.00<br>373.00<br>449.00 | 2,779.00<br>2,515.00<br>2,245.00<br>48,117.00<br>2,832.00<br>908.00<br>2,328.00<br>5,222.00<br>0.00 |
|         |             | b)            | <b>Machinery</b><br>Concrete mixer 0.28 / 0.4 cum capacity (6 mixers) with weigh batcher and suitable capacity calibrated water tank<br>Needle vibrator                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | hour<br>hour                                                | 36.00<br>9.00                                                           | 334.00<br>386.00                                                                       | 12,024.00<br>3,474.00                                                                               |



07.434.12  
75.335.4  
75.451.99  
0.421.8  
74640.45  
193.6  
2.5  
50.35  
246.6  
249.06

Type B.

37.45  
5.00  
6.00

5.00  
10.00  
2.50

0.93  
3.25  
361.2

337.13  
708.4  
64.57

1.20  
1.19  
6.96  
7.73

sign  
ates  
cum  
and  
the  
ing  
he  
and

0.0  
5.00  
0.0  
0.0  
0.0  
0.0  
0.0  
0.0  
0.0  
0.0

| Sl. No. | SDB Sl. No. | MORD Ref No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                           | Unit       | Quantity  | Rate      | Amount in Rs    |
|---------|-------------|--------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-----------|-----------|-----------------|
|         |             |              | Screed vibrator                                                                                                                                                                                                                                                                                                                                       | hour       | 9.00      | 102.64    | 0.00            |
|         |             |              | Plate vibrator                                                                                                                                                                                                                                                                                                                                        | hour       | 9.00      | 396.00    | 3,564.00        |
|         |             |              | Concrete joint cutting machine for initial & final cuts                                                                                                                                                                                                                                                                                               | hour       | 4.00      | 342.00    | 1,368.00        |
|         |             |              | Water tanker 6 kl capacity                                                                                                                                                                                                                                                                                                                            | hour       | 5.00      | 752.00    | 3,760.00        |
|         |             |              | Air Compressor (1 hour initial + 1 hour final)                                                                                                                                                                                                                                                                                                        | hour       | 2.00      | 440.00    | 880.00          |
|         |             | c)           | <b>Material</b>                                                                                                                                                                                                                                                                                                                                       |            |           |           |                 |
|         |             | (i)          | Crushed stone coarse aggregates, grading will be as per Clause 1501.2.4.1 (Table 1500.1) of specifications @ 0.90 cum/cum of concrete                                                                                                                                                                                                                 | cum        | 67.50     | 886.00    | 59,805.00       |
|         |             | (ii)         | Sand as per IS:383 and conforming to Clause 1500.2.4.2 @ 0.45 cum/cum of concrete                                                                                                                                                                                                                                                                     | cum        | 33.75     | 494.00    | 16,672.50       |
|         |             | (iii)        | Cement @ 350 kg/cum of concrete                                                                                                                                                                                                                                                                                                                       | t          | 26.25     | 5,854.80  | 153,688.50      |
|         |             | (iv)         | Polythene sheet 125 micron                                                                                                                                                                                                                                                                                                                            | sqm        | 412.50    | 14.68     | 6,055.50        |
|         |             | (v)          | Mild steel dowel bar 25 mm dia of grade S 240. 500 mm long 20 Nos. at culvert/bridge slab and at construction joint including 5 per cent wastage.                                                                                                                                                                                                     |            |           |           |                 |
|         |             |              | (4 x 20 x 0.500) + 5 per cent wastage = 42 m @ 2.80 kg per m = 117.6 kg.                                                                                                                                                                                                                                                                              | kg         | 0.00      | 57.67     | 0.00            |
|         |             |              | Bitumen primer @ 200 ml per joint for 23 joints                                                                                                                                                                                                                                                                                                       | t          | 0.005     | 50,361.50 | 251.81          |
|         |             |              | Bituminous sealant 800 ml per joint for 23 joints                                                                                                                                                                                                                                                                                                     | litre      | 19.00     | 27.24     | 517.56          |
|         |             |              | Jute rope 12 mm dia including 5 per cent wastage                                                                                                                                                                                                                                                                                                      | m          | 90.00     | 34.20     | 3,078.00        |
|         |             |              | Debonding strips 3.75 m (length) x 10 mm (width) x 5 mm (thick) cut-out of rubber filler board or similar material including 5 per cent wastage                                                                                                                                                                                                       | m          | 90.00     | 45.00     | 4,050.00        |
|         |             |              | Polythene sheathing, covering 2/3rd dowel bars (20x23) and tight fit including 5 per cent wastage                                                                                                                                                                                                                                                     | No.        | 0.00      | 14.68     | 0.00            |
|         |             |              | Plasticizer 0.5 per cent by weight of cement                                                                                                                                                                                                                                                                                                          | litre      | 122.00    | 214.86    | 26,212.92       |
|         |             |              | Curing compound (if used) @ 0.33 litre per sqm                                                                                                                                                                                                                                                                                                        | litre      | 131.25    | 0.00      | 0.00            |
|         |             |              | Water for curing                                                                                                                                                                                                                                                                                                                                      | kl         | 18.00     | 56.20     | 1,011.60        |
|         |             |              | Joint filler board 20 mm thick as per IS 1838 (4 x 3.75 x 0.200 = 3 sqm)                                                                                                                                                                                                                                                                              | sqm        | 3.00      | 957.49    | 0.00            |
|         |             | d)           | <b>Formwork @ 1% of (a+b+c)</b>                                                                                                                                                                                                                                                                                                                       |            |           |           | 3633.59         |
|         |             | e)           | <b>Overheads @ 12% on (a+b+c+d)</b>                                                                                                                                                                                                                                                                                                                   |            |           |           | 44,039.16       |
|         |             | f)           | <b>Contractor's profit @ 10% on (a+b+c+d+e)</b>                                                                                                                                                                                                                                                                                                       |            |           |           | 41103.21        |
|         |             |              | Rate per cum = (a+b+c+d+e+f)/75                                                                                                                                                                                                                                                                                                                       |            |           |           | 6028.47         |
|         |             |              | <b>Carriage Cost</b>                                                                                                                                                                                                                                                                                                                                  |            |           |           |                 |
|         |             |              | Carriage stone aggregate                                                                                                                                                                                                                                                                                                                              | cum        | 0.90      | 1864.83   | 1678.35         |
|         |             |              | Carriage sand                                                                                                                                                                                                                                                                                                                                         | cum        | 0.45      | 528.24    | 237.71          |
|         |             |              | Carriage cement                                                                                                                                                                                                                                                                                                                                       | ton        | 0.35      | 405.40    | 141.89          |
|         |             |              | Carriage steel                                                                                                                                                                                                                                                                                                                                        | kg         | 0.0000000 | 0.405     | 0.00            |
|         |             |              | Carriage bitumen                                                                                                                                                                                                                                                                                                                                      | ton        | 0.000067  | 1771.61   | 0.12            |
|         |             |              | Cost for 75 cum = a+b+c+d+e                                                                                                                                                                                                                                                                                                                           |            |           |           | 8,086.53        |
|         |             |              | Rate per cum = (a+b+c+d+e)/75                                                                                                                                                                                                                                                                                                                         |            |           |           | 8,086.53        |
|         |             |              | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                     | <b>cum</b> |           |           | <b>8,086.53</b> |
| 20      | 4.18        | 412          | <b>Brick Soling</b>                                                                                                                                                                                                                                                                                                                                   |            |           |           |                 |
|         |             |              | Laying brick soling layer on prepared sub-grade with brick on end edging according to lines, graded and cross-section shown on the drawing filling joints with sand and earth, spreading 25 mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kN as per Technical Specification Clause 412 |            |           |           |                 |
|         |             |              | Unit = sqm                                                                                                                                                                                                                                                                                                                                            |            |           |           |                 |
|         |             |              | Taking output = 150 sqm                                                                                                                                                                                                                                                                                                                               |            |           |           |                 |
|         |             | (a)          | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                         |            |           |           |                 |
|         |             |              | Mate                                                                                                                                                                                                                                                                                                                                                  | day        | 0.52      | 397.00    | 206.44          |
|         |             |              | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                   | day        | 10.00     | 373.00    | 3730.00         |
|         |             |              | Mason 1st Class                                                                                                                                                                                                                                                                                                                                       | day        | 3.00      | 503.00    | 1509.00         |
|         |             | (b)          | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                      |            |           |           |                 |
|         |             |              | Three wheel 80-100 kN static roller                                                                                                                                                                                                                                                                                                                   | hour       | 1.00      | 1593.00   | 1593.00         |
|         |             |              | Water tanker                                                                                                                                                                                                                                                                                                                                          | hour       | 1.00      | 752.00    | 752.00          |
|         |             | (c)          | <b>Material</b>                                                                                                                                                                                                                                                                                                                                       |            |           |           |                 |
|         |             |              | Brick 1st Class                                                                                                                                                                                                                                                                                                                                       | No.        | 8160.00   | 6.07      | 49523.04        |
|         |             |              | Brick 1st Class on edging                                                                                                                                                                                                                                                                                                                             | No.        | 1100.00   | 6.07      | 6675.90         |
|         |             |              | Fine Sand                                                                                                                                                                                                                                                                                                                                             | cum        | 5.66      | 143.32    | 811.19          |
|         |             |              | Water                                                                                                                                                                                                                                                                                                                                                 | kl         | 6.00      | 56.20     | 337.20          |
|         |             |              |                                                                                                                                                                                                                                                                                                                                                       |            |           |           | 7,816.53        |
|         |             | (d)          | <b>Overheads @ 12% on (a+b+c+d)</b>                                                                                                                                                                                                                                                                                                                   |            |           |           | 7295.43         |
|         |             | e)           | <b>Contractor's profit @ 10% on (a+b+c+d)</b>                                                                                                                                                                                                                                                                                                         |            |           |           | 535.00          |
|         |             |              | Cost for 150 sqm = a+b+c+d+e                                                                                                                                                                                                                                                                                                                          |            |           |           |                 |
|         |             | f)           | <b>Carriage Cost</b>                                                                                                                                                                                                                                                                                                                                  |            |           |           |                 |
|         |             |              | Brick 1st Class                                                                                                                                                                                                                                                                                                                                       | No.        | 61.73     | 0.80      | 49.31           |
|         |             |              | Fine Sand                                                                                                                                                                                                                                                                                                                                             | cum        | 0.04      | 266.27    | 10.05           |
|         |             |              | Rate per sqm = (a+b+c+d+e+f)                                                                                                                                                                                                                                                                                                                          |            |           |           | 594.36          |
|         |             |              | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                     | <b>cum</b> |           |           | <b>594.36</b>   |



| Sl. No. | Sub-item No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                     | Unit                  | Quantity | Rate     | Amount in Rs. |
|---------|--------------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------|----------|----------|---------------|
| 21      | 11.5         | 600 & 1200    | Brick masonry work in cement mortar in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 600, 1202 & 1203                                               |                       |          |          |               |
|         | (ii)         |               | Unit = cum                                                                                                                                                                                                      |                       |          |          |               |
|         | a)           |               | Brick masonry in 1:4 cement mortar                                                                                                                                                                              |                       |          |          |               |
|         |              |               | Material                                                                                                                                                                                                        |                       |          |          |               |
|         |              |               | Brick                                                                                                                                                                                                           | Nos.                  | 500.00   | 6.07     | 3034.50       |
|         |              |               | Cement mortar 1:4                                                                                                                                                                                               | cum                   | 0.24     | 3833.65  | 920.08        |
|         |              |               | Rates as per sub-analysis                                                                                                                                                                                       |                       |          |          |               |
|         | b)           |               | Labour                                                                                                                                                                                                          |                       |          |          |               |
|         |              |               | Mate                                                                                                                                                                                                            | day                   | 0.09     | 397.00   | 35.73         |
|         |              |               | Mason (1st Class)                                                                                                                                                                                               | day                   | 0.80     | 503.00   | 402.40        |
|         |              |               | Mazdoor (Unskilled)                                                                                                                                                                                             | day                   | 1.60     | 373.00   | 596.80        |
|         |              |               | Bhisti                                                                                                                                                                                                          | day                   | 0.20     | 373.00   | 74.60         |
|         | c)           |               | Overheads @ 12 % on (a+b)                                                                                                                                                                                       |                       |          |          | 607.69        |
|         | d)           |               | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                            |                       |          |          | 567.18        |
|         |              |               | Rate per cum = (a+b+c+d+e+f)                                                                                                                                                                                    |                       |          |          | 6238.98       |
|         |              |               | Total Cost                                                                                                                                                                                                      | cum                   |          |          | 6,238.98      |
|         |              |               | Sub-analysis                                                                                                                                                                                                    |                       |          |          |               |
|         |              |               | Cement mortar 1:4 (1 cement : 4 sand)                                                                                                                                                                           |                       |          |          |               |
|         |              |               | Unit = cum                                                                                                                                                                                                      |                       |          |          |               |
|         | a)           |               | Material                                                                                                                                                                                                        |                       |          |          |               |
|         |              |               | Cement                                                                                                                                                                                                          | t                     | 0.38     | 5,854.80 | 2,224.82      |
|         |              |               | Sand                                                                                                                                                                                                            | cum                   | 1.05     | 494.00   | 518.70        |
|         | b)           |               | Labour                                                                                                                                                                                                          |                       |          |          |               |
|         |              |               | Mate                                                                                                                                                                                                            | day                   | 0.04     | 397.00   | 15.88         |
|         |              |               | Mazdoor (Unskilled)                                                                                                                                                                                             | day                   | 0.90     | 373.00   | 335.70        |
|         |              |               | Bhisti                                                                                                                                                                                                          | day                   | 0.08     | 373.00   | 29.84         |
|         |              |               | CARRIAGE                                                                                                                                                                                                        |                       |          |          |               |
|         |              |               | Cement                                                                                                                                                                                                          | t                     | 0.38     | 405.40   | 154.05        |
|         |              |               | Sand                                                                                                                                                                                                            | cum                   | 1.05     | 528.24   | 554.65        |
|         |              |               | Total material and labour = (a+b)                                                                                                                                                                               |                       |          |          | 3833.65       |
| 22      | 10.1         | 1700          | Printing New Letters and Figures of any Shade                                                                                                                                                                   |                       |          |          |               |
|         |              |               | Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701                       |                       |          |          |               |
|         | ii)          |               | English and Roman                                                                                                                                                                                               |                       |          |          |               |
|         |              |               | Hyphens, commas and the like not to be measured and paid for. Detail for 100 letters of                                                                                                                         |                       |          |          |               |
|         |              |               | Unit = per cm height per letter                                                                                                                                                                                 |                       |          |          |               |
|         | a)           |               | Labour                                                                                                                                                                                                          |                       |          |          |               |
|         |              |               | Mate                                                                                                                                                                                                            | day                   | 0.07     | 397.00   | 27.79         |
|         |              |               | Painter 1st class                                                                                                                                                                                               | day                   | 1.25     | 476.00   | 595.00        |
|         |              |               | Mazdoor (Unskilled)                                                                                                                                                                                             | day                   | 0.50     | 373.00   | 186.50        |
|         | b)           |               | Material                                                                                                                                                                                                        |                       |          |          |               |
|         |              |               | Paint                                                                                                                                                                                                           | litre                 | 0.50     | 246.65   | 123.33        |
|         | c)           |               | Overheads @ 12 % on (a+b)                                                                                                                                                                                       |                       |          |          | 111.91        |
|         | d)           |               | Contractor's profit @ 10 % on (a+b+c)                                                                                                                                                                           |                       |          |          | 101.67        |
|         |              |               | Cost for 1600 cm = a+b+c+d                                                                                                                                                                                      |                       |          |          | 1,146.20      |
|         |              |               | Rate per cm height per letter = (a+b+c+d)/1600                                                                                                                                                                  |                       |          |          | 0.72          |
| 23      | 10.10        | 1700          | Kilometre stone                                                                                                                                                                                                 |                       |          |          |               |
|         |              |               | Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 |                       |          |          |               |
|         | i)           |               | 5th KILOMETRE STONE (precast)                                                                                                                                                                                   |                       |          |          |               |
|         |              |               | Unit = each                                                                                                                                                                                                     |                       |          |          |               |
|         |              |               | Taking output = 6 Nos.                                                                                                                                                                                          |                       |          |          |               |
|         | a)           |               | M-15 grade of concrete                                                                                                                                                                                          | cum                   | 2.35     | 6,861.10 | 16,123.58     |
|         |              |               | As per item No.12.5 of Chapter 12                                                                                                                                                                               |                       |          |          |               |
|         | b)           |               | Steel reinforcement @ 5 kg per sqm                                                                                                                                                                              | kg                    | 22.08    | 85.51    | 1,888.00      |
|         |              |               | As per item No.12.6 of Chapter 12                                                                                                                                                                               |                       |          |          |               |
|         | c)           |               | Excavation in soil for foundation                                                                                                                                                                               | cum                   | 1.68     | 410.66   | 689.91        |
|         |              |               | As per item No.11.1 of Chapter 11                                                                                                                                                                               |                       |          |          |               |
|         | d)           |               | Painting two coats on concrete surface                                                                                                                                                                          | sqm                   | 9.85     | 67.50    | 664.88        |
|         |              |               | As per item No.10.5 of Chapter 10                                                                                                                                                                               |                       |          |          |               |
|         | e)           |               | lettering on km post (average 30 letters of 10 cm height each)                                                                                                                                                  | per cm high per litre | 1,800.00 | 0.72     | 1,289.40      |
|         |              |               | As per item No.10.1 of Chapter 10                                                                                                                                                                               |                       |          |          |               |
|         | f)           |               | Transportation and fixing                                                                                                                                                                                       |                       |          |          |               |
|         |              |               | Labour                                                                                                                                                                                                          |                       |          |          |               |
|         |              |               | Mate                                                                                                                                                                                                            | day                   | 0.26     | 397.00   | 103.22        |
|         |              |               | Mason (1st Class)                                                                                                                                                                                               | day                   | 0.60     | 503.00   | 301.80        |
|         |              |               | Mazdoor (Unskilled)                                                                                                                                                                                             | day                   | 6.00     | 373.00   | 2,238.00      |

| No. | SDBSU No. | MORD Ref No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Unit                         | Quantity | Rate     | Amount in Rs |
|-----|-----------|--------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------|----------|----------|--------------|
|     |           | g)           | <b>Machinery</b><br>50 HP Tractor with trolley                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour                         | 6.00     | 676.00   | 4,056.00     |
|     |           | h)           | Overheads @ 12 % on (f+g)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                              |          |          | 803.88       |
|     |           | i)           | Contractor's profit @ 10% on (f+g+h)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                              |          |          | 750.29       |
|     |           |              | Cost for 6 Nos. 5th km stone = a+b+c+d+e+f+g+h+i                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                              |          |          | 28,909.10    |
|     |           |              | Rate for each 5th km stone = (a+b+c+d+e+f+g+h+i)/6                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | no.                          |          |          | 4,818.18     |
|     |           | ii)          | <b>KM STONE</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                              |          |          |              |
|     |           | (i)          | <b>Ordinary Kilometer Stone (Precast)</b><br>Unit = each<br>Taking output = 14 Nos                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                              |          |          |              |
|     |           | a)           | M15 grade of concrete<br>As per item No 12.5 of Chapter 12                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | cum                          | 3.77     | 6,861.10 | 25,866.35    |
|     |           | b)           | Steel reinforcement @ 5 kg per sqm<br>As per item No 12.6 of Chapter 12                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | kg                           | 26.32    | 85.51    | 2,250.62     |
|     |           | c)           | Excavation in soil for foundation<br>As per item No 11.1 of Chapter 11                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | cum                          | 2.77     | 410.66   | 1,137.53     |
|     |           | d)           | Painting two coats on concrete surface<br>As per item No 10.5 of Chapter 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | sqm                          | 11.41    | 67.50    | 770.18       |
|     |           | e)           | Lettering on km post (average 12 letters of 10 cm height each)<br>As per item No 10.1 of Chapter 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | per cm<br>high per<br>letter | 1,680.00 | 0.72     | 1,203.51     |
|     |           |              | <b>Transportation and fixing</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                              |          |          |              |
|     |           | f)           | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                              |          |          |              |
|     |           |              | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | day                          | 0.32     | 397.00   | 127.04       |
|     |           |              | Mason (1st Class)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | day                          | 1.00     | 503.00   | 503.00       |
|     |           |              | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | day                          | 7.00     | 373.00   | 2,611.00     |
|     |           | g)           | <b>Machinery</b><br>50 HP Tractor with trolley                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour                         | 6.00     | 676.00   | 4,056.00     |
|     |           | h)           | Overheads @12 % on (f+g)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                              |          |          | 875.64       |
|     |           | i)           | Contractor's profit @ 10% on (f+g+h)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                              |          |          | 817.27       |
|     |           |              | Cost for 14 Nos. ordinary km stone = (a+b+c+d+e+f+g+h+i)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                              |          |          | 40,218.14    |
|     |           |              | Rate for each ordinary km stone = (a+b+c+d+e+f+g+h+i)/14                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                              |          |          | 2,872.72     |
|     |           |              | Rate for each ordinary km stone = (a+b+c+d+e+f+g+h+i)/14                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                              |          |          | 2,872.72     |
|     |           | iii)         | <b>200 m STONE</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                              |          |          |              |
|     |           | (i)          | <b>200 m stone (precast)</b><br>Unit = each<br>Taking output = 33 Nos                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |                              |          |          |              |
|     |           | a)           | M15 grade of concrete<br>As per item No 12.5 of Chapter 12                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | cum                          | 1.50     | 6,861.10 | 10,291.54    |
|     |           | b)           | Steel reinforcement @ 5 kg per sqm<br>As per item No 12.6 of Chapter 12                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | kg                           | 56.00    | 85.51    | 5,643.66     |
|     |           | c)           | Excavation in soil for foundation<br>As per item No 11.1 of Chapter 11                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | cum                          | 1.39     | 410.66   | 570.82       |
|     |           | d)           | Painting two coats on concrete surface<br>As per item No 10.5 of Chapter 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | sqm                          | 6.23     | 67.50    | 423.23       |
|     |           | e)           | Lettering on the post (average 1 letter of 10 cm height each)<br>As per item No 10.1 of Chapter 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | per cm<br>per letter         | 330.00   | 0.72     | 236.40       |
|     |           |              | <b>Transportation and fixing</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |                              |          |          |              |
|     |           | f)           | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                              |          |          |              |
|     |           |              | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | day                          | 0.34     | 397.00   | 134.98       |
|     |           |              | Mason (1st Class)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | day                          | 1.50     | 503.00   | 754.50       |
|     |           |              | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | day                          | 7.00     | 373.00   | 2,611.00     |
|     |           | g)           | <b>Machinery</b><br>50 HP Tractor with trolley                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour                         | 6.00     | 676.00   | 4,056.00     |
|     |           | h)           | Overheads @12 % on (f+g)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                              |          |          | 906.78       |
|     |           | i)           | Contractor's profit @ 10% on (f+g+h)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                              |          |          | 846.33       |
|     |           |              | Cost for 33 Nos. 200 m stone = (a+b+c+d+e+f+g+h+i)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                              |          |          | 27,024.23    |
|     |           |              | Rate for each 200 m stone = (a+b+c+d+e+f+g+h+i)/33                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                              |          |          | 818.92       |
|     |           |              | Rate for each 200 m stone = (a+b+c+d+e+f+g+h+i)/33                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                              |          |          | 818.92       |
| 24  | 10.2 (A)  | 1700.3, 800  | <b>Retro-reflectorised Traffic Signs</b><br>Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm, firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801<br><br>Unit = Each<br>Taking output = one traffic sign |                              |          |          |              |



| Sl. No. | SDR No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Unit       | Quantity | Rate      | Amount in Rs    |
|---------|---------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|----------|-----------|-----------------|
|         |         | (ii)          | Cement Concrete M-15 grade<br>As per item No. 11.4 of Chapter 11                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | cum        | 0.126    | 6,861.10  | 864.50          |
|         |         | (iii)         | Painting on M.S. tube post with primer and two coat of epoxy paint as per specifications<br>As per item No. 10.7 of Chapter 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | sqm        | 0.50     | 163.30    | 96.35           |
|         |         | a)            | <b>Labour (For fixing at site)</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |            |          |           |                 |
|         |         |               | Male                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | day        | 0.01     | 397.00    | 1.97            |
|         |         |               | Male/door (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | day        | 0.25     | 373.00    | 91.25           |
|         |         | b)            | <b>Materials</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |          |           |                 |
|         |         | i)            | Support of MS sheet tube<br>47 mm x 47 mm of 12 SWG sheet 3050 mm long                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | kg         | 12.40    | 38.65     | 479.25          |
|         |         | ii)           | Angle iron 50 x 50 x 6 mm for lugs including 5% wastage                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | kg         | 1.00     | 28.91     | 30.64           |
|         |         | iii)          | 2 mm thick MS sheet strengthened by 25 mm x 5 mm MS flat iron & painted with stove enameled paint including lettering, signs, message, border with reflective tape of engineering grade of required shade and colour as per Technical Specifications<br>Add 1% cost of MS sheet angle iron towards the cost of fabrications, drilling, holes, nuts, bolts, etc.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | sqm        | 0.90     | 739.56    | 665.60          |
|         |         | c)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |          |           |                 |
|         |         |               | Tractor with Trolley                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour       | 0.08     | 676.00    | 54.08           |
|         |         | d)            | Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |            |          |           | 163.45          |
|         |         | e)            | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |            |          |           | 152.55          |
|         |         |               | Cost for 0.9 sqm = (i+ii+iii+a+b+c+d+e)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |            |          |           | 2,690.64        |
|         |         |               | Rate per sqm = (i+ii+iii+a+b+c+d+e) / 0.9                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |            |          |           | 2,989.60        |
|         |         |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | <b>SQM</b> |          |           | <b>2,989.60</b> |
| 27      | 10.16   | 1700          | <b>Providing and Fixing 'Logo' of MMGSV Project</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |            |          |           |                 |
|         |         |               | Providing and fixing of typical MMGSV information sign board with 1.5 m x 1.5 m per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded by 25mm x 25mm x 5mm of 12 SWG sheet tube posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm (450mm x 600mm x 600mm) in ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All MS work to be done as per drawing on both sides. Lettering and printing (arrows, border, etc.) will be painted with ready mixed synthetic enamel paint of required quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing clause 1701 and Annexure 1700.1 |            |          |           |                 |
|         |         |               | Unit = 1 each                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |            |          |           |                 |
|         |         |               | Taking out put of one typical board                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |            |          |           |                 |
|         |         |               | <b>Excavation for foundations</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |            |          |           |                 |
|         |         |               | As per item No. 11.1 of Chapter 11                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | cum        | 0.252    | 110.860   | 183.49          |
|         |         |               | <b>Cement Concrete M15 grade</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |          |           |                 |
|         |         |               | As per item No. 11.4 of Chapter 11                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | cum        | 0.252    | 6,861.100 | 1,729.00        |
|         |         |               | <b>Painting on MS Steel tubes with primer and two coats of epoxy paint</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |            |          |           |                 |
|         |         |               | As per item No. 10.7 of Chapter 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | sqm        | 1.80     | 163.30    | 293.94          |
|         |         |               | Printing new letters and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade.<br>Logo 60x45 = 1200 per cm height per letter<br>Figure 60x10 = 600 per cm height per letter<br>Middle plate words 26x5 = 130 per cm height per letter<br>Bottom plate border 150x2.5 = 1500 per cm height per letter<br>Bottom plate border 60x2.5 = 600 per cm height per letter<br>Words 161x2.5 = 252.5<br>Words 80x3 = 240.00<br>Total = 4532.5 per cm height per letter<br>As per item No. 10.1 of Chapter 10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | per cm     | 4532.50  | 0.72      | 3,216.90        |
|         |         | a)            | <b>Labour (for fixing at site)</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |            |          |           |                 |
|         |         |               | Male                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | day        | 0.03     | 397.00    | 11.91           |
|         |         |               | Male/door (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | day        | 0.75     | 373.00    | 279.75          |
|         |         | b)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |            |          |           |                 |
|         |         |               | 2 nos. MS tubes 75mm x 75mm of 12 SWG sheet 2650 mm long                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | kg         | 61.15    | 38.65     | 2,440.68        |
|         |         |               | 1 No. MS tube 47mm x 47mm of 12 SWG 1100 mm long                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | kg         | 4.47     | 38.65     | 172.76          |
|         |         |               | Angle iron 50mm x 50mm x 5 mm for lugs                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | kg         | 2.12     | 28.91     | 61.28           |
|         |         |               | 1.6 mm thick MS sheet strengthened by 25mm x 5 mm MS flat iron on top and middle plate angle iron 25mm x 25mm x 5 mm on bottom plate painting with stove enameled paint on both sides as per MORD specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | sqm        | 1.44     | 739.56    | 1,064.96        |
|         |         |               | Add 1% cost of MS tube and angle iron towards the cost of fabrications, drilling holes, nuts, bolts, etc.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |            |          |           | 112.19          |
|         |         | c)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |            |          |           |                 |
|         |         |               | Tractor with trolley                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | hour       | 0.24     | 676.00    | 162.24          |

| SL No. | SDB SL No. | MORD Ref No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Unit         | Quantity | Rate    | Amount in Rs. |
|--------|------------|--------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|----------|---------|---------------|
|        |            | d)           | Overheads @12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |              |          |         | 516.6         |
|        |            | e)           | Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |              |          |         | 482.25        |
|        |            |              | <b>COST OF ONE BOARD=</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |              |          |         | 10,670.11     |
|        |            |              | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | <b>Nos.</b>  |          |         | 10670.12      |
| 1      | 8.23       | 810          | <b>Metal Beam Crash Barrier</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |              |          |         |               |
|        |            | A            | Type - A, "W" : Metal Beam Crash Barrier                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |              |          |         |               |
|        |            | (RCD)        | Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS 1367 and IS 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810 |              |          |         |               |
|        |            |              | Unit = Running metre                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |              |          |         |               |
|        |            |              | Taking output = 4.5 metre length                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |              |          |         |               |
|        |            | a)           | Labour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |              |          |         |               |
|        |            |              | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | day          | 0.06     | 397.00  | 23.82         |
|        |            |              | Blacksmith                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | day          | 0.50     | 449.00  | 224.50        |
|        |            |              | Mazdoor                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | day          | 1.00     | 472.00  | 472.00        |
|        |            | b)           | Machinery                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |              |          |         |               |
|        |            |              | Tractor-trolley                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | hour         | 0.10     | 676.00  | 67.60         |
|        |            | c)           | Material                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |              |          |         |               |
|        |            |              | Corrugated sheet, 3 mm thick, "W" beam section railing, 4.5 m in length                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | kg           | 41.21    | 51.20   | 2,109.96      |
|        |            |              | Channel post 150 x 75 x 5 mm, 1.8 m long, 3 Nos @ 16.4 kg per metre                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | kg           | 88.56    | 51.20   | 4,534.27      |
|        |            |              | Spacer 150 x 75 x 5 mm channel 0.33 m long, 3 Nos @ 16.4 kg per metre                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | kg           | 16.24    | 51.20   | 831.49        |
|        |            |              | Nuts and bolts                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | kg           | 20.00    | 69.15   | 1,383.00      |
|        |            |              | Add 25 per cent of the cost of material for fabrication, nuts, bolts and washers etc.)                                                                                                                                                                                                                                                                                                                                                                                                                                                          |              |          |         | 2,214.68      |
|        |            | d)           | Overheads @12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |              |          |         | 1,423.36      |
|        |            |              | Contractor's profit @ 10%                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |              |          |         | 1,328.47      |
|        |            |              | Cost for 4.5 metre = (a+b+c+d+e)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |              |          |         | 14,613.13     |
|        |            |              | Rate per metre = (a+b+c+d+e)/4.5                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |              |          |         | 3,247.36      |
|        |            |              | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | <b>metre</b> |          |         | 3247.36       |
| 28     | 8.13       | 803          | <b>Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface</b>                                                                                                                                                                                                                                                                                                                                                                                                                               |              |          |         |               |
|        |            | RCD          | Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes.                                                                                                                                                                                                                                                  |              |          |         |               |
|        |            |              | Unit = sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |              |          |         |               |
|        |            |              | Taking output = 640 sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |              |          |         |               |
|        |            | a)           | Labour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |              |          |         |               |
|        |            |              | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | day          | 0.500    | 397.00  | 198.50        |
|        |            |              | Mazdoor                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | day          | 2.000    | 373.00  | 746.00        |
|        |            | b)           | Machinery                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |              |          |         |               |
|        |            |              | Road marking machine @ 80 sqm per hour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | hour         | 8.000    | 1411.00 | 11288.00      |
|        |            |              | Tractor-trolley                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | hour         | 8.000    | 676.00  | 5408.00       |
|        |            | c)           | Material                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |              |          |         |               |
|        |            |              | Hot applied thermoplastic compound                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | litre        | 2000.000 | 198.46  | 396920.00     |
|        |            |              | Reflectorising glass beads                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | kg           | 200.000  | 72.00   | 14400.00      |
|        |            |              | (d) Overheads @ 12% on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |              |          |         | 51475.26      |
|        |            |              | (e) Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |              |          |         | 48043.58      |
|        |            |              | Cost for 640 sqm = a+b+c+d+e                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |              |          |         | 528479.34     |
|        |            |              | Rate per sqm = (a+b+c+d+e)/640                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |              |          |         | 825.75        |
|        |            |              | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | <b>sqm</b>   |          |         | 825.75        |
| 29     | 8.16       | 800          | <b>Painting on concrete surface</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |              |          |         |               |
|        |            | RCD          | Providing and applying 2 coats of water based cement paint to unplastered concrete surface after cleaning the surface of dirt, dust, oil, grease, efflorescence and applying paint @ of 1 litre for 2 sqm.                                                                                                                                                                                                                                                                                                                                      |              |          |         |               |
|        |            |              | Unit = sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |              |          |         |               |
|        |            |              | Taking output = 10 sqm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |              |          |         |               |
|        |            | a)           | Labour                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |              |          |         |               |
|        |            |              | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | day          | 0.01     | 397.00  | 3.97          |
|        |            |              | Painter                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | day          | 0.25     | 476.00  | 119.00        |
|        |            |              | Mazdoor (Skilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | day          | 0.25     | 472.00  | 118.00        |



| Sl. No. | SUR Sl. No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                    | Unit        | Quantity | Rate         | Amount in Rs |
|---------|-------------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|----------|--------------|--------------|
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                               |             |          |              |              |
|         |             |               | water based paint of approved quality for cement concrete surface                                                                                                                                                                                                                              | Litre       | 5.00     | 115.16       | 575.80       |
|         |             | c)            | <b>Overheads @ 12 % on (a+b+c)</b>                                                                                                                                                                                                                                                             |             |          |              | 98.01        |
|         |             | d)            | <b>Contractor's profit @ 10% on (a+b+c+d)</b>                                                                                                                                                                                                                                                  |             |          |              | 91.48        |
|         |             |               | Cost for 10 sqm (a+b+c+d)                                                                                                                                                                                                                                                                      |             |          |              | 1,006.26     |
|         |             |               | Rate per sqm (a+b+c+d)/10                                                                                                                                                                                                                                                                      |             |          |              | 100.63       |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                              | sqm         |          |              | 100.63       |
| 30      | 8.13        | 803           | <b>Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Concrete Surface</b>                                                                                                                                                                                |             |          |              |              |
|         | RCD         |               | Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. |             |          |              |              |
|         |             |               | Unit = sqm                                                                                                                                                                                                                                                                                     |             |          |              |              |
|         |             |               | Taking output = 640 sqm                                                                                                                                                                                                                                                                        |             |          |              |              |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                  |             |          |              |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                           | day         | 0.500    | 397.00       | 198.50       |
|         |             |               | Mazdoor                                                                                                                                                                                                                                                                                        | day         | 2.000    | 373.00       | 746.00       |
|         |             | b)            | <b>Machinery</b>                                                                                                                                                                                                                                                                               |             |          |              |              |
|         |             |               | Road marking machine @ 80 sqm per hour                                                                                                                                                                                                                                                         | hour        | 8.000    | 1411.00      | 11288.00     |
|         |             |               | Tractor-trolley                                                                                                                                                                                                                                                                                | hour        | 8.000    | 676.00       | 5408.00      |
|         |             | c)            | <b>Material</b>                                                                                                                                                                                                                                                                                |             |          |              |              |
|         |             |               | Hot applied thermoplastic compound                                                                                                                                                                                                                                                             | Litre       | 2000.000 | 198.46       | 396920.00    |
|         |             |               | Reflectorising glass beads                                                                                                                                                                                                                                                                     | kg          | 200.000  | 72.00        | 14400.00     |
|         |             |               | (d) Overheads @12% on (a+b+c)                                                                                                                                                                                                                                                                  |             |          |              | 51475.26     |
|         |             |               | (e) Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                     |             |          |              | 48043.58     |
|         |             |               | Cost for 640 sqm = a+b+c+d+e                                                                                                                                                                                                                                                                   |             |          |              | 528479.34    |
|         |             |               | Rate per sqm = (a+b+c+d+e)/640                                                                                                                                                                                                                                                                 |             |          |              | 825.75       |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                              | sqm         |          |              | 825.75       |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                              | cum         | 26064    | 825.7489625= | 926.38       |
| 31      | 10.11       | 1700          | <b>Boundary Pillar</b>                                                                                                                                                                                                                                                                         |             |          |              |              |
|         |             |               | Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause                                                               |             |          |              |              |
|         |             |               | Unit = each                                                                                                                                                                                                                                                                                    |             |          |              |              |
|         |             |               | Taking output = 57 Nos.                                                                                                                                                                                                                                                                        |             |          |              |              |
|         |             | a)            | M-15 grade of Concrete                                                                                                                                                                                                                                                                         | cum         | 1.250    | 6861.100     | 8576.375     |
|         |             |               | As per Item No. 12.5 of Chapter 12                                                                                                                                                                                                                                                             |             |          |              |              |
|         |             | b)            | Steel reinforcement                                                                                                                                                                                                                                                                            | kg          | 79.800   | 85.510       | 6823.724     |
|         |             |               | As per Item No. 12.6 of Chapter 12                                                                                                                                                                                                                                                             |             |          |              |              |
|         |             | c)            | Excavation in soil                                                                                                                                                                                                                                                                             | cum         | 10.720   | 410.7        | 4402.275     |
|         |             |               | As per Item No. 11.1 of Chapter 11                                                                                                                                                                                                                                                             |             |          |              |              |
|         |             | d)            | lettering, each 10 cm high                                                                                                                                                                                                                                                                     | per litre   |          |              |              |
|         |             |               | As per Item No. 10.1 of Chapter 10                                                                                                                                                                                                                                                             | per cm high | 2280.0   | 0.72         | 1633.34      |
|         |             |               | <b>Transportation and fixing</b>                                                                                                                                                                                                                                                               |             |          |              |              |
|         |             | e)            | <b>Labour</b>                                                                                                                                                                                                                                                                                  |             |          |              |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                           | day         | 0.570    | 397.000      | 226.29       |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                            | day         | 14.250   | 373.000      | 5315.25      |
|         |             | f)            | <b>Machinery</b>                                                                                                                                                                                                                                                                               |             |          |              |              |
|         |             |               | Tractor with trolley                                                                                                                                                                                                                                                                           | hour        | 6.000    | 676.000      | 4056.00      |
|         |             | g)            | <b>Material</b>                                                                                                                                                                                                                                                                                |             |          |              |              |
|         |             |               | Stone spall                                                                                                                                                                                                                                                                                    | cum         | 11.970   | 351.360      | 4205.78      |
|         |             | h)            | Overhead @ 12% on (e+f+g)                                                                                                                                                                                                                                                                      |             |          |              | 1656.40      |
|         |             | i)            | Contractor's profit 10%                                                                                                                                                                                                                                                                        |             |          |              | 1545.97      |
|         |             |               | Cost for 57 Nos. boundary pillar = a+b+c+d+e+f+g+h                                                                                                                                                                                                                                             |             |          |              | 38441.40     |
|         |             |               | Rate for each boundary pillar = (a+b+c+d+e+f+g+h)/57                                                                                                                                                                                                                                           |             |          |              | 674.41       |
|         |             |               | on above                                                                                                                                                                                                                                                                                       |             |          |              | 674.41       |
|         |             |               | <b>Final rate Adopted in DPR</b>                                                                                                                                                                                                                                                               |             |          |              | 674.41       |
| 2       | 10.5        | 1700          | <b>Painting Two Coats on New Concrete Surfaces</b>                                                                                                                                                                                                                                             |             |          |              |              |
|         |             |               | Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701                                                                                      |             |          |              |              |
|         |             |               | Unit = sqm                                                                                                                                                                                                                                                                                     |             |          |              |              |
|         |             |               | Taking output = 40 sqm                                                                                                                                                                                                                                                                         |             |          |              |              |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                  |             |          |              |              |
|         |             |               | Mate                                                                                                                                                                                                                                                                                           | day         | 0.20     | 397.00       | 79.400       |
|         |             |               | Painter (1st Class)                                                                                                                                                                                                                                                                            | day         | 3.00     | 476.00       | 1428.000     |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                            | day         | 2.00     | 373.00       | 746.000      |



| Sl. No. | NDIS No.    | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Unit        | Quantity | Rate    | Amount in Rs. |
|---------|-------------|---------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|----------|---------|---------------|
|         |             | b)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | litre       | 3.00     | 115.16  | 345.480       |
|         |             |               | Cement Primer as per specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | litre       | 6.00     | 246.65  | 1479.900      |
|         |             |               | Paint conforming to requirement of Clause 1701.3.8                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |             |          |         | 22.53         |
|         |             |               | Add for scaffolding @ 1 per cent of labour cost where required                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |             |          |         | 492.16        |
|         |             | c)            | <b>Overheads @ 12% on (a+b)</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |             |          |         | 459.35        |
|         |             | d)            | <b>Contractor's profit @ 10% on (a+b+c)</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |             |          |         | 126.34        |
|         |             |               | <b>Rate per sqm = (a+b+c+d)/40</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |             |          |         | 126.32        |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |             |          |         | 126.32        |
| 29      | 10.8        | 1700          | <b>Painting lines, Dashes, Arrows, etc. on Road in Two Coats on New Work</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |          |         |               |
|         |             |               | Painting lines, Dashes, Arrows, etc. on Road in Two Coats on New Work with ready mixed road marking paint conforming to IS 164 on bituminous/concrete surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at sit and traffic control as per drawing and Technical Specification Clause 1702                                                                                                                                                                                                                                                                                                                                                                   |             |          |         |               |
|         |             |               | Assuming 100 mm Width                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |             |          |         |               |
|         |             |               | <b>Unit = sqm</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |             |          |         |               |
|         |             |               | <b>Taking output = 10 sqm</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |             |          |         |               |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |             |          |         |               |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | day         | 0.09     | 397.00  | 35.73         |
|         |             |               | Painter 1st Class                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | day         | 0.55     | 476.00  | 261.80        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | day         | 1.55     | 373.00  | 578.15        |
|         |             | b)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |             |          |         |               |
|         |             |               | Road marking paint as IS 164                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | liter       | 1.48     | 246.65  | 365.04        |
|         |             |               | (d) Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |             |          |         | 148.8         |
|         |             |               | (e) Contractor's profit 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |             |          |         | 138.96        |
|         |             |               | <b>Cost for 10 sqm = a+b+c+d+e</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |             |          |         | 1528.57       |
|         |             |               | <b>Rate per sqm = a+b+c+d+e/10</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |             |          |         | 152.86        |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | <b>Nos.</b> |          |         | 154.39        |
| 33      | 8.29<br>RCD |               | <b>Cable Duct Across the Road</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |             |          |         |               |
|         |             |               | Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC: 98:1997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings. |             |          |         |               |
|         |             |               | <b>Unit = Rm</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |             |          |         |               |
|         |             |               | <b>Taking output = 20 m</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |             |          |         |               |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |             |          |         |               |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | day         | 0.500    | 397.00  | 198.50        |
|         |             |               | Mazdoor (skilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | day         | 0.250    | 472.00  | 118.00        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | day         | 1.000    | 373.00  | 373.00        |
|         |             | b)            | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |             |          |         |               |
|         |             |               | Reinforced Cement Concrete pipe 300 mm dia                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Rm          | 20.000   | 562.67  | 11253.40      |
|         |             |               | Local Sand for bedding and sides of pipe                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Cum         | 7.200    | 143.32  | 1031.90       |
|         |             |               | Collar for joints 300 mm dia                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Each        | 9.000    | 118.00  | 1062.00       |
|         |             |               | Cement mortar 1:2 for joints                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Cum         | 0.020    | 4647.47 | 92.95         |
|         |             | c)            | <b>Machinery</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |             |          |         |               |
|         |             |               | Tractor-trolley                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Hour        | 0.500    | 676.00  | 338.00        |
|         |             |               | (d) Overheads @ 12 % on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |             |          |         | 1736.13       |
|         |             |               | (e) Contractor's profit @ 0.1 on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |             |          |         | 0.00          |
|         |             |               | (e) Contractor's profit @ 10% on (a+b+c+d)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |             |          |         | 1620.39       |
|         |             |               | <b>Cost for 20 Rm = a+b+c+d+e</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |             |          |         | 17824.27      |
|         |             |               | <b>Rate per Rm = a+b+c+d+e)/20 Sub Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |          |         | 891.21        |
|         |             |               | <b>Carriage Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |             |          |         |               |
|         |             |               | Local Sand                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Cum         | 0.36000  | 266.27  | 95.86         |
|         |             |               | <b>Rate per Rm = a+b+c+d+e)/20 Final</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |             |          |         | 987.07        |
|         |             |               | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | <b>Rm</b>   |          |         | 987.07        |
|         |             |               | <b>SUB HEAD : ANALYSIS OF CULVERT/ MINOR BRIDGES ITEMS</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |             |          |         |               |
| 34      | 11.1        | 300           | <b>Excavation for Structures</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |             |          |         |               |
|         |             |               | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.                                                                                                                                                                                                                                                                                                                                                                 |             |          |         |               |
|         |             | 1.            | <b>Ordinary soil</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |             |          |         |               |
|         |             | (i)           | <b>Upto 3 m depth</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |             |          |         |               |
|         |             |               | <b>Unit = cum</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |             |          |         |               |
|         |             |               | <b>Taking output = 10 cum</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |             |          |         |               |
|         |             | a)            | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |             |          |         |               |
|         |             |               | Mate                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | day         | 0.32     | 397.00  | 127.04        |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | day         | 8.00     | 373.00  | 2984.00       |
|         |             | b)            | <b>Overheads @ 20 % on (a)</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |             |          |         | 622.21        |



| Sl.No.  | SDB Sl. No. | MORD Ref No.                                     | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                               | Unit       | Quantity | Rate   | Amount in Rs |
|---------|-------------|--------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|----------|--------|--------------|
|         |             | c)                                               | Contractor's profit @ 10% on (a+b)                                                                                                                                                                                                                                                                                                                                                                        |            |          |        | 373.32       |
|         |             |                                                  | Cost for 10 cum = a+b+c                                                                                                                                                                                                                                                                                                                                                                                   |            |          |        | 4,106.57     |
|         |             |                                                  | Rate per cum = (a+b+c)/10                                                                                                                                                                                                                                                                                                                                                                                 | cum        |          |        | 410.66       |
|         |             |                                                  | Rate per cum = (a+b+c)/10                                                                                                                                                                                                                                                                                                                                                                                 | cum        |          |        | 410.66       |
|         |             | NOTE:                                            |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        |              |
|         |             | 1                                                | Cost of dewatering may be added, where required, up to 10 per cent of labour cost. Assessment for dewatering shall be made as per site conditions                                                                                                                                                                                                                                                         |            |          |        |              |
|         |             | 2                                                | The excavated earth if found suitable, can be used partly for backfilling in trenches & partly for road work. Hence cost of disposal has not been added except for marshy soil. This note is common to all cases of item 11.1 excluding 11.1 V                                                                                                                                                            |            |          |        |              |
| 35      | 9.2 (1)     | 1100 & 800                                       | <b>Type B (First Class) Bedding</b><br>Laying (First Class) bedding on well compacted sand, moorum or approved granular material as per Clause 1105 (ii)<br><b>Filling in foundation trenches as per drawing and technical specification Clause 305.3.9</b>                                                                                                                                               |            |          |        |              |
|         |             | 1.                                               | <b>Sand filling</b><br>Unit = cum                                                                                                                                                                                                                                                                                                                                                                         |            |          |        |              |
|         |             | a)                                               | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                             |            |          |        |              |
|         |             |                                                  | Mate                                                                                                                                                                                                                                                                                                                                                                                                      | day        | 0.01     | 397.00 | 3.97         |
|         |             |                                                  | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                       | day        | 0.30     | 373.00 | 111.90       |
|         |             | b)                                               | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        |              |
|         |             |                                                  | Sand (assuming 20 per cent voids)                                                                                                                                                                                                                                                                                                                                                                         | cum        | 1.20     | 143.32 | 171.98       |
|         |             | c)                                               | Overheads @20% on (a+b)                                                                                                                                                                                                                                                                                                                                                                                   |            |          |        | 57.57        |
|         |             | d)                                               | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                                                                                                                                                                                      |            |          |        | 34.54        |
|         |             |                                                  | <b>CARRIAGE COST</b>                                                                                                                                                                                                                                                                                                                                                                                      |            |          |        |              |
|         |             |                                                  | sand                                                                                                                                                                                                                                                                                                                                                                                                      | Cum        | 1.2      | 266.27 | 319.52       |
|         |             |                                                  | Rate per cum = a+b+c                                                                                                                                                                                                                                                                                                                                                                                      |            |          |        | 699.49       |
|         |             |                                                  | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                         | <b>CUM</b> |          |        | 699.49       |
| 36 (1)  | 9.3         | 1100                                             | <b>Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row</b><br>Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106. |            |          |        |              |
|         |             | A.                                               | <b>600 MM DIA</b><br>Unit = m<br>Taking output = 7.5 m<br>( 3 pipes of 2.5 m length each )                                                                                                                                                                                                                                                                                                                |            |          |        |              |
|         |             | a )                                              | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        |              |
|         |             | i) Sand at site                                  | cum                                                                                                                                                                                                                                                                                                                                                                                                       | 0.024      | 1022.24  |        | 24.53        |
|         |             | ii) Cement at site                               | ton                                                                                                                                                                                                                                                                                                                                                                                                       | 0.018      | 6260.20  |        | 112.68       |
|         |             | iii) RCC pipe NP 3 pipe including collar at site | m                                                                                                                                                                                                                                                                                                                                                                                                         | 7.50       | 762.50   |        | 5718.78      |
|         |             | b )                                              | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                             |            |          |        |              |
|         |             | Mate                                             | day                                                                                                                                                                                                                                                                                                                                                                                                       | 0.04       | 397.00   |        | 15.88        |
|         |             | Mason ( 1st class )                              | day                                                                                                                                                                                                                                                                                                                                                                                                       | 0.12       | 503.00   |        | 60.36        |
|         |             | Mazdoor ( Unskilled )                            | day                                                                                                                                                                                                                                                                                                                                                                                                       | 0.96       | 373.00   |        | 358.08       |
|         |             | Overheads @ 20 % on (a+b+c+d)                    |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        | 1258.06      |
|         |             | d) Contractor's profit @ 10% on (a+b+c)          |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        | 754.84       |
|         |             | Cost for 7.5m = ( a+b+c+d)                       |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        | 8303.21      |
|         |             | Rate per m = (a+b+c+d)/7.5                       |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        | 1107.10      |
|         |             |                                                  | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                         | <b>M</b>   |          |        | 1107.10      |
| 37 (II) | 9.3         | 1100                                             | <b>Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row</b><br>Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106. |            |          |        |              |
|         |             | B.                                               | <b>1000 MM DIA</b><br>Unit = m<br>Taking output = 7.5 m<br>( 3 pipes of 2.5 m length each )                                                                                                                                                                                                                                                                                                               |            |          |        |              |
|         |             | a )                                              | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        |              |
|         |             | i) Sand at site                                  | cum                                                                                                                                                                                                                                                                                                                                                                                                       | 0.04       | 1022.24  |        | 40.89        |
|         |             | ii) Cement at site                               | ton                                                                                                                                                                                                                                                                                                                                                                                                       | 0.03       | 6260.20  |        | 187.81       |
|         |             | iii) RCC pipe NP 3 pipe including collar at site | m                                                                                                                                                                                                                                                                                                                                                                                                         | 7.50       | 2989.54  |        | 22421.55     |
|         |             | b )                                              | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                             |            |          |        |              |
|         |             | Mate                                             | day                                                                                                                                                                                                                                                                                                                                                                                                       | 0.09       | 397.00   |        | 35.73        |
|         |             | Mason ( 1st class )                              | day                                                                                                                                                                                                                                                                                                                                                                                                       | 0.25       | 503.00   |        | 125.75       |
|         |             | Mazdoor ( Unskilled )                            | day                                                                                                                                                                                                                                                                                                                                                                                                       | 2.00       | 373.00   |        | 746.00       |
|         |             | c) Overheads @ 20 % on (a+b)                     |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        | 4711.55      |
|         |             | d) Contractor's profit @ 10% on (a+b+c)          |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        | 2826.93      |
|         |             | Cost for 7.5m = ( a+b+c+d)                       |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        | 31096.20     |
|         |             | Rate per m = (a+b+c+d)/7.5                       |                                                                                                                                                                                                                                                                                                                                                                                                           |            |          |        | 4146.16      |
|         |             |                                                  | <b>Total Cost</b>                                                                                                                                                                                                                                                                                                                                                                                         | <b>m</b>   |          |        | 4,146.16     |
| 37      | 9.5         | 1100                                             | <b>Providing and Laying Reinforced Cement Concrete Pipe NP3 as per Design in Double Row</b>                                                                                                                                                                                                                                                                                                               |            |          |        |              |



| Sl. No. | SDB Sl. No. | MORD Ref. No.                                                                                                         | DESCRIPTION                                                                                                                                                                                                                                                                                                      | Unit  | Quantity | Rate | Amount in Rs. |
|---------|-------------|-----------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|----------|------|---------------|
| (III)   | (C)         |                                                                                                                       | Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per Clause 1106 |       |          |      |               |
|         |             | C.                                                                                                                    | 2 X 1000 MM DIA<br>Unit = m<br>Taking output = 7.5 m<br>(6 pipes of 2.5 m length each in two rows)                                                                                                                                                                                                               |       |          |      |               |
|         |             | a) Material                                                                                                           |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | i) Sand at site                                                                                                       | cum                                                                                                                                                                                                                                                                                                              | 0.08  | 1022.24  |      | 81.78         |
|         |             | ii) Cement at site                                                                                                    | ton                                                                                                                                                                                                                                                                                                              | 0.06  | 6260.20  |      | 375.61        |
|         |             | iii) RCC pipe NP 3 pipe including collar at site                                                                      | m                                                                                                                                                                                                                                                                                                                | 15.00 | 2989.54  |      | 44843.10      |
|         |             | b) Labour                                                                                                             |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Mate                                                                                                                  | day                                                                                                                                                                                                                                                                                                              | 0.22  | 397.00   |      | 87.34         |
|         |             | Mason (1st class)                                                                                                     | day                                                                                                                                                                                                                                                                                                              | 0.6   | 503.00   |      | 301.80        |
|         |             | Mazdoor (Unskilled)                                                                                                   | day                                                                                                                                                                                                                                                                                                              | 4.80  | 373.00   |      | 1790.40       |
|         |             | c) Overheads @ 20 % on (a+b)                                                                                          |                                                                                                                                                                                                                                                                                                                  |       |          |      | 9496.04       |
|         |             | d) Contractor's profit @ 10% on (a+b+c)                                                                               |                                                                                                                                                                                                                                                                                                                  |       |          |      | 5697.60       |
|         |             | Cost for 7.5 m = (a+b+c)                                                                                              |                                                                                                                                                                                                                                                                                                                  |       |          |      | 62673.64      |
|         |             | Rate per m = (a+b+c)/7.5                                                                                              |                                                                                                                                                                                                                                                                                                                  |       |          |      | 8356.49       |
|         |             |                                                                                                                       | Total Cost including 1 % LABOUR CESS                                                                                                                                                                                                                                                                             | M     |          |      | 8440.05       |
| 38      | 11.4        | 800 & 1260                                                                                                            | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203                                                                                                                                                          |       |          |      |               |
|         |             | I. P.C.C grade M 10                                                                                                   |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | (i) Nominal mix 1:3:6<br>Unit = cum                                                                                   |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | a) Material                                                                                                           |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Cement                                                                                                                | t                                                                                                                                                                                                                                                                                                                | 0.250 | 5,854.80 |      | 1,463.70      |
|         |             | Coarse sand                                                                                                           | cum                                                                                                                                                                                                                                                                                                              | 0.48  | 494.00   |      | 237.12        |
|         |             | 40 mm aggregate                                                                                                       | cum                                                                                                                                                                                                                                                                                                              | 0.576 | 975.00   |      | 561.60        |
|         |             | 20 mm aggregate                                                                                                       | cum                                                                                                                                                                                                                                                                                                              | 0.288 | 1,186.00 |      | 341.57        |
|         |             | 10 mm aggregate                                                                                                       | cum                                                                                                                                                                                                                                                                                                              | 0.096 | 586.00   |      | 56.26         |
|         |             | b) Labour                                                                                                             |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Mate                                                                                                                  | day                                                                                                                                                                                                                                                                                                              | 0.08  | 397.00   |      | 31.76         |
|         |             | Mason (1st Class)                                                                                                     | day                                                                                                                                                                                                                                                                                                              | 0.10  | 503.00   |      | 50.30         |
|         |             | Mazdoor (Unskilled)                                                                                                   | day                                                                                                                                                                                                                                                                                                              | 1.63  | 373.00   |      | 607.99        |
|         |             | Bhisti                                                                                                                | day                                                                                                                                                                                                                                                                                                              | 0.27  | 373.00   |      | 100.71        |
|         |             | c) Machinery                                                                                                          |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Mechanical concrete mixer 0.4/0.28 cum capacity fitted with water measuring device and preferably also with load cell | hour                                                                                                                                                                                                                                                                                                             | 0.40  | 334.00   |      | 133.60        |
|         |             | d) Formwork @ 4% on cost of material, labour and machinery (a+b+c)                                                    |                                                                                                                                                                                                                                                                                                                  |       |          |      | 143.38        |
|         |             | e) Overheads @ 20 % on (a+b+c+d)                                                                                      |                                                                                                                                                                                                                                                                                                                  |       |          |      | 743.60        |
|         |             | f) Contractor's profit @ 10% on (a+b+c+d+e)                                                                           |                                                                                                                                                                                                                                                                                                                  |       |          |      | 447.36        |
|         |             | Rate per cum = (a+b+c+d+e+f)                                                                                          |                                                                                                                                                                                                                                                                                                                  |       |          |      | 4920.94       |
|         |             | Carriage cost:-                                                                                                       |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Cement                                                                                                                | t                                                                                                                                                                                                                                                                                                                | 0.250 | 405.40   |      | 101.35        |
|         |             | Coarse sand                                                                                                           | cum                                                                                                                                                                                                                                                                                                              | 0.48  | 528.24   |      | 253.56        |
|         |             | Aggregate                                                                                                             | cum                                                                                                                                                                                                                                                                                                              | 0.960 | 1,992.12 |      | 1,912.44      |
|         |             | Rate per cum including Carriage                                                                                       |                                                                                                                                                                                                                                                                                                                  |       |          |      | 7,188.28      |
|         |             |                                                                                                                       | Rate per cum = a+b+c+d=                                                                                                                                                                                                                                                                                          | cum   |          |      | 7188.28       |
|         |             | II. P.C.C grade M 15                                                                                                  |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | (i) Nominal mix (1:2.5:5)<br>Unit = cum                                                                               |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | a) Material                                                                                                           |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Cement                                                                                                                | t                                                                                                                                                                                                                                                                                                                | 0.275 | 5,854.80 |      | 1,610.07      |
|         |             | Coarse sand                                                                                                           | cum                                                                                                                                                                                                                                                                                                              | 0.48  | 494.00   |      | 237.12        |
|         |             | 40 mm aggregate                                                                                                       | cum                                                                                                                                                                                                                                                                                                              | 0.48  | 975.00   |      | 468.00        |
|         |             | 20 mm aggregate                                                                                                       | cum                                                                                                                                                                                                                                                                                                              | 0.24  | 1,186.00 |      | 284.64        |
|         |             | 10 mm aggregate                                                                                                       | cum                                                                                                                                                                                                                                                                                                              | 0.08  | 586.00   |      | 46.88         |
|         |             | b) Labour                                                                                                             |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Mate                                                                                                                  | day                                                                                                                                                                                                                                                                                                              | 0.08  | 397.00   |      | 31.76         |
|         |             | Mason (1st Class)                                                                                                     | day                                                                                                                                                                                                                                                                                                              | 0.10  | 503.00   |      | 50.30         |
|         |             | Mazdoor (Unskilled)                                                                                                   | day                                                                                                                                                                                                                                                                                                              | 1.63  | 373.00   |      | 607.99        |
|         |             | Bhisti                                                                                                                | day                                                                                                                                                                                                                                                                                                              | 0.27  | 373.00   |      | 100.71        |
|         |             | c) Machinery                                                                                                          |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Concrete mixer 0.4/0.28 cum capacity                                                                                  | hour                                                                                                                                                                                                                                                                                                             | 0.40  | 334.00   |      | 133.60        |
|         |             | d) Formwork @ 4% on cost of material, labour and machinery (a+b+c)                                                    |                                                                                                                                                                                                                                                                                                                  |       |          |      | 142.84        |
|         |             | e) Overheads @ 20 % on (a+b+c+d)                                                                                      |                                                                                                                                                                                                                                                                                                                  |       |          |      | 742.78        |
|         |             | f) Contractor's profit @ 10% on (a+b+c+d+e)                                                                           |                                                                                                                                                                                                                                                                                                                  |       |          |      | 445.67        |
|         |             | Rate per cum = (a+b+c+d+e+f)                                                                                          |                                                                                                                                                                                                                                                                                                                  |       |          |      | 4902.30       |
|         |             | Carriage cost:-                                                                                                       |                                                                                                                                                                                                                                                                                                                  |       |          |      |               |
|         |             | Cement                                                                                                                | t                                                                                                                                                                                                                                                                                                                | 0.275 | 405.40   |      | 111.44        |
|         |             | Coarse sand                                                                                                           | cum                                                                                                                                                                                                                                                                                                              | 0.48  | 528.24   |      | 253.56        |
|         |             | Aggregate                                                                                                             | cum                                                                                                                                                                                                                                                                                                              | 0.80  | 1,992.12 |      | 1,593.70      |



| Sl. No. | SDB Sl. No. | MORD Ref. No. | DESCRIPTION                                                                                                                                          | Unit | Quantity |          |          |
|---------|-------------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|----------|----------|
|         |             |               | Rate per cum including Carriage                                                                                                                      |      |          |          |          |
|         |             |               | Rate per cum = a+b+c+d                                                                                                                               | cum  |          |          |          |
|         |             | III.          | <b>P.C.C. grade M 20</b>                                                                                                                             |      |          |          |          |
|         |             |               | Nominal mix (1:2:4)                                                                                                                                  |      |          |          |          |
|         |             |               | Unit = cum                                                                                                                                           |      |          |          |          |
|         |             | a)            | <b>Material</b>                                                                                                                                      |      |          |          |          |
|         |             |               | Cement                                                                                                                                               | t    | 0.33     | 5,854.00 |          |
|         |             |               | Sand                                                                                                                                                 | cum  | 0.45     | 494.00   |          |
|         |             |               | 40 mm aggregate                                                                                                                                      | cum  | 0.36     | 975.00   |          |
|         |             |               | 20 mm aggregate                                                                                                                                      | cum  | 0.36     | 1,186.00 |          |
|         |             |               | 10 mm aggregate                                                                                                                                      | cum  | 0.18     | 586.00   |          |
|         |             | b)            | <b>Labour</b>                                                                                                                                        |      |          |          |          |
|         |             |               | Mate                                                                                                                                                 | day  | 0.08     | 397.00   |          |
|         |             |               | Mason (1st Class)                                                                                                                                    | day  | 0.10     | 503.00   |          |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                  | day  | 1.63     | 373.00   |          |
|         |             |               | Bhisti                                                                                                                                               | day  | 0.27     | 373.00   |          |
|         |             | c)            | <b>Machinery</b>                                                                                                                                     |      |          |          |          |
|         |             |               | Concrete mixer 0.4/0.28 cum capacity                                                                                                                 | hour | 0.40     | 334.00   |          |
|         |             | d)            | Formwork @ 4% on (a+b+c)                                                                                                                             |      |          |          | 1.       |
|         |             | e)            | Overheads @20 % on (a+b+c+d)                                                                                                                         |      |          |          | 82.      |
|         |             | f)            | Contractor's profit @ 10% on (a+b+c+d+e)                                                                                                             |      |          |          | 494.4    |
|         |             |               | Rate per cum = (a+b+c+d+e+f)                                                                                                                         |      |          |          | 5439.2   |
|         |             |               | <b>Carriage cost:-</b>                                                                                                                               |      |          |          |          |
|         |             |               | Cement                                                                                                                                               | t    | 0.33     | 405.40   | 133.78   |
|         |             |               | Coarse sand                                                                                                                                          | cum  | 0.45     | 528.24   | 237.71   |
|         |             |               | Aggregate                                                                                                                                            | cum  | 0.90     | 1,992.12 | 1,792.91 |
|         |             |               | Rate per cum including Carriage                                                                                                                      |      |          |          | 7,603.68 |
|         |             |               | Rate per cum = a+b+c+d                                                                                                                               | cum  |          |          | 7603.68  |
| 39      | 12.5        | 800           | Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 |      |          |          |          |
|         |             |               | For height upto 5 m                                                                                                                                  |      |          |          |          |
|         |             |               | Unit = cum                                                                                                                                           |      |          |          |          |
|         |             | II.           | <b>P.C.C grade M 15</b>                                                                                                                              |      |          |          |          |
|         |             | (i)           | <b>Nominal mix (1:2.5:5)</b>                                                                                                                         |      |          |          |          |
|         |             |               | Unit = cum                                                                                                                                           |      |          |          |          |
|         |             | a)            | <b>Material</b>                                                                                                                                      |      |          |          |          |
|         |             |               | Cement                                                                                                                                               | t    | 0.275    | 5,854.80 | 1,610.07 |
|         |             |               | Coarse sand                                                                                                                                          | cum  | 0.48     | 494.00   | 237.12   |
|         |             |               | 40 mm aggregate                                                                                                                                      | cum  | 0.48     | 975.00   | 468.00   |
|         |             |               | 20 mm aggregate                                                                                                                                      | cum  | 0.24     | 1,186.00 | 284.64   |
|         |             |               | 10 mm aggregate                                                                                                                                      | cum  | 0.18     | 586.00   | 105.48   |
|         |             | b)            | <b>Labour</b>                                                                                                                                        |      |          |          |          |
|         |             |               | Mate                                                                                                                                                 | day  | 0.08     | 397.00   | 31.76    |
|         |             |               | Mason (1st Class)                                                                                                                                    | day  | 0.10     | 503.00   | 50.30    |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                  | day  | 1.63     | 373.00   | 607.99   |
|         |             |               | Bhisti                                                                                                                                               | day  | 0.27     | 373.00   | 100.71   |
|         |             | c)            | <b>Machinery</b>                                                                                                                                     |      |          |          |          |
|         |             |               | Concrete mixer 0.4/0.28 cum capacity                                                                                                                 | hour | 0.40     | 334.00   | 133.60   |
|         |             | d)            | Formwork @ 10% on cost of material, labour and machinery (a+b+c)                                                                                     |      |          |          | 362.97   |
|         |             | e)            | Overheads @20 % on (a+b+c+d)                                                                                                                         |      |          |          | 798.53   |
|         |             | f)            | Contractor's profit @ 10% on (a+b+c+d+e)                                                                                                             |      |          |          | 479.12   |
|         |             |               | Rate per cum = (a+b+c+d+e+f)                                                                                                                         |      |          |          | 5270.28  |
|         |             |               | <b>Carriage cost:-</b>                                                                                                                               |      |          |          |          |
|         |             |               | Cement                                                                                                                                               | t    | 0.275    | 405.40   | 111.49   |
|         |             |               | Coarse sand                                                                                                                                          | cum  | 0.48     | 528.24   | 253.56   |
|         |             |               | Aggregate                                                                                                                                            | cum  | 0.90     | 1,992.12 | 1,792.91 |
|         |             |               | Rate per cum including Carriage                                                                                                                      |      |          |          | 7,428.23 |
|         |             |               | Rate per cum = a+b+c+d+e+f                                                                                                                           | cum  |          |          | 7428.23  |
|         |             | II.           | <b>P.C.C grade M 20</b>                                                                                                                              |      |          |          |          |
|         |             | (i)           | <b>Nominal mix (1:2:4)</b>                                                                                                                           |      |          |          |          |
|         |             |               | Unit = cum                                                                                                                                           |      |          |          |          |
|         |             | a)            | <b>Material</b>                                                                                                                                      |      |          |          |          |
|         |             |               | Cement                                                                                                                                               | t    | 0.33     | 5,854.80 | 1,932.08 |
|         |             |               | Sand                                                                                                                                                 | cum  | 0.45     | 494.00   | 222.30   |
|         |             |               | 40 mm aggregate                                                                                                                                      | cum  | 0.36     | 975.00   | 351.00   |
|         |             |               | 20 mm aggregate                                                                                                                                      | cum  | 0.36     | 1,186.00 | 426.96   |
|         |             |               | 10 mm aggregate                                                                                                                                      | cum  | 0.18     | 586.00   | 105.48   |
|         |             | b)            | <b>Labour</b>                                                                                                                                        |      |          |          |          |
|         |             |               | Mate                                                                                                                                                 | day  | 0.08     | 397.00   | 31.76    |
|         |             |               | Mason (1st Class)                                                                                                                                    | day  | 0.10     | 503.00   | 50.30    |
|         |             |               | Mazdoor (Unskilled)                                                                                                                                  | day  | 1.63     | 373.00   | 607.99   |
|         |             |               | Bhisti                                                                                                                                               | day  | 0.27     | 373.00   | 100.71   |
|         |             | c)            | <b>Machinery</b>                                                                                                                                     |      |          |          |          |





| SL No. | SP No. | MORD Ref No. | DESCRIPTION                                                                                                                                                              | Unit | Quantity | Rate     | Amount in Rs |
|--------|--------|--------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|----------|--------------|
|        |        | a)           | <b>Material</b>                                                                                                                                                          |      |          |          |              |
|        |        |              | Cement                                                                                                                                                                   | t    | 0.43     | 5,854.80 | 2,517.56     |
|        |        |              | Coarse sand                                                                                                                                                              | cum  | 0.45     | 494.00   | 222.30       |
|        |        |              | 20 mm aggregate                                                                                                                                                          | cum  | 0.54     | 1,186.00 | 640.44       |
|        |        |              | 10 mm aggregate                                                                                                                                                          | cum  | 0.36     | 586.00   | 210.96       |
|        |        | b)           | <b>Labour</b>                                                                                                                                                            |      |          |          |              |
|        |        |              | Mate                                                                                                                                                                     | day  | 0.08     | 397.00   | 31.76        |
|        |        |              | Mason (1st Class)                                                                                                                                                        | day  | 0.12     | 503.00   | 60.36        |
|        |        |              | Mazdoor (Unskilled)                                                                                                                                                      | day  | 1.73     | 373.00   | 645.29       |
|        |        |              | Bhisti                                                                                                                                                                   | day  | 0.27     | 373.00   | 100.71       |
|        |        | c)           | <b>Machinery</b>                                                                                                                                                         |      |          |          |              |
|        |        |              | Concrete mixer 0.4/0.28 cum capacity                                                                                                                                     | hour | 0.40     | 334.00   | 133.60       |
|        |        | d)           | For formwork and staging 20% of a+b                                                                                                                                      |      |          |          | 885.88       |
|        |        | e)           | Overheads @ 20% on (a+b+c+d)                                                                                                                                             |      |          |          | 1089.77      |
|        |        | f)           | Contractor's profit @ 10% on (a+b+c+d+e)                                                                                                                                 |      |          |          | 653.86       |
|        |        |              | Rate per cum = (a+b+c+d+e+f)                                                                                                                                             |      |          |          | 7192.50      |
|        |        |              | <b>Carriage cost:-</b>                                                                                                                                                   |      |          |          |              |
|        |        |              | Cement                                                                                                                                                                   | t    | 0.43     | 405.40   | 174.32       |
|        |        |              | Coarse sand                                                                                                                                                              | cum  | 0.45     | 528.24   | 237.71       |
|        |        |              | Aggregate                                                                                                                                                                | cum  | 0.90     | 1,992.12 | 1,792.91     |
|        |        |              | Rate per cum including Carriage                                                                                                                                          |      |          |          | 9,397.43     |
|        |        |              | Rate per cum = a+b+c+d+e+f =                                                                                                                                             | cum  |          |          | 9397.43      |
| 41     | 11.5   | 600 & 1200   | <b>Brick masonry work in cement mortar in foundation</b> complete excluding pointing and plastering as per drawing and technical specifications Clauses 600, 1202 & 1203 |      |          |          |              |
|        |        | I)           | <b>1 : 3 Cement Mortar</b>                                                                                                                                               |      |          |          |              |
|        |        |              | Unit = cum                                                                                                                                                               |      |          |          |              |
|        |        | L            | Brick masonry in 1:3 cement mortar                                                                                                                                       |      |          |          |              |
|        |        | a)           | <b>Material</b>                                                                                                                                                          |      |          |          |              |
|        |        |              | Brick                                                                                                                                                                    | Nos  | 500.00   | 6.07     | 3,034.50     |
|        |        |              | Cement mortar 1:3                                                                                                                                                        | cum  | 0.24     | 4,647.47 | 1,115.39     |
|        |        |              | (Rate as per Sub-analysis)                                                                                                                                               |      |          |          |              |
|        |        | b)           | <b>Labour</b>                                                                                                                                                            |      |          |          |              |
|        |        |              | Mate                                                                                                                                                                     | day  | 0.09     | 397.00   | 35.73        |
|        |        |              | Mason (1st Class)                                                                                                                                                        | day  | 0.80     | 503.00   | 402.40       |
|        |        |              | Mazdoor (Unskilled)                                                                                                                                                      | day  | 1.60     | 373.00   | 596.80       |
|        |        |              | Bhisti                                                                                                                                                                   | day  | 0.20     | 373.00   | 74.60        |
|        |        | c)           | Overheads @ 20% on (a+b)                                                                                                                                                 |      |          |          | 1051.88      |
|        |        | d)           | Contractor's profit @ 10% on (a+b+c)                                                                                                                                     |      |          |          | 631.13       |
|        |        |              | Rate per cum = (a+b+c+d)                                                                                                                                                 |      |          |          | 6942.44      |
|        |        |              | <b>Carriage Cost</b>                                                                                                                                                     |      |          |          |              |
|        |        |              | carriage brick                                                                                                                                                           | no   | 500.00   | 0.80     | 399.41       |
|        |        |              | Rate per cum including Carriage                                                                                                                                          |      |          |          | 7,341.85     |
|        |        |              | Rate per cum = a+b+c+d                                                                                                                                                   | cum  |          |          | 7341.85      |
|        |        |              | <b>Sub-analysis</b>                                                                                                                                                      |      |          |          |              |
|        |        |              | Cement mortar 1:3 (1 cement : 3 sand)                                                                                                                                    |      |          |          |              |
|        |        |              | Unit = cum                                                                                                                                                               |      |          |          |              |
|        |        | a)           | <b>Material</b>                                                                                                                                                          |      |          |          |              |
|        |        |              | Cement                                                                                                                                                                   | t    | 0.51     | 5,854.80 | 2,985.95     |
|        |        |              | Sand                                                                                                                                                                     | cum  | 1.05     | 494.00   | 518.70       |
|        |        | b)           | <b>Labour</b>                                                                                                                                                            |      |          |          |              |
|        |        |              | Mate                                                                                                                                                                     | day  | 0.04     | 397.00   | 15.88        |
|        |        |              | Mazdoor (Unskilled)                                                                                                                                                      | day  | 0.90     | 373.00   | 335.70       |
|        |        |              | Bhisti                                                                                                                                                                   | day  | 0.08     | 373.00   | 29.84        |
|        |        |              | Rate per cum = (a+b+c+d)                                                                                                                                                 |      |          |          | 3886.07      |
|        |        |              | <b>Carriage Cost</b>                                                                                                                                                     |      |          |          |              |
|        |        |              | carriage cement                                                                                                                                                          | t    | 0.51     | 405.40   | 206.75       |
|        |        |              | carriage sand                                                                                                                                                            | cum  | 1.05     | 528.24   | 554.65       |
|        |        |              | Rate per cum including Carriage                                                                                                                                          |      |          |          | 4,647.47     |
|        |        |              | Total material and labour = (a+b)                                                                                                                                        | cum  |          |          | 4647.47      |
|        |        | II.          | <b>Brick masonry in 1:4 cement mortar</b>                                                                                                                                |      |          |          |              |
|        |        |              | Unit = cum                                                                                                                                                               |      |          |          |              |
|        |        | a)           | <b>Material</b>                                                                                                                                                          |      |          |          |              |
|        |        |              | Brick                                                                                                                                                                    | Nos. | 500.00   | 6.07     | 3,034.50     |
|        |        |              | Cement mortar 1:4                                                                                                                                                        | cum  | 0.24     | 3,833.65 | 920.08       |
|        |        |              | Rates as per sub-analysis                                                                                                                                                |      |          |          |              |
|        |        | b)           | <b>Labour</b>                                                                                                                                                            |      |          |          |              |
|        |        |              | Mate                                                                                                                                                                     | day  | 0.09     | 397.00   | 35.73        |
|        |        |              | Mason (1st Class)                                                                                                                                                        | day  | 0.80     | 503.00   | 402.40       |
|        |        |              | Mazdoor (Unskilled)                                                                                                                                                      | day  | 1.60     | 373.00   | 596.80       |
|        |        |              | Bhisti                                                                                                                                                                   | day  | 0.20     | 373.00   | 74.60        |
|        |        | c)           | Overheads @ 20 % on (a+b)                                                                                                                                                |      |          |          | 1012.82      |
|        |        | d)           | Contractor's profit @ 10% on (a+b+c)                                                                                                                                     |      |          |          | 607.69       |

| Sl. No. | SPH. No. | MORTAR | DESCRIPTION                                                                                                             | Unit | Quantity | Rate    | Amount (₹) |
|---------|----------|--------|-------------------------------------------------------------------------------------------------------------------------|------|----------|---------|------------|
|         |          |        | Rate per cum (as above)                                                                                                 |      |          |         | 6685.42    |
|         |          |        | Carriage Cost                                                                                                           |      |          |         |            |
|         |          |        | Carriage brick                                                                                                          | no   | 500.00   | 0.80    | 399.50     |
|         |          |        | Rate per cum including Carriage                                                                                         |      |          |         | 6685.42    |
|         |          |        | Rate per cum including Carriage                                                                                         |      |          |         | 6685.42    |
|         |          |        | Sub analysis                                                                                                            |      |          |         |            |
|         |          |        | Cement mortar 1:4 (1 cement : 4 sand)                                                                                   |      |          |         |            |
|         |          |        | Unit = cum                                                                                                              |      |          |         |            |
|         |          | a)     | Material                                                                                                                |      |          |         |            |
|         |          |        | Cement                                                                                                                  | t    | 0.18     | 5854.80 | 2224.86    |
|         |          |        | Sand                                                                                                                    | cum  | 1.05     | 594.00  | 518.70     |
|         |          | b)     | Labour                                                                                                                  |      |          |         |            |
|         |          |        | Mate                                                                                                                    | day  | 0.04     | 147.00  | 17.08      |
|         |          |        | Mason (Unskilled)                                                                                                       | day  | 0.30     | 171.00  | 13.77      |
|         |          |        | Blundi                                                                                                                  | day  | 0.08     | 171.00  | 2.90       |
|         |          |        | Rate per cum (as above)                                                                                                 |      |          |         | 2324.54    |
|         |          |        | Carriage Cost                                                                                                           |      |          |         |            |
|         |          |        | Carriage cement                                                                                                         | t    | 0.18     | 405.40  | 15.49      |
|         |          |        | Carriage sand                                                                                                           | cum  | 1.05     | 528.24  | 55.43      |
|         |          |        | Rate per cum including Carriage                                                                                         |      |          |         | 2889.27    |
|         |          |        | Total material and labour = (a+b)                                                                                       |      |          |         | 5213.81    |
|         |          | III.   | In 1:5 cement mortar                                                                                                    |      |          |         |            |
|         |          |        | Unit = cum                                                                                                              |      |          |         |            |
|         |          | a)     | Material                                                                                                                |      |          |         |            |
|         |          |        | Bricks 1st class                                                                                                        | nos  | 500.00   | 6.07    | 3034.50    |
|         |          |        | Cement mortar                                                                                                           | cum  | 0.24     | 3195.81 | 764.90     |
|         |          | b)     | Labour                                                                                                                  |      |          |         |            |
|         |          |        | Mate                                                                                                                    | day  | 0.09     | 147.00  | 13.23      |
|         |          |        | Mason 1st class                                                                                                         | day  | 0.40     | 513.00  | 102.40     |
|         |          |        | Mason (Unskilled)                                                                                                       | day  | 1.40     | 171.00  | 239.40     |
|         |          |        | Blundi                                                                                                                  | day  | 0.10     | 171.00  | 17.10      |
|         |          |        | Add for scaffolding @ 5 per cent of cost of materials and labour (as above)                                             |      |          |         | 241.38     |
|         |          | c)     | Overheads @ 20% on (a+b)                                                                                                |      |          |         | 624.81     |
|         |          | d)     | Contractor's profit @ 10% on (a+b+c)                                                                                    |      |          |         | 6871.88    |
|         |          |        | Rate per cum = (a+b+c+d)                                                                                                |      |          |         | 6871.88    |
|         |          |        | Rate per cum                                                                                                            |      |          |         | 6871.88    |
|         |          |        | Sub analysis                                                                                                            |      |          |         |            |
|         |          |        | Cement mortar 1:5 (1 cement : 5 sand)                                                                                   |      |          |         |            |
|         |          | a)     | Material                                                                                                                |      |          |         |            |
|         |          |        | Cement                                                                                                                  | t    | 0.11     | 5854.80 | 1814.39    |
|         |          |        | Sand                                                                                                                    | cum  | 1.05     | 594.00  | 518.10     |
|         |          | b)     | Labour                                                                                                                  |      |          |         |            |
|         |          |        | Mate                                                                                                                    | day  | 0.05     | 127.00  | 11.00      |
|         |          |        | Mason (Unskilled)                                                                                                       | day  | 0.20     | 171.00  | 33.50      |
|         |          |        | Blundi                                                                                                                  | day  | 0.08     | 171.00  | 27.04      |
|         |          | c)     | Carriage cost                                                                                                           |      |          |         |            |
|         |          |        | Cement                                                                                                                  | t    | 0.11     | 405.40  | 11.56      |
|         |          |        | Sand                                                                                                                    | cum  | 1.05     | 528.24  | 55.43      |
|         |          |        | Total cost                                                                                                              |      |          |         | 2395.43    |
|         |          |        | Total material and labour = (a+b)                                                                                       |      |          |         | 2395.43    |
| 42      | 12.1     | 6000   | Brick masonry work in cement mortar in masonry wall, including scaffolding and plastering, at per running meter of wall |      |          |         |            |
|         |          |        | Specification Clause 103, 104, 105 & 114                                                                                |      |          |         |            |
|         |          | i.     | In 1:3 cement mortar                                                                                                    |      |          |         |            |
|         |          |        | Unit = cum                                                                                                              |      |          |         |            |
|         |          | a)     | Material                                                                                                                |      |          |         |            |
|         |          |        | Bricks                                                                                                                  | nos  | 500.00   | 6.07    | 3034.50    |
|         |          |        | Cement mortar (Rate as in Brick 1:3)                                                                                    | cum  | 0.24     | 3195.81 | 764.90     |
|         |          | b)     | Labour                                                                                                                  |      |          |         |            |
|         |          |        | Mate                                                                                                                    | day  | 0.09     | 147.00  | 13.23      |
|         |          |        | Mason 1st class                                                                                                         | day  | 0.40     | 513.00  | 102.40     |
|         |          |        | Mason (Unskilled)                                                                                                       | day  | 1.40     | 171.00  | 239.40     |
|         |          |        | Blundi                                                                                                                  | day  | 0.10     | 171.00  | 17.10      |
|         |          |        | Add for scaffolding @ 5 per cent of cost of materials and labour (as above)                                             |      |          |         | 207.40     |
|         |          | c)     | Overheads @ 20% on (a+b)                                                                                                |      |          |         | 1090.30    |
|         |          | d)     | Contractor's profit @ 10% on (a+b+c)                                                                                    |      |          |         | 656.03     |
|         |          |        | Rate per cum = (a+b+c+d)                                                                                                |      |          |         | 7316.43    |
|         |          |        | Carriage Cost                                                                                                           |      |          |         |            |
|         |          |        | Carriage brick                                                                                                          | no   | 500.00   | 0.80    | 399.41     |
|         |          |        | Rate per cum including Carriage                                                                                         |      |          |         | 7615.74    |
|         |          |        | Rate per cum = (a+b+c+d)                                                                                                |      |          |         | 7615.74    |
|         |          | II.    | In 1:4 Cement mortar                                                                                                    |      |          |         |            |



| Sl. No. | SDB Sl. No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                | Unit                     | Quantity                     | Rate                                 | Amount in Rs                        |
|---------|-------------|---------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|------------------------------|--------------------------------------|-------------------------------------|
|         |             | a)            | Unit = cum<br><b>Material</b><br>Bricks<br>Cement mortar<br>(Rate as in item 11.5 II)                                                                                      | Nos.<br>cum              | 500.00<br>0.24               | 6.97<br>3,833.65                     | 3,034.50<br>920.08                  |
|         |             | b)            | <b>Labour</b><br>Mate<br>Mason 1st Class<br>Mazdoor (Unskilled)<br>Bhisti<br>Add for scaffolding @ 5 per cent of cost of materials and labour (a+b)                        | day<br>day<br>day<br>day | 0.09<br>0.80<br>1.60<br>0.20 | 397.00<br>503.00<br>373.00<br>373.00 | 35.73<br>402.40<br>596.80<br>74.60  |
|         |             | c)            | Overheads @ 20% on (a+b)                                                                                                                                                   |                          |                              |                                      | 253.21                              |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                       |                          |                              |                                      | 1063.46                             |
|         |             |               | Rate per cum = (a+b+c+d)                                                                                                                                                   |                          |                              |                                      | 638.08                              |
|         |             |               | <b>Carriage Cost</b><br>carriage brick                                                                                                                                     | no.                      | 500.00                       | 0.80                                 | 7018.85                             |
|         |             |               | Rate per cum including Carriage                                                                                                                                            |                          |                              |                                      | 399.41                              |
|         |             |               | Rate per cum = a+b+c+d =                                                                                                                                                   | cum                      |                              |                                      | 7418.26                             |
| 43      | 12.2        | 600           | <b>Pointing with cement mortar (1:3)</b> on brickwork as per drawing and technical specification Clauses 613.3 and 1204                                                    |                          |                              |                                      | 7418.26                             |
|         |             |               | Unit = 10 sqm<br>Taking output = 10 sqm                                                                                                                                    |                          |                              |                                      |                                     |
|         |             | a)            | <b>Material</b><br>Cement mortar 1:3 (Rate as in item 11.5 I)                                                                                                              | cum                      | 0.03                         | 4,647.47                             | 139.42                              |
|         |             | b)            | <b>Labour</b><br>Mate<br>Mason 1st Class<br>Mazdoor (Unskilled)<br>Bhisti                                                                                                  | day<br>day<br>day<br>day | 0.04<br>0.50<br>0.50<br>0.20 | 397.00<br>503.00<br>373.00<br>373.00 | 15.88<br>251.50<br>186.50<br>74.60  |
|         |             | c)            | Overheads @ 20% on (a+b)                                                                                                                                                   |                          |                              |                                      | 133.58                              |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                       |                          |                              |                                      | 80.15                               |
|         |             |               | Rate per 10 sqm = (a+b+c+d)                                                                                                                                                |                          |                              |                                      | 881.63                              |
|         |             |               | Rate per sqm = (a+b+c+d)/10                                                                                                                                                |                          |                              |                                      | 88.16                               |
|         |             |               | <b>Total Cost</b>                                                                                                                                                          | sqm                      |                              |                                      | 88.16                               |
| 44      | 12.3        | 600 & 1200    | <b>Plastering with CM 1:4</b><br>Plastering with cement mortar (1:4), 15 mm thick on brickwork in substructure as per technical specification Clauses 613.4 & 1204         |                          |                              |                                      |                                     |
|         |             |               | Unit = 10 sqm<br>Taking output = 10 sqm                                                                                                                                    |                          |                              |                                      |                                     |
|         |             | a)            | <b>Material</b><br>Cement mortar 1:4 (Rate as in item 11.5 II)                                                                                                             | cum                      | 0.24                         | 3,833.65                             | 920.08                              |
|         |             | b)            | <b>Labour</b><br>Mate<br>Mason 1st Class<br>Mazdoor (Unskilled)<br>Bhisti                                                                                                  | day<br>day<br>day<br>day | 0.06<br>0.60<br>0.60<br>0.30 | 397.00<br>503.00<br>373.00<br>373.00 | 23.82<br>301.80<br>223.80<br>111.90 |
|         |             | c)            | Overheads @ 20% on (a+b)                                                                                                                                                   |                          |                              |                                      | 316.28                              |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                       |                          |                              |                                      | 189.77                              |
|         |             |               | Rate per 10 sqm = a+b+c+d                                                                                                                                                  |                          |                              |                                      | 2,087.44                            |
|         |             |               | <b>Total Cost</b>                                                                                                                                                          | Sqm                      |                              |                                      | 208.74                              |
| 45      | 11.7        | 1000 & 1200   | <b>Supplying, fitting and placing HYSD bar reinforcement in foundation</b> complete as per drawings and technical specifications (Clauses 1000 and 1202)                   |                          |                              |                                      |                                     |
|         |             |               | Unit = t                                                                                                                                                                   |                          |                              |                                      |                                     |
|         |             | a)            | <b>Material</b><br>HYSD bars including 5 per cent for overlaps and wastage<br>Binding wire                                                                                 | t<br>kg                  | 1.05<br>6.00                 | 57,667.00<br>75.04                   | 60,550.35<br>450.24                 |
|         |             | b)            | <b>Labour</b> for cutting, bending, shifting to site, tying and placing in position<br>Mate<br>Blacksmith<br>Mazdoor (Unskilled)                                           | day<br>day<br>day        | 0.40<br>2.00<br>6.00         | 397.00<br>449.00<br>373.00           | 158.80<br>898.00<br>2,238.00        |
|         |             | c)            | Overheads @ 20% on (a+b)                                                                                                                                                   |                          |                              |                                      | 12859.08                            |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                       |                          |                              |                                      | 7715.45                             |
|         |             |               | Rate per t = a+b+c+d                                                                                                                                                       |                          |                              |                                      | 84,869.91                           |
|         |             |               | <b>CARRIAGE</b><br>Reinforcement                                                                                                                                           | t                        | 1.05                         | 405.40                               | 425.67                              |
|         |             |               | Rate per t including Carriage                                                                                                                                              |                          |                              |                                      | 85295.58                            |
|         |             |               | Rate per t = a+b+c                                                                                                                                                         | t                        |                              |                                      | 85295.58                            |
| 46      | 12.6        | 1000          | <b>Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure</b> complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202 |                          |                              |                                      |                                     |
|         |             |               | Unit = t                                                                                                                                                                   |                          |                              |                                      |                                     |
|         |             | a)            | <b>Material</b><br>HYSD bars including 5 per cent overlaps and wastage<br>Binding wire                                                                                     | t<br>kg                  | 1.05<br>6.00                 | 57,667.00<br>75.04                   | 60,550.35<br>450.24                 |

| Item |       | Description |                                                                             | Unit | Quantity | Unit Price | Total Price |
|------|-------|-------------|-----------------------------------------------------------------------------|------|----------|------------|-------------|
| 41   | 1.1.1 | 0000        | Labour for cutting, bending, drilling for and tying and pinning in position |      |          |            |             |
|      |       |             | Man                                                                         | day  | 2.34     | 98.000     | 229.32      |
|      |       |             | Blacksmith                                                                  | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
| 42   | 1.1.2 | 0000        | Labour for cutting, bending, drilling for and tying and pinning in position |      |          |            |             |
|      |       |             | Man                                                                         | day  | 2.34     | 98.000     | 229.32      |
|      |       |             | Blacksmith                                                                  | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
| 43   | 1.1.3 | 0000        | Labour for cutting, bending, drilling for and tying and pinning in position |      |          |            |             |
|      |       |             | Man                                                                         | day  | 2.34     | 98.000     | 229.32      |
|      |       |             | Blacksmith                                                                  | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
| 44   | 1.1.4 | 0000        | Labour for cutting, bending, drilling for and tying and pinning in position |      |          |            |             |
|      |       |             | Man                                                                         | day  | 2.34     | 98.000     | 229.32      |
|      |       |             | Blacksmith                                                                  | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |
|      |       |             | Blacksmith (1/2 day)                                                        | day  | 2.00     | 119.000    | 238.00      |



| Sl. No. | SDP Sl. No. | MORD Ref No. | DESCRIPTION                                                                                                                                                               | Unit | Quantity | Rate      | Amount in Rs. |
|---------|-------------|--------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|-----------|---------------|
|         |             | b)           | <b>HYSD bar reinforcement (Rate as per item 13.2)</b>                                                                                                                     | t    | 1.46     | 87,092.05 | 126,445.19    |
|         |             | c)           | Overheads @ 20% on (a+b)                                                                                                                                                  |      |          |           | 32,904.15     |
|         |             | d)           | Contractor's profit @ 10% on (a+b+c)                                                                                                                                      |      |          |           | 19,742.49     |
|         |             |              | Cost for 4B m = (a+b+c+d)                                                                                                                                                 |      |          |           | 247,167.30    |
|         |             |              | Rate per m = (a+b+c+d)/4B                                                                                                                                                 |      |          |           | 4,569.56      |
|         |             |              | <b>Sub Analysis for Rate of Concrete</b>                                                                                                                                  |      |          |           |               |
|         |             | a)           | <b>Material</b>                                                                                                                                                           |      |          |           |               |
|         |             |              | Cement                                                                                                                                                                    | t    | 0.40     | 5,853.80  | 2,341.52      |
|         |             |              | Coarse sand                                                                                                                                                               | cum  | 0.45     | 494.00    | 222.30        |
|         |             |              | 20 mm aggregate                                                                                                                                                           | cum  | 0.54     | 1,186.00  | 640.44        |
|         |             |              | 10 mm aggregate                                                                                                                                                           | cum  | 0.46     | 506.00    | 232.76        |
|         |             | b)           | <b>Labour</b>                                                                                                                                                             |      |          |           |               |
|         |             |              | Mate                                                                                                                                                                      | day  | 0.08     | 397.00    | 31.76         |
|         |             |              | Mason (1st Class)                                                                                                                                                         | day  | 0.42     | 503.00    | 211.26        |
|         |             |              | Mazdoor (Unskilled)                                                                                                                                                       | day  | 1.73     | 373.00    | 645.29        |
|         |             |              | Bhisti                                                                                                                                                                    | day  | 0.27     | 373.00    | 100.71        |
|         |             | c)           | <b>Machinery</b>                                                                                                                                                          |      |          |           |               |
|         |             |              | Concrete mixer 0.4/0.2B cum capacity                                                                                                                                      | hour | 0.40     | 334.00    | 133.60        |
|         |             | d)           | <b>Formwork @ 12% (a+b+c)</b>                                                                                                                                             |      |          |           | 789.61        |
|         |             |              | Carriage cost:-                                                                                                                                                           |      |          |           |               |
|         |             |              | Cement                                                                                                                                                                    | t    | 0.40     | 405.40    | 162.16        |
|         |             |              | Coarse sand                                                                                                                                                               | cum  | 0.45     | 528.24    | 237.71        |
|         |             |              | Aggregate                                                                                                                                                                 | cum  | 0.90     | 1,992.12  | 1,792.91      |
|         |             |              | <b>Total Cost</b>                                                                                                                                                         |      |          |           | 7,369.23      |
|         |             |              | <b>Total (a+b+c+d)</b>                                                                                                                                                    | m    |          |           | 7,369.23      |
|         |             | 1            | 4B m length is the total linear length adding both sides of 2x12 m span                                                                                                   |      |          |           |               |
|         |             | 2            | Quantities of material have been adopted from standard plans of MORTH vide drawing No SD/202                                                                              |      |          |           |               |
| 50      | 13.9        | 600          | Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications. Clauses 600, 900 and 1208.4. Unit = cum |      |          |           |               |
|         |             | a)           | <b>Material</b>                                                                                                                                                           |      |          |           |               |
|         |             |              | Bricks                                                                                                                                                                    | No.  | 500.00   | 6.07      | 3,034.50      |
|         |             |              | Cement mortar (Rate as in item 11.5.1)                                                                                                                                    | cum  | 0.24     | 7,615.74  | 1,827.78      |
|         |             | b)           | <b>Labour</b>                                                                                                                                                             |      |          |           |               |
|         |             |              | Mate                                                                                                                                                                      | day  | 0.09     | 397.00    | 35.73         |
|         |             |              | Mason 1st Class                                                                                                                                                           | day  | 0.80     | 503.00    | 402.40        |
|         |             |              | Mazdoor (Unskilled)                                                                                                                                                       | day  | 1.60     | 373.00    | 596.80        |
|         |             |              | Bhisti                                                                                                                                                                    | day  | 0.20     | 373.00    | 74.60         |
|         |             | c)           | Overheads @ 20% on (a+b)                                                                                                                                                  |      |          |           | 1,194.36      |
|         |             | d)           | Contractor's profit @ 10% on (a+b+c)                                                                                                                                      |      |          |           | 716.62        |
|         |             |              | Rate per cum = a+b+c                                                                                                                                                      |      |          |           | 7,882.79      |
|         |             |              | Carriage cost:-                                                                                                                                                           |      |          |           |               |
|         |             |              | Brick                                                                                                                                                                     | No.  | 500.00   | 0.40      | 199.41        |
|         |             |              | <b>Total Cost per cum including Carriage</b>                                                                                                                              |      |          |           | 8,202.20      |
|         |             |              | <b>Rate per cum = a+b+c</b>                                                                                                                                               | cum  |          |           | 8,202.20      |
| 51      | 13.10       | 1200         | <b>Drainage spouts</b> complete as per drawing and technical specifications. Clause 1209. Unit = 1 No                                                                     |      |          |           |               |
|         |             | a)           | <b>Material</b>                                                                                                                                                           |      |          |           |               |
|         |             | i)           | Corrosion resistant structural steel grating including 5 per cent wastage                                                                                                 | kg   | 4.00     | 46.83     | 187.31        |
|         |             | ii)          | AC pipe 100 mm                                                                                                                                                            | m    | 1.00     | 44.28     | 44.28         |
|         |             | b)           | <b>Labour</b>                                                                                                                                                             |      |          |           |               |
|         |             |              | <b>For fabrication</b>                                                                                                                                                    |      |          |           |               |
|         |             |              | Mate                                                                                                                                                                      | day  | 0.02     | 397.00    | 7.94          |
|         |             |              | Blacksmith, Welder etc (Skilled)                                                                                                                                          | day  | 0.02     | 449.00    | 8.98          |
|         |             |              | Mazdoor (Unskilled)                                                                                                                                                       | day  | 0.20     | 373.00    | 74.60         |
|         |             |              | <b>For fixing in position</b>                                                                                                                                             |      |          |           |               |
|         |             |              | Mate                                                                                                                                                                      | day  | 0.01     | 397.00    | 3.97          |
|         |             |              | Mason (1st Class)                                                                                                                                                         | day  | 0.01     | 503.00    | 5.03          |
|         |             |              | Mazdoor (Unskilled)                                                                                                                                                       | day  | 0.20     | 373.00    | 74.60         |
|         |             |              | Add @ 5 per cent of cost of material and labour (a+b) for electrodes, gas cutting, sealant, anti corrosive bituminous paint, mild steel grating etc.                      |      |          |           | 87.76         |
|         |             | c)           | Overheads @ 20% on (a+b)                                                                                                                                                  |      |          |           | 83.09         |
|         |             | d)           | Contractor's profit @ 10% on (a+b+c)                                                                                                                                      |      |          |           | 49.86         |
|         |             |              | <b>Total Cost</b>                                                                                                                                                         |      |          |           | 548.41        |
|         |             |              | <b>Rate per m = a+b+c</b>                                                                                                                                                 | No.  |          |           | 548.41        |
| 52      | 13.16 IV)   | 1200         | <b>Filler joint</b><br>Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 per cent bitumen by weight.       |      |          |           |               |

| Sl. No. | SDH Sl. No. | MORD Ref. No. | DESCRIPTION                                                                               | Unit | Quantity | Rate      | Amount in Rs. |
|---------|-------------|---------------|-------------------------------------------------------------------------------------------|------|----------|-----------|---------------|
|         |             |               | Unit = Running m<br>Taking output = 7.5 m<br>7.5 m long x 100 mm wide x 10 mm deep recess |      |          |           |               |
|         |             | a)            | <b>Material</b>                                                                           |      |          |           |               |
|         |             |               | Sand                                                                                      | cum  | 0.008    | 494.00    | 3.95          |
|         |             |               | Volume = $7.5 \times 0.1 \times 0.01 = 0.008$ cum                                         |      |          |           |               |
|         |             |               | Weight = $0.008 \times 1400 = 11.2$ kg                                                    |      |          |           |               |
|         |             |               | Bitumen- $11.2 \times 0.06 = 0.672$ kg                                                    | t    | 0.0007   | 51,650.50 | 36.16         |
|         |             | b)            | <b>Labour</b>                                                                             |      |          |           |               |
|         |             |               | Mate                                                                                      | day  | 0.02     | 397.00    | 7.94          |
|         |             |               | Mazdoor (Skilled)                                                                         | day  | 0.50     | 472.00    | 236.00        |
|         |             |               | Mazdoor (Unskilled)                                                                       | day  | 0.10     | 373.00    | 37.30         |
|         |             | c)            | Overheads @ 20% on (a+b)                                                                  |      |          |           | 64.2          |
|         |             | d)            | Contractor's profit @ 10% on (a+b+c)                                                      |      |          |           | 38.56         |
|         |             |               | Cost for 7.5 m with 10 mm depth = a+b+c+d                                                 |      |          |           | 424.1         |
|         |             |               | Rate per m 1 cm depth = $(a+b+c+d)/7.5$                                                   |      |          |           | 56.55         |
|         |             |               | <b>Total Cost</b>                                                                         | m    |          |           | 56.55         |

**Note:** For arriving at the final rate for filler joints per m length and per cm depth of joint, filling compound, the rates of Sr. Nos (i), (ii), (iii) and (iv) shall be added.

|    |       |      |                                                                                                                         |     |       |          |           |
|----|-------|------|-------------------------------------------------------------------------------------------------------------------------|-----|-------|----------|-----------|
| 53 | 12.10 | 1200 | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3 |     |       |          |           |
|    |       |      | Unit = cum                                                                                                              |     |       |          |           |
|    |       |      | Taking output = 10 cum                                                                                                  |     |       |          |           |
|    |       | i)   | <b>Granular material</b>                                                                                                |     |       |          |           |
|    |       | a)   | <b>Material</b>                                                                                                         |     |       |          |           |
|    |       |      | Granular material                                                                                                       | cum | 12.00 | 165.20   | 1,982.40  |
|    |       | b)   | <b>Labour</b>                                                                                                           |     |       |          |           |
|    |       |      | Mate                                                                                                                    | day | 0.40  | 397.00   | 158.80    |
|    |       |      | Mazdoor (Unskilled)                                                                                                     | day | 10.00 | 373.00   | 3,730.00  |
|    |       |      | Bhisti                                                                                                                  | day | 0.40  | 373.00   | 149.20    |
|    |       | c)   | Overheads @ 20% on (a+b)                                                                                                |     |       |          | 1,194.72  |
|    |       | d)   | Contractor's profit @ 10% on (a+b+c)                                                                                    |     |       |          | 716.82    |
|    |       |      | Carriage cost:-                                                                                                         |     |       |          |           |
|    |       |      | Granular Material                                                                                                       | cum | 12.00 | 1,992.12 | 23,905.44 |
|    |       |      | Cost for 10 cum of granular backfill = a+b+c+d                                                                          |     |       |          | 31,750.44 |
|    |       |      | Rate per cum = $(a+b+c+d)/10$                                                                                           |     |       |          | 3,175.04  |
|    |       | ii)  | <b>Sandy material</b>                                                                                                   |     |       |          |           |
|    |       |      | Unit = cum                                                                                                              |     |       |          |           |
|    |       |      | Taking output = 10 cum                                                                                                  |     |       |          |           |
|    |       | a)   | <b>Material</b>                                                                                                         |     |       |          |           |
|    |       |      | Sand                                                                                                                    | cum | 12.00 | 143.42   | 1,721.04  |
|    |       | b)   | <b>Labour</b>                                                                                                           |     |       |          |           |
|    |       |      | Mate                                                                                                                    | day | 0.40  | 397.00   | 158.80    |
|    |       |      | Mazdoor (Unskilled)                                                                                                     | day | 10.00 | 373.00   | 3,730.00  |
|    |       |      | Bhisti                                                                                                                  | day | 0.40  | 373.00   | 149.20    |
|    |       | c)   | Overheads @ 20% on (a+b)                                                                                                |     |       |          | 1,151.52  |
|    |       | d)   | Contractor's profit @ 10% on (a+b+c)                                                                                    |     |       |          | 690.94    |
|    |       |      | Cost for per cum of sand backfill = $(a+b+c+d)/10$                                                                      |     |       |          | 260.88    |
|    |       |      | Carriage cost:-                                                                                                         |     |       |          |           |
|    |       |      | Sand                                                                                                                    | cum | 1.20  | 266.27   | 319.52    |
|    |       |      | Cost for per cum of sand backfill including carriage                                                                    |     |       |          | 1,079.52  |
|    |       |      | <b>Rate per cum = <math>(a+b+c+d)/10</math></b>                                                                         | cum |       |          | 1,079.56  |

|    |       |      |                                                                                                                                                                                                                                                                                                                                                                                                    |     |       |          |          |
|----|-------|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-------|----------|----------|
| 54 | 12.11 | 1200 | Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3 |     |       |          |          |
|    |       |      | Unit = cum                                                                                                                                                                                                                                                                                                                                                                                         |     |       |          |          |
|    |       |      | Taking output = 10 cum                                                                                                                                                                                                                                                                                                                                                                             |     |       |          |          |
|    |       | a)   | <b>Material</b>                                                                                                                                                                                                                                                                                                                                                                                    |     |       |          |          |
|    |       |      | Filter media as per specification                                                                                                                                                                                                                                                                                                                                                                  | cum | 12.00 | 678.14   | 8,137.68 |
|    |       | b)   | <b>Labour</b>                                                                                                                                                                                                                                                                                                                                                                                      |     |       |          |          |
|    |       |      | Mate                                                                                                                                                                                                                                                                                                                                                                                               | day | 0.40  | 397.00   | 158.80   |
|    |       |      | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                                                                                                | day | 9.00  | 373.00   | 3,357.00 |
|    |       |      | Mazdoor (Skilled)                                                                                                                                                                                                                                                                                                                                                                                  | day | 1.00  | 472.00   | 472.00   |
|    |       |      | Bhisti                                                                                                                                                                                                                                                                                                                                                                                             | day | 0.50  | 373.00   | 186.50   |
|    |       | c)   | Overheads @ 20% on (a+b)                                                                                                                                                                                                                                                                                                                                                                           |     |       |          | 2,462.40 |
|    |       | d)   | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                                                                                                                                                                               |     |       |          | 1,477.44 |
|    |       |      | Cost for per cum = $(a+b+c+d)/10$                                                                                                                                                                                                                                                                                                                                                                  |     |       |          | 1,625.12 |
|    |       |      | Carriage cost:-                                                                                                                                                                                                                                                                                                                                                                                    |     |       |          |          |
|    |       |      | Filter Material                                                                                                                                                                                                                                                                                                                                                                                    | cum | 1.20  | 1,992.12 | 2,390.54 |



| Sl. No. | SDR-51 No. | MORD Ref. No. | DESCRIPTION                                                                                                                                                                                                                                      | Unit       | Quantity | Rate    | Amount in Rs.  |
|---------|------------|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|----------|---------|----------------|
|         |            |               | Cost for per cum including carriage                                                                                                                                                                                                              |            |          |         | 4015.74        |
|         |            |               | Rate per cum = (a+b+c+d)/100                                                                                                                                                                                                                     |            |          |         | 4015.74        |
|         |            |               | <b>PROTECTION WORK</b>                                                                                                                                                                                                                           |            |          |         |                |
| 57      | 14.1       | 1300          | Providing and laying <b>boulder apron</b> for bed protection with stone boulders of minimum size and weight as per Table 1300-1, for fragment weighing less than 25 kg laid dry complete as per drawing and technical specifications Clause 1301 |            |          |         |                |
|         |            |               | Unit = cum                                                                                                                                                                                                                                       |            |          |         |                |
|         |            | a)            | <b>Material</b>                                                                                                                                                                                                                                  |            |          |         |                |
|         |            |               | Stone boulder (25 kg minimum)                                                                                                                                                                                                                    | cum        | 1.00     | 675.00  | 675.00         |
|         |            |               | Stone spalls                                                                                                                                                                                                                                     | cum        | 0.20     | 675.00  | 135.00         |
|         |            | b)            | <b>Labour</b>                                                                                                                                                                                                                                    |            |          |         |                |
|         |            |               | Mate                                                                                                                                                                                                                                             | day        | 0.04     | 127.00  | 5.08           |
|         |            |               | Mason 1st Class                                                                                                                                                                                                                                  | day        | 0.15     | 504.00  | 75.60          |
|         |            |               | Mazdoor (Unskilled)                                                                                                                                                                                                                              | day        | 0.75     | 174.00  | 129.75         |
|         |            | c)            | Overheads @ 20% on (a+b)                                                                                                                                                                                                                         |            |          |         | 256.34         |
|         |            | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                             |            |          |         | 154.80         |
|         |            |               | Rate per cum = (a+b+c+d)                                                                                                                                                                                                                         |            |          |         | 1691.82        |
|         |            |               | <b>Carriage Cost</b>                                                                                                                                                                                                                             |            |          |         |                |
|         |            |               | Stone boulder (25 Kg minimum)                                                                                                                                                                                                                    | cum        | 1        | 2062.67 | 2062.67        |
|         |            |               | Stone spalls                                                                                                                                                                                                                                     | cum        | 0.2      | 1992.12 | 398.42         |
|         |            |               | Rate per cum = (a+b+c+d)                                                                                                                                                                                                                         |            |          |         | 4152.91        |
|         |            |               | <b>NOTE:</b> Nominal excavation required for preparation of bed has been taken into account while making provision for labour                                                                                                                    |            |          |         |                |
|         |            |               | <b>Total Cost</b>                                                                                                                                                                                                                                | <b>CUM</b> |          |         | <b>4152.91</b> |
| 58      | 14.5       | 1300          | Providing and laying <b>boulder pitching on slopes</b> laid over prepared filter media as per drawing and technical specifications Clause 1302                                                                                                   |            |          |         |                |
|         |            |               | Unit = cum                                                                                                                                                                                                                                       |            |          |         |                |
|         |            | a)            | <b>Material</b>                                                                                                                                                                                                                                  |            |          |         |                |
|         |            |               | Stone boulder (25 kg minimum)                                                                                                                                                                                                                    | cum        | 1.00     | 675.00  | 675.00         |
|         |            |               | Stone spalls of minimum 25 mm size                                                                                                                                                                                                               | cum        | 0.20     | 675.00  | 135.00         |
|         |            | b)            | <b>Labour</b>                                                                                                                                                                                                                                    |            |          |         |                |
|         |            |               | Mate                                                                                                                                                                                                                                             | day        | 0.04     | 127.00  | 5.08           |
|         |            |               | Mason 1st Class                                                                                                                                                                                                                                  | day        | 0.15     | 504.00  | 75.60          |
|         |            |               | Mazdoor (Unskilled)                                                                                                                                                                                                                              | day        | 0.75     | 174.00  | 129.75         |
|         |            | c)            | Overheads @ 20% on (a+b)                                                                                                                                                                                                                         |            |          |         | 256.34         |
|         |            | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                             |            |          |         | 154.80         |
|         |            |               | Rate per cum = (a+b+c+d)                                                                                                                                                                                                                         |            |          |         | 1691.82        |
|         |            |               | <b>Carriage Cost</b>                                                                                                                                                                                                                             |            |          |         |                |
|         |            |               | Stone boulder (25 Kg minimum)                                                                                                                                                                                                                    | cum        | 1.00     | 2062.67 | 2062.67        |
|         |            |               | Stone spalls                                                                                                                                                                                                                                     | cum        | 0.20     | 1992.12 | 398.42         |
|         |            |               | Rate per cum including Carriage                                                                                                                                                                                                                  |            |          |         | 4152.91        |
|         |            |               | <b>Total Cost</b>                                                                                                                                                                                                                                | <b>CUM</b> |          |         | <b>4152.91</b> |
| 59      | 14.6       | 1300          | Providing and laying <b>filter material underneath pitching</b> in slopes complete as per drawing and technical specifications Clause 1302                                                                                                       |            |          |         |                |
|         |            |               | Unit = cum                                                                                                                                                                                                                                       |            |          |         |                |
|         |            | a)            | <b>Material</b>                                                                                                                                                                                                                                  |            |          |         |                |
|         |            |               | Graded stone aggregate of required size                                                                                                                                                                                                          | cum        | 1.20     | 160.00  | 192.00         |
|         |            | b)            | <b>Labour</b>                                                                                                                                                                                                                                    |            |          |         |                |
|         |            |               | Mate                                                                                                                                                                                                                                             | day        | 0.05     | 127.00  | 6.35           |
|         |            |               | Mazdoor (Noble 1)                                                                                                                                                                                                                                | day        | 0.25     | 472.00  | 118.00         |
|         |            |               | Mazdoor (Unskilled)                                                                                                                                                                                                                              | day        | 1.02     | 174.00  | 178.46         |
|         |            | c)            | Overheads @ 20% on (a+b)                                                                                                                                                                                                                         |            |          |         | 264.17         |
|         |            | d)            | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                             |            |          |         | 158.50         |
|         |            |               | Rate per cum = (a+b+c+d)                                                                                                                                                                                                                         |            |          |         | 1743.55        |
|         |            |               | <b>Carriage Cost</b>                                                                                                                                                                                                                             |            |          |         |                |
|         |            |               | Graded stone aggregate of required size                                                                                                                                                                                                          | cum        | 1.20     | 1992.12 | 2390.54        |
|         |            |               | Rate per cum including Carriage                                                                                                                                                                                                                  |            |          |         | 4134.09        |
|         |            |               | <b>NOTE:</b> Labour cost includes labour required for trimming of slope to proper profile and preparation of bed                                                                                                                                 |            |          |         |                |
|         |            |               | <b>Total Cost</b>                                                                                                                                                                                                                                | <b>Cum</b> |          |         | <b>4134.09</b> |
| 60      | 14.7       | 1300          | Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303                                                                                                                  |            |          |         |                |
|         |            |               | Unit = cum                                                                                                                                                                                                                                       |            |          |         |                |
|         |            | a)            | <b>Material</b>                                                                                                                                                                                                                                  |            |          |         |                |
|         |            |               | Bricks                                                                                                                                                                                                                                           | Nos        | 500.00   | 6.07    | 3034.50        |
|         |            |               | Cement mortar (1:3) [(Rate as in item 11.5 (i))]                                                                                                                                                                                                 | cum        | 0.15     | 6238.98 | 935.85         |
|         |            |               | Cement mortar bedding (1:5) [(Rate as in item 12.1 (ii))]                                                                                                                                                                                        | cum        | 0.25     | 5317.31 | 1329.33        |
|         |            | b)            | <b>Labour</b>                                                                                                                                                                                                                                    |            |          |         |                |
|         |            |               | Mate                                                                                                                                                                                                                                             | day        | 0.10     | 127.00  | 12.70          |
|         |            |               | Mason 1st Class                                                                                                                                                                                                                                  | day        | 0.80     | 504.00  | 403.20         |
|         |            |               | Mazdoor (Unskilled)                                                                                                                                                                                                                              | day        | 1.60     | 174.00  | 278.40         |
|         |            |               | Bhisti                                                                                                                                                                                                                                           | day        | 0.20     | 174.00  | 34.80          |
|         |            | c)            | Overheads @ 20% on (a+b)                                                                                                                                                                                                                         |            |          |         | 1282.63        |

| Sl. No. | SDP No. | MURD Ref No. | DESCRIPTION                                                                                                                                                                                                                                                                                                                   | Unit   | Quantity | Rate     | Amount in ₹ |
|---------|---------|--------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|----------|----------|-------------|
|         |         | d)           | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                                                                                                          |        |          |          | 769.58      |
|         |         |              | Rate per cum = (a+b+c+d)                                                                                                                                                                                                                                                                                                      |        |          |          | 8465.3      |
|         |         |              | Carriage Cost                                                                                                                                                                                                                                                                                                                 |        |          |          |             |
|         |         | i) Bricks    | Nos                                                                                                                                                                                                                                                                                                                           | 500.00 | 0.80     |          | 399.4       |
|         |         | ii) Cement   | cum                                                                                                                                                                                                                                                                                                                           | 0.15   | 405.40   |          | 62.4        |
|         |         | iii) Sand    | cum                                                                                                                                                                                                                                                                                                                           | 0.42   | 266.27   |          | 111.8       |
|         |         |              | Rate per cum including Carriage = a+b+c+d                                                                                                                                                                                                                                                                                     |        |          |          | 9,039.0     |
|         |         |              | Total Cost                                                                                                                                                                                                                                                                                                                    | cum    |          |          | 9039.0      |
| 61      | 12.9    | 600          | Providing <b>weepholes</b> in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 |        |          |          |             |
|         |         |              | Unit - Nos                                                                                                                                                                                                                                                                                                                    |        |          |          |             |
|         |         |              | Taking output - 30 Nos                                                                                                                                                                                                                                                                                                        |        |          |          |             |
|         |         | a)           | Material                                                                                                                                                                                                                                                                                                                      |        |          |          |             |
|         |         |              | AC pipe 100 mm dia including wastage @ 5 per cent. Average length of weep hole is taken as one metre for the purpose of estimating                                                                                                                                                                                            | m      | 41.50    | 44.28    | 1,394.6     |
|         |         |              | MS clamps                                                                                                                                                                                                                                                                                                                     | Nos    | 30.00    | 43.36    | 1,300.8     |
|         |         |              | Cement mortar 1:3 (For rate refer to item 11.5.1)                                                                                                                                                                                                                                                                             | cum    | 0.05     | 4,647.47 | 232.3       |
|         |         | b)           | Labour                                                                                                                                                                                                                                                                                                                        |        |          |          |             |
|         |         |              | Mate                                                                                                                                                                                                                                                                                                                          | day    | 0.03     | 397.00   | 11.9        |
|         |         |              | Mason 1st Class                                                                                                                                                                                                                                                                                                               | day    | 0.50     | 503.00   | 251.50      |
|         |         |              | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                           | day    | 0.25     | 373.00   | 93.25       |
|         |         | c)           | Overheads @ 20% on (a+b)                                                                                                                                                                                                                                                                                                      |        |          |          | 656.93      |
|         |         | d)           | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                                                                                                          |        |          |          | 394.16      |
|         |         |              | Cost for 30 Nos = (a+b+c+d)                                                                                                                                                                                                                                                                                                   |        |          |          | 4,335.74    |
|         |         |              | Rate per No = (a+b+c+d)/30 =                                                                                                                                                                                                                                                                                                  | no.    |          |          | 144.5       |
| 62      | 11.2    | 300 & 1200   | Filling in foundation trenches as per drawing and technical specification Clause 305.3.9                                                                                                                                                                                                                                      |        |          |          |             |
|         |         |              | Sand filling                                                                                                                                                                                                                                                                                                                  |        |          |          |             |
|         |         |              | Unit - cum                                                                                                                                                                                                                                                                                                                    |        |          |          |             |
|         |         | a)           | Labour                                                                                                                                                                                                                                                                                                                        |        |          |          |             |
|         |         |              | Mate                                                                                                                                                                                                                                                                                                                          | day    | 0.01     | 397.00   | 3.97        |
|         |         |              | Mazdoor (Unskilled)                                                                                                                                                                                                                                                                                                           | day    | 0.30     | 373.00   | 111.9       |
|         |         | b)           | Material                                                                                                                                                                                                                                                                                                                      |        |          |          |             |
|         |         |              | Sand (assuming 20 per cent voids)                                                                                                                                                                                                                                                                                             | cum    | 1.20     | 144.42   | 171.98      |
|         |         | c)           | Overheads @ 20% on (a+b)                                                                                                                                                                                                                                                                                                      |        |          |          | 57.5        |
|         |         | d)           | Contractor's profit @ 10% on (a+b+c)                                                                                                                                                                                                                                                                                          |        |          |          | 34.54       |
|         |         |              | Rate per cum = (a+b+c+d)                                                                                                                                                                                                                                                                                                      |        |          |          | 379.97      |
|         |         |              | Carriage Cost                                                                                                                                                                                                                                                                                                                 |        |          |          |             |
|         |         |              | Sand (assuming 20 per cent voids)                                                                                                                                                                                                                                                                                             | cum    | 1.20     | 266.27   | 319.51      |
|         |         |              | Rate per cum = a+b+c+d =                                                                                                                                                                                                                                                                                                      | cum    |          |          | 699.48      |
| 11.9    | 307 RCD |              | Planting of tree by the road side (Avenue Tree) in 0.6 m dia holes, 1 m deep dug in the ground. Mixing the soil with decayed farm yard/ slug manure, planting the saplings back filling the trench, watering, fixing the tree guard & maintain the Plant for One Year                                                         |        |          |          |             |
|         |         |              | Unit - each                                                                                                                                                                                                                                                                                                                   |        |          |          |             |
|         |         |              | Taking output - 10 tree                                                                                                                                                                                                                                                                                                       |        |          |          |             |
|         |         | a)           | Labour                                                                                                                                                                                                                                                                                                                        |        |          |          |             |
|         |         |              | Mate                                                                                                                                                                                                                                                                                                                          | day    | 1.700    | 397.00   | 674.90      |
|         |         |              | Mazdoor for planting                                                                                                                                                                                                                                                                                                          | day    | 2.000    | 373.00   | 746.00      |
|         |         |              | Mazdoor for maintenance for one year                                                                                                                                                                                                                                                                                          | day    | 15.000   | 373.00   | 5,595.00    |
|         |         | b)           | Machinery                                                                                                                                                                                                                                                                                                                     |        |          |          |             |
|         |         |              | Water tanker 6kl capacity                                                                                                                                                                                                                                                                                                     | hour   | 2.00     | 752.00   | 1,504.00    |
|         |         | c)           | Machinery                                                                                                                                                                                                                                                                                                                     |        |          |          |             |
|         |         |              | Sapling 2 m height 25 mm dia                                                                                                                                                                                                                                                                                                  | each   | 10.00    | 21.63    | 216.30      |
|         |         |              | Farm yard manure                                                                                                                                                                                                                                                                                                              | cum    | 0.94     | 29.73    | 685.92      |
|         |         |              | Pesticide                                                                                                                                                                                                                                                                                                                     | KG     | 0.50     | 73.26    | 36.63       |
|         |         |              | Cost of water                                                                                                                                                                                                                                                                                                                 | KL     | 12.00    | 56.20    | 674.40      |
|         |         | d)           | Overheads @ 20 % on (a+b+c)                                                                                                                                                                                                                                                                                                   |        |          |          | 2026.64     |
|         |         | e)           | CP @10 % on (a+b+c+d)                                                                                                                                                                                                                                                                                                         |        |          |          | 1215.91     |
|         |         |              | Cost for 10 tree = (a+b+c+d)                                                                                                                                                                                                                                                                                                  |        |          |          | 13375.7     |
|         |         |              | Rate per Tree = (a+b+c+d)/10                                                                                                                                                                                                                                                                                                  |        |          |          | 1337.5      |
|         |         |              | Total Cost                                                                                                                                                                                                                                                                                                                    | cum    |          |          | 13375.5     |