

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये
रु.1000

ONE THOUSAND RUPEES
Rs.1000



7/12/23 दिनांक - 25/03/2023 ₹ 1000 x एक हजार अक्षरों द्वारा गुप्ता कल्लु जरी शक्य प
बिहार विभाग पटना कोषागार सीक सं 9 आद्या/ अक्षाट कगदी जिला प. चम्पारण काक्ष एकप(नाम) AP 009312

केत. क न.म एवं पता

सरिन्द्र प्रसाद

Supplementary Agreement of 46 SBD/2022-23

कलेट्टा कोट, पटना

This Supplementary agreement made on 7/12/23 between Executive Engineer, R.W.D. works Division Baysi of the one part and Ashok Kumar Gupta /1220108/At Ward number 18 , Gandhi Nagar, Bagaha, West Champaran. Herein after called the contractor of the other part. Whereas the Employer has accepted the Difference amount of sanctioned GST revised rate @ 18% sanctioned by the Superintending Engineer, Rural works department, Works circle Purnera via Letter Number 1001 (अनु) Dated 05.09.2023 for Rupees 6,83,420.00 (Rupees Six Lakhs Eighty Three Thousand Four Hundred Twenty Only) as illustrated below:-

SI NO	Name of the road	Previously Approved Agreement	Approved Agreemented Value including 18 % GST
1	Nazam House to Musalmaan Tola	6373213.00	6709777.00
2	Muslim Tola PMGSY to Musalmaan Tola	6567341.00	6914197.00
3	Jhowali High School to Musalmaan Tola	1,18,48,068.00	1,18,48,068.00(not approved yet)
4	Rahariya More to Ghutha Tola		
Total		2,47,88,622.00	2,54,72,042.00
Difference Amount		6,83,420.00	
Total Value of Agreement After Approval of 18% GST for the Above Road(1+2) [Original + Suppl.] Agreement		2,54,72,042.00	

i.e Rupees Two Crores Fifty Four Lakhs Seventy Two Thousand and Forty Two Only

In this Agreement, Words and expression shall have the same meanings as are respectively assigned to them in the Condition of contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.

EXECUTIVE ENGINEER
RWD WORKS DIVISION BAISI

NOW THIS AGREEMENT WITNESSETH as follows :-

1. The following documents shall be deemed to form and be ready and construed as part of this Agreement, Viz.

- Letter of Superintending Engineer RWD works Circle ,Purnea
- BOQ Approved
- Original Agreement

It is expressly acknowledged and agreed by both parties that this supplementary agreement is intended to address specific aspects related to the GST claim, rest portion of execution, and maintenance of road, and it shall not in any way alter, modify, or affect the terms and conditions stipulated in the original agreement dated [Original Agreement Date]_____.

The original agreement remains in full force and effect, and any provisions not explicitly addressed in this supplementary agreement shall be governed by the terms of the original agreement.

In witness where of, the parties hereto execute this non-impact statement on the date first above written.

2. Deduction :- I.T, GST, Royalty & all other deduction will be deduced form each bill as per Govt. rule.


In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written

The Common Seal of

Was hereunto affixed in the presence of.....

Signed Sealed and Delivered by the said

In the presence of :


Binding Signature of Contractor



EXECUTIVE ENGINEER
RWD WORKS DIVISION BAISI
Binding Signature of Employer

बिहार सरकार
अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णियाँ।

पत्रांक 100/ (अड्डा)

पूर्णिमाँ / दिनांक 5 / 9 / 2023

प्रेषक,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, पूर्णियाँ।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बायसी।

विषय :- पुनरीक्षित परिमाण विपत्र स्वीकृत करने के संबंध में।

प्रसंग :- आपका पत्रांक 790 दिनांक 18.05.2023

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र के आलोक में सूचित करना है कि निम्नांकित पथों के स्वीकृत प्राक्कलन में 12% GST प्रावधान था, जबकि सरकार के पत्रांक 3322 दिनांक 12.05.2022 द्वारा GST 12% से बढ़ाकर 18% GST किए जाने के फलस्वरूप आपके द्वारा समर्पित GST प्रस्ताव की स्वीकृति दी जाती है। कार्यपालक अभियंता यह सुनिश्चित करेंगे की संवेदक द्वारा GST का भुगतान ससमय किया गया हो।

क्र०सं०	पथ का नाम	एकरारनामा संख्या	लंबाई	पूर्व में स्वीकृति परिमाण विपत्र की राशि (लाख में)	पुनरीक्षित परिमाण विपत्र की राशि (लाख में)
1	Najam House to Musalman Tola	46MBD/2022-23		6672835.77 6373213	6885354 6707777
2	Muslim Tola PMGSY to Musalman tola	46MBD/2022-23		6861418.76 6567341	7095123 6914197
3	Sonamani Chowk to Bajdih Musalman Tola	47MBD/2022-23		25458554.39 23744402	25775149 24999317
4	Baraili Mod to Pothia	47MBD/2022-23		15364213.82 14352153	15579583 15110638

विश्वासभाजन

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, पूर्णियाँ।

EXECUTIVE ENGINEER
RWD WORKS DIVISION BAISI

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work: MUSLIM TOLA PMGSY TO MUSALMAN TOLA

Contract No: Civil Works

Name of the
Bidder/ Bidding
Firm / Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	NUMBER # Quantity	TEXT # Units	NUMBER Estimated Rate	NUMBER # TOTAL AMOUNT With Taxes	TEXT # TOTAL AMOUNT In Words
1	2	4	5	6	54	55
1	Clearing and grubbing Road Land (By Manual Means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.262	Ha	59726.130	15648.25	INR Fifteen Thousand Six Hundred & Forty Eight and Paise Twenty Five Only
2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	883.580	Cum	261.680	231215.21	INR Two Lakh Thirty One Thousand Two Hundred & Fifteen and Paise Twenty One Only
3	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OM/C and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	99.780	Cum	2913.450	290704.04	INR Two Lakh Ninety Thousand Seven Hundred & Four and Paise Four Only
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405.	103.590	Cum	6343.530	657126.27	INR Six Lakh Fifty Seven Thousand One Hundred & Twenty Six and Paise Twenty Seven Only
5	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	116.860	Sqm	6199.300	724450.20	INR Seven Lakh Twenty Four Thousand Four Hundred & Fifty and Paise Twenty Only
6	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	1558.133	Sqm	60.360	94048.91	INR Ninety Four Thousand & Forty Eight and Paise Ninety One Only
7	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrilloc broom as per technical specification clause 503.	1558.133	Sqm	20.410	31801.49	INR Thirty One Thousand Eight Hundred & One and Paise Forty Nine Only

EXECUTIVE ENGINEER
RWD WORKS DIVISION BAIJI

15/5/23

8	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509.	1558.133	Cum	275.480	429234.48	INR Four Lakh Twenty Nine Thousand Two Hundred and Thirty Four and Paise Forty Eight Only
9	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.2 to 0.25 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503.	4957.838	Sqm	17.300	85770.60	INR Eighty Five Thousand Seven Hundred and Seventy and Paise Sixty Only
10	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	123.947	Cum	15098.560	1871421.22	INR Eighteen Lakh Seventy One Thousand Four Hundred and Twenty One and Paise Twenty Two Only
11	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703.					
12	ii) Km stone	2.000	No.	2935.790	5871.58	INR Five Thousand Eight Hundred and Seventy One and Paise Fifty Eight Only
13	iii) 200 m stone	6.000	No.	805.030	4830.18	INR Four Thousand Eight Hundred and Thirty and Paise Eighteen Only
14	Providing and fixing of Retro reflective cautionary, mandatory and Informatory sign board as per IRC :57 made of 1.5 mm thick MS steel duly stove white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.3.9 of MORC for rural road of required shade and colour supported and welded on 47mmx47mmx12swg sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm, 600mm below ground level as per approved drawing clause 1701.2.2.					
15	600 mm equilateral & triangle	5.000	No	4394.510	21972.55	Twenty One Thousand Nine Hundred and Seventy Two and Paise Fifty Five Only
16	600 mm circular	4.000	No	4334.200	17336.80	INR Seventeen Thousand Three Hundred and Thirty Six and Paise Eighty Only
17	600 mm x 450 mm rectangular	5.000	No	4190.470	20952.35	INR Twenty Thousand Nine Hundred and Fifty Two and Paise Thirty Five Only
18	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.					
19	At Edge For BT Portion	261.800	Sqm	762.510	199625.12	INR One Lakh Ninety Nine Thousand Six Hundred and Twenty Five and Paise Twelve Only
20	Providing and fixing of typical Informatory sign board with Logo as per MORC specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of enamel posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4.000	Each	12678.000	50712.00	INR Fifty Thousand Seven Hundred and Twelve Only

EXECUTIVE ENGINEER
DIVISION BAISI

12/12/27

21	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	36.000	Each	890.040	32041.44	INR Thirty Two Thousand & Forty One and Paise Forty Four Only
22	Half Brick circular tree guard, in 2nd class brick, internal diameter 1.25 metres, and height 1.2 metre, above ground 0.20 metre below ground, bottom two courses laid dry, and top three courses in cement mortar 1:6 (1 cement 6 sand and the intermediate courses being in dry honey comb masonry, as per design complete)	36.000	Each	2116.750	76203.00	Seventy Six Thousand Two Hundred & Three Only
23	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	8.640	cum	6659.520	57538.25	INR Fifty Seven Thousand Five Hundred & Thirty Eight and Paise Twenty Five Only
24	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	59.520	cum	224.590	13367.60	INR Thirteen Thousand Three Hundred & Sixty Seven and Paise Sixty Only
25	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	59.520	SQM	113.770	6771.59	INR Six Thousand Seven Hundred & Seventy One and Paise Fifty Nine Only
26	GST @ 18%, (IN LACS) =	1.000	RS	888955.763	888955.76	INR Eight Lakh Eighty Eight Thousand Nine Hundred & Fifty Five and Paise Seventy Six Only
27	LABOUR CESS @ 1% (IN LACS) =	1.000	RS	49386.431	49386.43	INR Forty Nine Thousand Three Hundred & Eighty Six and Paise Forty Three Only
28	Seigniorage Fee 10% (IN LACS) =	1.000	RS	34344.705	34344.71	INR Thirty Four Thousand Three Hundred & Forty Four and Paise Seventy One Only
29	Maintenance for 1st year	1.000	M	81680.000	81680.00	INR Eighty One Thousand Six Hundred & Eighty Only
30	Maintenance for 2nd year	1.000	M	167987.000	167987.00	INR One Lakh Fifty Seven Thousand Three Hundred & Eighty Seven Only
31	Maintenance for 3rd year	1.000	M	849005.000	849005.00	INR Three Lakh Forty Nine Thousand & Five Only
32	Maintenance for 4th year	1.000	M	166896.000	166896.00	INR One Lakh Fifty Five Thousand Eight Hundred & Ninety Six Only
33	Maintenance for 5th year	1.000	M	357759.000	357759.00	INR Three Lakh Fifty Seven Thousand Seven Hundred & Fifty Nine Only
34	GST @ 18% (IN LACS) =	1.000	RS	198310.560	198310.56	INR One Lakh Ninety Eight Thousand Three Hundred & Ten and Paise Eighty Six Only
35	LABOUR CESS @ 1% (IN LACS) =	1.000	RS	11017.270	11017.27	INR Eleven Thousand & Seventeen and Paise Twenty Seven Only
36	Seigniorage Fee 10% (IN LACS) =	1.000	RS	1369.823	1369.82	INR One Thousand Three Hundred & Sixty Nine and Paise Eighty Two Only
Total in Figures			Select	7095122.92	7223845.53	Seventy Two Lakh Twenty Three Thousand Eight Hundred & Forty Five and Paise Fifty Three Only
Quoted Rate in Figures				180925.43	0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

Total = 6914197.29

Revised B.O.Q as per order of Rwd 33004 dated 05/04/22 on GST for 12% to 18%.. Revised B.O.Q 72,23,845 (Twenty two Lacs twenty three thousand eight hundred forty five) only.

Overall in case for A/A 18.59%.

EXECUTIVE ENGINEER
RWD WORKS DIVISION BAISI

Revised B.O.Q. due to G.S.T. enhancement 12% to 18%.

69,14,197

Revised B.O.Q. approved for amount ~~70,45,123~~ (Rupees ~~seventy seven~~ ^{Sixty} ~~thousand~~ ^{ninety} ~~only~~ ^{three}) overall increase from 11/11 16.1%.



5/9/23

अधीक्षक अभिव्यंता
सामीण कार्य विभाग
कार्य अंचल, पूर्णिया

05/09/2023

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work:-NAJAM HOUSE TO MUSALMAN TOLA

Contract No: Civil Works/

Name of the
Bidder/ Bidding
Firm / Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER Estimated Rate	NUMBER # TOTAL AMOUNT With Taxes	TEXT # TOTAL AMOUNT In Words
1	2	4	5	6	54	55
1	Clearing and Grubbing Road Land (By Manual Means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.246	Ha	69726.130	14692.63	INR Fourteen Thousand Six Hundred & Ninety Two and Paise Sixty Three Only
2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	831.600	Cum	261.680	217613.09	INR Two Lakh Seventeen Thousand Six Hundred & Thirteen and Paise Nine Only
3	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	94.460	Cum	2875.150	271586.67	INR Two Lakh Seventy One Thousand Five Hundred & Eighty Six and Paise Sixty Seven Only
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405.	96.710	Cum	6138.900	593693.02	INR Five Lakh Ninety Three Thousand Six Hundred & Ninety Three and Paise Two Only
5	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	135.140	Sqm	6025.470	814282.02	INR Eight Lakh Fourteen Thousand Two Hundred & Eighty Two and Paise Two Only
6	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	1801.867	Sqm	60.340	108724.65	INR One Lakh Eight Thousand Seven Hundred & Twenty Four and Paise Sixty Five Only
7	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrilloc broom as per technical specification clause 503.	1801.867	Sqm	20.400	36758.09	INR Thirty Six Thousand Seven Hundred & Fifty Eight and Paise Nine Only
8	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 503.	1801.867	Cum		272.420	INR Four Lakh Ninety Thousand Eight Hundred & Sixty Four and Paise Sixty One Only

EXECUTIVE ENGINEER
RWD WORKS DIVISION BAISI

2/11/23

9	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.2 to 0.25 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrilloc broom as per technical specification clause 503.	4666.200	Sqm	17.290	80678.60	INR Eighty Thousand Six Hundred & Seventy Eight and Paise Sixty Only
10	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	116.655	Cum	14935.750	1742329.92	INR Seventeen Lakh Forty Two Thousand Three Hundred & Twenty Nine and Paise Ninety Two Only
11	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703.					
12	ii) Km stone	2.000	No.	2872.300	5744.60	INR Five Thousand Seven Hundred & Forty Four and Paise Sixty
13	iii) 200 m stone	5.000	No.	793.200	3966.00	INR Three Thousand Nine Hundred & Sixty Six Only
14	Providing and fixing of Retro reflective cautionary, mandatory and informative sign board as per IRC:67 made of 1.5 mm thick MS steel duly stove white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.3.9 of MORD for rural road of required shade and colour supported and welded on 47mmx47mmx12swg sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm, 600mm below ground level as per approved drawing clause 1701.2.2.					
15	600 mm equilateral & triangle	2.000	No	4363.210	8726.42	Eight Thousand Seven Hundred & Twenty Six and Paise Forty
16	600 mm circular	1.000	No	4302.900	4302.90	INR Four Thousand Three Hundred & Two and Paise Ninety Only
17	600 mm x 450 mm rectangular	2.000	No	4159.170	8318.34	INR Eight Thousand Three Hundred & Eighteen and Paise Thirty
18	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.					
19	At Edge For BT Portion	246.400	Sqm	762.610	187882.46	INR One Lakh Eighty Seven Thousand Eight Hundred & Eighty
20	Providing and fixing of typical informative sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4.000	Each	12615.400	50461.60	INR Fifty Thousand Four Hundred & Sixty One and Paise Sixty Only
21	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	33.000	Each	890.040	29371.32	INR Twenty Nine Thousand Three Hundred & Seventy One and Paise Thirty Two Only
22	Half Brick circular tree guard, in 2nd class brick, internal diameter 1.25 metres, and height 1.2 metre, above ground 0.20 metre below ground, bottom two courses laid dry, and top three courses in cement mortar 1:6 (1 cement 6 sand and the intermediate courses being in dry honey comb masonry, as per design complete	33.000	Each	2116.750	69852.75	Sixty Nine Thousand Eight Hundred & Fifty Two and Paise Seventy Five Only
23	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	5.760	cum	6663.790	38383.43	INR Thirty Eight Thousand Three Hundred & Eighty Three and Paise Forty Three Only
24	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	40.320	cum	214.280	8634.88	INR Eight Thousand Six Hundred & Thirty Nine and Paise Sixty Only

EXECUTIVE ENGINEER
RWD WORKS DIVISION BAISI

7/12/23

25	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	40.320	SQM	113.770	4587.21	INR Four Thousand Five Hundred & Eighty Seven and Paise Twenty One Only
26	GST @ 18% (IN LACS) =					
27	LABOUR CESS @ 1% (IN LACS) =	1.000	RS	862462.818	862462.82	INR Eight Lakh Sixty Two Thousand Four Hundred & Sixty Two and Paise Eighty Two Only
28	Seigniorage Fee 10% (IN LACS) =	1.000	RS	47914.601	47914.60	INR Forty Seven Thousand Nine Hundred & Fourteen and Paise Sixty Only
29	Maintenance for 1st year	1.000	RS	34246.975	34246.98	INR Thirty Four Thousand Two Hundred & Forty Six and Paise Ninety Eight Only
30	Maintenance for 2nd year	1.000	M	-88229.000	-88229.00	INR Eighty Eight Thousand Three Hundred & Twenty Nine Only
31	Maintenance for 3rd year	1.000	M	-157647.000	-157647.00	INR One Lakh Fifty Seven Thousand Six Hundred & Forty Seven Only
32	Maintenance for 4th year	1.000	M	-336885.000	-336885.00	INR Three Lakh Thirty Six Thousand Eight Hundred & Eighty Only
33	Maintenance for 5th year	1.000	M	-164792.000	-164792.00	INR One Lakh Fifty Four Thousand Seven Hundred & Ninety Two Only
34	GST @ 18% (IN LACS) =	1.000	M	-344695.000	-344695.00	INR Three Lakh Forty Four Thousand Six Hundred & Ninety Five Only
35	LABOUR CESS @ 1% (IN LACS) =	1.000	RS	-194822.640	-194822.64	INR One Lakh Ninety Four Thousand Eight Hundred & Twenty Two and Paise Sixty Four Only
36	Seigniorage Fee 10% (IN LACS) =	1.000	RS	10823.480	10823.48	INR Ten Thousand Eight Hundred & Twenty Three and Paise Forty Eight Only
Total in Figures		1.000	RS	-1236.645	-1236.65	INR One Thousand Two Hundred & Thirty Six and Paise Sixty Five Only
Quoted Rate in Figures	As per Agreement below @ 12.55% =		Select	6885353.75	-7025262.74	Seventy Lakh Twenty Five Thousand Two Hundred & Sixty Two and Paise Seventy Four Only
Quoted Rate in Words		INR Zero Only		-175576.52	0.00	INR Zero Only

Total = 6709777.23

Revised B.O.Q. due to G.S.T. enhancement 12% to 18%.

Revised B.O.Q. approved for amount Rs 68,85,353.75 (Rupees Sixty Eight Lakh nine thousand three hundred & fifty four only) overall increase from AIA 17.538%.

EXECUTIVE ENGINEER
RWD WORKS DIVISION
BAISIPUR
गामीन कार्य विभाग
कार्य अंचल, पूर्णिया

7/12/23

05/09/2023

25/2022-23

AGREEMENT Copy



बिहार सरकार

RURAL WORKS DEPARTMENT

1. NAME OF OFFICE :- OFFICE OF EXECUTIVE ENGINEER
Rural Works Department
Works Division, Baisi (Purnea)
2. NAME OF WORK :- (1) Jhowali High School to Musalman tola,
(2) Rahariya more to Ghutha Tola,
(3) Najam House to Musalman Tola,
(4) Muslim Tola PMGSY to Musalman Tola
(MR-N/22-23 Baisi/01 (Tender ID-121787)
under RWD(W) Division, Baisi in Distt: Purnea (Bihar)
3. NAME OF AGENCY :- Ashok Kumar Gupta (BID ID-525046)
4. AGREEMENT NO. :- 46 MBD/2022-23
5. TENDER VALUE :- Rs. 2,54,37,272.03
6. RATE APPROVED :- (-) 2.55 % Below
7. CONSTRUCTION COST :- Rs. 2,01,98,987.56
8. MAINTENANCE COST :- Rs. 45,89,633.44
9. AGREEMENT VALUE :- **Rs. 2,47,88,622.00**
(Rs. Two Crore Forty Seven Lakh Eighty Eight Thousand Six Hundred Twenty Two Only)
10. DATE OF COMMENCEMENT :- 20.03.2023
11. DATE OF COMPLETION :- 19.12.2023

[Signature]

[Signature]
20/03/2023
EXECUTIVE ENGINEER
Rural Works Department
Works Division Baisi