



बिहार BIHAR

24 JUL 2023

2006 एन सी 9000 वीरगंज मंडल बिहार 24/07/23 जिला कार निर्माण कार्य, बिहार

AS 603319

### AGREEMENT

Agreement No

:- 29 MBD / 2022-23

Name of Works

:- Construction of Road With 5 Year maintenance of Package No-MR-N/2022-23 Belsand/04 Under M/R 3054 scheme.

1. Baiganiya Shivanagar To Phulwariya
2. L034 Barharba To Jamla Parsa Road

Name of Agency

:- M/S Tariyani Engicon Private Limited  
AT- Rasalpur Saidpur, Bazid Panchayat Bhikhpura  
Block- Mushari, Distt- Muzaffarpur.

Date of Start

:- 24.01.2023

Date of Completion

:- 23.10.2023

E.M. Deposit

:- RS 1253.000/-

This Agreement Made on 24.01.2023 between Executive Engineer, Rural Work Department, Works Division, Belsand of the one part and M/S Tariyani Engicon Private Limited, AT- Rasalpur Saidpur, Bazid Panchayat Bhikhpura, Block- Mushari, Distt- Muzaffarpur. Whereas the Employer is desirous that the contractor execute the Works under M/R 3054 Scheme.

For

Tariyani Engicon Pvt. Ltd.

रविन्द्र कुमार सिंह  
Director

24/01/23  
Executive Engineer  
R. W. D. Works Division  
Belsand

24/01/23

Construction of Road With 5 Year maintenance Road from Package No-MR-N/2022-23 Belsand/04 Under M/R 3054 Scheme And the employer has accepted the bid by The Contractor for the execution and completion of such works and remedying of any defects therein at a cost of rupees-**2,43,93,428.00** (Two Crore Fourty Three Lakh Ninety Three Thousand Four Hundred Twenty Eight Only )

**NOW THIS AGREEMENT WITNESSETH as follows :**

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract thereafter referred to, and they shall be form and be read and constructed as part of this agreement.
2. In consideration of the payments to made by the Employer to the Contractor as herein after mentioned, the contractor hereby covenants with Employer to execute and complete the works and remedy any defects therein in conformity I all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and constructed as part of this agreement , viz.

- (i) Letter of Acceptance
- (ii) Notice to proceed with the works
- (iii) Contractor's Bid
- (iv) Contract Data
- (v) Special condition of contract and general conditions of contract.
- (vi) Specifications
- (vii) Drawings
- (viii) Bill of Quantities and

*Ratna*  
24.11.2023  
*Signature* Executive Engineer  
R. W. D. Works Division  
Belsand  
*Signature*  
24/11/23



For  
*Signature*  
Director

## AGREEMENT

1. Agreement No. :- 29 MBD / 2022-23
2. Name of Work :- Construction of Road With 5 Year maintenance of Package No-MR-N/2022-23 Belsand/04 Under M/R 3054 scheme.
  1. Bairganiya Shivnagar To Phulwariya
  2. L034 Barharba To Jamla Parsa Road
3. Name of Agency :- M/S Tariyani Engicon Private Limited  
AT- Rasalpur Saidpur, Bazid Panchayat Bhikhnpura  
Block- Mushari, Distt- Muzaffarpur.
4. Construction Cost :- Rs = 201,20,242 = 00
5. Maintenance Cost :- Rs = 42,73,186 = 00
- Total :- Rs = 2,43,93,428 = 00
6. Performance Security Deposit :- ~~Rs~~ - Rs = 12,27,000 = 00
7. B.G. No. / Bank :-
8. Work Allotted rate :- (-) 0.11% (Beldar)
9. The Employer shall retain S.D. of ( 8 % ) of the amount from each payment due to the contractor until completion of the whole of the construction work. No security deposit / retention shall be retained from the payment for routine maintenance of work.
10. Date of written order to commence :- 24.01.2023
11. Time required for the work from date of written order to commence :- 9 Month
12. Total No. of Items :-

Note : SBD Rules Terms and condition will be applicable.

For  
Tariyani Engicon Pvt. Ltd.  
राजेश कुमार सिंह  
Contractor Director

  
24/01/2023  
Executive Engineer  
R.W.D., Works Division  
Belsand  
  
24/01/23

Tender Inviting Authority: Engg-In Chief RWD Patna			
Name of Work: =		Bairganiya Silvagar To Phulweriya	
Name Of Block =		Barginiya	
Contract No: Civil Works/			
Bidder Name:		Excess ( + )	%

**SCHEDULE OF WORKS**

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.30	ha	61577.50	Rupees Sixty One Thousand Five Hundred Seventy Seven And Paise Fifty Only	18473.25
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	630.00	Cum	253.71	Rupees Two Hundred Fifty Three And Paise Seventy One Only	159837.30
3.00	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	39.85	Cum	2654.51	Rupees Two Thousand Six Hundred Fifty Four And Paise Fifty One Only	105782.22
4.00	WBM Grading 2 ( By Mechanical Means) : Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	28.30	Cum	5010.10	Rupees Five Thousand Ten And Paise Ten Only	141785.83

*Signature*

*Signature*

For

Tariyani Engicon Pvt. Ltd.

रवीन्द्र कुमार सिंह  
Director

Executive Engineer

R. W. D. Works Division  
Belsand

No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
2.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	135.00	Cum	326.71	Rupees Three Hundred Twenty Six And Paise Seventy One Only	44105.85
43.00	Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	14.00	Cum	7218.50	Rupees Seven Thousand Two Hundred Eighteen And Paise Fifty Only	101059.00
44.00	Brick masonry work in cement mortar (CM 1:4) in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	131.00	Cum	6102.10	Rupees Six Thousand One Hundred Two And Paise Ten Only	799375.10
45.00	Providing concrete for plain/reinforced concrete M-20 in coping over protection wall complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20	3.00	Cum	8167.25	Rupees Eight Thousand One Hundred Sixty Seven And Paise Twenty Six Only	24501.75
46.00	Providing Weepholes in brick masonry, Plain / Reinforced concrete abutement, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specification	100.00	nos	122.30	Rupees One Hundred Twenty Two And Paise Thirty Only	12230.00
47.00	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	140.00	Sqm	213.10	Rupees Two Hundred Thirteen And Paise Ten Only	29834.00
48.00	Brick Masonry in C.M.(1:3) In parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	2.88	Cum	6277.40	Rupees Six Thousand Two Hundred Seventy Seven And Paise Forty Only	18078.91
49.00	Plastering with cement mortar (1:4):- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical	20.16	Sqm	213.10	Rupees Two Hundred Thirteen And Paise Ten Only	4296.10
50.00	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause	58.56	Sqm	116.86	Rupees One Hundred Sixteen And Paise Eighty Six Only	6843.32
	<b>Total cost Of Construction</b>					<b>78,15,330.34</b>
51.00	Maintenance	20.00	Per 3 month	54424.90	Rupees Sixty Four Thousand Four Hundred Twenty Four And Paise Ninety Only	12,88,498.00
	<b>Total Estimated Cost In Figures</b>					<b>91,03,828.34</b>
	1% Labour					91,038.28
	18% GST					16,38,689.10
	<b>TOTAL SEIGNIORAGE FEE</b>					<b>1,12,633.70</b>
	<b>Quoted Amount</b>				<b>1,09,46,189.42</b>	<b>1,09,46,189.00</b>
	<b>Quoted Rate in Words</b>				<b>Rupees One Crore Nine Lakh(s) Forty Six Thousand One Hundred Eighty Nine Only</b>	

*Handwritten signature*  
15.09.2022

*Handwritten signature*  
22-09-2022

*Handwritten signature*

For  
Tariyani Engicon Pvt. Ltd.  
**खन्दि कुमार सिंह**  
Director

Executive Engineer  
R. W. D. Works Division  
Balsand



Tender Inviting Authority: Engg-in Chief RWD Patna

L034 Barharwa To Jamla Parsa Road (VR16)

Name of Work: =

Suppl

Name Of Block =

Contract No: Civil Works/

Excava ( )

Bidder

Name:

## SCHEDULE OF WORKS

AMOUNT  
Rs. P

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.54	ha	81577.50	Rupees Sixty One Thousand Five Hundred Seventy Seven And Paise Fifty Only	33251.85
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	1134.00	Cum	253.71	Rupees Two Hundred Fifty Three And Paise Seventy One Only	287707.14
3.00	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	62.74	Cum	2322.79	Rupees Two Thousand Three Hundred Twenty Two And Paise Seventy Nine Only	145731.84
4.00	WBM Grading 2 ( By Mechanical Means) : Providing laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405	42.94	Cum	4832.20	Rupees Four Thousand Eight Hundred Thirty Two And Paise Twenty Only	207494.67



For Taryani Engicon Pvt. Ltd.

 रविन्द्र कुमार सिंह  
 Director

 Executive Engineer  
 R. W. D. Works Division  
 Belsand

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
20.00	Road Marking with Hot Applied Thermoplastic :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes	540.00	Sqm	823.80	Rupees Eight Hundred Twenty Three And Paise Eighty Only	444852.00
21.00	Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and pointing arrows, border etc will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4.00	nos	10500.80	Rupees Ten Thousand Five Hundred And Paise Eighty Only	42003.20
22.00	Brick Masonry in C.M.(1:3) in parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	14.40	Cum	6277.40	Rupees Six Thousand Two Hundred Seventy Seven And Paise Forty Only	90394.56
23.00	Plastering with cement mortar (1:4) :- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical	100.80	Sqm	213.00	Rupees Two Hundred Thirteen Only	21470.40
24.00	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause	292.80	Sqm	116.86	Rupees One Hundred Sixteen And Paise Eighty Six Only	34218.61
	Total cost Of Construction					89,05,661.07
25.00	Maintenance	20.00	Per 3 month	115318.50	Rupees One Lakh(s) Fifteen Thousand Three Hundred Eighteen And Paise Fifty	23,06,370.00
Total Estimated Cost in Figures						1,12,12,031.07
1% Labour						1,12,120.31
18% GST						20,18,165.58
TOTAL SEIGNIORAGE FEE						1,32,060.02
Quoted Amount						1,34,74,376.99
Quoted Rate in Words						1,34,74,377.00
Rupees One Crore Thirty Four Lakh(s) Seventy Four Thousand Three Hundred Seventy Seven Only						

Boq approved for Rs 1,34,74,377 = INR Rupees one crore thirty four lakh seventy four thousand three hundred seventy seven only) Item NO 01 to 25

For  
Tanyani Engineering Pvt. Ltd.  
रवीन्द्र कुमार सिंह  
Director

Executive Engineer  
R. W. D. Works Division  
Balsand  
24/11/22

# CHECK LIST FOR TECHNICAL EVALUATION

1	NAME OF CIRCLE	R.W.D. Work Circle Sitamarhi			
2	NAME OF DIVISION	R.W.D. Works Division Belsand,			
3	NAME OF WORK	MR-N/23-23 Belsand/04 ( 1. Bairganiya shivnagar to Phulwariya. 2. to J4 Barharwa to jamla parva Road.			
4	TENDER ID NUMBER	2022_ECBIII_120988_1			
5	AMOUNT & DATE OF ADMINISTRATIVE APPROVAL	Rs- 247,94000 Lakh	Letter no - 975,	date 08.08.2022	
6	AMOUNT & DATE OF TECHNICAL SANCTION	Rs- 257.24 Lakh	letter no 2408,	date 21.09.2022	
7	CONST. COST IN LAKH	Rs- 201.42674 Lakh			
8	MAINT. CONST IN LAKH	Rs - 42.77892 Lakh			
9	TOTAL TENDER VALUE (IN LAKH)	Rs- 247,20566 Lakh ✓			
10	COST OF BOQ IN RS. (must be uplod by the tenderer with details Bank Draft)	Rs. 10,000.00	DD No.- 003322	date- 28-09-2022	1
11	PRESS RELEASE	NEWS PAPER IN WHICH TENDER PUBLISHED		DATE OF PUBLICATION	PR NO.
		Danik Jagran		04.09.2022	007439 (RWD) 2022-23
12	DATE OF RECEIPT OF TENDER INCLUDING BID ID & TENDER ID	Date of Receipt		Tender ID	BID ID
		30.09.2022		120988	522104
13	No of Bidder in this Package	6 ( Six)			
14	NAME OF CONTRACTOR(ID NUMBER) REGISTRATION NUMBER AND ADDRESS	Tariyani Engicon Private limited, At- Rasulpur, saidpur, Bazid , Panchyat, Bhikanpura, Block - mushari,Muzaffarpur Reg. no.- 1210042 3			
15	EARNST MONEY (EMD) DETAILS.( must be uplod by the tenderer value more than 1 crore( submitted before prescribed time)	Required	Submitted		
			Amount (in words Also) NSC/BG		
		Rs- 4,88,411.00 Lakh	Rs- 4,90,000.00 (FD)		2
16	REGISTRATION (DEPARTMENT,ORGANISATION & CLASS)	Registration No. & Class	Department/ Organisation	Valid Upto	
		1210042, Class- 1	RCD Bihar	12.12.2026	3
17	CHARACTER Issuing Authority (if validity Period not mentioned then Validity Period will be for one year from date of issue)	Issuing Authority		Valid Upto	
		Attached (S.P. Shcholar) Online		27-01-2023 20-01-2023 13-01-2023	318 to 320
18	LABOUR LICENCE	Registration No.		Place of Issue	
		N/A			
19	PAN No.-	AAIC16278J			
20	GST No -	10AAIC16278J1Z3			
21	E.P.F. No.	BRMU/22376828000			
22	LAST 5 YEAR ANNUEL TURN OVER (as per balance sheet by Chartered Accountant)	Year	Total Turnover (Lakh)	Similar Work	Civil Work (Lakh)
		2017-18	479.98		479.98
		2018-19	247.241	128.62 (P-234)	247.241
		2019-20	618.46	55.68 (P-249)	618.46
		2020-21	1441.13	830 (P- )	1441.13
		2021-22	2149.00	1275, (P-239)	2149.00
					101, 155, 223 108, 229 117, 137, 196 127, 219, 175 90,