



Government of Bihar  
Rural Works Department,  
Works Division, Saharsa

Head : MUKHYAMANTRI GRAM SAMPARK YOJNA (2020-21)

A. A. Amount : Rs. 28.47 lac vide letter no 1021 Dated : 07.09.20

Name of Work : Construction of Road from Baijnathpur  
Patel Chowk to Baijnathpur Hat (SC)  
Length 315.00 m + 45.00 = 360.00 m  
Under Sour Bazar Block

Name of Agency : Kaptcha Construction  
Tiranga Whowk, Gangjala W.No. 16  
Saharsa

Agreement No. : Supplementary Agreement of Agreement  
No. 30 SBD/ MMGSY/21-22

Agreement Value : Rs. 245762.00 (Const.)  
Rs. 0.00 (Maint.)

Total : Rs. 245762.00

Agreement Rate : 24.90 % Below on BOQ rates with all taxes

Date of Commencement : As original Agreement

Time for Completion : As Original Agreement

KAPTCHA CONSTRUCTION  
*[Signature]*  
P... R

*[Signature]*  
22/02/23

*[Signature]* 22-02-2023  
Executive Engineer  
Rural Work Department  
Works Division, Saharsa  
*[Signature]* 22/2/23





## Supplementary Agreement of Agreement No. 30

SBD/MMGSY/2021-22

प्रभात कुमार सिंह  
मुद्रांक विक्रेता  
निबंधन परिसर, सहरसा  
अनुज्ञापन सं०-211/04

This Supplementary agreement, made the .....  
2023 between Rural Works Department (Govt. of Bihar) Works  
Division Saharsa (hereinafter called "the Employer") of the one  
part, and Kaptcha Construction, Tiranga Chowk, Gangjala  
W.No.16, Saharsa (hereinafter called "the contractor" of the other  
part) Whereas the employer is desirous that the Contractor execute  
the construction and maintenance of road from Baijnathpur Patel  
Chowk to Baijnathpur Hat Block Seur Bazar District –  
Saharsa under Mukhyamantri Gram Sampark yojna (SC)  
(2020-21) (hereinafter called "the Works") and the employer has  
accepted the Bid by the Contractor for the execution and  
completion of such Works and the Routine maintenance of the  
work for 5 years of the contract price and remedying of any defects  
therein at a cost or Rupees (24.90% below) (Construction Cost :  
245762.00 + Maintenance Cost: 0.00) = 245762.00 (Two Lacs  
Forty Five Thousand, Seven Hundred Sixty Two) Only.

For  
KAPTCHA CONSTRUCTION  
Proprietor  
Kaptcha Construction  
22/02/23

Executive Engineer  
Rural Work Department  
Works Division, Saharsa  
22-02-2023  
22/02/23



**NOW THIS AGREEMENT WITNESSETH AS FOLLOWS :**

1. In this agreement, words and expressions shall have the same meaning as are respectively assigned to them in the conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of the agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz :
  - i. Letter of Acceptance ;
  - ii. Notice to proceed with the works;
  - iii. Contractor's Bid;
  - iv. Contract Data;
  - v. Special Conditions of contract and general conditions of contract;
  - vi. Specification;
  - vii. Drawings;
  - viii. Bill of Quantities; and
  - ix. Any other document listed in the contract data as forming part of the contract.

For  
**KAPTCHA CONSTRUCTION**  
*Kanchan Kaur*  
**PROPRIETOR**

*Bal*  
22/02/23

*P. M. M.*  
22-02-2023  
**Executive Engineer**  
Rural Work Department  
Works Division, Saharsa  
*P. M. M.*

Revised Bill of Quantity for the work of Supplementary Agreement of  
**Bajnathpur Patel Chowk to Bajnathpur Hat** Approved by S.E.  
 RWD Saharsa vide letter no. 1008 enc Dated 24.12.22 and  
 Revised Technically approved (Revised DPR) by SE, Saharsa vide letter  
 no..... Dated 25.11.22 Rs. 23.96475 Lac  
 Estimated Cost :-

Item	Original Cost (in Lac)	Excess Revised Cost (in Lac)	Total Cost (in Lac)
Const.	27.05188	3.27247	30.32435
Maint.	1.58609	0.00	1.58609
<b>Total</b>	<b>28.63797</b>	<b>3.27247</b>	<b>31.91044</b>

Agreement No. :- Suppl. Agreement of Agreement No.  
 30 S.B.D/ MMGSY/21-22

Item	Original Cost (in Lac)	Excess Revised Cost (in Lac)	Total Cost (in Lac)
Const.	20.31596	2.45762	22.77358
Maint.	1.19115	0.00	1.19115
<b>Total</b>	<b>21.50711</b>	<b>2.45762</b>	<b>23.96473</b>

Performance Security @ 2% **Rs. 5000.00 Required**

FD No. 18220310072721 (UCO Bank Saharsa ) Dated 15.03.23 Rs. 6000.00

**Total : Rs. 6000.00 Submitted**

Rest Performance Security @ 8% to be deducted from contractors bill

Additional Performance Guarantee : **Rs. 70000.00 Required**

FD No. 18220310072738 (UCO Bank Saharsa ) Dated 15.02.23 Rs. 70000.00

**Total : Rs. 70000.00 Submitted**

Date of Commencement : 29.01.21 (Vide Lt.No 229 Dated 29.01.21)

Time of Completion of Work :- 09 Months Up to 28.10.21 (Original Agreement)

For  
**KAPCHA CONSTRUCTION**  
*Kapcha*  
**PROPRIETOR**

*Bal*  
 22/02/23

*Puni*  
 22-02-2023  
**Executive Engineer**  
 Rural Work Department  
 Works Division, Saharsa  
*Puni*  
 22/02/23

**अधीक्षण अभियंता का कार्यालय,  
ग्रामीण कार्य विभाग, कार्य अंचल, सहरसा।**

पत्रांक 1508 / 2020

प्रेषक,

ई0 कृष्णनन्दन प्रसाद सिंह,  
अधीक्षण अभियंता,

सेवा में,

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, सहरसा।

सहरसा, दिनांक 24/12/2022 /

विषय : ग्रामीण कार्य विभाग, कार्य प्रमंडल, सहरसा के अधीन शीर्ष मुख्यमंत्री ग्राम सम्पर्क योजना अन्तर्गत पुनरीक्षित तकनीकी स्वीकृति के उपरान्त कुल-01 (एक) अदद पुनरीक्षित प्राक्कलन की पुनरीक्षित परिमाण विपत्र अनुमोदन करने के संबंध में।

प्रसंग : आपका पत्रांक 1702 अनु0, सहरसा, दिनांक 28.11.2022

महाशय,


उपर्युक्त विषयक प्रसांगिक पत्र द्वारा प्राप्त ग्रामीण कार्य विभाग, कार्य प्रमंडल, सहरसा के अधीन शीर्ष मुख्यमंत्री ग्राम सम्पर्क योजना अन्तर्गत पुनरीक्षित तकनीकी स्वीकृति के उपरान्त कुल-01 (एक) अदद पुनरीक्षित प्राक्कलन की पुनरीक्षित परिमाण विपत्र एक प्रति में अनुमोदित कर मूल रूप में अग्रेतर कार्रवाई हेतु भेजी जाती है।

साथ ही निदेश दिया जाता है कि अनुमोदित परिमाण विपत्र के मद एवं मदों की मात्रा, दर, इकाई, गणना आदि की जाँच आप अपने स्तर से भी कर संतुष्ट होने के पश्चात् ही अग्रेतर कार्रवाई करेंगे। किसी प्रकार की त्रुटि पाये जाने पर अधोहस्ताक्षरी से आवश्यक सुधार हेतु प्रस्तुत करेंगे।

SL. No.	Block	Name of Road/ Package No.	Length (KM)	A/A Amount (In Lakh)	Revised T/S Amount (In Lakh)	Revised B.O.Q. (In Amount)
1.	Sour Bazar	Baijnathpur Patel Chowk to Baijnathpur Hatt.	0.360	28.470	23.964	3,27,247=00

अनु0:-पुनरीक्षित परिमाण विपत्र एक प्रति मूल में।

विश्वासभाजन,

  
अधीक्षण अभियंता,  
ग्रामीण कार्य विभाग, कार्य अंचल,  
सहरसा।  
24/12/2022

For  
KAPCHA CONSTRUCTION  
  
PROPRIETOR



## Supplementary Agreement

### MUKHYA MANTRI GRAM SAMPARK YOJANA (MMGSY)-SC

Name of Road :- Baljnathpur Patel Chowk To Baljnathpur Hatt

Length :- 0.360 Km.

Block :- Sourbazar

District :- Saharsa

Items	Unit	(Revised Estimate)		
		Qty.	Rate	Amount
2	3	4	5	6
<b>Clearing and Grubbing Road Land</b> Clearing and Grubbing Road Land ( By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I ( By Manual Means) In area of non-thorny jungle	Hect.	0.010	52970.300	529.70
Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess).	Cum	11.250	192.000	2160.00
<b>Granular Sub-base with Well Graded Material (Table 400.1) :-</b> Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. (For Grading I Material)	Cum	17.200	2664.400	45827.68
<b>WBM Grading 3 :-</b> Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of, coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	12.880	3074.400	39598.27
<b>Cement Concrete Pavement M30</b> Construction of un-reinforced, expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including	Cum	27.520	6641.200	182765.82

For  
KAPCHA CONSTRUCTION  
Kana Kishor  
PR...

25-11-2022

Approved and Corrected

R.W.D. Works, Circle, Saharsa

21/12/22

