

Contruction of Road & CD work With 5 years maintenance of **Manik Chauk Prandhan Mantri Path to Mela Tola Under MMGSY scheme**. And the Employer has accepted the Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein at a cost of rupees 1,54,03,960.00 (One Crore Fifty Four Lakhs Three Thousand Nine Hundred Sixty only).

NOW THIS AGREEMENT WITNESSETH as follows :

1. In the Agreement, works and expressions shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
 - i) Letter of Acceptance;
 - ii) Notice to proceed with the work;
 - iii) Contractor's Bid;
 - iv) Contract Data;
 - v) Special Conditions of contract and General Conditions of Contract;
 - vi) Specifications;
 - vii) Drawings;
 - viii) Bill of Quantities; and
 - ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of

Was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said

In the presence of :

Binding Signature of Employer

Binding Signature of Contractor

S.N. ENTERPRISES

Roobi Kumar

Proprietor

[Handwritten Signature]
22/08/20
Executive Engineer
RWD Works Division
Besar. d. Jangar
22/08/2020

AGREEMENT

1. Agreement No. :- **73 SBD /2019-20**
2. Name of Work :- **Construction of Road & CD work With 5 years Maintenance of Manik Chauk Prandhan Mantri Path to Mela Tola Under MMGSY scheme.**
3. Name of Agency :- **S.N. Enterprises, Prop. Roobi Kumari
Mehandiganj, Po- Patna City,
Mahendaru, Patna.**
4. Constructions Cost:- **1,37,97,397=00**
5. Maintenance Cost :- **1,60,65,65=00**
Total :- **1,54,03,960=00**
6. Performance Security Deposit :- BG-
7. B.G. No. / Bank :-
8. Work Allotted rate :- **(-) 6.72% (Below)**
9. The Employer shall retain security deposit of 5% (five percent) and performance security of 2.5% (Two and half percent) of the amount from each payment due to the Contractor until completion of the whole of the Construction Work. No security deposit / retention shall be retained from the payments for routine maintenance works (As per SBD Close 43).
10. Date of written order to commence :- **22/08/2020**
11. Time required for the work from date of written order to commence :- **1 year**
12. Total No. of Items :- **35.**

Note : SBD Rules Terms and condition will be applicable.

S.N. ENTERPRISES

Roobi Kumari

Proprietor
Contractor

Executive Engineer

R.W.D., Work Division
Belsand

22/08/20

22/8/2020

Mukhya Mantri Gram Sampark Yojna (MMGSY)

NAME OF ROAD :- Manik Chauk Pradhan Mantri Path to Mela Tola

Length:- 2.425 KM

LOCK:-Runnisaidpur

DISTRICT:-Sitamarhi

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing & Fixing of Working benchmark Pillars 01 nos. per km & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I (Working benchmark Pillars)	2.43	Km	4255.85	Rupees Four Thousand Two Hundred Fifty Five And Paise Eighty Five Only	10341.72
2	Reference Pillars	2.43	Km	1964.65	Rupees One Thousand Nine Hundred Sixty Four And Paise Sixty Five Only	4764.28
3	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification-clause 201.1 and direction of E/I	1.70	Ha	49739.47	Rupees Forty Nine Thousand Seven Hundred Thirty Nine And Paise Forty Seven Only	84557.10
4	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	231.38	cum	81.20	Rupees Eighty One And Paise Twenty Only	18788.06
5	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site, spreading, grading to required slope and	2463.87	Cum	187.51	Rupees One Hundred Eighty Seven And Paise	462000.26
6	300.2 with a lead upto 1000 m & 100 m as per Technical Specification Clause 301.5 (1000m Lead) 100 m lead	5305.04	Cum	142.62	Rupees One Hundred Forty Two And Paise Sixty Two Only	756604.80
5	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (including Labour Cess).	1532.65	Cum	189.39	Rupees One Hundred Eighty Nine And Paise Thirty Nine Only	290268.58
6	Construction of granular sub-base by providing Well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller achieve the desired density, complete as per Technical specification clause 401.	908.66	Cum	3096.00	Rupees Three Thousand Ninety Six Only	2813211.36
7	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading Specification Clause 405.	473.34	Cum	3766.13	Rupees Three Thousand Seven Hundred Sixty Six And Paise Thirteen Only	1782659.97

S.N. ENTERPRISES

Rishi Kumar

Proprietor

Executive Engineer

Works Division

Beasani

Superintendent

RWD Works Circle

Sitamarhi

22/08/20

22/08/20

OF ROAD :- Manik Chauk Pradhan Mantri Path to Mela Tola
CK:-Runnisaidpur

Length:- 2.425 KM

DISTRICT:-Sitamarhi

Description of work

No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
10	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	6311.25	Sqm	51.50	Rupees Fifty One And Paise Fifty Only	325029.38
11	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriloc broom as per technical specification clause 503.	6311.25	Sqm	17.29	Rupees Seventeen And Paise Twenty Nine Only	109121.51
12	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509	6311.25	Sqm	237.57	Rupees Two Hundred Thirty Seven And Paise Fifty Seven Only	1499363.66
13	Construction of granular sub-base by providing Well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller achieve the desired density, complete as per Technical specification clause 401.	82.54	Cum	3096.00	Rupees Three Thousand Ninety Six Only	255543.84
14	Providing, laying, spreading and compacting stone of specified size to water bound base as per specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	222.33	Cum	3766.13	Rupees Three Thousand Seven Hundred Sixty Six And Paise Thirteen Only	837323.68
15	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501	474.30	Cum	7945.14	Rupees Seven Thousand Nine Hundred Forty Five And Paise Fourteen Only	3768379.90
16	Reinforced cement concrete M15 grade kilometer stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703	2501.80			Rupees Two Thousand Five Hundred One And Paise Eighty Only	7885.40

Supervisor
RWD Works Circle
Sitamarhi

Proprietor

Roobi Kumeri

S.N. ENTERPRISES

Executive Engineer
RWD Works Division
Be. sar.

OF ROAD :- Manik Chauk Pradhan Mantri Path to Mela Tola
CK:- Runnisaidpur

Length:- 2.425 KM

DISTRICT:- Sitamarhi

Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
			Figure	Words	
17 m 200 m stone (6)	10.00	No.	686.53	Rupees Six Hundred Eighty Six And Paise Fifty Three Only	6865.30
15 Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	80.00	No.	537.23	Rupees Five Hundred Thirty Seven And Paise Twenty Three Only	42978.40
16 Providing and fixing of Retro reflective cautionary, mandatory and informatory sign board as per IRC :67 made of 1.5 mm thick MS steel duly stove white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.3.9 of MORD for rural road of required shade and colour supported and welded on 47mmx47mmx12swg sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm, 600mm below ground level as per approved drawing clause 1701.2.2 (600 mm circular, (Speed Limit)	12.00 6.00	Nos Nos	5608.27 6407.79	Rupees Five Thousand Six Hundred Eight And Paise Twenty Seven Only Rupees Six Thousand Four Hundred Seven And Paise Seventy Nine Only	67299.24 38446.74
(6) 600 mm x 450 mm rectangular	5.00	Nos	5453.14	Five Thousand Four Hundred Fifty Three And Paise Fourteen Only	32718.84
17 Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	330.00	Sqm	850.93	Rupees Eight Hundred Fifty And Paise Ninety Three Only	280806.90
18 Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass Leads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. Providing and applying 2 coats of water based cement paint to unplastered concrete surface after cleaning the surface of dirt, dust, oil, grease, efflorescence and applying paint @ of 1 litre for 2 sqm.	155.00	Sqm	947.57	Rupees Nine Hundred Forty Seven And Paise Fifty Seven Only	146873.35
24 Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	166.00	Each	817.41	Rupees Eight Hundred Seventeen And Paise Forty One Only	135690.06

S.N. ENTERPRISES

Roobi Komari

Proprietor

Executive Engineer

Superintendent Engineer

RWD Works Division
Be. S. A. J. Singh
22/08/20

RWD Works Circle
Sitamarhi

OF ROAD :- Manik Chauk Pradhan Mantri Path to Mela Tola
 CK:-Rumisarapur

Length:- 2.425 KM

DISTRICT:-Sitamarhi

AMOUNT
 Rs. P

Description of work

No. or
 Qty.

Unit

Estimated Rate

Figure

Words

70584.00

25 Providing and laying of a reinforced cement concrete
 20 pipe duct, 300 mm dia, across the road (new
 construction), extending from drain to drain in cuts and
 toe of slope to toe of slope in fills, constructing head
 walls at both ends, providing a minimum fill of granular
 material over top and sides of RCC pipe as per
 IRC:981997, bedded on a 0.3 m thick layer of granular
 material free of rock pieces, outer to outer distance of
 pipe at least half dia of pipe subject to minimum 450
 mm in case of double and triple row ducts, joints to be
 made leak proof, invert level of duct to be above higher
 than ground level to prevent entry of water and dirt, all
 as per IRC: 98 - 1997 and approved drawings.

75.00

Rm

941.12

Rupees Nine
 Hundred Forty One
 And Paise Twelve
 Only

26 Providing and erecting direction and place identification
 21 retro-reflectorised sign as per IRC:67 made of
 encapsulated lens type reflective sheeting vide Clause
 17012.3, fixed over aluminium sheeting, 2 mm thick
 with area not exceeding 0.9 sqm supported on a mild
 steel single angle iron post 75 x 75 x 6 mm firmly fixed
 to the ground by means of properly designed
 foundation with M-15 grade cement concrete 450 x 450
 x 600 mm, 600 mm below ground level as per
 approved drawing and Technical Specification Clause
 1701

1.00

No.

3539.83

Rupees Three
 Thousand Five
 Hundred Thirty Nine
 And Paise Eighty
 Three Only

3539.83

27 Providing and fixing of typical MMGSY informatory sign
 22 board with Logo as per MORD specifications and
 drawing. Three MS Plates of 1.6 mm thick, top and

6.00

No.

11789.14

Rupees Eleven
 Thousand Seven
 Hundred Eighty
 Fourteen Only

70734.84

size on back on edges. The lower plate will be welded
 with MS angle iron frame of 25mm x 25mm x 5mm. The
 angle iron frame of the lower most plate and flat iron
 frame of middle plate will be welded to 2 nos. 75mm x
 75 mm of 12 SWG sheet tubes posts duly embedded in
 cement concrete M-15 grade blocks of 450mm x
 450mm x 600mm, 600mm below ground level. The top
 most diamond plate will be welded to middle plate by
 47mm x 47mm of 12 SWG steel plate tube. All M.S.
 will be stove enameled on both sides. Lettering and
 printing arrows, border etc. will be painted with ready
 mixed synthetic enamel paint of superior quality in
 required shade and colour. All sections of framed
 posts and steel tube will be painted with primer and two
 coats of epoxy paint as per drawing Clause 1701 and
 Annexure 1700 including citizen board

89.40

cum

261.90

Rupees Two
 Hundred Sixty One
 And Paise Ninety

23413.86

28 Earth work in excavation for foundation of structures
 23 upto 3.0 m depth as per drawing and technical
 specification clause 1104

8.88

cum

6238.48

Rupees Six
 Thousand Two
 Hundred Thirty
 Eight And Paise
 Forty Eight Only

55397.70

29 Providing M15 (PCC 1:2.5:5) as levelling course in
 24 foundation :- Providing PCC M 15 (1:2.5:5) concrete
 for plain concrete in open foundations complete as per
 drawings and technical specifications Clause 802, 803,
 1202 & 1203

91.83

cum

6932.62

Rupees Six
 Thousand Nine
 Hundred Thirty Two

636622.49

30 Providing concrete for plain/reinforced concrete in open
 25 foundations complete as per drawings and technical
 specifications Clause 802, 803, 1202 & 1203

S.N. ENTERPRISES

Roobi Komari
 Proprietor

Excavation Engin.
 RWD Works Division
 Be.sar
 22/08/20

Superintendent Engineer
 RWD Works Circle
 Sitamarhi

OF ROAD :- Manik Chauk Pradhan Mantri Path to Mela Tola

Length:- 2.425 KM

UCK:-Runnisaipur

DISTRICT:-Sitamarhi

No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
26	Providing and laying RCC pipe NP-3 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106	22.50	m	3859.46	Rupees Three Thousand Eight Hundred Fifty Nine And Paise Forty Six Only	86837.85
27	Painting Two Coats on New Concrete Surfaces. Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	348.72	Sqm	108.98	Rupees One Hundred Eight And Paise Ninety Eight Only	38003.51
28	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	3.12	cum	6108.03	Rupees Six Thousand One Hundred Eight And	19057.05
29	Providing PCC M-20 architectural coping on the top of wing wall, return wall etc. complete as per drawing and technical specification Clauses 615, 710 and 1204.3.11	13.00	m	464.66	Rupees Four Hundred Sixty Four And Paise Sixty Six Only	6040.58
30	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications <i>clause 613.4.3 1204</i>	21.76	sqm	186.41	Rupees One Hundred Eighty Six And Paise Forty One Only	4056.28
31	1st Year Maintenance cost	1	year	93420.00	Rupees Ninety Three Thousand Four Hundred Twenty Only	93420.00
32						133101.00
33	3rd Year Maintenance cost	1	year	607776.00	Rupees Six Lakh(s) Seven Thousand Seven Hundred Seventy Six Only	607776.00
34	4th Year Maintenance cost	1	year	217774.00	Rupees Two Lakh(s) Seventeen Thousand Seven Hundred Seventy Four Only	217774.00
35	5th Year Maintenance cost	1	year	683228.00	Rupees Six Lakh(s) Eighty Three Thousand Two Hundred Twenty Eight Only	683228.00
Total Cost of Project		Rupees One Crore Sixty Five Lakh(s) Thirteen Thousand Seven Hundred Thirty Two And Paise Thirty Two Only say 1,65,13,732.32				16513732.32

S.N. ENTERPRISES

Rishi Kumari
Proprietor

Approved35.....(Thirty five) items

Valuing Rs. 1,65,13,732.00 (One crore sixty five lakh thirteen thousand seven hundred thirty two) only

Executive Engineer

RWD Works Division

Bewar

Superintendent Engineer

RWD Works Circle

Sitamarhi

S. E.

RWD WORKS CIRCLE

**मुख्य अभियंता-3, पटना का कार्यालय,
ग्रामीण कार्य विभाग, बिहार, पटना।**

पत्रांक- II/मु0अ0-3 प0पु0 1-886/19

प्रेषक,

/पटना, दिनांक-

मुख्य अभियंता-3,
ग्रामीण कार्य विभाग,
बिहार, पटना।

सेवा में,

अधीक्षक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, सीतामढ़ी।

विषय : शीर्ष MMGSY योजना अन्तर्गत कार्य प्रमण्डल, बेलसंड के अधीन Manik Chauk Pradhan Mantri Path To Mela Tola तक पथ निर्माण (TenderID-76966) कार्य के निविदा निष्पादन के संबंध में।

महाशय,

शीर्ष MMGSY योजना अन्तर्गत कार्य प्रमण्डल, बेलसंड के अधीन Manik Chauk Pradhan Mantri Path To Mela Tola तक पथ निर्माण (TenderID-76966) कार्य निविदा के वित्तीय बीड में राफल निविदाकार S.N. Enterprises, Prop. Roobi Kumari (354412) को उनके द्वारा उद्धृत दर जो कि परिमाण विपत्र की दर से 6.72 प्रतिशत कम है अर्थात् कुल राशि 1,54,03,960.00 (एक करोड़ चौबन लाख तीन हजार नौ सौ साठ) रु0 मात्र पर कार्यहित आपकी अनुशंसा के आलोक में यह कार्य आवंटित किया जाता है।

2. निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।

3. कार्यपालक अभियंता, कार्य प्रमण्डल, बेलसंड संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ जमा किये गये संबंधित एन0एस0सी0/पासबुक आदि का सत्यापन संबंधित डाकघर से कराकर प्रमण्डलीय कार्यालय में अभिलेखित करेंगे एवं कार्यदेश निर्गत करने के पूर्व अग्रधन की राशि के सत्यापन से संबंधित कागजात अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।

4. एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जाय एवं साथ में इसकी भी जाँच कर ली जाय कि संवेदक डीबार सूची से मुक्त है।

5. अधीक्षक अभियंता एवं कार्यपालक अभियंता अग्रतर कार्रवाई से पूर्व मली भौति आश्वस्त हो लेंगे कि पथ का हस्तांतरण हेतु विभाग द्वारा अनापत्ति प्रमाण पत्र निर्गत नहीं किया गया है।

6. कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य कराते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।

7. इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावैधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लिखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।

8. अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करयेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की जायेगी।

9. एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जांच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।

10. कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपबंध से पूरी तरह आश्वस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावैधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये निदेश का अनुपालन सुनिश्चित करायेंगे।

11. कार्यदेश निर्गत करने से पहले संबंधित संवेदक से एकारारित अवधि के अन्दर कार्य समाप्त करने हेतु विस्तृत मदवार कार्य प्रोग्राम प्राप्त कर ही एकरारनामा किया जाय।

12. अधीक्षक अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुरूप निर्धारित कार्य अवधि के अंदर पूरा की जाय।

CHECK LIST FOR TECHNICAL EVALUATION (SBD)MMGSY

05	NAME OF CIRCLE	RWD (Work) Circle, Sitamarhi		
06	NAME OF DIVISION	RWD (Work) Division, Belsand		
07	NAME OF WORK	Manik Chank Pradhan Mantoi Path to Mela Tola		
08	TENDER ID NUMBER	2019-ET/14-76966-1		
09	AMOUNT & DATE OF ADMINISTRATIVE APPROVAL	172.460 / 232 dt 7.3.19		
10	AMOUNT & DATE OF TECHNICAL SANCTION	168.46 / 2615 dt 18.3.19		
11	CONSTRUCTION COST IN LAKH	147.91430 Lakh		
12	MAINTENANCE COST IN LAKH	17.22302 Lakh		
13	TOTAL TENDER VALUE (IN LAKH)	165.13732 Lakh		
14	COST OF BOQ IN Rs. (Details must be uploaded by the tenderer with details Bank Draft)	10000=0 (Ten thousand) S/31, DD No - 481297 / ——— ①		
15	PRESS RELEASE	Newspaper in which Tender Published Dainik Jagaran	Date of Publication 10.3.19	PR NO 19435 (RWD) 20/3/19
16	DATE OF RECEIPT OF TENDER INCLUDING BID ID & TENDER ID	Date of Receipt 8.4.19	Tender I.D. 76966	Bid I.D. 354412
17	NAME OF CONTRACTOR ID NO./ REGISTRATION NO. and ADDRESS	S.N. Enterprises Prop Roopi Kumari Mehandiganj, P.O. - Patna City, Mahendru, Patna. Regd-2180038. 4632, 47004164 Adhar		
18	Earnest Money (EMD) Details (must be uploaded by the tenderer NSC/TD/FD/ BG if tender value more than one crore (Submitted before prescribed time)	Required	Submitted	
19			Amount (in words also)	NSC/BG
20		Rs 3,30,275=0	3,31,000=0	FD
21	Registration (Department Organisation & Class)	Registration No & class 2180038 / Class-2	Department/ Organisation RWD	Valid upto 23.01.23
22	Labour Licence	Issuing Authority	Valid upto	
23	CHARACTER issuing Authority (if validity Period not mention then validity period will be for in year from date of issue)	Issuing Authority Sr S P Office Patna	Valid upto 26.8.19	
24	Vat Registration No. & Place of issue	Registration No.	Place of Issue	

Pan CTIPK 5498R ——— ⑫
 GST-10CTIPK 5498R12W ——— ⑮
 EPF-BR PAT 1730388000 ——— ⑮

PMGSY Tenders

eProcurement System for Pradhan Mantri Gram Sadak Yojana (PMGSY)

Bid Submission Confirmation

Date : 05-Apr-2019 02:52 PM

Print

Bid Information

Bid ID :	354412
Bidder Name :	S. N. ENTERPRISES, PROP. ROOBI KUMARI
Organisation Chain :	Er in Chief, Bihar
Tender Ref No :	MMGSY-19-BELSAND-58
Tender ID :	2019_ECBIH_76966_1
Tender Title :	Manik Chauk Pradhan Mantri Path to Mela Tola
Bid Submitted Date & Time :	05-Apr-2019 02:52 PM

Corporate Tenderer Details

Login ID:	snenterprises619@gmail.com	User Type:	Corporate/Bidder
Company Name:	S. N. ENTERPRISES, PROP. ROOBI KUMARI	Registration Number:	2180038
Registered Address :	AT- MEHANDIGANJ, P.O- PATNA CITY, P.S- MEHANDIGANJ, DIST- PATNA	Name of Partners / Directors :	Nil
City :	PATNA	State :	Bihar
Postal Code :	800008	PAN Number:	CTIPK5498R
Company's Establishment Year (yyyy):	2018	Company's Nature of Business:	ALL
Company's Legal Status:	Others	Company Category :	Medium Unit as per MSME
Title :	Mrs	Contact Name:	ROOBI KUMARI
DOB (Date Of Birth):	01-Mar-1986	Designation :	Nil
Correspondence Email:	snenterprises619@gmail.com	Phone :	95238 - 91 - 79321
Mobile:	9523879321		

* Tender Fee in : 10,000 in : 0.00 in : 0.00 in : 0.00

Offline Tender Fee Payment Details

S.No	Instrument No.	Name	Issued Date	Expiry Date	Acc.No	Amount in .
1	481297	DD	05-Apr-2019	04-Jul-2019		10,000
Total in . :						10,000

Offline EMD Fee Payment Details

S.No	Instrument No.	Name	Issued Date	Expiry Date	Acc.No	Amount in .
1	38374574127	FD	05-Apr-2019	05-Apr-2020		3,31,000
Total in . :						3,31,000

Bid Documents

File