

BIHAR RURAL ROADS DEVELOPMENT AGENCY
(GOVERNMENT OF BIHAR)

BID DOCUMENT

FOR

CONSTRUCTION AND MAINTENANCE OF RURAL
ROADS

DISTRICT: Banka

BLOCK: Banka

Sl. No.	Name of Road	Length In Km	Cost of Const. (Rs. In Lakhs)	Maintenance Cost (Rs. In Lakhs)	Total Cost (Rs. In Lakhs)
Package No.- MR-N/22-23 Banka-1/19					
1.	Banka Katoria Path Chutiya PMGSY Path to Bhoga Tak	1.600	59.37411	17.32010	76.69421
2.	Banka Katoriya PWD Path To Kelabari Mawora Tak	1.172	61.83652	12.50589	74.34241
3.	Banka Katoria T03 To Koribandha Korichak	1.687	59.05860	19.30107	78.35967
Total-		4.459	180.26923	49.12706	229.39629

Financial Bid
Year 2022-23


Under
M/R Head 3054
MINISTRY OF RURAL DEVELOPMENT
GOVERNMENT OF BIHAR

For,
KHUSHAVU CONSTRUCTION PRIVATE LIMITED
3107212154
(Director)

SR. Divisional Account Officer
R.W.D. (W) Div. Banka-01

Executive Engineer
R.W.D. Works Division
BANKA-1

		Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing and fixing of typical MR informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1				
		No.	5.00	10527.96	52639.80
20	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.				
		Rm	22.50	1000.25	22505.63
	Parapet				
21	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	Sqm	100.80	164.82	16613.86
22	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	100.80	114.73	11564.78
				Total =	5754870.45
				Labour cess @1% =	57548.70
				GST @18% =	1035876.68
				Add Seigniorage Fee @ 10%	67733.16
				Total (A) =	6916028.99
23	5 YEAR ORDINARY MAINTENANCE COST	Quarterly	20	84563.29	1691265.84
				Labour cess @1% =	16912.66
				GST @18% =	304427.85
				Add Seigniorage Fee @ 10%	4877.78
				Total (B) =	2017484.13
				Grand Total Cost (A+B) =	8933513.12


 14/9/22
 R.V.V.D. Works Division
 BANKA-1