

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

बिहार BIHAR

Agreement No

Name of Works

Name of Agency

Date of Start

Date of Completion

E.M. Deposit

AGREEMENT

S8 MBD / 2020-21

Construction of Road With 5 Year maintenance of  
Package No-MR-N/2019-20 Belsand 08 M/R

1. Ramni Middle School To Harpur Middle School
2. Sarkhauli PWD Road To Sarkhauli Village
3. Sarkhauli To Kanhauli Gajpatti

Smt- Sunita Devi  
At- Lichi Gachhi Prabhat Nagar, Nazirpur, Ahiyapur,  
Dist- Muzaffarpur.

15.07.2020

14.04.2021

355000 = 0

This Agreement Made on 15.07.2020 between Executive Engineer, Rural Work Department, Works Division, Belsand of the one part and Smt- Sunita Devi, At- Lichi Gachhi Prabhat Nagar, Nazirpur, Ahiyapur, Dist- Muzaffarpur. Whereas the Employer is desirous that the contractor execute the Works under M/R 3054 Scheme.

Executive Engin  
RWD Works Division  
Belsand

15/07/2020

सुनीता देवी

Construction of Road With 5 Year maintenance Road from Package No-MR-N/2019-20 Belsand/08 Under M/R 3054 scheme And the employer has accepted the bid by The Contractor for the execution and completion of such works and remedying of any defects therein at a cost of rupees – 1,79,26,476.00 (One Crore Seventy Nine Lacs Twenty Six thousand Four Hundred Seventy Six only )

**NOW THIS AGREEMENT WITNESSETH as follows :**

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract thereafter referred to, and they shall be form and be read and constructed as part of this agreement.
2. In consideration of the payments to made by the Employer to the Contractor as herein after mentioned, the contractor hereby covenants with Employer to execute and complete the works and remedy any defects therein in conformity I all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and constructed as part of this agreement , viz.
  - (i) Letter of Acceptance
  - (ii) Notice to proceed with the works
  - (iii) Contractor's Bid
  - (iv) Contract Data
  - (v) Special condition of contract and general conditions of contract.
  - (vi) Specifications

*Signature*

*Signature*  
15/7/20  
Executive Engr  
R.W.D Works Division  
Be...  
15.7.2020

- (vii) Drawings
- (viii) Bill of Quantities and
- (ix) Any other document listed in the contract Data as froming part the contract

In witness, where of the parties there to have caused this Agreement to be executed the day and year first before written.

The common seal of

Was hereunto affixed in the presence of

Signed, sealed and Delivered by the said

In the presence of

Binding signature of Employer

Binding signature of contractor.

15/07/20  
Executive Engr  
RWD Works Division  
Bersar  
15.07.2020

सुनीता ठोंग

## AGREEMENT

1. Agreement No. :- 58 MBD / 2020-21
2. Name of Work :- Construction of Road With 5 Year maintenance of Package No-MR-N/2019-20 Belsand/08 Under M/R 3054 scheme.
3. Name of Agency :- Smt- Sunita Devi  
At- Lichi Gachhi Prabhat Nagar, Nazirpur,  
Ahiyapur, Dist- Muzaffarpur.
4. Construction Cost :- 13445502 = ₹
5. Maintenance Cost :- 4480974 = ₹
- Total :- 17926476 = ₹
6. Performance Security Deposit :- BG - NSC - 355000 = ₹
7. B.G. No. / Bank :-
8. Work Allotted rate :- 0.11% below
9. The Employer shall retain S.D. of ( 8 % ) of the amount from each payment due to the contractor until completion of the whole of the construction work. No security deposit / retention shall be retained from the payment for routine maintenance of work.
10. Date of written order to commence :- 15.07.2020
11. Time required for the work from date of written order to commence :- 9 months
12. Total No. of Items :- 96

Note : SBD Rules Terms and condition will be applicable.

अनीता देवी  
Contractor

15/07/20  
Executive Engineer  
R.W.D., Works Division  
Belsand  
15/07/2020

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work: = Sarkhuli PWD Road To Sarkhuli Village

Name Of Block = Parsauni

Contract No: Civil Works/


Bidder Name: Excess (+) %

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P.
				Figure	Words	
1.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation grass, bushes, shrubs, saplings and trees of girth upto 300mm; removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/R	0.34	ha	49496.70	Rupees Forty Nine Thousand Four Hundred Ninety Six And Paise Seventy Only	16939.82
2.00	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads transporting to site; spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 401	707.70	Cum	176.75	Rupees One Hundred Seventy Six And Paise Seventy Five Only	124945.95
3.00	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	49.09	Cum	2123.92	Rupees Two Thousand One Hundred Twenty Three And Paise Ninety Two Only	104233.33
4.00	WBM Grading 2 ( By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 401	41.67	Cum	3826.86	Rupees Three Thousand Eight Hundred Twenty Five And Paise Eighty Six Only	160452.54

*[Handwritten signature]*


*[Handwritten signature]*  
 15/7/20  
 Executive Engineer  
 RWD Works Division  
 Beas  
 15.07.2020

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
5.00	WBM Grading 3 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical	77.08	Cum	354.25	Rupees Three Thousand Five Hundred Thirty Four And Paise Twenty Five Only	272419.99
6.00	Prime Coat (Low porosity) :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	1027.73	Sqm	41.38	Rupees Forty One And Paise Thirty Eight Only	42527.47
7.00	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrioc broom as per technical specification clause 503	1057.73	Sqm	14.03	Rupees Fourteen And Paise Three Only	14819.55
8.00	Patch work over WBM using Mix seal surface With Waste Plastic for bituminous and Existing CC Pavement :- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 With waste plastic	1057.73	Sqm	205.71	Rupees Two Hundred Five And Paise Seventy One Only	217545.44
9.00	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrioc broom as per technical specification clause 503	6318.75	Sqm	11.77	Rupees Eleven And Paise Seventy Seven Only	74371.65


  
 15/7/20  
 Executive Engin  
 R W D Works Division  
 Be. S. J. 1  
 15-07-2020



Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
10.00	Semi-Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects	157.97	Cum	10298.75	Rupees Ten Thousand Two Hundred Ninety Eight And Paise Seventy Five Only	1626393.54
11.00	Kilometre stone :- Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. i) 5th km Stone	0.00	nos	4560.70	Rupees Four Thousand Five Hundred Sixty And Paise Seventy Only	0.00
12.00	ii) km stone	3.00	nos	2452.01	Rupees Two Thousand Four Hundred Fifty Two And Paise One Only	7356.03
13.00	ii) 200 m Stone	6.00	nos	657.49	Rupees Six Hundred Fifty Seven And Paise Forty Nine Only	3944.94
14.00	Direction and Place Identification signs with size more than 0.9 sqm size board :- Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per	0.00	Sqm	12450.38	Rupees Twelve Thousand Four Hundred Fifty Six And Paise Thirty Eight Only	0.00
15.00	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 i) 600 mm equilateral & triangle	4.00	nos	3733.04	Rupees Three Thousand Seven Hundred Thirty Three And Paise Four Only	14932.16
16.00	600 mm circular	2.00	nos	3832.39	Rupees Three Thousand Eight Hundred Thirty Two And Paise Thirty Nine Only	7664.78
17.00	600 mm x 450 mm rectangular	2.00	nos	3703.27	Rupees Three Thousand Seven Hundred Three And Paise Twenty Seven Only	7406.54

  
 15/7/20  
 Executive Engr  
 R W E Works Division  
 Baisa  
 15.07.2020

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P.
				Figure	Words	
18.00	Boundary Pillar/Guard Post :- Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC-25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	36.00	nos	517.14	Rupees Five Hundred Seventeen And Paise Fourteen Only	18617.04
19.00	Printing New Letters and Figures of any Shade :- Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	0.00	per cm height per line	0.51	Rupees And Paise Fifty Only	0.00
20.00	Planting of Trees and their Maintenance for one Year :- Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard	76.00	Each	800.30	Rupees Eight Hundred And Paise Thirty Only	60822.80
21.00	Road Marking with Hot Applied Thermoplastic :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	337.00	Sqm	735.40	Rupees Seven Hundred Thirty Five And Paise Forty Only	247929.80
22.00	Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron (frame of 25mm x 25mm x 5mm). The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause	2.00	nos	9494.40	Rupees Nine Thousand Four Hundred Ninety Four And Paise Forty Only	18988.80
23.00	Brick Masonry in C.M.(1:3) in parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications. Clauses 600, 900 and 1208.4	9.64	Cum	5266.93	Rupees Five Thousand Two Hundred Sixty Six And Paise Ninety Three Only	45506.28

  
 Executive Engineer  
 R.W.D. Works Division  
 Begal  
 15.07.2020

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
24.00	Plastering with cement mortar (1:4):- Plastering with cement mortar (1:4 ) on brick work in sub-structure as per Technical Specifications	60.48	Sqm	194.27	Rupees One Hundred Ninety Four And Paise Twenty Seven Only	11749.45
25.00	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	175.68	Sqm	95.63	Rupees Ninety Five And Paise Sixty Three Only	16800.28
26.00	Maintenance for 1st year	1.00	Year	96684.00	Rupees Ninety Six Thousand Six Hundred Eighty Four Only	96684.00
27.00	Maintenance for 2nd year	1.00	Year	171790.00	Rupees One Lakh(s) Seventy One Thousand Seven Hundred Ninety Only	171790.00
28.00	Maintenance for 3rd year	1.00	Year	188273.00	Rupees One Lakh(s) Eighty Eight Thousand Two Hundred Seventy Three Only	188273.00
29.00	Maintenance for 4th year	1.00	Year	207188.00	Rupees Two Lakh(s) Seven Thousand One Hundred Eighty Eight Only	207188.00
30.00	Maintenance for 5th year	1.00	Year	363428.00	Rupees Three Lakh(s) Sixty Three Thousand Four Hundred Twenty Eight Only	363428.00
Total Estimated Cost in Figures						41,43,221.85
31	1% Labour					41,432.22
32	12% GST					4,97,186.62
Quoted Amount				46,81,840.70		46,81,841.00
Quoted Rate in Words		Rupees Forty Six Lakh(s) Eighty One Thousand Eight Hundred Forty One Only				

CM  
28

Approved .....32.....(thirty two) items  
Valuing Rs. 46,81,841.00 (Rs. Forty six Lacs eighty one thousand eight hundred forty one) only  
as Corrected

S. E.  
R W D WORKS CIRCLE  
SITAMARHI

15/7/20  
Executive Engineer  
R W D Works Division  
Belsah  
15.07.2020

15/07/20