

कार्यपालक अभियंता का कार्यालय  
ग्रामीण कार्य विभाग, कार्य प्रमंडल, पटोरी

पत्रांक.....8.61

पटोरी, दिनांक.....24.6.23

प्रेषक:-

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल पटोरी।

सेवा में,

नोडल पदाधिकारी,  
एमआर-3054 कोषांग,  
ग्रामीण कार्य विभाग,  
बिहार, पटना।

विषय:-

एमआर 3054 (नई अनुसूचना नीति-2018) अंतर्गत MR-N/19-20/Patori-02 Package के तहत एकरारित पथों को Foreclose करने के संबंध में।

महाशय,

उपरोक्त विषय के संबंध में सूचित करना है कि कार्य प्रमंडल, पटोरी अंतर्गत एमआर 3054 न्यू मेंटेनेंस पॉलिसी अंतर्गत MR-N/19-20/Patori-02 Package के तहत एकरारित पथों की सं० तीन है। एकरारनामा सं० 06 MBD/2019-20 है। जिसमें से दो पथ का कार्य स्वीकृत एवं एकरारित लंबाई में हो चुका है। उक्त एकरारनामा का एकरारित पथ पटोरी महुदाबाद पीडब्लुडी रोड ठाकुर चौक से दुमदुमा की स्वीकृत लंबाई 2.20 कि०मी० है जिसमें से 1.870 कि०मी० का निर्माण कार्य पूर्ण किया जा चुका है। शेष 330 मीटर में पूर्व में पंचायत स्तर से निर्माण कार्य कराया जा चुका है, जिस कारण पूरे एकरारित लंबाई में कार्य नहीं हो सका। DPR Consultant को भी 1.870 कि०मी० लंबाई के अनुसार भुगतान किया गया है। संवेदक को किए गए कार्य लंबाई- 1.870 कि०मी० के अनुसार भुगतान किया गया है एवं अनुसूचना कार्य का भुगतान भी समानुपातिक लंबाई के अनुसार किया जाएगा।

अतः अनुरोध है कि इस पथ को Foreclose करने कृपा की जाए।

विश्वासभाजन

*Sanjay* 24.6.23

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग, कार्य प्रमंडल पटोरी

# भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

## AGREEMENT FORM

OLNESH KUMAR  
Stamp Vendor  
No. 106/1987

This agreement, made the 28 Day of Jan. 2020 between the Executive Engineer, Rural Work Department, Work Division, Patari and Arpit Engicon Pvt. Ltd., At- Naya Tola, Dighi Khurd, Hajipur, Distt - Vaishali - 844101 (Bihar) hereinafter called "The Contractor" of the other part.

Whereas The Employer is desirous that the Contractor execute the work - MR-N/19-20 Patari/02 under head MR (3054. Details of roads are as follow-

Sl No	Name of Road	Length in K.M	Const. Cost in Rs.	12% GST	1% Labour Cess	Const. Cost(4+5+6) in Rs.	Less Quoted rate 10%	Mainten and Cost of Five Year	12% GST	1% Labour Cess	Total Maintenance Cost	Maintenance cost after deduction of quoted rate 10%	Grand Total after deduction of quoted rate 10% (8+13)
1	Patari Madudabad PWD Road Thakar Chowk to Dolduma	2.20	4628071.80	555368.60	46280.7	5229721.10	4706309.40	2053758.00	246451.00	20537.6	2320746.5	2086671.85	6794891.25
2	Patari Madudabad Purni Bazar to Sultanpur	6.50	13260969.9	1591316.4	132609.7	1498489.59	13486406.31	5778784.00	693454.10	57787.80	6530025.90	5877023.31	19363429.62
3	Chaklalsahi Jandaha RFO Road Near AND College Chaklalsahi	3.57	687438.10	824992.60	68749.40	776680.10	6991812.09	3160297.00	379235.60	34603.00	3571135.60	3214022.04	10205834.13
	TOTAL	12.27	18576479.8	2271677.6	247639.80	2798329.71	23184427.80	10992839.00	1319140.7	109928.4	1242190.800	11179717.20	36364145.00

(hereinafter called "The works and the Employer has accepted the Bid by the contractor for the execution and completion of such works and the remedying of any defects therein on his quoted rate 10 % (Ten Percent) below of the B.O.Q. rate for a cost of Rs. 36364145.00 (Rs. Three Crore Sixty Three Lakh Sixty Four Thousand One Hundred Forty Five) only. Which Include (Construction Cost. 25184427.80 and Maint. Cost. 11179717.20) only.

ARPIT ENGICON PVT. LTD.

Ramhars Ray  
25.11.20  
Director

28/01/2020  
कार्यपालक अभियन्ता  
वाजीण कार्य विभाग  
कार्य प्रमं प्रलेरी (समस्तीपुर)  
28/11/2020

**NOW THIS AGREEMENT WITNESSETH AS FOLLOWS-**

1. In this Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to, and they shall be deemed to form and be constructed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the contract at the times and the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and constructed as part of this Agreement, Viz.-
  - i) Letter of Acceptance
  - ii) Notice to proceed with the works
  - iii) Contractor's Bid
  - iv) Contract Data
  - v) Special Conditions of contract and general condition of contract
  - vi) Specifications
  - vii) Drawings
  - viii) Bill of Quantity and
  - ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written.

The Common Seal of \_\_\_\_\_

Was hereunto affixed in the presence of:-

Signed, Sealed and Delivered by the said \_\_\_\_\_

In the presence of:

Binding Signature of Employer \_\_\_\_\_

Binding Signature of Contractor \_\_\_\_\_

ARPIT ENGICON PVT. LTD.

Ram Kishore  
28.4.20  
Director

28/1/2020  
Executive Engineer  
RWD Works Division, Patna  
and District Engineer (Civil)  
Patna

MR 3054					
BILL OF QUANTITIES (BOQ)					
Name of Road :	Patori Mudadabad PWD road Thakur Chowk to Dumduma				
Block :	Patori	District :	Samastipur		
Length :	2.20 km				
Sl No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Clearing and Grubbing Road Land (By manual means) Including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	Ha	0.44	49,496.70	21778.55
2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	Cum	1,977.00	176.75	349434.75
3	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	Cum	72.52	2,004.19	145343.86
4	WBM Grading 2 ( By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	60.7	3,650.66	221595.06
5	WBM Grading 3 ( By Mechanical Means):- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	112.83	3,283.74	369847.64
6	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	Sqm	1,501.70	41	61569.70

Ban  
19/7/19

Executive Engineer  
Rural Works Department  
Works Division, Patori

ARPIT ENG'CO. PVT. LTD.

Ramharan  
28.1.19  
Director

अधीक्षण अभियंता  
ग्रामीण कार्य विभाग  
कार्य अंकर, रामस्तीपुर

28/1/19

जनसंपर्क अभियंता  
ग्रामीण कार्य विभाग  
कार्य अंकर, रामस्तीपुर

ii	Road strips	Nos	72	218.63	15741.36
14	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	Nos	84	486.46	40862.64
15	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	m height per	352	0.5	176.00
16	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	Each	37	800.3	29611.10
17	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.				
18	At Edge for BT Portion	Sqm	440	735.4	323576.00
19	Pedestrian Crossing(2 m in length and providing at 50 cm apart)	SQm	12	735.4	8824.80
20	Providing and fixing of typical MGSY Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	No.	2	9,249.05	18498.10
	1x 2.5m RCC SLAB CULVERT		0	0	0.00
21	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1206.4	cum	33.04	5,169.75	170808.54
22	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	sqm	227.84	161.09	36702.75
23	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	sqm	634.88	95.63	
				Total	4628071.8
24	12 % GST				555368.6
25	1% LABOUR CESS				46280.7
26	Total Construction Cost			(B)	5229721.1
27	1st Year Maintenance cost	Year	1	238858.00	238858.0
28	2nd Year Maintenance cost	Year	1	263666.00	263666.0
29	3rd Year Maintenance cost	Year	1	595764.00	595764.0

Ben  
19/7/19  
Executive Engineer  
Rural Works Department  
Works Division, Patoli

ARPIT ENGICON PVT. LTD.

R. K. Singh

Inspector

अधीक्षक अभियंता  
ग्रामीण कार्य विभाग  
बार्न अंबला, समस्तीपुर

30	4th Year Maintenance cost	Year	1	285732.00	285732.0
31	5th Year Maintenance cost	Year	1	669738.00	669738.0
				<b>Total</b>	<b>2053758.0</b>
32	12 % GST				246451.0
33	1% LABOUR CESS				20537.6
34	Total Maintenance Cost			(B)	2320746.5
	<b>Grand Total Cost (A+B)</b>				<b>7549868.5</b>

19/7/19

Executive Engineer  
Rural Works Department

BOA approved for Rs. 7549868 =

(Rs Seventy five lacs forty nine thousand  
eight hundred sixty eight) only  
Certify copy

अधीक्षण अधिकारी  
ग्रामीण कार्य विभाग  
कार्य अंचल, समस्तीपुर

अधीक्षण अधिकारी  
ग्रामीण कार्य विभाग  
कार्य अंचल, समस्तीपुर

ARPIT ENGICON PVT. LTD.

Ramkrishna Ray  
28.7.20

Director

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य अंचल, समस्तीपुर