

Name of	Sambhal Tola PMGSY Road To Sanchi Tola And Khapadiya Baba				
Block :	Piro	District :	Bhojpur		
Length :	0.700 km				
Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
28	300MM Irrigation Pipe Providing and laying of a reinforced cement concrete pipe duct,300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills,constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997,bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	RM	30.00	928.07	27842.10
				Total	6325385.6
	GST 12%				759046.3
	L.C 1%				63253.9
	Total Construction(A)				7147685.7
29	1st Year Maintenance cost	Year	1	17951.00	17951.0
30	2nd Year Maintenance cost	Year	1	20628.00	20628.0
31	3rd Year Maintenance cost	Year	1	138341.00	138341.0
32	4th Year Maintenance cost	Year	1	25135.00	25135.0
33	5th Year Maintenance cost	Year	1	143112.00	143112.0
				Total	345167.0
	GST 12%				41420.0
	L.C 1%				3451.7
	Seigniorage Fee @ 10%				719.6
	Total Maintenance (B)				390758.3
	Grand Total Cost (A+B)				7538444.0

Executive Engineer
Rural Works Department
Works Division Piro

Bill of Quantity approved for Rs. 75.384 Lakhs

Seventy five lakh Thirty Eight Thousand four hundred only

Superintending Engineer
Rural Works Department
Works Circle, ARA