



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

SUPPLYMENTRY AGREEMENT  
**HEAD 3054M/R TO ROAD**



UNDER  
RWD WORKS DIVISION BIHARSHARIF

C/S Approved By S.E. RWD Work Circle Nalanda Vide Letter 621(we) Dated 17.03.15

PROJECT NAME :- M/R TO ROAD FROM SH-78 TO ALIPUR  
INCLUDING FIVE YEAR MAINT.

REG. NO.- .....

PAN NO- .....

TENDER ID-34393

BID ID-116212

NAME OF CONRACTOR :- SUNITA PRITAM

CONTRACTOR ADD. :-BHAISASUR, BIHARSHARIF, NALANDA

Rate for Supplementary Agreement Approved Vide S.E. RWD Work Circle

Nalanda Letter No.- 320 (अनु०) Dated 08.04.2022

SUPPLEMENTARY AGREEMENT NO.- MBD-04(S)/2014-15

IN CONTIUATION TO AGREEMENT NO.- MBD-04/2014-15

REVISED BOQ COST :- Rs. 93,60,603.00

ORIGINAL BOQ COST:- Rs. 78,99,465.00

ACCEPTED RATE :- 10.00% Below of BOQ Rate

ORIGINAL AGREEMENT VALUE:- Rs. 71,09,519.00

TOTAL AGREEMENT VALUE :- Rs. 84,24,543.00

SUPPLEMENTARY AGREEMENT VALUE :- Rs. 13,15,024.00

Sunita Pritam

12/10

Executive Engineer  
R.W.D. Work Division  
Biharsharif

एक हजार रुपये

ONE THOUSAND RUPEES

रु.1000

Rs.1000



9888 नं! 8/4 अमर 90001 सुनीता प्रिताम पति सुनील कुमार  
र BIHAR 22, शाका निहार शरीफ AM 419009  
साकेत जयेश्वर टाट भैसासुर  
जिला गानगा 5 नंका जामा एसीए (नाक विकिता सा.व.41)

**Agreement**

This agreement made the 25 day of 02 **DEC** 2021

Between Executive Engineer, Rural Works Department, Works Division, Bihar Sharif under Non Plan M/R-3054 for BRRDA 5<sup>th</sup> Floor Vishweshwaraiya Bhawan, Jawaharlal Nehru Marg, Patna.- 15 (Name and address of Employer)

(hereinafter called "the Employer") of part, and

**SUNITA PRITAM,  
DHANESHWARGHAT, BHAISASUR  
BIHARSHARIF, NALANDA**

Whereas the Employer is desirous that the Contractor execute of the M/R to Road From SH-78 to Alipur including five year maintenance under Head M/R-3054. [Name and identification number of Contract] (here in after called "the works") and the Employer has accepted the Bid by the Contractor for the execution and completion of such Works and the remedying of any defects there in at a cost of Rupees 13,15,024.00 (Thirteen Lakh Fifteen Thousand & Twenty Four) only i.e on 10.00% (Ten Point Zero, Zero Percent) below of Estimated Rate.

*[Signature]*  
**Executive Engineer**  
12/10/22

**Sr. Treasury Officer**  
Nalanda

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expressions shall have the same meaning as are respectively assigned to them in conditions of contract hereinafter referred to, and they shall be deemed to form and read and construed as part of this Agreement.
2. In consideration of the payments to be made by the employer to the contractor as hereinafter mentioned, the contractor hereby covenants with the employer to execute and complete the works and remedy any defects therein in conform in all aspects with the provisions of the contract.
3. The employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and read and construed as part of this Agreement, Viz:
  - (i) Letter of Acceptance:
  - (ii) Notice to proceed with the works:
  - (iii) Contractor's Bid:
  - (iv) Contract Data:
  - (v) Special Conditions of contract and general conditions of contract:
  - (vi) Specifications:
  - (vii) Drawings:
  - (viii) Bill of Quantities and
  - (ix) Any other document listed in the contract data as forming part of the contract.All others clause of contract and terms and condition stipulated in original agreement no MBD-04/2014-15 will be admissible and applicable in this agreement.

The Common Seal of \_\_\_\_\_

Was here un to affixed in the presence of :

Signed, Sealed and Delivered by the said \_\_\_\_\_

In the presence of : \_\_\_\_\_

Binding Signature of Employee \_\_\_\_\_

Binding Signature of Contractor \_\_\_\_\_

Semita Panjam

  
12/10

  
12/11/22  
Executive Engineer  
R.W.D. Work Division  
Biharsharif  
12/11/22

अधीक्षण अभियंता का कार्यालय,  
ग्रामीण कार्य विभाग, कार्य अंचल, नालन्दा।

पत्रांक- 320-अनु०  
प्रेषक,

/नालन्दा, दिनांक- 08/4/22

अधीक्षण अभियंता  
ग्रामीण कार्य विभाग  
कार्य अंचल, नालन्दा।

सेवामें,

कार्यपालक अभियंता,  
ग्रा०का०वि०, कार्य प्रमंडल, विहारशरीफ।

विषय:- शीर्ष 3054 (मरम्मत) विहार ग्रामीण पथ अनुरक्षण नीति-2018 अंतर्गत स्वीकृत कुल 01 (एक) अदद पथ के निर्माण/मरम्मत कार्य के पुनरीक्षित परिमाण विपत्र अनुमोदन के संबंध में।

प्रसंग:- आपका पत्रांक-120 अनु०, दिनांक-29.01.2022

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र द्वारा प्राप्त कुल 01 (एक) अदद पथ का पुनरीक्षित परिमाण विपत्र अनुमोदन कर वापस की जाती है। सभी पृष्ठ अनुमोदित है। पुनरीक्षित एकरारनामा का दर मूल एकरारनामा के दर के समान होगा। अपने स्तर से भी अनुमोदित पुनरीक्षित परिमाण विपत्र की जांच कर ली जाय। त्रुटि दृष्टिगोचर होने पर इसका समाधान के पश्चात् ही पुरक एकरारनामा किया जाय।

क्रमांक	योजना का नाम	पुनरीक्षित परिमाण विपत्र की राशि (रुपया में)	प्रशासनिक अनुमोदन की राशि (निर्माण, अनुरक्षण, एवं आकस्मिक कार्य) (लाख में)	पुनरीक्षित तकनीकी स्वीकृति की राशि (निर्माण एवं, अनुरक्षण, कार्य) (लाख में)
1.	SH-78 to Alipur	Rs. 93,60,603.00	78.26771	93.598

अनु०-यथोक्त। (एक प्रति में)

विश्वासभाजन

अधीक्षण अभियंता

ग्रामीण कार्य विभाग, कार्य अंचल, नालन्दा

12/10/22

12/10

Executive Engineer  
R.W.D. Work Division,  
Biharsharif

12/10/22

Sumita Prasad

(Ministry of Rural Work Department, Govt. of Bihar)  
MR(3054)

Revised Bill of Quantities Including Restoration Work

S.No.	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction	0.80	Het	35807.53	28646.02
3	Box Cutting Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	260.00	Cum	204.82	53253.20
6	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m & 100 m as per Technical Specification Clause 301.5. (Including Royalty & Labour Cess).				
7	For 100 m lead	7350.38	Cum	166.29	122294.69
11	Granular Sub-base with Well Graded Material-Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	639.83	Cum	1985.71	1270516.83
12	WBM Grading 2-Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical	362.65	Cum	3304.36	1198326.15
13	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical	491.03	Cum	3203.02	1572778.91
14	Prime Coat Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	6547.07	Sqm	55.80	365326.32
45	Tack Coat-Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.3 kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503.	9553.00	Sqm	17.90	170998.70

Semita Paitam

*(Signature)*  
12/10

**Executive Engineer**  
**R.W.D. Work Division**  
**Biharsharif**

*(Signature)*  
29/11/22

15/7/22 70,000/-

S.No.	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
17	Premix Carpet -Providing, laying and rolling of Close-graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100, kN static roller capacity, finished to required level and grades to be followed by	9553.00	Sqm	189.69	1812108.57
18	Seal Coat- Type B-Providing , laying seal coat sealing the voids in a bituminous surface laid to the specified levels ,grades and cross fall using Type B as per the specification in clause 510 ( With Bituminous Binder S-90 )	9553.00	Sqm	54.34	519110.02
23	Kilometre-stone Reinforced cement concrete M15 grade kilometre local stone of standard design asper IRC:8 fixing in position including painting and printing , etc as per drawing and technical specification clause 1703.				
24	i) 5th km stone				
25	ii) Km stone	1.00	Nos	3667.35	3667.35
	iii) 200 m stone	2.00	Nos	2195.12	4390.24
		6.00	Nos	607.92	3647.52
	Providing and Fixing 'Logo' of MMGSY Project - Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate	1.00	Nos	4889.83	4889.83
	Painting Two Coats dashes, lines, Arrows etc. on Road in Two Coats on New Work	320.00	Nos	90.24	28876.80
26	Total (A)				8258831.16
27	Maintenance For 1st Year	1.000	Year	59,818.57	59818.57
28	For 2nd Year	1.000	Year	98,899.97	98899.97
29	For 3rd Year	1.000	Year	2,46,076.67	246076.67
30	For 4th Year	1.000	Year	3,13,879.95	313879.95
31	For 5th Year	1.000	Year	3,83,096.24	383096.24
32	Total (B)				1101771.40
33	Grand Total (A+B)				9360602.56
Say Rs (in Lakh)					9360603.00

29/1/22  
me

29/1/22

12/10

Gurinder Pratam

Executive Engineer  
R.W.D. Work Division  
Bijarnsharif

अधोक्षण अभियन्ता  
ग्रामीण कार्य विभाग  
झारखंड अंचल (जालन्दा)

29/1/22  
EO

Bill of Quantity Approved as corrected for Item No.

① to ② for Rs. 936063.00 (Rupees. ~~100000~~  
less extra trees and site for 100000 only)

Including Five Years Maintenance.

~~6/11/22~~  
अधोक्षण अभियन्ता  
ग्रामीण कार्य विभाग  
कार्य अंचल (नालन्दा)  
8/7/22  
ED

  
12/10

Sumita Prasad

  
12/10/22  
Executive Engineer  
R.W.D. Work Division  
Bihar Sharif  
108/22



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

11

**MBD AGREEMENT**

**HEAD 3054 M/R TO ROAD**



**UNDER**

**RWD WORKS DIVISION BIHARSHARIF**

Smt. SUNITA PRITAM.

**PROJECT NAME :- M/R TO ROAD FROM SH-78 TO ALIPUR**  
**Inc. 5Yr. MAINTANANCE.**

**BLOCK :-**

**BIND**

AGREEMENT No.

:-

MBD- ...04.../2014-15

ACCEPTED RATE

:-

10.0% Below of BOQ Rate.

AGREEMENT Value

:-

Rs. 71,09,519.00

WORK STARTED DATE

:-

20.03.2015

INTENDED DATE OF COMPLETION:-

Six Months

Smt. Pritam

25/5/15  
Executive Engineer  
RWD (W) Division  
Biharsharif

binarsharif