

1 8

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

INDIA

बिहार BIHAR

AE 807950

जिला कोषागार, पूर्वी चम्पारण, मोतिहारी

Agreement

अरुण कुमार श्रीवास्तव
गुप्तक विक्रेता
मोतिहारी
रजि. नं०-133/88-89

07 FEB 2020

Agreement No :- MBD/---MR/-01 of 2019-20

बिहार कोषागार प्रशासिका
पूर्वी चम्पारण, मोतिहारी

Name of work :- MR-N/19-20 Sheohar/-01
T. Id - 81586
AP:-

Name of Agency :- Parmar Enterprises.
Chhoti Buzurgpur, Motihari.

Date of Start :- 27.04.2020
Date of Completion :- 26.04.2021
SD :- 1286100

A.P.G :- 21,300

Total :- 1307400 (एक लाख तीस हजार चार सौ रुपये)

This Agreement, made on the 27 April Day of 2020 between Executive Engineer, Rural works Department, Works Division, Sheohar of the one part and Parmar Enterprises. Whereas the Employer is desirous that the Contractor execute the work under MR/- Construction & CD Work of MR-N/19-20 Sheohar 01 and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein at a cost of Rupees 2572195.4=

Parmar Enterprises
मोतिहारी

अरुण कुमार श्रीवास्तव
गुप्तक विक्रेता
मोतिहारी

NOW THIS AGREEMENT WITNESSETH as follows.

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of Contract hereinafter referred to and they shall be deemed to form and be read and construed a part of this agreement .
2. In consideration of the payment to be made by the employer to the Contractor as herein after mentioned, the Contractor hereby covenants with employer to execute and complete the work and remedy any defects therein conformity in all aspects with the provision of the Contractor.
3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following document shall be deemed to form and be read and construed as part of this Agreement viz.
 - (i) Letter of Acceptance
 - (ii) Notice to proceed with the works
 - (iii) Contractor's Bid
 - (iv) Contract Data
 - (V) Special conditions of contract and general conditions of contract.
 - (Vi) Additional condition
 - (Vii) Drawings
 - (Viii) Bill of Quantities and
 - (ix) Any other document listed in the contract data as forming part of the contract.

In witness , where of the parties there to have caused this Agreement to be executed the day and year first before written.

The Common seal of

Was hereunto affixed in the presence of

Signed, Sealed and Delivered by the said

In the presence of

Binding Signature of Employer

Binding Signature of Contractor

Parmer Enterprises

सत्य रिंग
Proprietor


EXECUTIVE ENGINEER
RWD, WD
SHEDWAR
27/4/2020

Agreement

1. Name of work :- MR-N/19-20 Sheohar-01
2. Agreement No. :- MBD/ MR / 01 of 2019-20
3. Name of Agency :- Parmar Enterprises
Chhotu Brijraj pur, Motilal
4. Construction Cost :- 17022059 = 169,65,886 =
5. Maintenance Cost :- 8755968 = 0 =
- Total :- 25721854 =
6. Security Deposit :- SD :- 12,86,100 =
21,30,000 =
A.P.G :- 1347864 = 0 =
7. Work allotted rate :- 0.33 % Below of S.R.
8. The Employer shall retain S.D. of 5 % (Five percent) and performance security of 3% (Three percent) of the amount from each payment due to the contractor until completion of the whole of the construction work.
9. Date of written order to commence :- One year from Date - 27.4.2020
10. Time required for the work from date of written order to ONE YEAR.
Commence :- _____
11. Total No. items:- _____

Note- SBD Rules Terms and Conditions will be applicable

Parmar Enterprises

सुधा सिंह
Proprietor

Contractor

Executive Engineer
R.W.D. Works Division
Sheohar.

- 17 Hiranya to Hiranta-
- 11) Gangedhampur to Laksuka
- 11) Sunhanti to Mchadava Gadh.

27.4.20
EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
SHEOHAR

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT
WORKS DIVISION-SHEOHAR

Letter No. 338/

Dated 27.4.2020

Issue of notice to proceed with work.

To,

Parmar Enterprises:
Chhat Brijpur,
Mothari

Subject :- Issue of notice to proceed with work. MR-N-19-20 Sheohar - 01

Sir,

Pursuant to your furnishing the requisite performance security as stipulated in ITB Clause 30 and signing of the contract for the construction of MR-N-19/20 Sheohar - 01 And routine maintenance for five years after completion of construction, you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours Faithfully


Executive Engineer
Rural Works Department
Works Division, Sheohar.

Parmar Enterprises

सुधा सिंह
Proprietor


Executive Engineer
RWD, WD
SHEOHAR
A.P.
27/4/2020

मुख्य अभियंता 3, पटना का कार्यालय,
ग्रामीण कार्य विभाग, बिहार, पटना।

/पटना, दिनांक-12-2-2020

पत्रांक- II/मु0अ0-3 प0पु0 1-1849/19

1260315

प्रेषक,

मुख्य अभियंता-3,
ग्रामीण कार्य विभाग,
बिहार, पटना।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, शिवहर।

विशय : शीर्ष 3054 एम0आर0 योजना अन्तर्गत कार्य प्रमंडल, शिवहर के अधीन **MR-N/19-20 Sheohar/-01**
(Tender-ID-81586) के निविदा निष्पादन के संबंध में।

महाशय,

शीर्ष 3054 एम0आर0 योजना अन्तर्गत कार्य प्रमंडल, शिवहर के अधीन **MR-N/19-20 Sheohar/-01**
(Tender-ID-81586) पथ निर्माण कार्य के निविदा के वित्तीय बीड में सफल निविदाकार Parmar Enterprises
(377757) को उनके द्वारा उद्धृत दर जो कि परिमाण विपत्र की दर से 0.33 प्रतिशत कम है, अर्थात् कुल राशि
2,57,21,854.00 (दो करोड़ सनतावन लाख इक्कीस हजार आठ सौ चौबन) रु0 मात्र पर कार्यहित एवं आपकी अनुशंसा
के आलोक में यह कार्य आवंटित किया जाता है।

2. निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधार नहीं होगा।
3. कार्यपालक अभियंता, कार्य प्रमंडल, शिवहर संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ
अग्रधन के रूप जमा किये गये संबंधित एन0एस0सी0/पासबुक/ बैंक फिक्स डिपोजिट/ बैंक गारंटी की सत्यता एवं वैधता
आदि का सत्यापन कराकर प्रमंडलीय कार्यालय में अभिलेखित करेंगे एवं कार्यादेश निर्गत करने के पूर्व अग्रधन की राशि के
सत्यापन से संबंधित कागजात अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।

4. एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी बांछित कागजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति निश्चित
रूप से प्राप्त कर लिया जाय एवं साथ में इसकी भी जांच कर ली जाय कि संवेदक डीयार सूची से मुक्त है।

5. कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य कराते समय अगर
इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।

6. इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावैधिक स्वीकृति तथा
निविदा आमंत्रण सूचना में उल्लिखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ
एकरारनामा किया जायेगा।

7. अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जांच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की
स्थिति में दस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करवेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की
जायेगी।

8. एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जांच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित
करेंगे कि इसमें कोई त्रुटि न हो।

9. कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये
उपबंध से पूरी तरह आश्वस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावैधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये
निर्देश का अनुपालन सुनिश्चित करायेंगे।

10. कार्यादेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु विस्तृत मदवार
कार्य प्रोग्राम प्राप्त कर ही एकरारनामा किया जाय।

11. अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुरूप निर्धारित
कार्य अवधि के अंदर पूरा की जाय।

12. कार्य समाप्ति की अवधि परिमाण विपत्र के अनुसार होगी।

13. कार्यपालक अभियंता कार्य आवंटित किये गये संवेदक से 10 दिनों के अन्दर एकरारनामा कसमें-निश्चय करेंगे
अन्यथा उनके अग्रधारणीय शर्तों का पालन नहीं किया जाय।

Attachment letter 20198

सुधा सिंह
Proprietor

12/2/20
EXECUTIVE ENGINEER
RWD, WO
SHEOHAR

14. इस कार्य का व्यय विभाग द्वारा निर्गत प्रशासनिक स्वीकृति में अंकित शीर्ष अन्तर्गत होगा।

15. एकरारनामा के समय प्राक्कलन के अनुसार इस कार्य को पूरा करने हेतु संवेदक से मदवार कार्य योजना एकरारनामा के समय प्राप्त किया जाय तथा उस कार्य योजना की प्रति संबंधित कनीय अभियंता एवं सहायक अभियंता को भी उपलब्ध कराया जाय, ताकि कनीय अभियंता एवं सहायक अभियंता निर्धारित समय के साथ मदवार प्रगति का आकलन कर कार्यपालक अभियंता एवं संबंधित संवेदक को सूचित प्रत्येक 15 दिनों पर करेंगे। अगर संवेदक द्वारा निर्धारित समय के अन्दर उक्त मद के मात्रा का लक्ष्य प्राप्त नहीं किया गया तो कार्यपालक अभियंता दंडात्मक कार्रवाई संवेदक के विरुद्ध करेंगे। कार्यपालक अभियंता अगर उक्त निदेश का पालन नहीं करते हैं तो वे स्वयं कार्रवाई के पात्र होंगे।

16. सभी निविदा कागजात एवं तुलनात्मक विवरणी यंत्र मूल प्रति आवश्यक कार्रवाई हेतु लौटाई जाती है। आप निविदा कागजातों एवं तुलनात्मक विवरणी के जांचोपरांत आप आवश्यक निदेशों को अपने स्तर से निर्गत करेंगे।

17. एकरारनामा से पहले निविदाताओं द्वारा दिये गये कागजात का सत्यापन उनके मूल कागजात से मिलान कर ली जाय।

18. इस निविदा की राशि में अगर कोई अंतर होता है तो इसकी सूचना तुरन्त इस कार्यालय को दी जाय।

19. कार्यपालक अभियंता, एकरारनामा करने के पूर्व संवेदक का निबंधन संख्या पूर्ण पता एवं दूरभाष संख्या कार्यदेश में अंकित करेंगे तथा इस कार्यालय को सूचित करेंगे।

20. परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा निदेश के आलोक में अतिरिक्त वांछित परफॉरमेंस सिक्यूरिटी की राशि जमा कराना सुनिश्चित करेंगे।

21. किसी भी परिस्थिति में निजी जमीन पर निर्माण नहीं कराया जाय।

22. प्रत्येक 15 दिनों पर संवेदक से स्वहस्ताक्षरित विपत्र प्राप्त कर स्थल से मिलान कर मापी पुस्तिका में मापी दर्ज कर भुगतान सुनिश्चित करेंगे।

23. संवेदक से बीड वैधता का प्रमाण लेने के पश्चात ही एकरारनामा करना सुनिश्चित करें।

24. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, शिवहर को निदेशित किया जाता है कि विभागीय पत्रांक-मु0अ0-4-(मु0) विविध-23-291/2014-131 पटना दिनांक-13.12.2019 के आलोक में पत्र प्राप्ति के 24 घंटा के भीतर Letter of Acceptance (LOA) संबंधित संवेदक को निर्गत कर इसकी सूचना इस कार्यालय को भी उपलब्ध कराना सुनिश्चित करेंगे।

कृपया पत्र प्राप्ति की सूचना देंगे।

अनु0-यथा उपर्युक्त।

ज्ञापांक- मु0अ0-3, 1260
प्रतिलिपि: अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना को सूचनार्थ समर्पित।

ज्ञापांक- मु0अ0-3, 1260
प्रतिलिपि: अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, सीतामढ़ी को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

ज्ञापांक- मु0अ0-3, 1260
प्रतिलिपि: सहायक आई0टी0 मैनेजर, मुख्य अभियंता-3 का कार्यालय, ग्रामीण कार्य विभाग, बिहार पटना को सूचनार्थ एवं ई-मेल पर अपलोड करने हेतु प्रेषित।

विश्वासभाजन

मुख्य अभियंता-3, पटना
/पटना, दिनांक-12-2-2020

मुख्य अभियंता-3, पटना

/पटना, दिनांक-12-2-2020


मुख्य अभियंता-3, पटना

/पटना, दिनांक-12-2-2020

मुख्य अभियंता-3, पटना

Parmar Enterprises

Proprietor

20	Road Marking with Hot Applied Thermoplastic :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	292.04	Sqm	735.49	214736.80	INR Two Lakh Fourteen Thousand Seven Hundred & Thirty Six and Paise Eighty Only
21	Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical MMGSY Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.00	nos	9578.22	19156.44	INR Nineteen Thousand One Hundred & Fifty Six and Paise Forty Four Only
22	Brick Masonry in C.M.(1:3) in parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1203.4	2.88	Cum	5206.93	15168.76	INR Fifteen Thousand One Hundred & Sixty Eight and Paise Seventy Six Only
23	Plastering with cement mortar (1:4) :- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	20.16	Sqm	183.89	3808.02	INR Three Thousand Eight Hundred & Eight and Paise Two Only
24	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	68.56	Sqm	95.63	5500.09	INR Five Thousand Six Hundred and Paise Nine Only
25	1% Labour	1.00	RS	28401.22	28401.22	INR Twenty Eight Thousand Four Hundred & One and Paise Twenty Two Only
26	12% GST	1.00	RS	340814.67	340814.67	INR Three Lakh Forty Thousand Eight Hundred & Fourteen and Paise Sixty Seven
27	Maintenance	20.00	HAU TEL	58096.20	1173924.00	INR Eleven Lakh Seventy Three Thousand Nine Hundred & Twenty Four
28	1% Labour	1.00	RS	11739.24	11739.24	INR Eleven Thousand Seven Hundred & Thirty Nine and Paise Twenty Four Only
29	12% GST	1.00	RS	140870.88	140870.88	INR One Lakh Forty Thousand Eight Hundred & Seventy and Paise Eighty Eight
30	Sumhau To Mahadeva bandh	Parmar Enterprises  Proprietor				
31	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of EI	0.45	ha	49156.70	22273.52	INR Twenty Two Thousand Two Hundred & Seventy Three and Paise Fifty Two Only
32	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	949.20	Cum	176.75	167771.10	INR One Lakh Sixty Seven Thousand and Paise Seventy One

33	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	75.36	Cum	2487.37	167448.20	INR One Lakh Eighty Seven Thousand Four Hundred & Forty Eight and Paise Twenty Only
34	WBM Grading 2 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	59.93	Cum	4603.09	275063.18	INR Two Lakh Seventy Five Thousand Eight Hundred & Sixty Three and Paise Eighteen Only
35	WBM Grading 3 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	183.58	Cum	4218.55	774461.50	INR Seven Lakh Seventy Four Thousand Four Hundred & Sixty One and Paise Sixty Only
36	Prime Coat (Low porosity) :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	2447.73	Sqm	41.20	100845.48	INR One Lakh Eight Hundred & Forty Six and Paise Forty Eight Only
37	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.36 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrilac broom as per technical specification clause 503.	2447.73	Sqm	13.97	34194.79	INR Thirty Four Thousand One Hundred & Ninety Four and Paise Seventy Nine Only
38	Patch work over WBM using Mix seal surface With Waste Plastic for bituminous and Existing CC Pavement :- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509. With waste plastic	2447.73	Sqm	218.15	533972.30	INR Five Lakh Thirty Three Thousand Nine Hundred & Seventy Two and Paise Thirty Only
39	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.36 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrilac broom as per technical specification clause 503.	8475.00	Sqm	11.72	99327.00	INR Ninety Nine Thousand Three Hundred & Twenty Seven Only
40	Semi-Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	211.88	Cum	10965.44	2323357.43	INR Twenty Three Lakh Twenty Three Thousand Three Hundred & Fifty Seven and Paise Forty Three Only
41	Kilometre stone :- Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. i) km Stone	3.00	nos	2531.72	7595.16	INR Seven Thousand Five Hundred & Ninety Five and Paise One Only

Parmer Enterprises

Proprietor

2	100 m Stone	9.00	nos	671.66	6044.94	INR Six Thousand & Forty Four and Paise Ninety Four Only
43	Direction and Place Identification signs with size more than 0.9 sqm size board :- Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	1.92	Sqm	12506.11	24011.73	INR Twenty Four Thousand & Eleven and Paise Seventy Three Only
44	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 i) 600 mm equilateral & triangle	10.00	nos	3770.33	37703.30	INR Thirty Seven Thousand Seven Hundred & Three and Paise Thirty Only
45	600 mm circular	8.00	nos	3869.68	30957.44	INR Thirty Thousand Nine Hundred & Fifty Seven and Paise Forty Four Only
46	600 mm x 450 mm rectangular	10.00	nos	3746.56	37465.60	INR Thirty Seven Thousand Four Hundred & Five and Paise Sixty Only
47	Boundary Pillar/Guard Post :- Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	108.00	nos	523.63	56552.04	INR Fifty Six Thousand Five Hundred & Fifty Two and Paise Four Only
48	Planting of Trees and their Maintenance for one Year :- Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	113.00	Each	800.30	90433.90	INR Ninety Thousand Four Hundred & Thirty Three and Paise Ninety Only
49	Road Marking with Hot Applied Thermoplastic :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	452.00	Sqm	735.40	332400.80	INR Three Lakh Thirty Two Thousand Four Hundred and Paise Eighty Only
50	Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical MMGSY informative sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tube posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.00	nos	9568.98	19137.96	INR Nineteen Thousand One Hundred & Thirty Seven and Paise Ninety Six Only
51	Brick Masonry in C.M.(1:3) in parapet :- Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	25.92	Cum	5266.93	136518.83	INR One Lakh Six Thousand Five Hundred & Eighteen and Paise Eighty Three Only

52	Plastering with cement mortar (1:4) :- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	181.44	Sqm	188.15	34137.94	INR Thirty Four Thousand One Hundred & Thirty Seven and Paise Ninety Four Only
53	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	527.04	Sqm	95.63	55400.84	INR Fifty Thousand Four Hundred and Paise Eighty Four Only
54	1% Labdur	1.00	RS	53828.16	53828.16	INR Fifty Three Thousand Eight Hundred & Twenty Eight and Paise
55	12% GST	1.00	RS	645937.93	645937.93	INR Six Lakh Forty Five Thousand Nine Hundred & Thirty Seven and Paise Ninety Three
56	Maintainance	20.00	QUARTEL	95172.65	1903453.00	INR Nineteen Lakh Three Thousand Four Hundred & Fifty Three Only
57	1% Labour	1.00	RS	19034.53	19034.53	INR Nineteen Thousand & Thirty Four and Paise Fifty Three Only
58	12% GST	1.00	RS	228414.35	228414.35	INR Two Lakh Twenty Eight Thousand Four Hundred & Fourteen and Paise Thirty Six
59	Gangadharamper To Lohsurka Road					
60	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of Eit	0.74	ha	49496.70	36627.56	INR Thirty Six Thousand Six Hundred & Twenty Seven and Paise Fifty Six Only
61	Construction of subgrade and earthen shoulders :-Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1554.00	Cum	176.75	274659.50	INR Two Lakh Seventy Four Thousand Six Hundred & Sixty Nine and Paise Fifty Only
62	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	205.43	Cum	2467.13	506822.52	INR Five Lakh Six Thousand Eight Hundred & Twenty Two and Paise Fifty Two Only
63	WBM Grading 2 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	157.40	Cum	4559.90	717728.26	INR Seven Lakh Seventeen Thousand Seven Hundred & Twenty Eight and Paise Twenty Six Only
64	WBM Grading 3 (By Mechanical Means) :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	254.78	Cum	4180.54	1065117.58	INR Ten Lakh Six Thousand Five Hundred & Seventy Eight and Paise Eight Only