

INTEGRATED ACTION PLAN

AGREEMENT NO. : RWD,Dehri/0.2...MMGSY/SBD/2022-23 Dated:- 25.4.22 (Supplement)

NAME OF WORK : Dehri Tilauthu (Patanwa Polytechnic Collage More) to Shankarpur

NAME OF CONT. : Rakesh Chaubey, 89, Jakki Bigha, Canal Road, Dehri on Sone, Rohtas 821307


ESTIMATED COST:- 1,78,67,123/- (One Crore Seventy eight Lac Sixty Seven thousand one hundred Twenty three) only

AGREEMENT AMOUNT : Rs. 1,60,80,411/- (Rs. One Crore Sixty Lac Eighty Thousand Four Hundred Eleven) only.

DATE OF WORK START : 25.4.2022.

TIME OF COMPLETION : MONTH 03 (Three) Months i.e. 24.7.22

RATE QUOTED : 00.00% Below 10% (Ten Percent) below.



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

Certified

Rakesh Chaubey

25.04.22
Executive Engineer

R. W. D. (W) Divn. Dehri

25/4/22

25/04/22


भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000



BIHAR

13/03

डेनक 283 माय
विवेश चौक डी रि आन सोन

AM 865560

AGREEMENT FORM

Agreement No :- RWD,Dehri/.....MMGSY/SBD/2022-23 Dated:-.....

This Agreement, made the.....Day of.....2021 between Executive Engineer, RWD(W) Division, Dehri on behalf of BRRDA, Bihar, Patna (hereinafter called "The Employer") of the one part and Rakesh Chaubey, 89, Jakki Bigha, Canal Road, Dehri on Sone, Rohtas 821307 hereinafter called "The Contractor" of the other part.

Whereas the Employer is desirous that the contractor execute Output and performance based Rural Road Contract for the Construction & Five Year Maintenance of Road Dehri Tilauthu (Patanwa Polytechnic Collage More) to Shankarpur Under MMGSY (SC) hereinafter called "The Works" & the Employer has accepted the Bid by the Contractor for the execution & completion of such works & the remedying of any defects. there in a cost of Rs. 1,60,80,411/- (Rs. One Crore Sixty Lac Eighty Thousand Four Hundred Eleven) only. *Date of start 25.4.22 and Comp:- 24.7.22*


NOW THIS AGREEMENT WITNESSETH and the Parties hereto agree as follows:

1. In this Agreement, words and expressions shall have the same meaning as are respectively assigned to them in the conditions of Contract hereinafter to and they shall be deemed to form and be read and construed as part of the Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein conformity in all aspects with the provisions of the Contract.

Rakesh chaubey

3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the works and the remedying the defects wherein the Contract price or such other sum as may become payable under provisions of the contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz.
- (i) Letter of Acceptance
 - (ii) Contractor's Bid
 - (iii) Section VI – General Conditions
 - (iv) Section VII- Particular Conditions.
 - (v) Section V- Technical Specification (General and Supplementary Technical Specification)
 - (vi) Appendix A - Drawings
 - (vii) Section IV- Work Schedule
 - (viii) Quality Plan for Output and performance Based Road Contract as per Clause A14.1 of the Technical Specifications.
 - (ix) Appendices to the Contract
 - (x) Addenda issued during bid period.

In Witness where of the parties there to have caused this Agreement to be executed the day and year first before written.


Signature of the Contractor
Address:-

Executive Engineer,
R.W.D(W) Division, Dehri
On behalf of BRRDA,
Bihar, Patna.

Witness

Witness

1.Name:.....
Address:.....
.....
.....

2.Name.....
Address:.....
.....
.....

MEMORANDUM

Agreement No.RWD,Dehri/.....MMGSY/SBD/ 2021-22 Dated:.....

1. Name of Work:- Dehri Tilauthu (Patanwa Polytechnic Collage More) to Shankarpur
2. Name and Address of the Contractor:- Rakesh Chaubey, 89, Jakki Bigha, Canal Road, Dehri on Sone, Rohtas 821307
3. Rate Approved by:- SE-, RWD Circle Sasaram vide his letter No:- 189 Dated:-08.03.2022
4. Agreement Value:- Rs. 1,60,80,411/- Lac. (10%)
5. Approved rate:- ~~00.00%~~ Below of B.O.Q. Ten Percent below
6. Earnest Money:- Rs.
7. Additional Earnest Money To be deposited at time Of Agreement :- Rs.
8. Amount to be deducted From gross amount Of the Bill :- @ 8%
9. Time required for the work From the date of written order of commence :- Month.
10. Date of written order of commence:-
11. Date of Completion :-
12. Total No.of Items of work Tendred for :-

Rakesh Chaubey

Executive Engineer,
R.W.D.Works Division,
Dehri.

**अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल सासाराम (रोहतास)**

पत्रांक...199/2021/ सासाराम, दिनांक...08/08/2022

प्रेषक,
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल सासाराम (रोहतास)

सेवा में,
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल डिहरी।

विषय:- शीर्ष "MMGSY (SC)" योजनान्तर्गत पुनरीक्षित परिमाण विपत्र (BOQ) स्वीकृति के उपरांत वापस करने के सम्बंध में।

प्रसंग:- आपका पत्रांक 1039 अनु0, दिनांक-26.11.2021

महाशय,
उपर्युक्त विषयक प्रासंगिक पत्र के आलोक में शीर्ष "MMGSY (SC)" योजनान्तर्गत पुनरीक्षित BOQ (परिमाण विपत्र) अनुमोदनोपरांत अग्रतर कार्रवाई हेतु वापस किया जाता है जिनकी सूची निम्न प्रकार है-

क्र0स0	प्रखण्ड	पथ का नाम	लम्बाई (कि०मी० में)	BOQ (परिमाण विपत्र) की राशि
1	Dehri	Dehri Tilauthu (Patanwa Polytechnic Collage more) to Shankarpur.	3.510	1,78,67,123.00

अनु0:- परिमाण विपत्र एक एक प्रति में।

विश्वासभाजन

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल सासाराम

Rakesh Choudhary

MMGSY-SC

REVISED BQQ

Name of Road : Dehri Tilauthu (Patanwa Polytechnic college more) To Shankarpur

Block : Dehri

Length : 3.51 km

Sl. No.	Description of Items	Unit	Quantity	Rate	Amount
1	2	3	4	5	6
1 7	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess).	Cum	1052.16	176.47	185674.68
2 9	WBM Grading 2 :-Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405.	Cum	717.19	4576.78	3282420.85
3 10	WBM Grading 3 :-Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	717.19	3546.61	2543593.23
4 12	Tack Coat:- Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	Sqm	9562.50	14.31	136839.38
5 14	BM :- Providing and laying bituminous macadam with 100-120 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction.	Cum	478.13	11290.47	5398312.42

M.M.
E.E.

W.P.
8/3/22

Rakesh Chakraborty

Sl. No.	Description of Items	Unit	Quantity	Rate	Amount
1	2	3	4	5	6
6	SDBC :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	Cum	239.06	13634.52	3259468.35
7	Cement Concrete Pavement M30 Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501.	Cum	154.53	6279.80	970417.49
				Total	15776726.39
				12 % GST	1893207.17
				1 % LC	157767.26
	TOTAL CONSTRUCTION COST (A)				17827700.82
8	1st Year Maintenance cost	Year	1.00	2326.00	2326.00
9	2nd Year Maintenance cost	Year	1.00	4651.00	4651.00
10	3rd Year Maintenance cost	Year	1.00	6977.00	6977.00
11	4th Year Maintenance cost	Year	1.00	9304.00	9304.00
12	5th Year Maintenance cost	Year	1.00	11629.00	11629.00
				Total	34887.00
				12 % GST	4186.44
				1 % LC	348.87
	Total Maintenance Cost (B)				39422.31
	Grand Total Cost (A+B) =				17867123.13

Revised B.O.C. approved for Rs. 1,78,67,123.13 (Rupees One crore, seventy eight lacs sixty seven thousand one hundred twenty three) only from S.No. 1 to 12

Rakesh Chakraborty

26.11.21
E.E.