

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये
रु.1000



ONE THOUSAND RUPEES
Rs.1000

2830 रिजक 16.10.23 पाइन ग्लोबल इन्फ्रा पटना बिहार BIHAR AT 905924
100001-10000

3 JUL 2023 FD ① 245004000008049 Rs. - 5,40,000/-
कोषागार पदाधिकारी ② 245004000006326 Rs. - 3,56,067/-
पुणे ③ 245004000005061 Rs. - 26363/-

Date of Start: - 01.11.23

Date of Completion: - 31.07.24 Below: - 10%

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 41/MBD/2023-24

This agreement, made the 01 November Day of 2023 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and Pine Global Infra Proprietor Amrita Singh, 2nd Floor Saahimalti Bhawan Road no. 2 Sanjay Gandhi Nagar Near Kali Mandir Road Hanuma Nagar, Kankarbag Patna, Pin- 800020.

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road Contract of the maintenance of road from MR-N/23-24/Lakhisarai/06 Package Under of Block in Lakhisarai, Under M/R in Lakhisarai District and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 1,13,05,604.00 (One Crore Thirteen Lakh Five Thousand Six Hundred Four) only & five year Maintenance cost Rs. 16,04,635.00 (Sixteen Lakh Four Thousand Six Hundred Thirty Five) only. Total Cost Rs. 1,29,10,239.00 (One Crore Twenty Nine Lakh Ten Thousand Two Hundred Thirty Nine) only.

Pine Global Infra

Amrita Singh
Proprietor

Groom
01/11/23

Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

01/11/23

SLN o.	Name of Road	Const. Cost	Maintenance cost	Agreement Value
1	Lakhisarai Pachna Path to Jok Maila Village	113.05604	16.04635	129.10239
Total		113.05604	16.04635	129.10239

NOW THIS AGREEMENT WITNESSTH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to and they shall be deemed to from and be read and construed as part of this agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the Execution adcompletion of the works and the remedying the defects hear in Contract price or such other sum as may become payable under the provision of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz
 - a. Latter of Acceptance
 - b. Contractor's Bid
 - c. Section VI -General Conditions
 - d. Section VII- Particular Condition
 - e. Section V - Technical Specification (General and Supplementary Technical Specification
 - f. Appendix A - Drawings
 - g. Section IV - Works Schedule
 - h. Quality plan for output and performance based road contract as per clause A14.1 of the technical specifications
 - i. Appendices of the contract
 - j. Addenda issued during bid period
 - k. Any other relevant documents listed in the particular conditions together with any post bid correspondence.

In witness whereof the parties thereto have caused this agreement to be executed the day and year first before written

The Common Seal of was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said

..... in the presence of:

.....
Sd/-
Signature of Employer

.....
Signature of Contractor

.....
Signature of Employer

.....
Signature of Contractor

.....
Signature of Executive Engineer

.....
Signature of Executive Engineer

OFFICE OF THE EXECUTIVE ENGINEER
RURALWORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:-41/MBD/2023-24

NAME OF WORK: - MR-N/23-24/Lakhisarai/06 Package Under of Block in
Lakhisarai, Under M/R in Lakhisarai District.

NAME OF AGENCY:-

Pine Global Infra Proprietor Amrita Singh,
2nd Floor Saahimalti Bhawan Road no. 2
Sanjay Gandhi Nagar Near Kali Mandir Road
Hanuma Nagar, Kankarbag Patna, Pin- 800020

Reference

:-

Chief Engineer-2,
R.W.D, Bihar, Patna
Vide Letter No. 3316 Date :-12.10.2023

AGREEMENT AMOUNT – Main work:- 1,13,05,604.00
Maintenance work:- 16,04,635.00
Total Amount: - 1,29,10,239.00

Performance Security: - Deposited @ 5 % & Next 5% deducted from Bill

Date of Completion :- 01 November 2023

Date of Agreement :- 31 July 2024

No. of Item of Work :- As per B.O.Q (Nos)

Rate Quoted :-10.00 % below (One zero Point zero zero percent below)

Contractor Signature

Pine Global Infra
Amrita Singh
Proprietor

[Signature]
01/11/23

[Signature]
Executive Engineer
Rural Works Division, Lakhisarai
Work, Div, Lakhisarai

01/11/23

139

Order Issuing Authority: Engg-in Chief RWD Patna

☒ YASDATE

Name of Work: Construction of Road & CD Works for Lakhisarai Pancha Path To Jok Malia Village

☒ PRINT

Khassara Block Under: MFT-3054

Contract No: Civil Works/

☒ FILE

Order No: Excess (+) %

SCHEDULE OF WORKS						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.32	Hect	75573.34	Rupees Seventy Five Thousand Five Hundred & Seventy Three and Paise Thirty Four Only	24183.00
2	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	259.00	Cum	103.96	Rupees One Hundred & Three and Paise Ninety Six Only	26926.00
3	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1224.00	Cum	262.74	Rupees Two Hundred & Sixty Two and Paise Seventy Four Only	321594.00
4	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with roller at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	484.00	Cum	2546.77	Rupees Two Thousand Five Hundred & Forty Six and Paise Seventy Seven Only	1232637.00
5	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	302.25	Cum	3220.73	Rupees Three Thousand Two Hundred & Twenty and Paise Seventy Three Only	973465.00
6	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	3030.00	Sqm	59.79	Rupees Fifty Nine and Paise Seventy Nine Only	181164.00
7	Patch work over WBM using Mix seal surface for bituminous and Existing CC Pavement :- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509.	3030.00	Sqm	277.18	Rupees Two Hundred & Seventy Seven and Paise Eighteen Only	839855.00

P/nc Glob... Infra

Signature of Tenderer with seal

Amesh Prasad

A32
Executive Engineer
Rural Work, Department
Work, Div. Lakhisarai

Tender Inviting Authority: Engg-In Chief RWD Patna

Name of Work: Construction of Road & CD Works for Lakhisarai Pachna Path To Jok Malla Village
Lakhisarai Block Under MR-3054

Contract No: Civil Works/

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
34	Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 per cent bitumen by weight	15.00	RM	55.61	Rupees Fifty Five and Paise Sixty One Only	834.00
35	Providing Weepholes in brick masonry, Plain / Reinforced concrete abutment, wing wall, Return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of TV: 20H towards drawing	40.00	No	191.77	Rupees One Hundred & Ninety One and Paise Seventy Seven Only	7671.00
Cost of Construction :-						10404178.00
Add 18% GST						1872752.04
Add 1% Labour Cess						104041.78
Seigniorage Fee						180810.76
Total Cost of Construction :-						12561782.58
36	Five Year Maintenance cost	20.000	Quarry	74624.80	Rupees Seventy Four Thousand Six Hundred & Twenty Four and Paise Eighty Only	1492496.00
Cost of Maintenance :-						1492496.00
Add 18% GST						268649.28
Add 1% Labour Cess						14924.96
Seigniorage Fee						6858.50
Total Cost of Maintenance :-						1782928.74
Total Cost of Project Including Five Year Maintenance :-						14344711.32
Rupees One Crore Forty Three Lakh Forty Four Thousand Seven Hundred & Eleven and Paise Thirty Two Only						

A82
Executive Engineer
RWD Works Division, Lakhisarai


Rakesh K.
95.7.23

Pino Glob... Infra
Ananta Singh
Programmer

Signature of Tenderer with seal

A82
Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

S. E. Letter No. 1070 Dt. 5/7/73
 Construction Cost Rs. 12561782.58
 5 yrs. Maintenance Cost Rs. 1782928.74
 Total Cost Rs. 14344711.32
 BOQ Approved For Rs. 14344700.00
 (Rupees one crore forty three lakh
forty four thousand seven hundred only)
 including 5 yrs Maintenance Vide
 item no. 01 to 36


 Superintending Engineer
 Rural Works Department
 Circle, Munger


Ausika Singh

Govt. of Bihar
Rural Works Department
Office of the Engineer-in-Chief, Rural Works Department, Bihar
BRIDA, 3rd Floor, Land Development Bank Building, Bodhi Marg, Patna, Bihar - 800001
(बिहार ग्रामीण पथ अनुरक्षण नीति, 2010)

Notice Inviting Tender for Rural Roads Maintenance based on Output and performance based Contract through e-procurement mode on Model Bidding Document (MBD).

(Notice Inviting Tender No. - MII-3054-08/2023-24)

- | | |
|---|--|
| 1. Designation and Address of the Advertiser | : Office of Engineer-in-Chief, Rural Works Department, Bihar, Patna |
| 2. Date of Issue of Notice Inviting Tender | : 17.05.2023 |
| 3. Period for downloading of Tender documents | : From 12.06.2023 (9:00) to 27.06.2023 up to 15:00 hrs. From website - http://pmuaytenderbids.gov.in |
| 4. Date, Time & Place of Pre- Bid Meeting | : Date 16.06.2023 (time 15:00 hrs.
Place O/o Concerned Superintending Engineer |
| 5. Last Date & Time for uploading tender Document by bidder | : Date 27.06.2023 up to: 15:00 hrs.
http://pmuaytenderbids.gov.in |
| 6. Date, time for online opening of Technical bid | : Date 27.06.2023 up to Time: 15:30 hrs. |
| 7. Last date, time and place for submission of Original instrument of EMD, Cost of BOQ, Bank credit facility certificate and an Affidavit regarding correctness of Information provided with bid document | : Till 15:00 hrs on 27.06.2023
: Place- O/o-concerned
(i) Executive Engineer
Or
(ii) Superintending Engineer
Or
(iii) Chief Engineer |

8. The Engineer in chief, Rural Works Department on behalf of Governor of Bihar invites bids from the eligible bidders for the works detailed below.

Project Scope & Duration:

- I. To undertake, Initial Rectification Works including surface renewal and Ordinary Maintenance for a period of 5 years after completion of initial rectification works including surface renewal Works on selected roads as described in para 9.
- II. The Initial Rectification may include improvement and pavement strengthening and widening work, road safety measures and tree plantation in flanks as per contract document. The initial rectification including surface renewal of works will be done in such a way that after rectification it complies all technical standards and safety measures to bring the road under prescribed service level. The time of completion for initial rectification works including surface renewal shall be 09 months from the date of issue of LOA.
- III. After completion of initial rectification with surface renewal the selected roads will be maintained for next five years to comply the prescribed service level, to maintain road for traffic worthy. The ordinary maintenance work will also include cross drainage works, minor works on bridges and road maintenance within road side maintenance within selected roads.
- IV. The Ordinary Maintenance works will be carried out under performance based road maintenance on a lump sum basis paid Quarterly.
- V. Initial Rectification Works including surface renewal will be paid on measured quantity to the value of contract.
- VI. There is a requirement for specialised maintenance equipment and the contract obligation is for continuous input over the contract period i.e. initial rectification including surface renewal and ordinary maintenance period.
- VII. To undertake emergent repair due to natural calamities like flood, earthquake, etc
- VIII. Bidders are strongly encouraged to download the bidding documents prior to the pre-bid meeting in order for bidders to have a good understanding of the scope of work under this contract for discussion and clarification at the pre-bid meeting. Bidders are also advised to visit each road, be acquainted with the physical condition of road, satisfy themselves and then participate in the bid.

9. Details of Works:-

Pinc Glob .. Infra

Anvita Singh
Project Officer