

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, सिकहरना, ढाका।

पत्रांक - 1222...../सिकहरना, ढाका, दिनांक-18.10.2023

सेवा में,

Surendra Kumar,
Balua Tal Azad Nagar,
Motihari, East Champaran

विषय :- पुनरीक्षित कार्यादेश के संबंध में


प्रसंग :- अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल-मोतिहारी का ज्ञापांक-709
(अनु0) दिनांक- 30.06.2023

महाशय,

उपर्युक्त विषयक अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल-मोतिहारी का ज्ञापांक- 709 दिनांक-30.06.2023 के द्वारा MMGSY (SC) योजना अन्तर्गत Masaudha Chandmohan to Sisanani का पथ निर्माण कार्य आपको आवंटित हुआ था, जिसका एकरारनामा आपके द्वारा दिनांक-02.12.2022 को किया गया था। अधीक्षण अभियंता के प्रासंगिक पत्र के द्वारा पुनरीक्षित परिमाण विपत्र का तकनीकी स्वीकृति प्राप्त हुआ है। जिसके आलोक में किये गये एकरारनामा के राशि में आवश्यक संशोधन कर उक्त कार्य को दिनांक-18.10.23 से प्रारंभ का निर्धारित अवधि दिनांक-18.10.23 तक समाप्त करने हेतु पुनरीक्षित कार्यादेश दिया जाता है।

अतः आप संबंधित कनीय अभियंता एवं सहायक अभियंता के देख-रेख में उक्त कार्य को मानक विशिष्टियों के अनुरूप निर्धारित अवधि में सम्पादित करना सुनिश्चित करें।

विश्वासभाजन


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सिकहरना, ढाका।

18/10/23

INDIA NON JUDICIAL Government of Bihar

e-Stamp



Certificate No. IN-BR-2301022267
Certificate Issue Date 10-Oct-2023 01:19 PM
GRN No. BHR2023.1000261128E
Unique Doc Reference EST-BR-4600-2300034574
Party Name SURENDRA KUMAR
Purchased by SURENDRA KUMAR
Purpose NA Article no (NA)
Stamp Duty Paid (Rs.) 1000 (One Thousand Only)
Reg. Fee (Rs.) 0 (Zero Only)
LLR & P Fee (Rs.) 0 (Zero Only)
Miscellaneous Fee (Rs.) 0 (Zero Only)
Discore SC (Rs.) 0 (Zero Only)
Total Amount (Rs.) 1000 (One Thousand Only)

Supplementary Agreement

14 SBD(s) / 2022-23

Agreement No. SBD/ R.W.D. Dhaka/MMGSY(NDB-BRICS)

This agreement, made the _____ day of _____ 20_____,
Between Executive Engineer RWD (W) Div. , Dhaka of the one part, and **Surendra Kumar, Balua Tal Azad Nagar, Motihari, East Champaran** of the another part.
Whereas the Employer is desirous that the Contractor execute Construction of **Masaudha Chandmohan to Sisanani Under MMGSY(SC) Tender ID-113787 Under MMGSY(SC) Tender ID-113787** and the employer has accepted the Bid by the contractor for the execution and completion of such works and the remedying of any defects therein at a cost of **Rupees 4,09,054.00 (Rupees Four Lac Nine Thousand Fifty Four) Only**

NOW THIS REVISED AGREEMENT WITNESSETH as follows:

1. In this Revised Agreement, words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.

Statutory Alert:

1. The authenticity of this Stamp certificate should be verified at: <https://enibandhan.bihar.gov.in> or using enibandhan Mobile App. Any discrepancy in the details on this Certificate and as available on the website/Mobile App renders it invalid.
2. The onus of checking the legitimacy is on the users of the certificate.
3. In case of any discrepancy please inform the Competent Authority.

EXECUTIVE ENGINEER
R.W.D., WORKS DIVISION
SIKARAHNA (DHAKA)

18/10/23

of the payments to be made by the Employer to the Contractor as
tioned, the Contractor hereby covenants with the Employer to execute
the Works and remedy any defects therein in conformity in all aspects
provisions of the Contract.

Employer hereby covenants to pay the Contractor in consideration of the
ution and completion of the Works and the remedying the defects wherein the
Contract Price or such other sum as may become payable under the provisions of the
Contract at the times and in the manner prescribed by the Contract.

4. The following documents shall be deemed to form and be read and construed as
part of this Agreement, viz:

- i) Letter of Acceptance;
- ii) Notice to proceed with the works;
- iii) Contractor's Bid;
- iv) Contract Data;
- v) Special Conditions of contract and General Conditions of Contract;
- vi) Specifications;
- vii) Drawings;
- viii) Bill of Quantities; and
- ix) Any other document listed in the Contract Data as forming part of the contract.


In witness whereof the parties thereto have caused this Agreement to be executed the
day and year first before written.

The Common Seal of

_____ was hereunto affixed in the presence of:
Signed, Sealed and Delivered by the said

_____ in the presence of:
Binding Signature of Employer

_____ Binding Signature of Contractor


18/10/23


EXECUTIVE ENGINEER
R.W.D., WORKS DIVISION
SIKARAHNA (DHAKA)

18/10/23

अधीक्षण अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, मोतिहारी

पत्रांक 709 अनु

मोतिहारी, दिनांक 30/06/2023

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल मोतिहारी

सेवा में,

कार्य पालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल ढाका

विषय :-

ग्रामीण कार्य विभाग, कार्य प्रमंडल ढाका के अधीन MMGSY(SC) अन्तर्गत पथ के पुनरीक्षित परिमाण विपत्र अनुमोदनोपरान्त वापस करने के सम्बन्ध में।

प्रसंग :-

आपका पत्रांक-722 अनु0 दिनांक-29.05.2023


महाशय,

उपरोक्त विषयक प्रासांगिक पत्र द्वारा प्राप्त ग्रामीण कार्य विभाग, कार्य प्रमंडल ढाका के अधीन MMGSY(SC) अन्तर्गत निम्नलिखित पथ के जी0एस0टी0 दर 12 प्रतिशत से 18 प्रतिशत होने के कारण अद्यतन पुनरीक्षित परिमाण विपत्र अनुमोदनोपरान्त वापस किया जाता है।

क्र.सं	पथ का नाम	परिमाण विपत्र की राशि (लाख में)
1	Masaudha Chandmohan to Sisahani	8195150.14

अनु0- यथोक्त।

विश्वासभाजन



अधीक्षण अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, मोतिहारी

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, सिकहरना, ढाका।

पत्रांक - 722/अब/१ सिकहरना, ढाका, दिनांक-29-05-2022

प्रेषक :-

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सिकहरना, ढाका।

सेवा में,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल मोतिहारी।

विषय :- MMGSY(SC) योजनान्तर्गत पथों के पुनरीक्षित परिणाम विपत्र अनुमोदन हेतु समर्पित करने के संबंध में।


महाशय,

उपर्युक्त विषय के संबंध में कहना है कि इस प्रमंडल के अधीन MMGSY(SC) योजनान्तर्गत निम्न अंकित पथ में GST में हुई बढ़ोतरी कि अनुरूप पुनरीक्षित परिणाम विपत्र 12% से बढ़ा कर 18% करते हुए भवदीय से अनुमोदन हेतु समर्पित की जा रही है।

क्र०	योजना का नाम	निर्माण की राशि	अनुरक्षण की राशि	कुल राशि
1	Masaudha Chandmohan to Sisahani	7554842.74	640307.40	8195150.14

अनुलग्नक :- परिमाण विपत्र

विश्वासभाजन


29.5.22
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
सिकहरना, ढाका।

Revised Abstract of BOQ for MMGSY(SC)
Rural Works Department, Works Division, Dhaka

Sl.No.	Name of Road	Block	Length (K.M.)	Cost of BOQ on 12% (In Rs.)		Total Cost of BOQ on 12% (In Rs.)		Cost of BOQ on 18% (In Rs.)		Total Cost of BOQ on 18% (In Rs.)	
				Const.	Maint.			Const.	Maint.		
1	Masaudha Chandmohan to Sisahani	Dhaka	0.970	7178054.00	608042.00	7786096.00		7554842.74	640307.40	8195150.14	
Total :-				7178054.00	608042.00	7786096.00		7554842.74	640307.40	8195150.14	

[Signature]
Executive Engineer
Rural Works Department
Works Division, Dhaka

Superintending Engineer
Rural Works Department
Works Circle, Motihari

A- A vide letter no 1178 dt 24/10/2019

total amount = 71,330 Lac

Revised B.O.R. due to increase in GST from 12-1. to 18-1. is approved for RS 8195150.00

[Signature]
29/12/23
28.12.23
28.12.23

(Eighty one lac ninety five thousand one hundred and fifty only) for further action follow in letter no 761 dt 23.03.2022 the instructions given

[Signature]
Superintending Engineer
Rural Works Department
Works Circle, Motihari
29/01/2023

COMPARATIVE STATEMENT OF REVISED BOQ

Length of Road :- 0.970 KM

Name of Road- Masaudha Chandimohan to Sisohani
Block- Dhaka

District- East Champaran

Sl.No.	Item Description	Units	As Per Sanctioned Estimate / BOQ on 12 % GST			As Per Revised Estimate / BOQ on 18 % GST			Difference		% (+/-) Amount	Remarks
			Quantity	Estimated Rate	Total Amount Without Taxes	Quantity	Estimated Rate	Total Amount Without Taxes	Quantity	Amount		
1	Construction of Reference & Working Benchmark as per specification and drawing 200.1 & 200.2	Per Km.	0.97	10637.10	10317.99	0.97	10637.10	10317.99	0.00	0.00	0.00%	
2	Construction of Reference Pillars/Burpees as per specification and drawing 200.1 & 200.2	Per Km.	0.97	11115.97	10782.49	0.97	11115.97	10782.49	0.00	0.00	0.00%	
3	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201.	Hectare	0.29	51133.76	14828.79	0.29	51133.76	14828.79	0.00	0.00	0.00%	
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	Cum.	650.70	202.52	131779.76	650.70	202.52	131779.76	0.00	0.00	0.00%	
5	Construction of subgrade & earthen shoulders with approved material obtained from borrow pits with all lifts and lead, transporting to site, spreading, grading to required slope and compacted to meet requirement of Tables 300.2 with lead upto 1000m as per Technical Specification Clause 301.4.1	Cum.	561.02	204.16	114537.84	561.02	204.16	114537.84	0.00	0.00	0.00%	
6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100m as per Technical Specification Clause 301.5	Cum.	1518.29	167.41	254176.93	1518.29	167.41	254176.93	0.00	0.00	0.00%	
7	Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	Cum.	91.22	74.16	6764.88	91.22	74.16	6764.88	0.00	0.00	0.00%	
8	Laying brick soling layer on prepared sub-grade with brick on . graded and cross-section shown on the drawing filling joints with sand and earth, over brick soling, watering and rolling the same with three Wheeled Road roller 80-100kN as per TS clause 412	Sqm.	585.00	472.43	276371.55	585.00	472.43	276371.55	0.00	0.00	0.00%	
9	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401 (For Grading I Material)	Cum.	172.83	2965.47	512522.18	172.83	2965.47	512522.18	0.00	0.00	0.00%	

Approved
Superintending Engineer
Rural Works Division, Motihari

10	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405	Cum.	223.68 ✓	3689.85 ✓	825345.65 ✓	223.68 ✓	3689.85 ✓	825345.65	0.00	0.00	0.00%
11	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 405	Sqm.	719.63 ✓	44.53 ✓	32045.12 ✓	719.63 ✓	44.53 ✓	32045.12	0.00	0.00	0.00%
12	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503	Sqm.	719.63 ✓	15.14 ✓	10895.20 ✓	719.63 ✓	15.14 ✓	10895.20	0.00	0.00	0.00%
13	Mix Seal Surfacing with Waste Plastic (Type B) By Mechanical Means- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509	Sqm.	719.63 ✓	222.96 ✓	160448.70 ✓	719.63 ✓	222.96 ✓	160448.70	0.00	0.00	0.00%
14	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M 25 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork, spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, construction joints, admixtures as approved, curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501	Cum	471.32 ✓	7311.33 ✓	3445976.06 ✓	471.32 ✓	7311.33 ✓	3445976.06	0.00	0.00	0.00%
15	(i) 5th Kilometre Stone (precast)- Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703								0.00	0.00	0.00%

Approved

Superintending Engineer
Rural Works Department
Works Circle, Motihari

16	(ii) Ordinary Kilometer Stone (Precast)- Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC-8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703	Each	1.00	2491.57	2491.57	2491.57	1.00	2491.57	2491.57	0.00	0.00	0.00%
17	(iii) 200 m stone (precast)- Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC-8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703	Each	4.00	639.62	2558.48	2558.48	4.00	639.62	2558.48	0.00	0.00	0.00%
18	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC-25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	Each	8.00	513.18	4105.44	4105.44	8.00	513.18	4105.44	0.00	0.00	0.00%
19	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701 (For culverts)	Sqm.	22.32	97.96	2186.47	2186.47	22.32	97.96	2186.47	0.00	0.00	0.00%
20	Providing and applying 2 coats of water based cement paint to unplastered concrete surface after cleaning the surface of dirt, dust, oil, grease, efflorescence and applying paint @ of 1 litre for 2 sqm. (at rigid pavement below road marking)	Sqm.	156.00	90.98	14192.88	14192.88	156.00	90.98	14192.88	0.00	0.00	0.00%
21	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes.	Sqm.	194.00	735.44	142675.36	142675.36	194.00	735.44	142675.36	0.00	0.00	0.00%
22	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	/cm h/letter	44.00	0.52	22.88	22.88	44.00	0.52	22.88	0.00	0.00	0.00%
23	Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	Each	2.00	11522.05	23044.10	23044.10	2.00	11522.05	23044.10	0.00	0.00	0.00%

Approved

Plm
Superintending Engineer
Rural Works Department
Works Circle, Motihari

24	Providing and fixing of typical Maintenance Board as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	Each	2.00	11522.05	23044.10	2.00	11522.05	23044.10	0.00	0.00	0.00%
25	600 mm equilateral triangle- Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting as per drawings and Technical Specification Clause 801	No.	6.00	3550.77	21304.62	6.00	3550.77	21304.62	0.00	0.00	0.00%
26	600 mm Circular- Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting as per drawings and Technical Specification Clause 801								0.00	0.00	0.00%
27	600 mm x 450 mm rectangular- Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting as per drawings and Technical Specification Clause 801	No.	2.00	4194.35	8388.70	2.00	4194.35	8388.70	0.00	0.00	0.00%
28	900 mm side octagon- Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting as per drawings and Technical Specification Clause 801	No.	2.00	8151.20	16302.40	2.00	8151.20	16302.40	0.00	0.00	0.00%
29	Providing and laying 300 mm Dia RCC Hume pipe NP-3 for irrigation purpose	RM	7.50	872.96	6547.20	7.50	872.96	6547.20	0.00	0.00	0.00%
30	Planting of Trees and their Maintenance for one Year Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	Each	20.00	819.92	16398.40	20.00	819.92	16398.40	0.00	0.00	0.00%
31	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	cum	15.82	269.32	4260.64	15.82	269.32	4260.64	0.00	0.00	0.00%
32	Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108 - rate as per item No. 11.2 (D) of Chapter 11	cum	1.39	400.59	556.82	1.39	400.59	556.82	0.00	0.00	0.00%
33	Brick Flat Soling in foundation.- Brick Flat Soling in foundation Trenches as per drawing and technical specification Clause 1108								0.00	0.00	0.00%

Superintending Engineer
Rural Works Department
Works Circle, Motihari

34	Providing PCC Grade M15 for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	cum	0.90	6129.36	5516.42	0.90	6129.36	5516.42	0.00	0.00	0.00
35	Providing Reinforced cement RCC GRADE M-25 concrete in box cell complete as per drawings and technical specifications Clauses 802, 804, 806, 807, 1202 and 1204	cum	14.64	7659.32	112132.44	14.64	7659.32	112132.44	0.00	0.00	0.00
36	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (Granular Materials)	cum	7.20	2837.43	20429.50	7.20	2837.43	20429.50	0.00	0.00	0.00
37	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clause 614, 709, 1204.3.7	Each	10.00	83.11	831.10	10.00	83.11	831.10	0.00	0.00	0.00
38	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	MT	1.08	46107.33	49785.92	1.08	46107.33	49785.92	0.00	0.00	0.00
39	Total Construction cost Excluding all Taxes	Rs.			6283578.58			6283578.58	0.00	0.00	0.00
40	Add GST @ 12% / 18%	Rs.	1.00	754029.43	754029.43			1131044.14	0.00	377014.71	50.00%
41	Add Cess @ 1%	Rs.	1.00	62835.79	62835.79	1.00	62835.79	62835.79	0.00	0.00	0.00%
42	Add Seigniorage Fee	Rs.	1.00	81919.86	81919.86	1.00	81919.86	81919.86	0.00	0.00	0.00%
43	TOTAL CONSTRUCTION COST INCLUDING ALL TAXES				7182363.66			7559378.37	0.00	377014.71	5.25%
44	less 0.06% Below as per Agreement (-)				4309.42			4535.63	0.00	226.21	5.25%
45	Total Construction				7178054.24			7554842.74	0.00	376788.50	5.25%
46	Maintenance for 1st year	Year	1.00	26230.00	26230.00	1.00	26230.00	26230.00	0.00	0.00	0.00%
47	Maintenance for 2nd year	Year	1.00	45147.00	45147.00	1.00	45147.00	45147.00	0.00	0.00	0.00%
48	Maintenance for 3rd year	Year	1.00	196713.00	196713.00	1.00	196713.00	196713.00	0.00	0.00	0.00%
49	Maintenance for 4th year	Year	1.00	60021.00	60021.00	1.00	60021.00	60021.00	0.00	0.00	0.00%
50	Maintenance for 5th year	Year	1.00	209971.00	209971.00	1.00	209971.00	209971.00	0.00	0.00	0.00%
51	Total Maintenance cost Excluding all Taxes	Rs.			538082.00			538082.00	0.00	0.00	0.00%
52	Add GST @ 12% / 18%	Rs.	1.00	64569.84	64569.84	1.00	64569.84	64569.84	0.00	32284.92	50.00%
53	Add Cess @ 1%	Rs.	1.00	5380.82	5380.82	1.00	5380.82	5380.82	0.00	0.00	0.00%
54	Add Seigniorage Fee	Rs.	1.00	374.24	374.24	1.00	374.24	374.24	0.00	0.00	0.00%
55	TOTAL Maintenance COST INCLUDING ALL TAXES				608406.90			640691.82	0.00	32284.92	5.31%
56	less 0.06% Below as per Agreement (-)				365.04			384.42	0.00	19.38	5.31%
57	Total Maintenance				608041.86			640307.40	0.00	32265.54	5.31%
58	COST OF PROJECT IN RS. (A+B)				7786096.10			8195150.14	0.00	409054.04	5.25%

AP/MS/16.2M

Superintending Engineer
Rural Works Department
Works Circle, Motihari

29.5.23

NOV
29/5/23
AB

29/5/23 R.W.D.
18/5/23
2/5/23