

बिहार BIHAR

6-10-2023

अनुपम

AS 930588
HIO
श्री १०००
श्री १०००
श्री १०००

Standard Form: Agreement N. ५९/२३.२५

Agreement

This agreement made the 12 Day of .. DCA 20.23
Between **Executive Engineer RWD (W) Division Narkatiaganj** [name and address of Employer]
(Hereinafter called "the Employer" of the one part, and **Samiur Rahman, At- Ward No-02, Majharia, P.S.-Purushottampur, District-West Champaran** [Name and address of Contractor (hereinafter called "the Contractor" of the other part).

Whereas the Employer is desirous that the Contractor execute C.T.S.Ny...T.O...श्री १०००...श्री १०००
मंगल परकीर्ण नम नमनी अर्क [Name and identification number of Contract] (Hereinafter called "the Works") and Employer has accepted the Bid by the Contractor for the execution and completion of such Works and the remedying of nay defects therein at a cost of Rupees .. 20.77.325 = श्री १००० अर्क अर्क श्री १००० श्री १०००

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the employer to the Contractor as hereinafter Mentioned the Contractor hereby covenants with the Employer to execute and complete the Works and remedy and defects therein in conformity in all aspects with the provisions of the Contract.

Samiur Rahman

12-10-23

कार्यपालक अभियंता
राजीव काय विभाग, कार्य प्रमण्डल
बरेली विभाग

3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price of such other sum as may become payable under the provisions of the Contract at the time and in the manner prescribed by the Contract.

4. The following documents shall be deemed to form and be read and construed as part of this Agreement, via:

- i) Letter of Agreement:
- ii) Notice to Proceed with the works:
- iii) Contractor's Bid:
- iv) Contract Data:
- v) Special Conditions of contract and general Conditions of Contract:
- vi) Specifications:
- vii) Drawings:
- viii) Bill of Quantities: and
- ix) Any other document listed in the Contract Data as forming part of the contract in witness

Whereof the parties thereto have caused this Agreement to be executed the year first Before written.

The Common Seal of

Was hereunto affixed in the presence of :

Signed, Sealed and Delivered by the said ... *Deben : 0.25.1. 0.25.1.*

..... In the presence of:

Binding Signature of Employer

Binding Signature of Contractor *Samiur Rahman*

12/10/23
कायपः
ग्रामीण कार्य विभाग, कार्य प्रणाली
नरकटियागंज
12/10/23

BILL OF QUANTITY

REPAIR OF ROAD - RESTORATION OF T01 SEBEYAN TO BHANGHA PARSANI ROAD

BLOCK - MAINATAND
DIVISION - R.W.D. WORKS DIVISION, NARKATIAGANJ.

LENGTH OF ROAD - 1990 M
DISTRICT - WEST CHAMPARAN

SI.NO.	SOR	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
1	303.1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification.	41.40	Cum	170.39	7054.15
2	401 (ii)	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. GRADING - II	20.25	Cum	2766.69	56025.47
3	1500	Construction of un-reinforced plain cement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete of not less than 0.2cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick plythene film, wedges, steel plates including levelling the formwork as per drawing) spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/ culvert and construction joints, admixtures as approved, curing of concrete slab for 14 days curing compound (where specified) and water finishing to lines and grade as per drawing and Technical specification clause 1501.	25.65	CUM	8492.21	217825.19
4	11.1	Earth work in excavation of foundation trenches :- Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	199.49	Cum	249.20	49712.91
5	11.2	Sand Filling in Foundation :- Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108.	2.72	Cum	383.64	1043.50
6	11.4 (II)	Providing M15 (PCC 1:2.5:5) as levelling course in foundation :- Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	30.61	Cum	6731.06	206037.75
7	11.5 (ii)	Brick Masonry in C.M.(1:4) in Foundation :- Brick masonry work in cement mortar (CM 1:4) in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	124.30	Cum	5825.21	724073.60
8	12.1 (II)	Brick Masonry in C.M.(1:4) in Sub Structure :- Brick masonry work in cement mortar (CM 1:4) in substructure and Kerb complete excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	83.30	Cum	6026.24	501985.79
9	12.5 II	Plain/reinforced cement concrete (M-20) in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	4.29	Cum	8076.27	34647.20
10	13.1	Providing RCC M25 in Deck Slab :- Providing and laying reinforced cement concrete in superstructure (Deck slab M25) as per drawing and technical specifications Clauses 800, 1205.4, 1205.5	13.21	Cum	8827.65	116613.26
11	13.2	Supplying, fitting and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications	1.77	MT	61921.32	109600.74
12	13.9	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	4.80	Cum	6070.00	29136.00
13	12.3 (IA)	Plastering with cement mortar (1:4) :- Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	126.56	Sqm	188.14	23811.00

Samir Raha


4/10/23
कार्यपालक अभियंता
राष्ट्रीय कार्य विभाग, कार्य प्रमंडल

OF ROAD - RESTORATION OF T01 SEBEYAN TO BHANGHA PARSAUNI ROAD

BLOCK - MAINATAND
DIVISION - R.W.D. WORKS DIVISION, NARKATIAGANJ.


LENGTH OF ROAD - 1990 M
DISTRICT - WEST CHAMPARAN

SI.NO.	SOR	ITEM OF WORK	QUANTITY	UNIT	RATE	AMOUNT
14	12.9	Providing weep holes in abutement :- Providing Weepholes in brick masonry , Plain / Reinforced concrete abutement , wing wall , return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing	42.00	Nos	118.20	4964.40
						2082531.00
		TOTAL CONSTRUCTION COST -		Rs.		2,082,531.00



Executive Engineer
Rural Works Department
Works Division, Narkatiaganj

Revised BOQ approved item No-(1) to (14) for Rs = 20,82,531.00
(Rupees twenty lacs Eighty two thousand five hundred thirty one)

31/01/23
अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल बेतिया


02/10/23
E.O.

Samiur Rahman


कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग, कार्य अंचल
नारकटियागंज
12/10/23