

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

1 मिलावट 2023 BIHAR

पुनर् 273 दिनांक 24/8/2023 को बालकृष्ण भालोटिया कन्स्ट्रक्शन प्रॉजैक्ट लिमिटेड जमुई के मो 1000/- रु का कार्य AT 630613

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 23 /MBD/2023-24

This agreement, made the 31 August Day of 2023 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and Balkrishna Bhalotia Construction Pvt. Ltd. Jamui Bajaj Shawroom, Jamui.

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road Contract of the maintenance of road from MR-N/21-22/Lakhisarai/04 Package Under of Block in Halsi Under M/R in Lakhisarai District and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 2,24,59,117.00 (Two Crore Twenty Four Lakh Fifty Nine Thousand One Hundred Seventeen) only & five year Maintenance cost Rs. 36,69,265.00 (Thirty Six Lakh Sixty Nine Thousand Two Hundred Sixty Five) only,

SL No	Name of Road	Const. Cost	Maintenance cost	Agreement Value
1	Halsi Tarhari RCD Path se Tarhari Gram hote huye High School Tarhari tak	45.31015 ✓	4.14183 ✓	49.45198
2	Sikandra Sheikhpura NH-(333A) Path Maharth more se Bela Gaon tak	179.28102 ✓	32.55082 ✓	211.83184
Total		224.59117	36.69265	261.28382

Total Cost Rs. 2,61,28,382.00 (Two Crore Sixty One Lakh Twenty Eight Thousand Three Hundred Eighty Two) only

A. He has deposited Performance Security Deposit and Additional Performance Guarantee vide FD No. 197613004500 Rs.13,06,500 & FD No. 197613004501 Rs. 5,07,700

Balkrishna Bhalotia Const. Pvt. Ltd

Director

Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 23/MBD/2023-24

NAME OF WORK:- MR-N/21-22/Lakhisarai/04 Package Under of Block in Halsi
Under M/R in Lakhisarai District.

NAME OF AGENCY:- Balkrishna Bhalotia Construction Pvt. Ltd.
Jamui Bajaj Shawroom, Jamui.

Reference :- Chief Engineer -2
R.W.D works Bihar, Patna
Vide Letter No. 2578 Date :- 18.08.2023

AGREEMENT AMOUNT – Main work:- 2,24,59,117.00
Maintenance work:- 36,69,265.00
Total Amount:- 2,61,28,382.00

Performance Security :- Deposited @ 5% Next 5 % deducted from Bill

Date of Agreement :- 31 August 2023

Date of Completion :- 30 May 2024

No. of Item of Work :- As per B.O.Q (Nos)


Rate Quoted :- 10.00 % below (One Zero Point zero zero percent below)

Contractor Signature


31/8/23


Executive Engineer
RWD, Works Division, Lakhisarai
Work, Div, Lakhisarai
31/8/23

Balkrishna Bhalotia Const. Pvt. Ltd.


Director

**OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI**

AGREEMENT NO:- 23 /MBD/2023-24

This agreement, made the 31 August Day of 2023 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and **Balkrishna Bhalotia Construction Pvt. Ltd. Jamui Bajaj Shawroom, Jamui.**

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road Contract of the maintenance of road from **MR-N/21-22/Lakhisarai/04 Package Under of Block in Halsi Under M/R in Lakhisarai District** and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 2,24,59,117.00 (Two Crore Twenty Four Lakh Fifty Nine Thousand One Hundred Seventeen) only & five year Maintenance cost Rs. 36,69,265.00 (Thirty Six Lakh Sixty Nine Thousand Two Hundred Sixty Five) only,

Sl. No	Name of Road	Const. Cost	Maintenance cost	Agreement Value
1	Halsi Tarhari RCD Path se Tarhari Gram hote buye High School Tarhari tak	45.31015	4.14183	49.45198
2	Sikandra Sheikhpura NH-(333A) Path Maharth more se Bela Gaon tak	179.28102	32.55082	211.83184
Total		224.59117	36.69265	261.28382

Total Cost Rs. 2,61,28,382.00 (Two Crore Sixty One Lakh Twenty Eight Thousand Three Hundred Eighty Two) only

A. He has deposited Performance Security Deposit and Additional Performance Guarantee vide FD No.- 197613004500 Rs.13,06,500 & FD No. 197613004501 Rs. 5,07,700

Balkrishna Bhalotia Const. Pvt. Ltd

[Signature]
Director

[Signature]
31/8/23

[Signature]
Executive Engineer
Rural Work. Department
Work. Div. Lakhisarai
31/8/23

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 23/MBD/2023-24

NAME OF WORK:- MR-N/21-22/Lakhisarai/04 Package Under of Block in Halsi
Under M/R in Lakhisarai District.

NAME OF AGENCY:- Balkrishna Bhalotia Construction Pvt. Ltd.
Jamui Bajaj Shawroom, Jamui.

Reference :- Chief Engineer -2
R.W.D works Bihar, Patna
Vide Letter No. 2578 Date :- 18.08.2023

AGREEMENT AMOUNT – Main work:-	2,24,59,117.00
Maintenance work:-	36,69,265.00
Total Amount:-	2,61,28,382.00

Performance Security :- Deposited @ 5% Next 5 % deducted from Bill

Date of Agreement :- 31 August 2023

Date of Completion :- 30 May 2024

No. of Item of Work :- As per B.O.Q (Nos)

Rate Quoted :- 10.00 % below (One Zero Point zero zero percent below)

Contractor Signature

Balkrishna Bhalotia Const. Pvt. Ltd.

Director

Executive Engineer
R.W.D. Works Division, Lakhisarai
Rural Work, Department
Work, Div, Lakhisarai

Tender Inviting Authority: Engg-In Chief RWD Patna

Name of Work: Construction of Road & CD Works for Sikandara Sheikhpura NH - (333 A) Path Maharth Morz So Bela Gaon Tak

Contract No: Civil Works/

Bidder Name: Excess (+) %



No.	Description of work	SCHEDULE OF WORKS		Estimated Rate		AMOUNT Rs. P
		No. or Qty.	Unit	Figure	Words	
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removal of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	1.30	Hect	72697.86	Rupees Seventy Two Thousand Six Hundred & Ninety Seven and Paise Eighty Six Only	94507.22
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	432.00	Cum	254.33	Rupees Two Hundred & Fifty Four and Paise Thirty Three Only	109870.56
3	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	3046.50	Cum	257.69	Rupees Two Hundred & Fifty Seven and Paise Sixty Nine Only	785052.59
4	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	268.79	Cum	1659.76	Rupees One Thousand Six Hundred & Fifty Nine and Paise Seventy Six Only	446126.89
5	WBM Grading 2 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	103.60	Cum	3071.93	Rupees Three Thousand & Seventy One and Paise Ninety Five Only	318254.02
6	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	262.58	Cum	2492.06	Rupees Two Thousand Four Hundred & Ninety Two and Paise Six Only	654365.11
7	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	1971.07	Sqm	60.64	Rupees Sixty and Paise Sixty Four Only	119525.68

Signature of Tenderer with seal

Balkrishna Bhalotia Const. Pvt. Ltd

Director

31/8/23

Executive Engineer
Rural Work. Department
Work, Div. Lakhisarai

Order Inviting Authority: Engg-in Chief RWD Patna

Name of Work: Construction of Road & CD Works for Sikandara Sheikhupura NH -(333 A) Path Maharth More Se Bela Gaun Tak
 Work Under M/R (3054)
 Contract No: Civil Works/

VALIDATE

PRINT

REPR

Sl. No.	Description of work	SCHEDULE OF WORKS				AMOUNT Rs. P
		No. or Qty.	Unit	Estimated Rate		
				Figure	Words	
8	Patch work over WBM using Mix seal surface for bituminous and Existing CC Pavement :- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509.	1971.07	Sqm	289.40	Rupees Two Hundred & Eighty Nine and Paise Forty Only	570427.66
9	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydriluc broom as per technical specification clause 503.	8091.07	Sqm	20.79	Rupees Twenty and Paise Seventy Nine Only	168213.35
10	Semi-Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH hatch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	153.00	Cum	14063.95	Rupees Fourteen Thousand & Sixty Three and Paise Ninety Five Only	2151784.35
11	Dry Lean Cement Concrete :- Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregates conforming to IS:383, the size of coarse aggregate not exceeding 25mm, aggregate cement ratio not to exceed 15:1 aggregate gradation after blending to be as per table 600-1 cement content not to be less than 150kg/cum optimum moisture content to be determined during trial length construction, concrete strength not be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing. (PCC M-15)	70.31	Cum	6191.61	Rupees Six Thousand One Hundred & Ninety One and Paise Sixty One Only	435332.10

Signature of Tenderer with seal

Rajkrishna Bhalotia Const. Pvt. Ltd.

Rajkrishna Bhalotia

Director

P. Bhalotia
31/8/23

Abhishek
Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai
31/8/23

Under Inviting Authority: Engr-in Chief RWD Patna

Name of Work: Construction of Road & CD Works for Sikandara Sheikhpora NH -(333 A) Path Maharth More Se Bela Gaon Tak
 Work Under M/R (3054)
 Contract No: Civil Works/

VALIDATE

PRINT

HELP

Sl. No.		Description of work		SCHEDULE OF WORKS		Estimated Rate		AMOUNT Rs. P	
		No. or Qty.	Unit						
				Figure	Words				
12	Cement Concrete Pavement :- Construction of unreinforced plain cement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete of not less than 0.2cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick plythene film, wedges, steel plates including levelling the formwork as per drawing) spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/ culvert and construction joints, admixtures as approved, curing of concrete slab for 14 days curing compound (where specified) and water finishing to lines and grade as per drawing and Technical specification clause 1501.	1099.80	Cum	7741.57	Rupees Seven Thousand Seven Hundred & Forty One and Paise Ninety Seven Only			7817841.31	
13	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. Km stone	4.00	Each	2730.24	Rupees Two Thousand Seven Hundred & Thirty and Paise Twenty Four Only			10920.96	
14	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. 200 m stone	13.00	Each	793.87	Rupees Seven Hundred & Ninety Three and Paise Eighty Seven Only			10320.31	
15	Direction and Place Identification signs with size more than 0.9 sqm size board :- Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	1.92	Sqm	12622.73	Rupees Twelve Thousand Six Hundred & Twenty Two and Paise Seventy Three Only			24235.64	
16	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 1701 (600 mm equilateral & triangle)	16.00	Each	3609.15	Rupees Three Thousand Six Hundred & Nine and Paise Fifteen Only			57746.40	

Signature of Tenderer with seal

Balkrishna Bhalotia Const. Pvt. Ltd.

31/07/23

Executive Engineer
 Rural Work, Department
 Work, Div. Lakhisarai

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work: Construction of Road & CD Works for Sikandara Sheikhpura NH - (333 A) Path Maharath More Se Bela Gaon Tak
Block Unde M/R (3054)

Contract No: Civil Works/

Bidder
me:

Excess (+)

%

AMOUNT
Rs. P

No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
17	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801. (600 mm circular)	14.00	Each	3779.65	Rupees Three Thousand Seven Hundred & Seventy Nine and Paise Sixty Five Only	52915.10
18	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801. (600 mm x 450 mm rectangular)	4.00	Each	3653.30	Rupees Three Thousand Six Hundred & Fifty Five and Paise Thirty Only	14621.20
19	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801. (900 mm octagon shape board)	2.00	Each	7500.36	Rupees Seven Thousand Five Hundred and Paise Thirty Six Only	15000.72
20	Boundary Pillar/Guard Post - Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	72.00	Each	694.06	Rupees Six Hundred & Ninety Four and Paise Six Only	49972.32
21	Printing New Letters and Figures of any Shade - Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	352.00	height per	0.72	Rupees and Paise Seventy Two Only	253.44
22	Planting of Trees and their Maintenance for one Year - Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sedge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	89.00	Each	1231.74	Rupees One Thousand Two Hundred & Thirty One and Paise Seventy Four Only	98539.20
23	Road Marking with Hot Applied Thermoplastic Compound with Reflectors/Glass Beads on Bituminous Surface - Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectors/glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes	320.00	Sqm	783.78	Rupees Seven Hundred & Eighty Three and Paise Seventy Eight Only	250809.60

Signature of Tenderer with seal

B. Krishna Bhalotia Const. Pvt. Ltd.

Director

Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

Bidding Name:		SCHEDULE OF WORKS				Excess (+)		%	
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P			
				Figure	Words				
24	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Concrete Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	330.00	Sqm	888.96	Rupees Eight Hundred & Eighty Eight and Paise Ninety Six Only	293356.80			
25	(1) Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	3.00	Each	11227.45	Rupees Eleven Thousand Two Hundred & Twenty Seven and Paise Forty Five Only	33682.35			
26	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	198.62	Cum	363.28	Rupees Three Hundred & Eighty Three and Paise Twenty Eight Only	76127.07			
27	Providing M15 (PCC 1:2:5:5) as levelling course to foundation :- Providing PCC M 15 (1:2:5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	139.76	Cum	6191.61	Rupees Six Thousand One Hundred & Ninety One and Paise Sixty One Only	865339.41			
28	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	120.96	Sqm	181.69	Rupees One Hundred & Eighty One and Paise Sixty Nine Only	21977.22			
29	Brick masonry work in cement mortar 1:3 in parapet including pointing and plastering as per drawing and technical specifications Clauses 605, 900 and 1208.4	17.28	Cum	6130.73	Rupees Six Thousand One Hundred & Thirty and Paise Seventy Three Only	105939.01			
30	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	177.28	Sqm	123.24	Rupees One Hundred & Twenty Three and Paise Twenty Four Only	21847.99			
31	Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108.	3.27	Cum	563.71	Rupees Five Hundred & Sixty Three and Paise Seventy One Only	1843.30			
32	Plain/Reinforced cement concrete (PCCM-20) in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	93.88	Cum	7234.36	Rupees Seven Thousand Two Hundred & Thirty Four and Paise Thirty Six Only	679161.70			

Signature of Tenderer with seal

Balkrishna Bhalotia Const. Pvt. Ltd

Director

Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

Inviting Authority: Engg-in-Chief RWD Patna

Name of Work: Construction of Road & CD Works for Sikandara Shalokipura NH - (333 A) Path Maharth More Se Bela Gaon Tak
Block Under M/R (3054)

Contract No: Civil Works/

Bidder Name:

☒ VALIDATE

☐ PRINT

☐ HELP

Sl. No.	Description of work	SCHEDULE OF WORKS		Excess (+)	%	AMOUNT Rs. P
		No. or Qty.	Unit			
33	Providing Bitumen painting over top surface of Abutment cap & inner vertical surface of Dirt Wall including Heating the bitumen & cost of painting brush etc. all complete	29.10	Sqm	20.79	Rupees Twenty and Paise Seventy Nine Only	604.99
34	RCC M25 in Deck Slab :- Providing and laying reinforced cement concrete in superstructure (Deck slab M25) as per drawing and technical specifications Clauses 800, 1205.4, 1205.5	12.62	Com	7990.19	Rupees Seven Thousand Nine Hundred & Ninety and Paise Nineteen Only	100836.20
35	Supplying, fitting and placing HYSD bar reinforcement in super-structure complete as per drawing and technical specifications	1.92	MT	77921.87	Rupees Seventy Seven Thousand Nine Hundred & Twenty One and Paise Eighty Seven Only	149609.99
36	Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 per cent bitumen by weight	30.00	RM	53.21	Rupees Fifty Three and Paise Twenty One Only	1596.30
37	Providing Weepholes in brick masonry, Plain / Reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing	80.00	No	93.12	Rupees Ninety Three and Paise Twelve Only	7449.60
Cost of Construction :-						16616007.71
Add 18% GST						2990881.39
Add 1% Labour Cess						166160.08
Seigniorage Fee						147064.00
Total Cost of Construction :-						19920113.17
38	Five Year Maintenance	20.000	Quarterly	151356.90	Rupees One Lakh Fifty One Thousand Three Hundred & Fifty Six and Paise Ninety Only	3027138.00
Cost of Maintenance :-						3027138.00
Add 18% GST						544884.84
Add 1% Labour Cess						30271.38
Seigniorage Fee						14464.00
Total Cost of Maintenance :-						3616758.22
Total Cost of Project Including Five Year Maintenance :-						23536871.39
Noted Rate in Words		Rupees Two Crore Thirty Five Lakh Thirty Six Thousand Eight Hundred & Seventy One and Paise Thirty Nine Only				

Signature of Tenderer with seal

Bal Krishna Bhalotia Const. Pvt. Ltd

Director

[Signature]
31/8/23

[Signature]
Executive Engineer
Rural Work, Department
Work, Div. Lakhisarai

31/8/23

Tender Inviting Authority: Engr-in Chief RWD Patna

Name of Work: Construction of Road & CD Works for Halsi Tarhart RCD Path Se Tarhart Gram Hote Huye High School Tarhart Tak
Block Unde M/R (3054)

Contract No: Civil Works/

VALIDATE

PRINT

HELP

Bidder
Name:

Excess (+)

%

AMOUNT
Rs. P

Sl. No.	Description of work	SCHEDULE OF WORKS		Estimated Rate		AMOUNT Rs. P
		No. or Qty.	Unit	Figure	Words	
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removal of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 301.1 and direction of E/I	8.22	Hect	72697.86	Rupees Seventy Two Thousand Six Hundred & Ninety Seven and Paise Eighty Six Only	15993.53
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	450.00	Cum	254.33	Rupees Two Hundred & Fifty Four and Paise Thirty Three Only	114448.50
3	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	247.50	Cum	257.69	Rupees Two Hundred & Fifty Seven and Paise Sixty Nine Only	63778.28
4	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method, with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	95.63	Cum	1806.92	Rupees One Thousand Eight Hundred & Six and Paise Ninety Two Only	172795.76
5	WDM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes in water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 30-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	71.72	Cum	2289.03	Rupees Two Thousand Two Hundred & Eighty Nine and Paise Three Only	164169.23
6	Dry Lean Cement Concrete :- Construction of dry lean cement concrete sub-base over a prepared sub-grade with coarse and fine aggregates conforming to IS:383, the size of coarse aggregate not exceeding 25mm, aggregate cement ratio not to exceed 15:1 aggregate gradation after blending to be as per table 600-1 cement content not to be less than 150kg/cum optimum moisture content to be determined during trial length construction, concrete strength not be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing. (PCC M -15)	4.22	Cum	5987.94	Rupees Five Thousand Nine Hundred & Eighty Seven and Paise Ninety Four Only	25269.11

Signature of Tenderer with seal

Balkrishna Bhalotia Const. Pvt. Ltd

Director

Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work: Construction of Road & CD Works for Halsei Tarhari RCD Path Se Tarhari Gram Nete Huye High School Tarhari Tak
Block Under M/R (3054)

Contract No: Civil Works/

Bidder
Name:

☒ VALIDATE

☐ PRINT

☐ HELP

Sl. No.	Description of work	SCHEDULE OF WORKS				AMOUNT Rs. P
		No. or Qty.	Unit	Estimated Rate		
				Figure	Words	
7	Cement Concrete Pavement :- Construction of un-reinforced plain cement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete of not less than 0.2cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick plythene film, wedges, steel plates including levelling the formwork as per drawing) spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/ culvert and construction joints, admixtures as approved, curing of concrete slab for 14 days curing compound (where specified) and water finishing to lines and grade as per drawing and Technical specification clause 1501.	336.60	Cum	7512.82	Rupees Seven Thousand Five Hundred & Twelve and Paise Eighty Two Only	2528915.21
8	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. Km stone	2.00	Each	2675.40	Rupees Two Thousand Six Hundred & Seventy Five and Paise Four Only	5350.80
9	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. 200 m stone	2.00	Each	784.11	Rupees Seven Hundred & Eighty Four and Paise Eleven Only	1568.22
10	Direction and Place Identification sign with size more than 0.9 sqm size board :- Retro-reflectivised Traffic Sign providing and erecting direction and place identification retro-reflectivised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 3 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	1.92	Sqm	12588.51	Rupees Twelve Thousand Five Hundred & Eighty Eight and Paise Fifty One Only	24169.94
11	Providing and fixing of retro-reflectivised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 1701 (600 mm equilateral triangle)	6.00	Each	3583.49	Rupees Three Thousand Five Hundred & Eighty Three and Paise Forty Nine Only	21500.94

Signature of Tenderer with seal

Ba Arishna Bhalodia Const. Pvt. Ltd.

A. Bhalodia

Director

P. Bhalodia
31/8/23

Executive Engineer
Rural Work, Department
Work, Div. Lakhisarai

A. Bhalodia
31/8/23

AK 3/18/23

Tender Inviting Authority: Engr-in-Chief RWD Patna

Name of Work: Construction of Road & CD Works for Haldi Tarhari RCD Path Se Tarhari Gram Hote Huye High School Tarhari Taluk

Block Under M/R (3054)

Contract No: Civil Works/

Bidder Name:

Excess (+)

AMOUNT Rs. P

Sl. No.	Description of work	SCHEDULE OF WORKS		Estimated Rate		AMOUNT Rs. P
		No. or Qty.	Unit	Figure	Words	
18	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	166.00	Cum	383.29	Rupees Three Hundred & Eighty Three and Paise Twenty Eight Only	63524.48
19	Providing M15 (PCC 1:2.5:5) as levelling course in foundation :- Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	27.60	Cum	5987.94	Rupees Five Thousand Nine Hundred & Eighty Seven and Paise Ninety Four Only	165267.14
20	Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108	18.40	Cum	563.71	Rupees Five Hundred & Sixty Three and Paise Seventy One Only	10372.26
21	Plain/Reinforced cement concrete (PCCM-20) in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	65.70	Cum	7005.23	Rupees Seven Thousand & Five and Paise Twenty Three Only	460243.61
22	REC M25 in Deck Slab :- Providing and laying reinforced cement concrete in superstructure (Deck slab M25) as per drawing and technical specifications Clauses 800, 1205.4, 1205.5	14.10	Cum	7761.06	Rupees Seven Thousand Seven Hundred & Sixty One and Paise Six Only	109430.95
23	Supplying, fitting and placing HYSD bar reinforcement in super-structure complete as per drawing and technical specifications	1.10	MT	77921.87	Rupees Seventy Seven Thousand Nine Hundred & Twenty One and Paise Eighty Seven Only	91947.81
Cost of Construction :-						4198105.12
Add 18% GST						755658.92
Add 1% Labour Cess						41981.05
Seigniorage Fee						38716.00
Total Cost of Construction :-						5034461.09
24	Five Year Maintenance	20.000	Quarterly	19324.25	Rupees Nineteen Thousand Three Hundred & Twenty Four and Paise Twenty Five Only	386485.00
Cost of Maintenance :-						386485.00
Add 18% GST						69567.30
Add 1% Labour Cess						3864.85
Seigniorage Fee						287.00
Total Cost of Maintenance :-						460204.15
Total Cost of Project Including Five Year Maintenance :-						5494665.24
Estimated Rate in Words		Rupees Fifty Four Lakh Ninety Four Thousand Six Hundred & Sixty Five and Paise Twenty Four Only				

Signature of Tenderer with seal

Balkrishna Bhalodia Const. Pvt. Ltd.

Director

Executive Engineer
Rural Work. Department
Work. Div. Lakhsarai

Govt. of Bihar
Rural Works Department
Office of the Executive Engineer, Rural Works Department,
Works Division Lakhisarai

(बिहार ग्रामीण मय अनुसूक्षण नीति, 2018)

Notice Inviting Tender for Rural Roads Maintenance based on Output and performance based Contract through e-procurement mode on Model Bidding Document (MBD).

(Notice Inviting No. - Re-Tender -MR-3054-1/2022-23)

1. Designation and Address of the Advertiser
2. Date of Issue of Notice Inviting Tender
3. Period for downloading of Tender Documents
4. Date, Time & Place of Pre-Bid Meeting
5. Last Date & Time for uploading tender Document by bidder
6. Date, time for online opening of Technical bid
7. Last Date, time and place for submission of Original statement of EMD, Cost of BOQ and Affidavit regarding correctness of Information provided with bid document

- Executive Engineer, Rural Works Department, Works Division Lakhisarai
- At, 12/2/2022
- From 24.01.2023 (9:00) to 31.01.2023 up to 15:00 hrs. From
- website-<http://mnpaytenders.bih.gov.in>
- Date 30.01.2023, time 15:00 hrs.
- Place On Concerned Superintending Engineer
- Date 31.01.2023 up to 15:00 hrs.
- <http://mnpaytenders.bih.gov.in>
- Date 31.01.2023 up, Time: 15:30 hrs.

- Till 15:00 hrs on 31.01.2023
- Place - Ofc concerned
- (i) Executive Engineer
- Or
- (ii) Superintending Engineer
- Or
- (iii) Chief Engineer

8. The Engineer in Chief, Rural Works Department on behalf of Governor of Bihar invites bids from the eligible bidders for the works detailed below:

Project Scope & Duration:

- I. To undertake, Initial Rectification Works including surface renewal and Ordinary Maintenance for a period of 3 years after completion of initial rectification works including surface renewal Works on selected roads as detailed in part 9.
- II. The Initial Rectification may include improvement and pavement strengthening and widening work, road safety measures and tree plantation in Rural as per contract document. The initial rectification including surface renewal of works will be done in such a way that after rectification it complies all technical standards and safety measures to bring the road under prescribed service level. The time of completion for initial rectification works including surface renewal shall be 03 months from the date of issue of L.O.A.
- III. After completion of initial rectification with surface renewal the selected roads will be maintained for next five years to comply the prescribed service level, to maintain road for traffic worthy. The ordinary maintenance work will also include cross drainage works, minor works on bridges and road maintenance within road side maintenance within selected roads.
- IV. The Ordinary Maintenance works will be carried out under performance based road maintenance on a lump sum basis paid Quarterly.
- V. Initial Rectification Works including surface renewal will be paid on measured quantity to the value of contract.
- VI. There is a requirement for specialized maintenance equipment and the contract obligation is for continuous input over the contract period i.e. initial rectification including surface renewal and ordinary maintenance period.
- VII. To undertake emergent repair due to natural calamities like flood, earthquake, etc.
- VIII. Bidders are strongly encouraged to download the bidding documents prior to the pre-bid meeting in order for bidders to have a good understanding of the scope of work under this contract for discussion and clarification at the pre-bid meeting. Bidders are also advised to visit each road, be acquainted with the physical condition of road, satisfy themselves and then participate in the bid.

9. Details of Works:-

Sl. No.	Package No.	District	Division	Block	Name of Road	Length (in KM)	Cost of Initial Rectification (Rs Lakhs)	Cost of 3 years Maintenance (Rs Lakhs)	Total Estimated Cost (Rs Lakhs)	Cost of BOQ (Rs Lakhs)	Bid Security (Rs. In Lakhs)	Amount Payable to works Division
1	MR-3054-1/22 Lakhisarai	Lakhisarai	Lakhisarai	Hali	PMGSY Purnea Path to Durga Arjun (Juchaya Pathayur Bhawan Tal)	1.900	118.72	15.12	133.840	16000	4.201	EE, RWD, Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	Hali	RWD Purnea Path to Kalamoti Pool (Kalamoti Tal)	0.550	47.50	7.53	55.030			
Total for the Group						2.450	166.220	22.650	188.870			
2	MR-3054-2/22 Lakhisarai	Lakhisarai	Lakhisarai	Bangorh chuk	Small Yamlied to Boudhi Village	0.600	21.32	6.31	27.630	20000	3.073	EE, RWD, Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	Bangorh chuk	PMGSY Gola Path to Nawadhi Tal	1.300	110.79	11.12	121.910			
Total for the Group						1.900	132.110	17.430	149.540			

Balkrishna Bhalotia Const. Pvt. Ltd
[Signature]
Director

A-2
31/01/23
Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai
At
31/01/23

3	MR-N21-22 Lakhisarai003	Lakhisarai	Lakhisarai	Banhiya	PO-80 Bridge Right to Ramnagar Tola (at Mondir via middle school)	1.000	69.22	8.46	77.680	10000	7.108	EE, RWD Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	Ramgarh chowk	Lakhisarai Bhandra Road to Sonahri	2.500	101.427	18.118	127.545			
		Lakhisarai	Lakhisarai	Ramgarh chowk	PONGSY Ramgarh Path to Gramin Path Ramgarh tak	2.700	115.89	19.26	145.150			
Total for the Group						7.200	287.537	35.834	340.375			
4	MR-N21-22 Lakhisarai004	Lakhisarai	Lakhisarai	State	State Tachari HC-10 Path to Tachari Gramin Path Bhoja High School Tachari tak	0.350	42.3277	4.1006	47.467	12000	5.064	EE, RWD Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	State	Bhandra Bhandra N21 (D21A) Path Mondir near to Bhoja Gram tak	3.350	173.50	24.79	295.790			
Total for the Group						3.700	215.825	28.891	253.217			
5	MR-N21-22 Lakhisarai005	Lakhisarai	Lakhisarai	Ramgarh chowk	Lakhisarai Bhandra Path to Gramin Path Ramgarh Chowk	1.000	21.0000	6.1829	27.1829	10000	3.345	EE, RWD Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	Ramgarh chowk	Lakhisarai Bhandra Path to Gramin Path Ramgarh Chowk	1.000	125.11	14.57	139.68			
Total for the Group						2.000	146.110	20.855	167.745			
6	MR-N21-22 Lakhisarai006	Lakhisarai	Lakhisarai	Lakhisarai	Lakhisarai Path to Path to Nari Path tak	0.800	50.8428	0.9941	51.8369	10000	2.118	EE, RWD Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	Lakhisarai	Lakhisarai Bhandra Path to Gramin Path Ramgarh Chowk	0.200	41.0724	2.0326	43.1050			
Total for the Group						1.000	91.915	3.0267	95.858			
7	MR-N21-22 Lakhisarai007	Lakhisarai	Lakhisarai	Banhiya	Tal Sharni Ramgarh Path to Mondir Tola Ramgarh	0.300	82.800	8.460	91.260	10000	7.230	EE, RWD Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	Banhiya	Banhiya Bhandra Path to Gramin Path Ramgarh Chowk	0.300	45.210	8.120	53.330			
		Lakhisarai	Lakhisarai	Banhiya	Gramin Path to Ramgarh Path to Mondir Tola Ramgarh	1.000	52.284	8.120	60.404			
		Lakhisarai	Lakhisarai	State	State Tachari HC-10 Path to Tachari Gramin Path Bhoja High School Tachari tak	0.300	20.955	7.632	28.587			
		Lakhisarai	Lakhisarai	State	State Tachari HC-10 Path to Tachari Gramin Path Bhoja High School Tachari tak	0.417	41.710	8.120	49.830			
		Lakhisarai	Lakhisarai	State	State Tachari HC-10 Path to Tachari Gramin Path Bhoja High School Tachari tak	0.710	27.143	7.630	34.773			
Total for the Group						3.027	207.802	47.962	264.454			
8	MR-N21-22 Lakhisarai008	Lakhisarai	Lakhisarai	Lakhisarai	Lakhisarai Path to Path to Nari Path tak	0.600	28.500	4.250	32.750	10000	8.713	EE, RWD Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	Lakhisarai	Lakhisarai Path to Path to Nari Path tak	0.700	28.400	4.243	32.643			
		Lakhisarai	Lakhisarai	Lakhisarai	Lakhisarai Path to Path to Nari Path tak	1.000	158.710	19.440	178.150			
		Lakhisarai	Lakhisarai	Lakhisarai	Lakhisarai Path to Path to Nari Path tak	1.200	158.700	21.370	180.070			
Total for the Group						3.500	374.310	61.303	435.613			
9	MR-N21-22 Lakhisarai009	Lakhisarai	Lakhisarai	Lakhisarai	Bhandra Path to Ramgarh Path to Mondir Tola Ramgarh	1.000	65.450	20.800	85.250	10000	7.672	EE, RWD Works Division, LAKHISARAI
		Lakhisarai	Lakhisarai	Lakhisarai	Bhandra Path to Ramgarh Path to Mondir Tola Ramgarh	1.000	71.741	15.877	87.618			
		Lakhisarai	Lakhisarai	Lakhisarai	Bhandra Path to Ramgarh Path to Mondir Tola Ramgarh	1.000	87.390	22.540	109.930			
		Lakhisarai	Lakhisarai	Lakhisarai	Bhandra Path to Ramgarh Path to Mondir Tola Ramgarh	1.075	77.452	17.705	95.157			
Total for the Group						4.075	302.033	76.922	378.624			

10. Validity: 120 days from the date of opening of bid.

Bharat Bhalotia Const. Pvt. Ltd

Director

Executive Engineer
Rural Work Department
Muz. Div. Lakhisarai

31/8/23

मुख्य अभियंता-2 का कार्यालय
ग्रामीण कार्य विभाग, पटना।

पत्रांक-
प्रेषक.

/पटना, दिनांक-

ई० श्रीप्रकाश
मुख्य अभियंता-2

सेवा में,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, लखीसराय।

विषय : शीर्ष 3054 MR योजनान्तर्गत कार्य प्रमण्डल, लखीसराय के अधीन पैकेज सं०-MR-N/21-22
Lakhisara/04 (Tender Id-122982) कार्य की निविदा की स्वीकृति के संबंध में।

महाराय,

विभागीय ज्ञापक-मु०अ०-4(मु०)निविदा-04-392/2023-4406 अनु० दिनांक-14.08.2023 द्वारा संसूचित आदेश के अनुपालन में उपर्युक्त विषय के संबंध में बिहार लोक निर्माण संहिता के कंडिका-163 के आलोक में इस कार्य को इसके योग्य सफल एकल निविदाकार Balkrishna Bhalotia Const. Pvt. Ltd. (बीड आईडी-530421) को उनके द्वारा निविदित दर, जो परिमाण विपत्र की दर से 10.00% (दस दशमलव शून्य प्रतिशत) कम है, को स्वीकृत करते हुए सम्पूर्ण कार्य कुल 2,61,28,382 /- (दो करोड़ एकसठ लाख अठाईस हजार तीन सौ बेरासी) रुपये मात्र की लागत पर आपकी अनुशंसा एवं कार्यादेशों में आवंटित किया जाता है।

- निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।
- संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ जमा किये गये संबंधित एन०एस०सी०/Fixed Deposit/BG आदि का सत्यापन संबंधित डाकघर/बैंक से कराकर प्रमंडलीय कार्यालय में अभिलेखित किया जायेगा। कार्यपालक अभियंता, कार्य प्रमण्डल, लखीसराय कार्यादेश निर्गत करने के पूर्व अग्रघन की राशि के सत्यापन से संबंधित कामजात अवोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।
- एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कामजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जायेगा।
- एकरारनामा से पूर्व कार्यपालक अभियंता यह सुनिश्चित कर लेंगे कि निविदाकार डिबार सूची/काली सूची या कार्य लंबित सूची में शामिल न हों।
- कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य कराते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।
- इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लेखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।
- अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में यस्तुस्थिति से तत्क्षण अवोहस्ताक्षरी को अवगत करायेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की जायेगी।
- एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जाँच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।
- कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपबंध से पूरी तरह आश्वस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये निदेश का अनुपालन सुनिश्चित करायेंगे। पथ का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, प्रशासनिक स्वीकृति की राशि, संवेदक द्वारा उद्धृत दर, परक्रमित दर, Bid Capacity आदि का मिलान कर ही कार्य आवंटन आदेश निर्गत करेंगे। कार्यपालक अभियंता कार्य आवंटन/LOA निर्गत करने से पूर्व मिलान कर लेंगे कि परिमाण विपत्र की राशि प्रशासनिक अनुमोदन की राशि के अनुज्ञेय सीमा के अन्दर है। यदि अनुज्ञेय सीमा से अधिक हो तो एकरारनामा के पूर्व पुनरीक्षित प्रशासनिक अनुमोदन प्राप्त कर लिया जाय।
- कार्यादेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु मासिक कार्य प्रोग्राम हस्ताक्षरित कराकर प्राप्त कर लेंगे जो की एकरारनामा का भाग होगा।

12. अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुरूप निर्धारित कार्य अवधि के अंदर पूरा की जायेगी।
13. कार्य समाप्ति की अवधि निविदा आमंत्रण सूचना के अनुसार होगी।
14. इस कार्य का व्यय 3054 MR योजनान्तर्गत से मिलने वाले राशि अन्तर्गत उपबंधित राशि से विकलित होगा।
15. कार्य का प्रगति प्रतिवेदन प्रत्येक महीने की सातवीं तारीख तक निश्चित रूप से इस कार्यालय को समर्पित की जाय।
16. सभी निविदा कागजात एवं तुलनात्मक विवरणी की मूल प्रति आवश्यक कार्रवाई हेतु लौटाई जाती है। आप निविदा कागजातों एवं तुलनात्मक विवरणी के जांचोपरान्त आप आवश्यक निर्देशों को अपने स्तर से निर्गत करेंगे।
17. एकरारनामा से पहले निविदाताओं द्वारा दिये गये कागजात का सत्यापन उनके मूल कागजात से मिलान कर लेंगे। कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय तुलनात्मक विवरणी की एक अभिप्रायित प्रति अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर को अभिलेख हेतु उपलब्ध करा देंगे। निर्देश दिया जाता है कि संवेदक से कार्य प्रोग्राम प्राप्त कर लेंगे तथा उनका कार्यक्षमता कुशलता एवं पूर्व से आवंटित कार्यों की प्रगति से संतुष्ट हो लें।
18. इस निविदा की राशि में अगर कोई अंतर होता है तो इसकी सूचना तुरन्त इस कार्यालय को दी जाय।
19. कार्यपालक अभियंता, एकरारनामा करने के पूर्व संवेदक का निबंधन संख्या, पूर्ण पता एवं दूरभाष संख्या कार्यादेश में अंकित करेंगे तथा इस कार्यालय को सूचित करेंगे।
20. परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा निर्देश के आलोक में अतिरिक्त वांछित परफॉरमेंस सिक्यूरिटी की राशि जमा कराना सुनिश्चित करेंगे।
21. किसी भी परिस्थिति में निजी जमीन पर निर्माण नहीं कराया जाय।
22. प्रत्येक 15 दिनों पर संवेदक से स्वहस्ताक्षरित विपत्र प्राप्त कर स्थल से मिलान कर मापी पुस्तिका में मापी दर्ज कर भुगतान सुनिश्चित करेंगे।
23. कार्यपालक अभियंता कार्यावंटन आदेश प्राप्त होते ही संवेदक को अविलंब LOA (Letter of Acceptance) निर्गत करेंगे एवं MBD की ITB की कंडिका 34.1 में निहित प्रावधान के आलोक में निर्धारित 21 दिनों के अन्दर एकरारनामा की कार्रवाई सुनिश्चित करेंगे। विशेष परिस्थिति में उक्त निर्धारित अवधि के पश्चात् एकरारनामा करने हेतु Proper Justification उचित माध्यम से समर्पित करेंगे एवं अधोहस्ताक्षरी के अनुमति के उपरान्त ही एकरारनामा करेंगे।
24. विभागीय पत्रांक-मु0अ0-4 (मु0) विविध-23-291/2014-131, दिनांक 13.12.2019 के आलोक में पत्र प्राप्ति के 24 घंटे के भीतर Letter of Acceptance (LOA) संबंधित संवेदक को निर्गत करेंगे।

कृपया पत्र प्राप्ति की सूचना देंगे।
अनु0-यथा उपर्युक्त।

विश्वासनाजन
ह0/-
मुख्य अभियंता-2

ज्ञापक- 2578 /
प्रतिलिपि :

/पटना, दिनांक- 19-03-23 /23

1. अभियंता प्रमुख, ग्रामीण कार्य विभाग, पटना को सूचनार्थ समर्पित।
2. अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।
3. सहायक आई0टी0 मैनेजर को सूचनार्थ एवं संबंधित अधीक्षण अभियंता/कार्यपालक अभियंता के ई-मेल आई0डी0 पर अपलोड करने हेतु प्रेषित।

मुख्य अभियंता-2