



Prohibition Excise &
Registration Department,
Government of Bihar



INDIA NON JUDICIAL
Other



First Party Name * : Not Applicable
Second Party Name * : RAHUL KUMAR PANKAJ
Purchased By * : RAHUL KUMAR PANKAJ
Certificate Number : BR038162021675319905644
Consideration Price : ₹0.00/-
Stamp Duty Paid : ₹1,100.00/-
Registration Fee & Other Fees : ₹0.00/-
LLR & Proc Fee : ₹0.00/-
Miscellaneous Fees : ₹0.00/-
Discore SC : ₹0.00/-
Total Amount : ₹1,100.00/- (One Thousand One Hundred)



This stamp paper will only be valid if embossed below with special RED ink impression



Phone No.
Sold To/Issued To:
Rahul Kumar
For Show/ID Proof
Pankaj



₹ 0000100/-
28102021675319905644-00000000
2810202 9591

Supplementary Agreement

Supplementary Agreement of AG No-¹⁰...../SBD/20¹⁷⁻¹⁸ Date ¹⁷⁻⁰⁶17.6.23

This agreement, Made the...¹⁷ June...day of 2023.. between Executive Engineer, Rural Works Department, Works Division, Sonpur, Saran [Name and address of employer] of One Part, and SRI RAHUL KUMAR PANKAJ, AT-RAMNAGAR, PO- SADHA, PS- MUFFASIL, SARAN (Hereinafter called "the Contractor) of the other part Whereas the employer is desirous that the Contractor execute **Restoration of Road From Suresh Rai House to Samudayk Bhawan Tak under GTSNY** . (Name and identification number of Contract) (hereinafter called "the works") and the Employer has accepted the Bid by the Contractor) execution and completion of such works and the remedying of any defects therein at a Cost of Rupees. ₹ 5011379 = 00 ₹ 3794224 = 0 ₹ 1217155 = 0

एकरारनामा की पुनरीक्षित राशि- 5011379 = 00

मूल एकरारनामा की राशि- 3794224 = 0

एकरारनामा में अंतर राशि- 1217155 = 0

कार्य समाप्ति की तिथि

Executive Engineer
Rural Works Department
Work Division, Sonpur

Rahul Kumar Pankaj

17.6.23

NOW THIS AGREEMENT WITNESSETH as follow:

1. In This Agreement , words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and constructed as part of this agreement.
2. In Consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and remedy any defects there in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the works and the remedying the defects wherein the Contract price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The Following documents shall be deemed to form and be read and constructed as part of this Agreement, Viz :-
 - I. Letter of Acceptance;
 - II. Notice to proceed with works;
 - III. Contractors Bid;
 - IV. Conditions of Contract: General and Special.
 - V. Contract Data;
 - VI. Additional Conditions
 - VII. Drawings;
 - VIII. Bill of Quantities
 - IX. Any Other documents listed in the Contract Data as following part of the contract.

In witness where of the parties there to have caused this Agreement to be executed the day and year first before written.

The Common Seal of -----

Was hereunto affixed in the presence of :

Signed, Sealed and Delivered by the said -----

In the presence of :

Binding Signature of Employer -----

Binding Signature of Contractor -----

Ramesh Chandra Panigrahy

[Signature]
Executive Engineer
Rural Works Department
Work Division, Sonapur

[Signature]
17/5/2013

अधीक्षण अभियन्ता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, छपरा।

पत्रांक: 509/230

छपरा, दिनांक 16/6/23

प्रेषक,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, छपरा।

सेवा में,

कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सोनपुर।

विषय :- GTSNY योजनान्तर्गत कुल 01 (एक) अदद पथ का प्राक्कलन तकनीकी स्वीकृति उपरान्त एवं पुनरीक्षित परिमाण विपत्र अनुमोदनोपरान्त लौटाने के संबंध में।

प्रसंग :- आपका पत्रांक-1283 अनु0 दिनांक-13.06.2023


महाशय,

उपर्युक्त प्रासंगिक विषय के आलोक में GTSNY योजनान्तर्गत कुल 01 (एक) अदद पथ का प्राक्कलन तकनीकी स्वीकृति उपरान्त एवं पुनरीक्षित परिमाण विपत्र अनुमोदनोपरान्त अग्रेतर कारवाई हेतु भेजा जा रहा है। जो निम्नलिखित है :-


क्र० सं०	प्रखंड का नाम	शीर्ष	पथ का नाम	पथ की लम्बाई (कि०मी०)	परिमाण विपत्र राशि	T.S Amount In Lakh
1	Parsa	GTSNY	Restoration Estimate For Suresh Rai House to Samudayik Bhawan.	0.600	55,68,200	55.682


अनु० :- BOQ एवं प्राक्कलन एक प्रति में।

विश्वासभाजन


16.6.23

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, छपरा।


Executive Engineer
Rural Works Department
Public Division, Sonapur


12/6/23

Tender Inviting Authority: Engg in Chief RWG Patna						
Name of Work: =		Suresh Rai House To Samudayik Bhawan				
Name Of Block =		Patna				
Contract No: Civil Works/						
Bidder Name:		Excess (+)			%	
SCHEDULE OF WORKS						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Providing & Fixing of Working benchmark Piers 01 nos per km. & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I	0.60	ha	7525.34	Rupees Seven Thousand Six Hundred Twenty Five And Paise Thirty Four Only	4575.20
2.00	Reference Pillars	0.60	Cum	5199.81	Rupees Five Thousand One Hundred Ninety Nine And Paise Eighty One Only	3119.89
3.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.30	Cum	46390.19	Rupees Forty Six Thousand Three Hundred Ninety And Paise Nineteen Only	13917.06
4.00	Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross-sections, and transporting to the embankment location with a lift upto 1.5 m and lead upto 1000 m as per Technical Specification Clause 302.3 (Including Royalty & Labour Cess).	16.88	Cum	71.42	Rupees Seventy One And Paise Forty Two Only	1205.57
5.00	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Labour Cess).	803.88	Cum	169.45	Rupees One Hundred Sixty Nine And Paise Forty Five Only	136217.47
6.00	Construction of granular sub-base by providing Well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller achieve the desired density, complete as per Technical specification clause 401.	372.90	Sqm	2379.79	Rupees Two Thousand Three Hundred Seventy Nine And Paise Seventy Nine Only	887423.69
7.00	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501	452.44	Sqm	7566.62	Rupees Seven Thousand Five Hundred Sixty Six And Paise Sixty Two Only	3423441.55
8.00	Kilometre stone - Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC-8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703 Cess) i) km stone ii) 5th km stone	1.00	Sqm	2383.64	Rupees Two Thousand Three Hundred Eighty Three And Paise Sixty Four Only	2383.64
9.00	iii) 200 m stone	2.00	Sqm	622.14	Rupees Six Hundred Twenty Two And Paise Fourteen Only	1244.28

Signature

Signature

Signature
Executive Engineer
 Rural Works Department
 District Division, Sonapur
 17/8/23

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
10.00	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 26, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	12.00	Cum	504.16	Rupees Five Hundred Four And Paise Sixteen Only	6049.92
11.00	Providing and fixing of typical GTSNY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.00	Cum	11083.34	Rupees Eleven Thousand Eighty Three And Paise Thirty Four Only	22166.68
12.00	Providing and fixing of Retro reflective cautionary , mandatory and informatory sign board as per IRC :67 made of 1.5 mm thick MS steel duly stove white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per clause 1701.3.9 of MORD for rural road of required shade and colour supported and welded on 47mmx47mmx12swg sheet tube firmly fixed to the ground by mean of properly designed foundation with M15 grade cement concrete 450x450x600 mm ,600mm below ground level as per approved drawing clause 1701.2.2. 600 mm circular	7.00	Cum	4026.65	Rupees Four Thousand Twenty Six And Paise Sixty Five Only	28186.55
13.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	100.48	nos	244.36	Rupees Two Hundred Forty Four And Paise Thirty Six Only	24554.27
14.00	Sand Filling in Foundation Trenches as per drawing and technical specification Clause 1108.	2.02	nos	447.87	Rupees Four Hundred Forty Seven And Paise Sixty Seven Only	906.08
15.00	Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	14.24	Sqm	5805.31	Rupees Five Thousand Eight Hundred Five And Paise Thirty One Only	82679.23
16.00	Brick masonry work in cement mortar (CM 1:4) in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	56.32	nos	6017.28	Rupees Six Thousand Seventeen And Paise Twenty Eight Only	338893.21
17.00	Brick masonry work in cement mortar (CM 1:4) in substructure and Kerb complete excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	39.39	nos	6711.85	Rupees Six Thousand Seven Hundred Eleven And Paise Eighty Five Only	264406.62
18.00	Plain/Reinforced cement concrete(M-20) in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	4.43	nos	7628.07	Rupees Seven Thousand Six Hundred Twenty Eight And Paise Seven Only	33777.09
19.00	Providing Bitumen painting over top surface of Abutment cap & inner vertical surface of Dirt Wall including Heating the bitumen & cost of painting brush etc. all complete.	15.00	nos	14.38	Rupees Fourteen And Paise Thirty Eight Only	215.70
20.00	RCC M25 in Deck Slab :- Providing and laying reinforced cement concrete in superstructure (Deck slab M25) as per drawing and technical specifications Clauses 800, 1205.4, 1205.5	8.01	per on hege	6928.14	Rupees Six Thousand Nine Hundred Twenty Eight And Paise Fourteen Only	55494.40
21.00	Supplying, fitting and placing HYSD bar reinforcement in super-structure complete as per drawing and technical specifications	1.16	Each	50374.48	Rupees Fifty Thousand Three Hundred Seventy Four And Paise Forty Eight Only	58232.90
22.00	Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 per cent bitumen by weight	15.00	Sqm	33.24	Rupees Thirty Three And Paise Twenty Four Only	498.57
23.00	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	4.32	nos	6264.03	Rupees Six Thousand Two Hundred Sixty Four And Paise Three Only	27060.61

Signature

Signature
Executive Engineer
Rural Works Department
District, Sonapatna

Signature
22/11/23

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
24.00	Plastering with cement mortar (1:4), 15 mm Thick on brick work in sub-structure as per Technical Specifications Clause 613.4 & 1204	88.10	Cum	237.19	Rupees Two Hundred Thirty Seven And Paise Nineteen Only	20897.15
25.00	Providing 1.5 mm cement punning including curing carriage of water with all leads and lifts as per building specification and direction of E/I	29.76	Cum	45.89	Rupees Forty Five And Paise Eighty Nine Only	1365.69
26.00	Providing Weepholes in brick masonry, Plain / Reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing	40.00	Cum	111.04	Rupees One Hundred Eleven And Paise Four Only	4441.49
Total Cost Of Construction (A)						54,43,354.51
27.00	Maintenance for 1st year	1.00	Year	18097.00	Rupees Sixteen Thousand Ninety Seven Only	16,097.00
28.00	Maintenance for 2nd year	1.00	Year	20724.00	Rupees Twenty Thousand Seven Hundred Twenty Four Only	20,724.00
29.00	Maintenance for 3rd year	1.00	Year	25900.00	Rupees Twenty Five Thousand Nine Hundred Only	25,900.00
30.00	Maintenance for 4th year	1.00	Year	29106.00	Rupees Twenty Nine Thousand One Hundred Six Only	29,106.00
31.00	Maintenance for 5th year	1.00	Year	33026.00	Rupees Thirty Three Thousand Twenty Six Only	33,026.00
Total Cost Of Maintenance (B)						1,24,853.00
Total Estimated Cost in Figures (A+B)						55,68,207.51
Quoted Amount				55,68,207.51		55,68,208.00
Quoted Rate in Words				Rupees Fifty Five Lakh(s) Sixty Eight Thousand Two Hundred Eight Only		

Say = 5568200/-

13/6/23
1E

Executive Engineer
Rural Works Department
Work Division, Sonapur

Revised BOQ having sl No-1 to 31, amounting Rs = 5568200/-
(Rs Fifty five lakhs sixty eight thousand and two hundred only)
is hereby approved:

16/6/23
हाकिमन प्रधानाधिकारी
हामीय कार्य विभाग
कायं संचन कक्षा

16/06/23
TECHNICAL ADVISER
RURAL WORKS DEPTT.
WORKS CIRCLE, CHAPRA

16.6.23
Superintending Engineer
Rural (Works) Deptt.
Circle, Chapra

Kumar-Purwar

Executive Engineer
Rural Works Department
Division, Sonapur

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक—
प्रेषक,

BRRDA(HQ)GTSNY-248/22- 866

पटना, दिनांक- 24/05-2023

संजय दूबे (भा.प्र.सो.)
विशेष सचिव,
ग्रामीण कार्य विभाग,
बिहार, पटना।

सेवा में,

महालेखाकार (लेखा एवं हकदारी)
बिहार, पटना।

विषय :

योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय (सामान्य)-लघु शीर्ष-103- ग्राम विकास राज्य योजना उप शीर्ष-0119-ग्रामीण टोला सम्पर्क निश्चय योजना, 5301-मूल निर्माण कार्य के अन्तर्गत राज्य के सारण जिला में कार्य प्रमंडल, सोनपुर के क्षेत्राधीन ग्रामीण टोला सम्पर्क निश्चय योजना अंतर्गत परसा प्रखंड में "Suresh Rai House To Samudayik Bhawan" पथ निर्माण कार्य जिसकी लम्बाई 0.600 कि०मी० है, के मूल निर्माण कार्य हेतु Rs. 54.433 लाख एवं पंचवर्षीय अनुरक्षण की राशि Rs. 1.249 लाख अर्थात् कुल राशि Rs. 55.682 लाख (पचपन लाख अरसठ हजार दो सौ रुपये मात्र) की लागत पर पुनरीक्षित प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महाशय,

ग्रामीण टोला सम्पर्क निश्चय योजनान्तर्गत कार्य प्रमंडल, सोनपुर में वित्तीय वर्ष 2023-24 के लिए पथ निर्माण की कुल 1 (एक) योजना "Suresh Rai House To Samudayik Bhawan" के निर्माण कार्य हेतु निम्न तालिका के स्तम्भ-13 में अंकित राशि की पुनरीक्षित प्रशासनिक स्वीकृति प्रदान की जाती है।
तालिका

Sl. No.	District	Works Division	Block	GTSNY Sl. No.	Habitat ion Code	Name of Road	Length (km)	Revised AA Amount				
								(In Lakh)				
								Const. Amt	5 Yrs. Maint. Amt	Total Amt	Cost of Land	Grand Total
1	2	3	4	5	6	7	8	9	10	11	12	13
1	Saran	Sonpur	Parsa	3516	3303	Suresh Rai House To Samudayik Bhawan	0.600	54.433	1.249	55.682	0.000	55.682
Total							0.600	54.433	1.249	55.682	0.000	55.682

- योजना की तकनीकी स्वीकृति प्रदान किये जाने के पूर्व संबंधित कार्यपालक अभियंता तथा अधीक्षण अभियंता यह सुनिश्चित कर लेंगे कि प्राक्कलन में प्रावधानित सभी मद GTSNY के दिशा-निर्देशों के अनुरूप हैं तथा निर्माण सामग्रियों की दुलाई का प्रावधान निकटतम स्रोत से विभागीय दिशा-निर्देश के आलोक में है।
- इस योजना को वर्ष 2023-24 में पूरा किये जाने का लक्ष्य है।
- कार्यपालक अभियंता, कार्य प्रमंडल, सोनपुर योजना की विस्तृत कार्य योजना तैयार करेंगे तथा उसके अनुरूप कार्यों को समयबद्ध ढंग से पूर्ण कराना सुनिश्चित करेंगे।

Rohit K. Panjari

Executive Engineer
Rural Works Department
Sonpur Division, Sonpur

24/5/23

आंतरिक वित्तीय सलाहकार द्वारा अनौपचारिक रूप से परामर्शित

5. कार्यपालक अभियंता, कार्य प्रमंडल, सोनपुर सुनिश्चित करेंगे कि स्वीकृत पथ किसी अन्य योजना अन्तर्गत सम्मिलित नहीं है।
6. कार्यपालक अभियंता, कार्य प्रमंडल, सोनपुर योजना के कार्य सम्पादन हेतु निकासी एवं व्ययन पदाधिकारी होंगे।
7. कार्यों की गुणवत्ता सुनिश्चित करने की जिम्मेवारी संबंधित कार्यपालक अभियंता की होगी। किये गये कार्यों का भुगतान गुणवत्ता के जाँच फल के गुण-दोष के आधार पर किया जायेगा।
8. कार्यों का क्रियान्वयन GTSNY की मार्गदर्शिका के आलोक में किया जायेगा।
9. योजना के कार्यान्वयन के पूर्व डी0पी0आर0 पर सक्षम पदाधिकारी से प्रावधिक स्वीकृति प्राप्त कर ली जायेगी। वित्त विभाग के संकल्प संख्या-एम-4-53/2007-3758/वि0 पटना दिनांक-31.05.2017 के कंडिका 5 में अंकित निदेशों का पूरी तरह पालन किया जाय।
10. योजना की तकनीकी स्वीकृति प्रदान किये जाने के क्रम में प्रावधानित प्रत्येक मद की संभाव्यता की जाँच सक्षम प्राधिकार द्वारा सुनिश्चित किया जायेगा।
11. (क) बिहार कोषागार संहिता में निहित प्रावधानों के आलोक में बजट प्रावधान के अन्तर्गत ही राशि की निकासी की जाय।
(ख) वित्त विभाग के संकल्प संख्या-एम-4-53/2007-3758/वि0 पटना दिनांक -31.05.2017 में निहित निदेशों का अक्षरशः पालन किया जाय तथा बिहार वित्त नियमावली के सुसंगत प्रावधानों के आलोक में योजना में उपबंधित राशि की उपलब्धता के आधार पर व्यय की जाय।
(ग) यह राशि उसी मद में खर्च की जायेगी, जिसके लिए पुनर्विनियोजित की गयी है, अन्य मद में नहीं।
(घ) प्राक्कलन की विशिष्टताओं के अनुसार निर्धारित समयावधि के अन्दर कार्य पूर्ण कराना सुनिश्चित किया जाय।
(ङ) योजना के कार्यान्वयन के क्रम में इनका निर्धारित निरीक्षण (नियमित अन्तराल पर) अनिवार्य रूप से किया जाय तथा प्रतिवेदन अमिलेखबद्ध किया जाय।
12. कार्यपालक अभियंता, संबंधित कार्य प्रमंडल द्वारा योजना का वित्तीय एवं भौतिक प्रतिवेदन प्रत्येक माह की पाँच तारीख तक ऑनलाईन प्रविष्ट कराते हुए अधीक्षण अभियंता एवं मुख्य अभियंता के माध्यम से विभाग को निश्चित रूप से उपलब्ध करायेंगे।
13. इस योजना की पुनरीक्षित प्रशासनिक स्वीकृति के लिये सक्षम प्राधिकार माननीय उप मुख्य (ग्रामीण कार्य) मंत्री महोदय द्वारा संचिका सं0-BRRDA(HQ)GTSNY-248/22 के पृष्ठ सं0-09/टि0 पर अनुमोदन प्राप्त है।
14. इस योजना मद में व्यय, बजट से प्राप्त राशि की उपलब्धता के आधार पर मरम्मत शीर्ष 3064 से किया जायेगा। यह आदेश वित्त विभाग की संकल्प पत्रांक-एम0 4-53/2007-3758/वि0 पटना, दिनांक 31.05.2017 की कंडिका-4 एवं 5 में निहित प्रावधान के आलोक में एवं संचिका सं0-BRRDA(HQ)GTSNY- 248/22 के पृष्ठ सं0- 13 / टि0 पर दिनांक 24.5.2013 को जारी

Fuller Parker

Executive Engineer
Public Works Department
Division, Sonap

सचिव महोदय के आदेशानुसार आंतरिक वित्तीय सलाहकार की सहमति से निर्गत किया जा रहा है।
आंतरिक वित्तीय सलाहकार की सहमति संचिका सं०-BRRDA(HQ)GTSNY-248/22 के पृष्ठ
सं०-13/टि० पर दिनांक 12.5.2023 को प्राप्त है।

विश्वासभाजन

24/5/2023

विशेष सचिव
ग्रामीण कार्य विभाग,
बिहार, पटना

ज्ञापांक:- BRRDA(HQ)GTSNY-248/22 866 /पटना, दिनांक- 24.05.2023
प्रतिलिपि:- संबंधित कोषागार पदाधिकारी, जिला कोषागार/उप कोषागार को सूचनार्थ एवं आवश्यक
कार्रवाई हेतु प्रेषित।

24/5/2023

विशेष सचिव

ज्ञापांक:- BRRDA(HQ)GTSNY-248/22 866 /पटना, दिनांक- 24.05.2023
प्रतिलिपि:- माननीय उप मुख्य (ग्रामीण कार्य) मंत्री महोदय के आप्त सचिव, प्रधान सचिव, योजना एवं
विकास विभाग/वित्त विभाग (आय-व्यय शाखा)/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/
प्रमण्डलीय आयुक्त, सारण/जिला पदाधिकारी, सारण/उपविकास आयुक्त, छपरा/अभियंता प्रमुख,
ग्रामीण कार्य विभाग, पटना/अवर सचिव, बजट शाखा, ग्रामीण कार्य विभाग/मुख्य अभियंता-3,
ग्रामीण कार्य विभाग, पटना/मुख्य अभियंता-4, ग्रामीण कार्य विभाग/अधीक्षण अभियंता, कार्य अंचल,
छपरा/कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमण्डल, सोनपुर को सूचनार्थ एवं आवश्यक
कार्रवाई हेतु प्रेषित तथा IT Manager ग्रामीण कार्य विभाग को विभाग के वेबसाइट पर अपलोड करने
हेतु प्रेषित।

24/5/2023

विशेष सचिव

jm m

Rohit K. Singh

Executive Engineer
Rural Works Department
Sonepur

13/5/23