

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000



बिहार BIHAR

पूजापत्र
निवेदन

06

प्रमाणित

Mahadev Construction & Baxaghat Road Seta
- Old Rs Chat -

AE 067601

10/12/19
Binay Kumar Singh

STAMP VENDOR

10/12/19, PURNE

**S.B.D
MMGSY
Agreement**

08/01/2020

Executive Engineer

Rural Works Department

Works Division, Dhamdaha (Purnea)

Agreement No.- 33 SBD / 20.12.19

Name and Firm of contractor:- Mahadev Construction

Name of Work- Construction of Road from Dibra Dhani to Dibra Dhani Tola

Agreement Value:- Rs. 97,91,152.00 (Ninety Seven Lakh Ninety One Thousand One Hundred & Fifty Two Only)

Date of Agreement :- 08/01/2020

Date of Completion :- 07/01/2024

This agreement made on 08/01/2020 between Executive Engineer, R.W.D. Works Division, Dhamdaha, Purnea. [Name and address of Employer] (hereinafter called

"The Employer") of the one part and :- Mahadev Construction, Mahadev Construction, Pro- Shree Prakash Jha, Baxa Ghat, Purnea. [Name and address of Contractor] (herein after called the "Contractor" of the other part). Whereas the

Employer is desirous that Contractor execute the Construction of Road from Dibra Dhani to Dibra Dhani Tola [Name and identification number of Contract] [Herein after Called the works"] and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the Remedying of any Defects therein Such as 5 years Routine Maintenance, as a Cost of Rs. 97,91,152.00 (Ninety Seven Lakh Ninety One Thousand One Hundred & Fifty Two Only).

Mahadev Construction

Proprietor

मुख्य अभियंता-2 का कार्यालय
ग्रामीण कार्य विभाग, पटना।

/पटना, दिनांक- 18.11.17

पत्रांक- 4301
प्रेषक,

ई0 योगेश्वर पाण्डेय
मुख्य अभियंता-2
ग्रामीण कार्य विभाग, पटना।

सेवा में,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, पूर्णियाँ।

विषय : शीर्ष MMGSY योजनान्तर्गत कार्य प्रमण्डल, धमदाहा के अधीन Dibra Dhani To Dibra Dhani तक
(Tender ID- 82032) पथ निर्माण कार्य की निविदा की स्वीकृति के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में बिहार लोक निर्माण संहिता के कंडिका-163 के आलोक में इस कार्य को द्वारा के योग्य एवं सफल न्यूनतम दरदाता Mahadev Construction (Bid ID-372021) को उनके द्वारा निविदा दर, जो परिमाण विपत्र के दर से -09% (शून्य नौ) प्रतिशत कम है, को स्वीकृत करते हुए सम्पूर्ण कार्य कुल 97,91,152/- (सन्तानवें लाख एकानवें हजार एक सौ बावन) रुपये मात्र की लागत पर आपकी अनुशंसा एवं कार्यहित में आवंटित किया जाता है।

- निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।
- संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ जमा किये गये संबंधित एन0एस0सी0/Fixed Deposit/BG आदि का सत्यापन संबंधित डाकघर/बैंक से कराकर प्रमंडलीय कार्यालय में अभिलेखित किया जायेगा। कार्यपालक अभियंता कार्य प्रमंडल, धमदाहा कार्यादेश निर्गत करने के पूर्व अग्रचन की राशि के सत्यापन से संबंधित कागजात अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।
- एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जायेगा।
- एकरारनामा से पूर्व कार्यपालक अभियंता यह सुनिश्चित कर लेंगे कि निविदाकार डिवार सूची/काली सूची या कार्य लंबित सूची में शामिल न हो।
- कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य करता समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।
- इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावैधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लेखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।
- अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करायेगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की जायेगी।
- एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जांच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।
- कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपबंध से पूरी तरह आश्वस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावैधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये निदेश का अनुपालन सुनिश्चित करायेंगे। पथ का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, प्रशासनिक स्वीकृति की राशि, संवेदक द्वारा उद्धृत दर, परक्रमित दर Bid Capacity आदि का मिलान कर ही कार्य आवंटन आदेश निर्गत करेंगे। अधीक्षण अभियंता/कार्यपालक अभियंता कार्य आवंटन/L0A निर्गत करने से पूर्व मिलान कर लेंगे कि परिमाण विपत्र की राशि प्रशासनिक अनुमोदन की राशि के अनुज्ञेय सीमा के अन्दर है; यदि अनुज्ञेय सीमा से अधिक हो तो एकरारनामा के पूर्व पुनरीक्षित प्रशासनिक अनुमोदन प्राप्त कर लिया जाय।
- कार्यादेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु मासिक कार्य प्रोग्राम हस्ताक्षरित कराकर प्राप्त कर लेंगे जो की एकरारनामा का भाग होगा।

Dhamda Finle

- अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुक्रम निर्धारित अवधि के अंदर पूरा की जायेगी।
13. कार्य समाप्ति की अवधि निविदा आमंत्रण सूचना के अनुसार होगी।
14. इस कार्य का लक्ष्य शीर्ष **MMGSY** योजनान्तर्गत से मिलने वाले राशि अन्तर्गत उपबंधित राशि से विकसित होगा।
15. कार्य का प्रगति प्रतिवेदन प्रत्येक गहीने की सातवीं तारीख तक निश्चित रूप से इस कार्यालय को समर्पित की जाय।
16. सभी निविदा कागजात एवं तुलनात्मक विवरणी की मूल प्रति आवश्यक कार्रवाई हेतु लौटाई जाती है। आप निविदा कागजातों एवं तुलनात्मक विवरणी के जांचोपरांत आप आवश्यक निदेशों को अपने स्तर से निर्गत करेंगे।
17. एकरारनामा से पहले निविदाताओं द्वारा दिये गये कागजात का सत्यापन उनके मूल कागजात से मिलान कर लेंगे। कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रबंधन, धनदाहा तुलनात्मक विवरणी की एक अनिप्रमाणित प्रति अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णियों को अभिलेख हेतु उपलब्ध करा देंगे। निदेश दिया जाता है कि संवेदक से कार्य प्रोग्राम प्राप्त कर लेंगे तथा उनका कार्यक्षमता कुशलता एवं पूर्व से आवंटित कार्यों की प्रगति से संतुष्ट हो लें।
18. इस निविदा की राशि में अगर कोई अंतर होता है तो इसकी सूचना तुरन्त इस कार्यालय को दी जाय।
19. कार्यपालक अभियंता, एकरारनामा करने के पूर्व संवेदक का निबंधन संख्या, पूर्ण पता एवं दूरभाष संख्या कार्यादेश में अंकित करेंगे तथा इस कार्यालय को सूचित करेंगे।
20. परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा निदेश के आलोक में अतिरिक्त वांछित परफॉरमेंस सिक्चरिटी की राशि जमा कराना सुनिश्चित करेंगे।
21. किसी भी परिस्थिति में निजी जमीन पर निर्माण नहीं कराया जाय।
22. प्रत्येक 15 दिनों पर संवेदक से स्वहस्ताक्षरित विपत्र प्राप्त कर स्थल से मिलान कर मापी पुस्तिका में मापी दर्ज कर भुगतान सुनिश्चित करेंगे।
23. कार्यपालक अभियंता कार्यावंटन आदेश प्राप्त होते ही संवेदक को अविलंब **LOA (Letter of Acceptance)** निर्गत करेंगे एवं **SBD** की **ITB** की कंडिका 31.1 में निहित प्रावधान के आलोक में 15 दिनों के अन्दर **Performance Security** प्राप्त कर लेंगे। **LOA** निर्गत करने की तिथि से 21 दिनों के अन्दर एकरारनामा की कार्रवाई सुनिश्चित करेंगे। निर्धारित अवधि के अन्दर **Performance Security** जमा नहीं करने की स्थिति में **ITB** की कंडिका 31.3 के आलोक में कार्रवाई करते हुए अधीक्षण अभियंता के माध्यम से प्रस्ताव अधोहस्ताक्षरी को समर्पित करेंगे। विशेष परिस्थिति में निर्धारित अवधि के पश्चात एकरारनामा करने हेतु **Proper Justification** के साथ प्रस्ताव उचित माध्यम से समर्पित करेंगे एवं अधोहस्ताक्षरी के अनुमति के उपरान्त ही एकरारनामा करेंगे।

कृपया पत्र प्राप्ति की सूचना देंगे।

अनु0-यथा उपर्युक्त।

विस्वात्मज्जन

28.11.17

मुख्य अभियंता-2

ग्रामीण कार्य विभाग, पटना।

आपाड - 11808 (शुक्रवार/दिनांक:- 24/11/2017)

नतिनिधि:- आर्गपाकड अभियंता, ग्रामीण कार्य विभाग, पटना।
कार्यपालक अभियंता, ग्रामीण कार्य विभाग, पटना।
कार्रवाई हेतु प्रेषित।

अधीक्षण अभियंता
ग्रामीण कार्य विभाग, पटना।



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

Govt. Of Bihar

MMGSY

Bill Of Quantity

DIBRA DHANI TO DIBRA DHANI

District :	:	-	PURNEA
Block :	:	-	BARHARA KOTHI
Package No :	:	-	
Link No. :	:	-	S0
Total Length :	:	-	1.000 KM
Construction Cost : (In Rs.)	:	-	88,89,140.48
Maintenance Cost : (In Rs.)	:	-	9,10,951.76
Total Project Cost : (In Rs.)	:	-	98,00,092.24

Submitted By: ◆

Bill Of Quantity (BOQ)

Road : DIBRA DHANI TO DIBRA DHANI

District : PURNEA

Length : 1.000 KM

Block : BARIHARA KOTIII

Total Construction Cost (With Gst 12% + L.C 1%) :

88,89,140.40

Link No : 50

Total Maintenance Cost (With Gst 12% + L.C 1%) :

9,10,951.76

Package No

Sl. No.	Description Of Work	Qty.	Unit	Rate	AMOUNT (In Rs.)
1.00	Setting Out Pillars	1.00	Km	33472.22	33472.00
2.00	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I	0.35	Ha	49496.70	17324.00
3.00	SUB HEAD : EARTHWORK Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a <u>lead upto 1000 m</u> as per Technical Specification Clause 301.5 .	953.08	Cum	184.19	175548.00
4.00	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a <u>lead upto 100 m</u> as per Technical Specification Clause 301.5 .	1131.06	Cum	147.35	166662.00
5.00	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	2416.75	Cum	176.75	427161.00
6.00	SUB HEAD : BITUMINOUS ITEMS Granular Sub-base (Grading-I) Construction of Gravel/Soil-aggregate base by providing well graded material, spreading in uniform layers with motor pn prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kn static roller to achieve the desired density, complete as per Technical Specification Clause 402.(With Coarse Sand)	572.67	Cum	2951.83	1690424.00
7.00	WBM Grading 3 (By Maclnical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.(With Stone Screening Type "B" 11.2mm)	284.06	Cum	3663.47	1040645.00
8.00	Prime Coat (Low porosity) Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.80 kg/sqm using mechanical means as per Technical Specification Clause 502.	2651.25	Sqm	42.55	112811.00

Sl. No.	Description Of Work	Qty.	Unit	Rate	AMOUNT (In Rs.)
29.00	Providing PCC Grade M20 concrete for plain/reinforced concrete in Sub Structure(Retain Wall) complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	51.47	Cum	5456.18	280802.00
30.00	RCC GRADE M-25 Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	9.75	Cum	7357.48	71735.00
31.00	RCC GRADE M-25 Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5	13.56	Cum	7517.84	101942.00
32.00	Filter media behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	21.50	Cum	2426.86	52187.00
33.00	Providing Weepholes.	36.00	Nos	242.98	8747.00
34.00	Providing Pressure Relief Pipe.	6.00	Nos	413.96	2484.00
35.00	Providing Boulder Aprons.	20.40	Cum	3236.02	66015.00
36.00	R.C.C Railing	5.00	M	6511.24	32556.00
37.00	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	3.38	M	62984.42	213026.00
Total Construction Cost:					78,66,496.00
Add Gst 12%:					9,43,979.52
Add L.C 1%:					78,664.96
Total Construction Cost (With Gst 12% + L.C 1%):					88,89,140.48
38.00	First Year Maintenance Cost	1.000	Year	41990.00	41990.00
39.00	Second Year Maintenance Cost	1.000	Year	53081.00	53081.00
40.00	Third Year Maintenance Cost	1.000	Year	259629.00	259629.00
41.00	Forth Year Maintenance Cost	1.000	Year	136060.00	136060.00
42.00	Fifth Year Maintenance Cost	1.000	Year	315392.00	315392.00
Total Maintenance Cost:					8,06,152.00
Add Gst 12%:					96,738.24
Add L.C 1%:					8,061.52
Total Maintenance Cost (With Gst 12% + L.C 1%):					9,10,951.76
Total Estimated Cost ((With Gst 12% + L.C 1%):					98,00,092.24

98,00,092.24

For
09/07/19


and
25/7/19
EE

AO

(B.O.Q approved for Rs 9800098/- (Rs _____

Crore... ninty eight Lac. _____

Thousand _____ Hundred ninty two only)


26/7/11
SUPERINTENDING ENGINEER
R.W.D. WORKS CIRCLE, PURNIA

26/07/11