

कार्यपालक अभियंता, का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ

पत्रांक 451/313/ बिहारशरीफ, दिनांक 24.4.2024

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बिहारशरीफ ।

सेवा में,

नोडल पदाधिकारी NABARD MAINTENANCE
ग्रामीण कार्य विभाग बिहार पटना।

विषय:-

शीर्ष NABARD मरम्मति/अनुरक्षण योजनान्तर्गत पूर्ण पथों का 5-वर्षीय रूटीन अनुरक्षण कार्य के कार्यान्वयन हेतु अधियाचना पत्र समर्पित करने के संबंध में।

महापय,

NABARD मरम्मति/अनुरक्षण योजनान्तर्गत पूर्ण पथों का 5-वर्षीय रूटीन अनुरक्षण कार्य संवेदक द्वारा कराये गये पथों में एकरारनामा के अनुसार राशि की अधियाचना पत्र समर्पित की जा रही है।

अनुरोध है कि 5-वर्षीय रूटीन अनुरक्षण कार्य कराने हेतु संलग्न सूची के अनुसार राशि उपलब्ध कराने की कृपा की जाय ताकि संवेदक को भुगतान किया जा सके।

अनु०:- यथोक्त।

24/4/24

विश्वासभाजन

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बिहारशरीफ

24/4/24

FORM GFR 19-A

(See Government of India's Decision (1) below Rule-150)

Form of Utilisation Certificate up to the month of -20.4.2024

(NABARD MAINTENANCE FUND)

PIU- BIHARSHARIF

Year-2024-25


Sl. No.	Name of Scheme	Sanction No. & Date with Amount (in Rs. Lacs)	Amount Received (in Rs. Lacs)	Particulars	Remarks
1	Construction of Rural Roads under NABARD (4515) MAINTENANCE FUND	Order No-8466 Date-30.01.2023	22.48793	Certified that out of Rs 22.48793 received & balance during the years 2024-25 in favour of Ex. Engineer, R.W.D. Works Division Biharsharif, sum of Rs 22.48793 has been utilized for the purpose of NABARD MAINTENANCE FUND scheme as given in the margin for which it was sanctioned and that the balance of Rs 0.0 lacs remaining unutilized at the end of the period under- 20.04.2024	
	Total Rs.		22.48793		



2 Certified that I have satisfied myself that the conditions on which the grants-in- aid was Kind of Checks exercised :-

- Works have been supervised by Executive Engineer/Superintending Engineer.
- Periodical inspection has been conducted by Executive Engineer/Superintending Engineer.
- Construction material have been tested.
- Measurements have been recorded in the MBs and test check conducted by the Assistant .
- All other codal formalities have been observed.

3 Physical Progress achieved:

- Construction of Road Works.
- Construction of CD works


24/4/24
Divisinal Accounts Officer
Rural Works Department
Works Division Biharsharif


24/4/24
Executive Engineer
Rural Works Department
Works Division Biharsharif

24/4/24

राज्य योजना (नाबार्ड) अन्तर्गत पथों में पंचवर्षीय अनुरक्षण अधियाचना प्रपत्र

राज्य योजना (नाबार्ड) अन्तर्गत पथों में पंचवर्षीय अनुसूक्षण अधियाचना प्रपत्र																													
क्र. सं०	कार्य का वर्णन, विवरणात्मक	एकराशना के अनुसार प्राकल्पित राशि वर्षवार					व्यय की राशि वर्षवार					कुल राशि (लाख में)	प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि(लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि(लाख में)	कुल राशि (लाख में)	प्रशासनिक स्वीकृति की राशि एवं प्रमाण दिनांक सहित पत्रांक (लाख में)	पंचवर्षीय अनुसूक्षण की राशि सहित अनुमानित स्वीकृति का पत्रांक/दिनांक (लाख में)	अनुसूक्षण हेतु प्रस्तावित स्वीकृति का वार्षाधिक निधि	वर्तमान अधियाचित राशि					कुल राशि (लाख में)	कुल अधियाचित राशि (लाख में)	Remain k.s
		प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि(लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)	प्रथम वर्ष राशि(लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)																		
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27			
		Slh-78 to Kuthar	0.296	0.389	0.663	0.919	1.0859	3.35303	0.29593	0.6544	1.10543			2.05579	137.67 1901/ 08.08.16	3.726		28.03.2018				1.53341	1.81120	3.34461	3.34461	1341/29 09.23			
2		Sare Nuawan road of Nuawan to Nuawan Sarhabli High Level Bridge	1.1068	1.9226	7.4383	4.4192	5.2369	20.12385	0	0	0	0	0	0.00000	145.614 1652/01.06 2020	13.553	1652/01.06 2020	24.04.2022	1.0808	1.89753				2.97835	2.97835	972/19 07.2023			
3	Biharshahri	Raghuaship ur Darogh To Village Lamapur Via Daulatpur	0.31180	0.45945	2.94561	1.02282	3.28860	8.02528	0.3118	0	0	0	0	0.31180	94.376 779/26.02.2 019	8.946	779/26.02.201	27-12-2020		0.52071	0.80116				1.32187	1.32187	972/19 07.2023		
4		Bihar Nigay Road to Mathurapur Road in Chandunsa More to Hwasanpura south west	0.38072	0.45669	5.94710	0.78051	6.17612	13.74114	0	0	0	0	0	0.00000	197.818 829/27.02.2 019	13.823	829/27.02.2 019	30-12-2020	0.2934	0.36394	0.64571				1.30301	1.30301	972/19 07.2023		
Total-																										8.94784			

1 कार्य विवरणों के अनुरूप पूर्ण कर लिया गया है।

2 पथ में MOMU/POM/IE से संबंधित कोई सुधार प्रतिवेदन लक्षित नहीं है।

3 अनुमानित परिमाण विपत्र की कुल राशि प्रशासनिक स्वीकृति की राशि से 20% अधिकतम सीमा के भीतर है साथ ही अनुमानित परिमाण विपत्र के मदों की मात्रा का विस्तार का विवरण

4 अनुमानक - प्रशासनिक स्वीकृति का पत्र अनुमानित परिमाण विपत्र एवं एकराशना की अभिप्रायित प्रति।

प्रमंडलीय लेखा पदाधिकारी
ग्रामीण कार्य विभाग
कार्य प्रबन्धन, बिहारराशिक

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रबन्धन, बिहारराशिक
20/03/24



ग्रामीण कार्य विभाग
Rural Works Department, Govt of Bihar

SBD GREEMENT
NABARD RAJYA YOJNA

UNDER

RWD WORKS DIVISION BIHARSHARIF

Main work - 82,29,797/-
Maintenance - 8,02,828/-
Total - 90,32,625/-

C/S Approved By S.E. RWD Work Circle Nalanda Vide Letter 1834(we) Dated 28.10.19

PROJECT NAME :- CONST. OF ROAD FROM RAGHUNATHPUR

DARGAH KE GRAM LAKSHMIPUR VIA

DAULATPUR ROAD INCL. FIVE YEAR MAINT.

REGISTRATION NO.-

1190187 CLASS-I, PAN NO.- AFXPC7065D

TEENDER ID- 78350

BID ID- 357185

NAME OF CONTRACTOR :- BRAHM PRAKASH CHOUDHARY

CONTRACTOR ADD. :- NAISARAI, BIHARSHARIF, NALANDA.

BLOCK :- RAHUI

AGREEMENT No. :- SBD- 53.../2019-20

ACCEPTED RATE :- 10.00% Below of BOQ Rate.

AGREEMENT Value :- Rs. 90,32,625.00

WORK STARTED DATE :- 18/11/19

INTENDED DATE OF COMPLETION:- 17/11/2020

original copy

Received


Brahm Prakash Choudhary

Executive Engineer
R.W.D. Work Division

Biهارsharif

Misc
18/11/19

18/11/19



सुन्दाक विक्रता जा.नं.4/34
जि.पा.प्र.प. (वा.प.प.)

Between Executive Engineer, Rural Works Department, Works Division,
Biharsharif under Plan Head Nabard (Rajya Yojna) for BRRDA 5th Floor
Vishweshwaraiya Bhawan, Jawaharlal Nehru Marg, Patna.- 15 (Name and address
of Employer) (hereinafter called" the Employer") of part, and,
Brahm Prakash Choudhary,
Patel Nagar, Nai Sarai,
Biharharif, Nalanda.

Whereas the Employer is desirous that the Contractor execute of the of Construction of Road from Raghunathpur Dargah Ke Gram Lakshimpur Via Daulatpur Road including five year maintenance under Head Nabard Rajya Yojna. [Name and identification number of Contract] (here in after called" the works") and the Employer has accepted the Bid by the Contractor for the execution and completion of such Works and the remedying of any defects there in at a cost of Rupees 90,32,625.00 (Ninety Lacs Thirty Two Thousand Six Hundred & Twenty Five) only i.e on 10.00% (Ten Point Zero Percent) below of Estimated Rate with the intended completion date for the whole of the works 12 (Twelve) months from the date of issue of LOA.

Brotherhood of the Church.

Executive Engineer
R.W.D. Work Division
Marsharif

Tender Inviting Authority: Engg-in Chief RWD Patna

Percentage BoQ

Name of Work: Raghunathpur Dargah to Laxmipur Village Via Daultapur

Contract No: Civil Works/

Name of the Bidder/

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words		
1	2	3	4	5	6	7		
1	Providing & Fixing of Working benchmark/Reference Pillars 01 nos. per km & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I				0.00	INR Zero Only		
2	Benchmark Pillars 01 nos. per km	2	No	3871.21	7742.42	INR Seven Thousand Seven Hundred & Forty Two and Paise Forty Two Only		
3	Reference Pillars 04 nos. per km	5	No	1745.09	8725.45	INR Eight Thousand Seven Hundred & Twenty Five and Paise Forty Five Only		
4	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I (By Manual Means) In area of non-thorny	0.92	Hect.	49496.70	45536.96	INR Forty Five Thousand Five Hundred & Thirty Six and Paise Ninety Six Only		

Bidder's Signature

Executive Engineer
R.W.D. Work Division
Patna
Signature
18/11/19

5	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	1271.17	Cum	174.83	222238.65	INR Two Lakh Twenty Two Thousand Two Hundred & Thirty Eight and Paise Sixty Five Only
6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5	581.29	Cum	130.86	76067.61	INR Seventy Six Thousand & Sixty Seven and Paise Sixty One Only
7	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour	3359.06	Cum	176.96	594419.26	INR Five Lakh Ninety Four Thousand Four Hundred & Nineteen and Paise Twenty Six Only
8	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. (For Grading I Material)	927.03	Cum	1836.40	1702397.89	INR Seventeen Lakh Two Thousand Three Hundred & Ninety Seven and Paise Eighty Nine Only
9	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical	375.81	Cum	2564.01	963580.60	INR Nine Lakh Sixty Three Thousand Five Hundred & Eighty and Paise Sixty Only
10	Prime Coat (Low Porosity) :- Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause	3672.00	Sqm	41.12	150992.64	INR One Lakh Fifty Thousand Nine Hundred & Ninety Two and Paise Sixty Four Only

Prakash Khandke

Cultive Engineer
R.W.D. Work Division

Biharshari

11	Tack Coat:- Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	3672.00	Sqm	13.95	51224.40	INR Fifty One Thousand Two Hundred & Twenty Four and Paise Forty Only
12	Mix Seal Surfacing Type B Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN Cement Concrete Pavement M30	3672	Sqm	181.88	667863.36	INR Six Lakh Sixty Seven Thousand Eight Hundred & Sixty Three and Paise Thirty Six Only
13	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501.	214.20	Cum	6101.94	1307035.55	INR Thirteen Lakh Seven Thousand & Thirty Five and Paise Fifty Five Only
14	Hard Shouldering :- Laying brick soling layer on prepared sub-grade with brick on end edging according to lines, graded and cross-section shown on the drawing filling joints with sand and earth, spreading 25 mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kN as per Technical Specification Clause 412	175.00	sqm	542.59	94953.25	INR Ninety Four Thousand Nine Hundred & Fifty Three and Paise Twenty Five Only

Binahar Patel

Executive Engineer
R.W.D. Work Division
Nishtar
18/11/19

15	Reinforced cement concrete M15 grade kilometre stone local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703				0.00	INR Zero Only
16	Ordinary Kilometer Stone (Precast)	2	Each	1883.67	3767.34	INR Three Thousand Seven Hundred & Sixty Seven and Paise Thirty Four Only
17	200 m stone (precast)	5	Each	548.58	2742.90	INR Two Thousand Seven Hundred & Forty Two and Paise Ninety Only
18	(1) Providing and Fixing 'Logo' of MMGSY Project :- Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4	Each	9035.94	36143.76	INR Thirty Six Thousand One Hundred & Forty Three and Paise Seventy Six Only
19	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	132	per cm height per letter	0.50	66.00	INR Sixty Six Only
20	Boundary Pillar/ Guard Post Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	24	No	463.27	11118.48	INR Eleven Thousand One Hundred & Eighteen and Paise Forty Eight Only

Barbari Patel Chaudhary

Executive Engineer
R.W.D. Work Design
Biharshah

Sl	Ordinary Kilometer Stone (Precast)	Grade 8:20:100 fixing in kilometre	M15 grade concrete	Reinforced stone local stone of standard design as per IRC:8:20:100 and Technical Specification Clause 1703	91	51
21	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sheeting vide Clause 1701.2.3 fixed over aluminium post 75 mm x 75 mm thick supported on a mild steel angle iron means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801					
22	600 mm equilateral & triangle	10	Each	3605.62	0.00	INR Zero Only
23	800 mm x 600 mm rectangular	4	Each	36056.20		INR Thirty Six Thousand & Fifty Six and Paise Twenty Only
24	600 mm x 450 mm rectangular	4	Each	27402.04		INR Twenty Seven Thousand Four Hundred & Two and Paise Four Only
25	900 mm side octagon, OR	4	Each	18989.36		INR Eighteen Thousand Nine Hundred & Eighty Nine and Paise Thirty Six Only
26	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	2	Each	17546.82		INR Seventeen Thousand Five Hundred & Forty Six and Paise Eighty Two Only
27	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Concrete Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	192.00	Sqm	735.40	141196.80	INR One Lakh Forty One Thousand One Hundred & Ninety Six and Paise Eighty Only
28	Planting of tree by the road side (Avenue Tree) in 0.6 m dia holes, 1 m deep dug in the Ground. Mixing the soil with decayed farm yard/ slug manure, planting the saplings back filling the trench, watering, fixing the tree guard & maintain the Plant for One Year.	70.00	Sqm	820.58	57440.60	INR Fifty Seven Thousand Four Hundred & Forty and Paise Sixty Only
		96.00	Nos.	790.81	75917.76	INR Seventy Five Thousand Nine Hundred & Seventeen and Paise Seventy Six Only

Borhan Robert Khushf

Executive Engineer
R.W.D. Work Division

Nisul
18/11/19

29	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	294.82	Cum	260.59	76827.14	INR Seventy Six Thousand Eight Hundred & Twenty Seven and Paise Fourteen Only
30	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15 Grade	23.73	Cum	4253.36	100932.23	INR One Lakh Nine Hundred & Thirty Two and Paise Twenty Three Only
31	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-20 Grade	91.41	Cum	4961.99	453575.51	INR Four Lakh Fifty Three Thousand Five Hundred & Seventy Five and Paise Fifty One Only
32	Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202	0.399	MT	55638.06	22199.59	INR Twenty Two Thousand One Hundred & Ninety Nine and Paise Fifty Nine Only
33	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-20 Grade	83.20	Cum	4766.89	396605.25	INR Three Lakh Ninety Six Thousand Six Hundred & Five and Paise Twenty Five Only
34	Providing and laying RCC pipe NP-3 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106	7.50	M	3643.15	27323.63	INR Twenty Seven Thousand Three Hundred & Twenty Three and Paise Sixty Three Only
35	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	85.73	Cum	95.63	8198.36	INR Eight Thousand One Hundred & Ninety Eight and Paise Thirty Six Only
36	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204 3.7	90.00	Cum	109.62	9865.80	INR Nine Thousand Eight Hundred & Sixty Five and Paise Eighty Only
37	Plain reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 RCC M-25 Grade	28.86	Cum	5572.53	160823.22	INR One Lakh Sixty Thousand Eight Hundred & Twenty Three and Paise Twenty Two Only
38	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	2.86	MT	55774.44	159514.90	INR One Lakh Fifty Nine Thousand Five Hundred & Fourteen and Paise Ninety Only

For Project Engineer

For Project Engineer

Sl. No.	Particulars	Unit	Rate	Amount	Total	Remarks
39	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (With Sandy Materials)	Cum	65.00	78.76	78.76	INR Sixty Two Thousand & Eighty Eight and Paise Seventy Seven Only
40	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8	Cum	89.88	640.24	62034.72	INR Sixty Two Thousand & Eighty Eight and Paise Seventy Seven Only
41	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 RCC M-30 Grade	Cum	50.33	2118.18	106608.00	INR One Lakh Six Thousand Six Hundred & Eight Only
42	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202	Cum	12.06	6134.54	73982.55	INR Seventy Three Thousand Nine Hundred & Eighty Two and Paise Fifty Five Only
43	Drainage spouts complete as per drawing and technical specifications Clause 1209	MT	1.04	56795.78	59067.61	INR Fifty Nine Thousand & Sixty Seven and Paise Sixty One Only
44	Providing and laying cement concrete wearing course M 30 grade including reinforcement complete as per drawing and technical specifications Clauses 800 and 1206.3	Nos.	8.00	397.97	3183.76	INR Three Thousand One Hundred & Eighty Three and Paise Seventy Six Only
45	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202.	Cum	1.482	11110.21	16465.33	INR Sixteen Thousand Four Hundred & Sixty Five and Paise Thirty Three Only
46	(B) Cement Concrete	Cum	0.150	473.83	71.07	INR Seventy One and Paise Seven Only
47	(C) Reinforced Cement Concrete	Cum	1.680	1062.80	1785.50	INR One Thousand Seven Hundred & Eighty Five and Paise Fifty Only
48	Dismantling of existing structures like culverts, bridges, retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lift and lead of 1000 m as per Technical Specification Clause 202.	Cum	24.750	228.72	5660.82	INR Five Thousand Six Hundred & Sixty and Paise Eighty Two Only

Shri. R. W. D. Work Division

Executive Engineer
R.W.D. Work Division
Biharsharif

Misled
18/11/19

49	Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia. across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC: 981997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	30.000	RM	877.78	26333.40	INR Twenty Six Thousand Three Hundred & Thirty Three and Paise Forty Only
50	GST @ 12% ON (PART A) & LABOUR CESS @ 1%	1.000	Thausend	1051990.00	1051990.00	INR Ten Lakh Fifty One Thousand Nine Hundred & Ninety Only
51	1st Year Maintenance cost	1	Year	30659.00	30659.00	Thirty Thousand Six Hundred & Fifty Nine Only
52	2nd Year Maintenance cost	1	Year	45177.00	45177.00	Forty Five Thousand One Hundred & Seventy Seven Only
53	3rd Year Maintenance cost	1	Year	289638.00	289638.00	Two Lakh Eighty Nine Thousand Six Hundred & Thirty Eight Only
54	4th Year Maintenance cost	1	Year	100573.00	100573.00	One Lakh Five Hundred & Seventy Three Only
55	5th Year Maintenance cost	1	Year	323361.00	323361.00	Three Lakh Twenty Three Thousand Three Hundred & Sixty One Only
56	GST @ 12% ON (PART A) & LABOUR CESS @ 1%	1.000	Thausend	102623.00	102623.00	INR One Lakh Two Thousand Six Hundred & Twenty Three Only
Total in Figures						
Quoted Rate in Figures			Select		10036249.54	One Crore Thirty Six Thousand Two Hundred & Forty Nine and Paise Fifty Four Only
Quoted Rate in Words			INR Zero Only			
INR One Crore Thirty Six Thousand Two Hundred & Fifty Only						

Signature Red-Sub Chaudhary

Executive Engineer
W & D Work Division

Dr. P. K. Singh

784400
892001
9144219

8229599
802828

Executive Engineer
R.W.D. Work Division
Biharsharif

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक मु० अ०-४ (मु०)रा०यो०-०३-५९७/२०१८

७७७

/पटना, दिनांक-२६/०२/१९

सेवा के

विजय कुमार, गांधीनगर
सचिव।

सेवा के

महालेखाकार (लेखा एवं हकदारों)
बिहार, पटना।

विषय योजना शीर्ष ४५१५-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना-१०३-ग्राम विकास-राज्य योजना-०१०५-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत राज्य के नालन्दा जिलान्तर्गत कार्य प्रमंडल, बिहारशरीफ अन्तर्गत रहुई प्रखंड के रघुनाथपुर दरगाह के ग्राम लक्ष्मीपुर माया दौलतपुर तक पथ निर्माण कार्य जिसकी लम्बाई १.३१० कि०मी० निर्माण हेतु रु० ९४.३७६ लाख एवं अनुसंधान की राशि रु० ८.९४६ लाख अर्थात् कुल १०३.३२२ लाख रुपये (एक करोड़ तीन लाख बत्तीस हजार दो सौ रुपये) की लागत पर प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महोदय,

निदेशानुसार योजना शीर्ष ४५१५-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना-१०३-ग्राम विकास-राज्य योजना-०१०५-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत राज्य के नालन्दा जिलान्तर्गत कार्य प्रमंडल, बिहारशरीफ अन्तर्गत रहुई प्रखंड के रघुनाथपुर दरगाह के ग्राम लक्ष्मीपुर माया दौलतपुर तक पथ निर्माण कार्य जिसकी लम्बाई १.३१० कि०मी० निर्माण हेतु रु० ९४.३७६ लाख एवं अनुसंधान की राशि रु० ८.९४६ लाख अर्थात् कुल १०३.३२२ लाख रुपये (एक करोड़ तीन लाख बत्तीस हजार दो सौ रुपये) की लागत पर प्रशासनिक स्वीकृति प्रदान किया जाता है।

१. इस योजना को दो वित्तीय वर्ष २०१८-१९ एवं २०१९-२० में पूरा किये जाने का लक्ष्य है।
२. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ द्वारा इस योजना के कार्य सम्पादन हेतु निकासी एवं व्ययन पदाधिकारी होंगे। कार्य निविदा के माध्यम से कराया जाएगा।
३. योजना के क्रियान्वयन से पूर्व इस पर सक्षम पदाधिकारी से प्रावधिक स्वीकृति प्राप्त कर ली जायगी।
४. इस योजना का व्यय योजना शीर्ष ४५१५-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना-१०३-ग्राम विकास-राज्य योजना-०१०५-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष जिसका विपत्र कोड ३७-४५१५००१०३०१०५ के अन्तर्गत वित्तीय वर्ष २०१८-१९ में उपबंधित राशि से विकलनीय होगा।
५. योजना शीर्ष ४५१५-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परियोजना-१०३-ग्राम विकास-राज्य योजना-०१०५-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत वित्तीय वर्ष २०१८-१९ में ४५९.३१ करोड़ रुपये का बजट उपबंध स्वीकृत है।
६. संबंधित कार्यपालक अभियंता, द्वारा योजनाओं का वित्तीय एवं भौतिक प्रतिवेदन प्रत्येक माह के पाँच तारीख तक ऑनलाईन प्रविष्टि कराते हुए अधीक्षण अभियंता, कार्य अंचल नालन्दा एवं मुख्य अभियंता के माध्यम से विभाग को निश्चित रूप से उपलब्ध करायेंगे।
७. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ यह सुनिश्चित करेंगे कि यह योजना किसी अन्य योजना शीर्ष अन्तर्गत स्वीकृत नहीं है।
८. इस योजना का चयन मा० मंत्री, ग्रामीण कार्य विभाग, द्वारा संचिका संख्या- मु० अ०-४ (मु०)रा०यो०-०३-५९७/२०१८ के पृ० सं०-०३/२० पर दिनांक-१८.०१.२०१९ को किया गया है।

B. K. P. S. Choudhary

25/1/19

Executive Engineer
R.W.D. Work Division
Biharsharif

9. इस योजना की स्वीकृति स्वयं प्राधिकार सचिव, ग्रामीण कार्य विभाग द्वारा सचिका सं०- मु० अ०-४ (मु०)रा०यो०-०३-५७९/२०१८ के पृ० सं०-०५/टि० पर दिनांक-२५.०१.२०१९ को प्राप्त है।
10. बाज्रा के निर्धारित प्रावधान/प्रक्रिया के आलोक में बजट प्रावधान के अंतर्गत राशि की निकासी की जाएगी।
11. कार्यपालक अभियंता (PIU) का उत्तरदायित्व होगा कि कार्य का विशिष्टताओं/विशिष्ट के अनुरूप कार्यान्वित करा कर एकरारनामा एवं सुसंगत वित्तीय प्रावधानों के पालन उपरान्त पूर्णतः संतुष्ट होकर ही राशि की निकासी एवं व्ययन करेंगे।
12. वित्त विभाग के संकल्प संख्या-३७५६ दिनांक-३१.०५.२०१७ में निहित निर्देशों को अक्षरशः पालन किया जाएगा तथा बिहार वित्त नियमावली के सुसंगत प्रावधानों के आलोक में योजना में उपबंधित राशि की उपलब्धता के आधार पर व्यय की जाएगी।
13. यह आदेश आंतरिक वित्तीय सलाहकार की सहमति प्राप्त कर निर्गत किया जा रहा है। आंतरिक वित्तीय सलाहकार की सहमति सचिका सं०- मु० अ०-४ (मु०)रा०यो०-०३-५७९/२०१८ के पृष्ठ संख्या-१०/टि० पर दिनांक-२०.०२.१९ को प्राप्त है।
14. यह राशि उसी मद में खर्च की जायेगी, जिसके लिए पुनर्विनियोजित की गयी है, अन्य मद में नहीं।
15. प्रावकलन की विशिष्टताओं के अनुसार निर्धारित समयावधि के अंदर कार्य पूर्ण कराना सुनिश्चित किया जाएगा।
16. योजना के कार्यान्वयन के क्रम में इनका निर्धारित निरीक्षण सरकार से निर्गत आदेशों में प्रावधानित सक्षम नियंत्री पदाधिकारियों द्वारा नियमित अंतराल पर अनिवार्य रूप से किया जाएगा एवं कार्य को ससमय तथा गुणवत्तापूर्वक सम्पन्न कराना सुनिश्चित कराया जाएगा। योजना के कार्यान्वयन में अनियमितता की स्थिति में सभी निरीक्षी प्राधिकार भी उत्तरदायी माने जाएंगे।
17. वित्त विभाग के पत्रांक-७७०, दिनांक २०.०९.११ के द्वारा सूचित किया गया है कि नाबार्ड से RIDF के अन्तर्गत नई परियोजनाओं की प्रशासनिक अनुमोदन प्राप्त करने के उपरान्त ही स्वीकृति हेतु नाबार्ड को भेजी जाये।

विभागाध्यक्ष

(विशेष कुमार)

सचिव

ज्ञापक- मु० अ०-४ (मु०)रा०यो०-०३-५७९/२०१८ ७७९

प्रतिलिपि- कोषागार पदाधिकारी, नालन्दा को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

/पटना, दिनांक-२६/०२/१९

सचिव

/पटना, दिनांक-२६/०२/१९

ज्ञापक- मु० अ०-४ (मु०)रा०यो०-०३-५७९/२०१८ ७७९

प्रतिलिपि- माननीय मंत्री के आप्त सचिव, ग्रामीण कार्य विभाग/प्रधान सचिव, योजना एवं विकास विभाग/वित्त विभाग (आय-व्यय शाखा)/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/मंत्रिमंडल सचिवालय एवं समन्वय विभाग/कार्मिक एवं प्रशासनिक सुधार विभाग, प्रमण्डलीय आयुक्त, पटना/जिला पदाधिकारी, नालन्दा/उप विकास आयुक्त, नालन्दा/अभियंता प्रमुख सह-सचिव, BRRDA, ग्रा० का० वि०, बिहार, पटना/मुख्य अभियंता-१, पटना, ग्रामीण कार्य विभाग/मु० अ०-४ (मुख्यालय), ग्रा० का० वि०/अधीक्षण अभियंता, ग्रा० का० वि०, कार्य अंचल, नालन्दा/कार्यपालक अभियंता, ग्रा० का० वि० कार्य प्रमंडल, बिहारशरीफ/मुख्य महाप्रबंधक नाबार्ड, बिहार क्षेत्रीय कार्यालय, (मौर्या कम्पलेक्स, पाँचवी मंजिल) डाक बंगला रोड, पटना को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। आई०टी० नोडल, ग्रामीण कार्य विभाग को विभाग के वेबसाइट पर अपलोड करने हेतु प्रेषित। एम०आई०एस० नोडल, ग्रामीण कार्य विभाग को स्टेट एम०आई०एस० में प्रविष्टि हेतु प्रेषित।

सचिव

Executive Engineer
R.W.D. Work Division
Rashid