

कार्यपालक अभियंता, का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ

पत्रांक 451/313/ बिहारशरीफ, दिनांक 24.4.2024

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बिहारशरीफ ।

सेवा में,

नोडल पदाधिकारी NABARD MAINTENANCE
ग्रामीण कार्य विभाग बिहार पटना।

विषय:-

शीर्ष NABARD मरम्मति/अनुरक्षण योजनान्तर्गत पूर्ण पथों का 5-वर्षीय रूटीन अनुरक्षण कार्य के कार्यान्वयन हेतु अधियाचना पत्र समर्पित करने के संबंध में।

महापय,

NABARD मरम्मति/अनुरक्षण योजनान्तर्गत पूर्ण पथों का 5-वर्षीय रूटीन अनुरक्षण कार्य संवेदक द्वारा कराये गये पथों में एकरारनामा के अनुसार राशि की अधियाचना पत्र समर्पित की जा रही है।

अनुरोध है कि 5-वर्षीय रूटीन अनुरक्षण कार्य कराने हेतु संलग्न सूची के अनुसार राशि उपलब्ध कराने की कृपा की जाय ताकि संवेदक को भुगतान किया जा सके।

अनु०:- यथोक्त।

24/4/24

विश्वासभाजन

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बिहारशरीफ

24/4/24

24/4/24

FORM GFR 19-A

(See Government of India's Decision (1) below Rule-150)

Form of Utilisation Certificate up to the month of -20.4.2024

(NABARD MAINTENANCE FUND)

PIU- BIHARSHARIF

Year-2024-25


Sl. No.	Name of Scheme	Sanction No. & Date with Amount (in Rs. Lacs)	Amount Received (in Rs. Lacs)	Particulars	Remarks
1	Construction of Rural Roads under NABARD (4515) MAINTENANCE FUND	Order No-8466 Date-30.01.2023	22.48793	Certified that out of Rs 22.48793 received & balance during the years 2024-25 in favour of Ex. Engineer, R.W.D. Works Division Biharsharif, sum of Rs 22.48793 has been utilized for the purpose of NABARD MAINTENANCE FUND scheme as given in the margin for which it was sanctioned and that the balance of Rs 0.0 lacs remaining unutilized at the end of the period under- 20.04.2024	
Total Rs.			22.48793		



2 Certified that I have satisfied myself that the conditions on which the grants-in- aid was Kind of Checks exercised :-

- Works have been supervised by Executive Engineer/Superintending Engineer.
- Periodical inspection has been conducted by Executive Engineer/Superintending Engineer.
- Construction material have been tested.
- Measurements have been recorded in the MBs and test check conducted by the Assistant .
- All other codal formalities have been observed.

3 Physical Progress achieved:

- Construction of Road Works.
- Construction of CD works


24/4/24
Divisinal Accounts Officer
Rural Works Department
Works Division Biharsharif


24/4/24
Executive Engineer
Rural Works Department
Works Division Biharsharif

24/4/24

[illegible]

4. अनुलानक - प्रशासनिक षवीकृति का पत्र. अनुमोदित परिमाण विपत्र एव एकरानागा की अभिप्रमाणित प्रति ।

प्रमंडलीय लेखा पदाधिकारी

ग्रामीण कार्य विभाग.
कार्य प्रमंडल, बिहारराष्ट्रीय

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कावे प्रकल्प, विहारराशिक
सिर्सना/अम्
24/5/24
24/5/24

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक-गु0 अ0-4 (गु0) नाबार्ड-03-264/2015

/पटना दिनांक-

प्रेषक,

नरेन्द्र कुमार झा,
अपर सचिव।

सेवा में,

महालेखाकार, बिहार
वीरचन्द पटेल पथ, पटना।

आंतरिक वित्तीय सलाहकार द्वारा
अनुपचारिक रूप से परामर्शित

विषय:- योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत राज्य के नालन्दा जिलान्तर्गत कार्य प्रमंडल, बिहारशरीफ क्षेत्राधीन वेन प्रखंड अन्तर्गत एस0एच0-78 से कुशहर तक पथ निर्माण जिसकी लम्बाई 1.70 कि0मी0 हेतु 137.67 लाख रुपये (एक करोड़ सैतीस लाख सड़सठ हजार रुपये) मात्र है, का प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महाशय,

निदेशानुसार योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-उप शीर्ष-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उप शीर्ष के अन्तर्गत राज्य के नालन्दा जिलान्तर्गत कार्य प्रमंडल, बिहारशरीफ क्षेत्राधीन वेन प्रखंड अन्तर्गत एस0एच0-78 से कुशहर तक पथ निर्माण जिसकी लम्बाई 1.70 कि0मी0 हेतु 137.67 लाख रुपये (एक करोड़ सैतीस लाख सड़सठ हजार रुपये) मात्र है, का प्रशासनिक स्वीकृति प्रदान किया जाता है।

1. इस योजना को वित्तीय वर्ष 2016-17 एवं 2017-18 में पूरा किये जाने का लक्ष्य है।
2. योजना के लिए कार्यपालक अभियंता, बिहारशरीफ से विस्तृत कार्य योजना मांगी जावेगी और उसके अनुरूप कार्यों के समयबद्ध ढंग से पूर्ण कराया जायेगा।
3. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ इस योजना के कार्य सम्पादन हेतु निकासी एवं व्ययन पदाधिकारी होंगे। कार्य निविदा के माध्यम से कराया जाएगा।
4. योजना के क्रियान्वयन से पूर्व इस पर सक्षम पदाधिकारी से प्रावैधिक स्वीकृति प्राप्त कर ली जायगी।
5. इस योजना का व्यय योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष जिसका विपत्र कोड P-4515001030105 एवं स्कीम कोड-5369 के अन्तर्गत वित्तीय वर्ष 2016-17 में उपबधित राशि से विकलनीय होगा।
6. योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत वित्तीय वर्ष 2016-17 में 454.31 करोड़ रुपये का बजट उपबध स्वीकृत है।
7. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ द्वारा इस योजना की भातिका एवं वित्तीय प्रगति प्रतिवेदन प्रत्येक माह के 10 तारीख तक निश्चित रूप से अधीक्षण अभियंता, कार्य अंचल, नालन्दा एवं मुख्य अभियंता-1, पटना के माध्यम से ग्रामीण कार्य विभाग, मुख्यालय को उपलब्ध करायेगें एवं इसे State MIS में दर्ज करेंगे। तदनुसार विभाग द्वारा आवंटन उपलब्ध कराया जाएगा।
8. इस योजना का चयन माननीय मंत्री, ग्रामीण कार्य विभाग द्वारा संचिका सं0- गु0 अ0-4 (गु0) नाबार्ड-03-264/2015 के पृ0 सं0-11/टि0 पर दिनांक 02.06.2016 को किया गया।



Certified Copy

HEAD-4515 NABARD

UNDER

Executive Engineer
Rural Works Department
Works Division, Bham
RWD

RWD WORKS DIVISION BIHARSHARIF

Open from 68+ 372558.82

PROJECT NAME:- CONSTRUCTION OF ROAD FROM SH-78 TO KUSHAHAR (Including 5years Maint.)

C/S Approved By S.E. RWD Work Circle Nalanda Vide Letter 230 (we) Dated 09.02.17
CONTRACTOR NAME :- SRI SHIV SHARMA

CONTRACTOR NAME :- SRI SHIV SHANKAR PRASAD,
CONTRACTOR ADDRESS :-

CONTRACTOR ADDRESS:- VILL+PO- MANORAMPUR, ASTHAWAN NALANDA
BLOCK

BLOCK :- BIND.

ESTIMATED COST :- Rs. 1,20,81,736.00 Agreement Value - 108,73,560/-

AGREEMENT No. :-08....F2/2016-17

ACCEPTED RATE :- 10.00% Below of BOQ Rate.

AGREEMENT Value :- Rs. 1,08,73,560.00

EARNEST MONEY :- 548,000/-

WORK STARTED DATE :- 29.03.2017

INTENDED DATE OF COMPLETION:- 28.03.2018

Executive Engineer
Rural Works Department
Works Division, Bihar Sharif

TENDER FOR WORKS

I/We hereby tender for the execution for the Government of Bihar of the work specified in the under write memorandum at the rates specified there in within a period of year month form the date of written order to commence and in accordance in all respects with the specification designs, drawing and other documents referred to rule her of and subject to the annexed conditions of contract with, such conditions so as applicable.

MEMORANDUM

(a) If several sub-works are included they should be detained in a separate list

(b) This deposit will be 5% of the estimated cost of the work.

(c) This percentage deduction from bills will be credited to the contractors security deposit

(A) Name of work:- Construction of Road From SH-78 to Kushar.

(B) Estimated cost Rs. 108,73,560/-

(C) Earnest money Rs. N/A 50,000/- 2,50,000/-

(D) Initial security deposits (including earnest money) to be deposited before the commencement of the work. N/A 206000/-

(E) Percentage to be deducted from bills Rs. 5% (Rupees five 89,000/- 2,95,000/- percent).....

(F) Time required for the work from date of written order to commence..... (12) Twelve Month

(G) Date of written order to commence 29.03.2017

(H) Total number of item of work tendered for 40

10% below of BOB Rate.

Item No.	Item of work	RATE TENDERED		Per
		In figures	In words	
1	(A) PREPRATORY WORK & SITE CLEARANCE			
	(B) Setting Out			
	Setting Out as MORD Specification 100			
	Item Nos (i), (ii), (iii) & (iv)			
(i)	Construction of Reference & Working Benchmarks		Rupees Five Thousand One Hundred Twenty Four & Paisa Fifty Only.	
	1.700 Km.	5124.50		
(ii)	Construction of Reference Pillars/Burjees		Rupees Four Thousand Six Hundred Forty Five & Paisa Ten Only.	
	1.700 Km.	4645.10		

शिव शंकर यादव

Executive Engineer
Rural Work Department
Works Division, Bihar Sharif

Schedule XLV – Form No. – 61

2	<p>Clearing and Grubbing Road Land Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201. (By Manual Means) In area of non-thorny jungle.</p>	1.02 Hect.	38252.95	Rupees Thirty Eight Thousand Two Hundred Fifty Two & Paisa Ninety Five Only.
3	<p>Construction of Embankment with Material Obtained from Borrow Pits Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100m as per Technical Specification Clause 301.5. (With 100M Lead).</p>	7562.37 Cum	162.33	Rupees One Hundred Sixty Two & Paisa Thirty Three Only.
4	<p>Construction of Embankment with Material Obtained from Borrow Pits Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100m as per Technical Specification Clause 301.5. (With 1000M Lead)</p>	1543.55 Cum.	243.49	Rupees Two Hundred Forty Three & Paisa Forty Nine Only.
5	<p>Construction of Subgrade Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1. (1000 M Lead)</p>	5101.52 Cum	230.96	Rupees Two Hundred Thirty & Paisa Ninety Six Only.

10/10/2019

Executive Engineer
Rural Works

6	Granular Sub-base with* Well Graded Material (Table 400.1) Construction of granular sub-base by providing well graded material (Crushed Stone Aggregates and Local Sand), spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401 (For Grading II Material). 1157.84 Cum.	1860.47	Rupees One Thousand Eight Hundred Sixty & Paise Forty Seven Only.	Per m ³
7	Water Bound Macadam with crushable screening Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405. (WBM Grading 2) By Manual Means 369.29 Cum.	3368.54	Rupees Three Thousand Three Hundred Sixty Eight & Paise Fifty Four Only.	Per m ³
8	Water Bound Macadam with Stone screening Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (WBM Grading 3) (A) By Manual Means. 369.29 Cum.	3037.96	Rupees Three Thousand Thirty Seven & Paise Ninety Six Only.	Per m ³
9	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 502. 4923.75 Sqm.	32.96	Rupees Thirty Two & Paise Ninety Six Only.	Per m ²

1000 2000 3000

Executive Engineer
Rural Works Department
Works Division, Bahar Sharif

10	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503. 4923.75 Sqm	11.64	Rupees Eleven & Paise Sixty Four Only.
11	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm size @ 0.18 cum per 10 sqm & 11.2 mm size @ 0.09 cum per 10 sqm aggregates using penetration grade/modified bitumen @ 14.6 kg/10sqm to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A as per Technical Specification Clause 508. Bitumen (S-90) Case-I By Manual Means 4923.75 Sqm.	155.96	Rupees One Hundred Fifty Five & Paise Ninety Six Only.
12	Seal Coat Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A as per Technical Specification Clause 510 4923.75 Sqm.	40.36	Rupees Forty & Paise Thirty Six Only.
13	Cement Concrete Pavement M30 Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501 287.85 Cum.	6366.08	Rupees Six Thousand Three Hundred Sixty Six & Paise Eight Only.

1/27. 2/27. 3/27

Executive Engineer

14	Laying brick soling layer on prepared sub-grade with brick on end edging according to lines, graded and cross-section shown on the drawing filling joints with sand and earth, spreading 25 mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kN as per Technical Specification Clause 412. 400.00 Cum.	515.38	Rupees Five Hundred Fifteen & Paisa Thirty Eight Only	Per m ³
15	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703			
(i)	Ordinary Kilometer Stone (Precast) 2 Each	2222.80	Rupees Two Thousand Two Hundred Twenty Two & Paisa Eighty Only.	Per Nos.
(ii)	200 m stone (precast) 7 Each	565.31	Rupees Five Hundred Sixty Five & Paisa Thirty One Only.	Each
16	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704 34 Each	448.39	Rupees Four Hundred Forty Eight & Paisa Thirty Nine Only.	Per M
17	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701 (For culverts) 22.32 Sqm.	79.63	Rupees Seventy Nine & Paisa Sixty Three Only.	Per m ²
18	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701. (English and Roman (For Culverts)) 88 Letter	0.40	Rupees Zero & Paisa Forty Only.	Per Letter
19	Providing and laying of hot applied thermoplastic compound 2.5mm thick including reflectorising glass beads @250 gms per sqm area 260.00 Sqm	806.60	Rupees Eight Hundred Six & Paisa Sixty Only.	Per m ²

13/09/2016

Executive Engineer
Rural Works Department
Works Division, Bahar Sharif

Schedule XLV - Form No. - 61

20	Providing and fixing of typical PMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1				
21	Retro-reflectorised Traffic Signs Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801	2 Each	10430.27		Rupees Ten Thousand Four Hundred Thirty & Paisa Twenty Seven Only.
(i)	600 mm equilateral triangle				Rupees One Thousand Two Hundred Twenty Nine & Paisa Twelve Only.
(ii)	600 mm x 450 mm rectangular	8 Each	1229.12		Rupees One Thousand Four Hundred Fourteen & Paisa Seventy Two Only.
(iii)	900 mm side octagon	4 Each	1414.72		Rupees Seven Thousand Five Hundred Forty Four & Paisa Seventy Two Only.
		1 Each	7544.72		

12/10/2016

Executive Engineer
Rural Works Department

22	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material 73.07 Cum.	219.20	Rupees Two Hundred Nineteen & Paisa Twenty Only.	Per m ³
23	Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 7.23 Cum.	391.23	Rupees Three Hundred Ninety One & Paisa Twenty Three Only.	Per m ³
24	Bricks flat soling in foundation Trenches as per drawing and technical specification Clause 1108 51.00 Sqm.	258.26	Rupees Two Hundred Fifty Eight & Paisa Twenty Six Only.	Per m ²
25	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15. 9.20 Cum.	5383.44	Rupees Five Thousand Three Hundred Eighty Three & Paisa Forty Four Only.	Per m ³
26	Brick masonry work in cement mortar in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 600, 1202 & 1203 CM.(1:4) 34.17 Cum.	6354.84	Rupees Six Thousand Three Hundred Fifty Four & Paisa Eighty Four Only.	Per m ³
27	Brick masonry work in cement mortar in substructure complete excepting pointing and plastering, as per drawing and technical specification Clauses 602, 603, 604, 1202 & 1204 C.M.(1:4) 33.24 Cum.	5608.98	Rupees Five Thousand Six Hundred Eight & Paisa Ninety Eight Only.	Per m ³
28	Plain/reinforced cement concrete, in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 (M-20) 3.22 Cum.	6808.56	Rupees Six Thousand Eight Hundred Eight & Paisa Fifty Six Only.	Per m ³
29	Providing Bitumen painting over top surface of Abutment cap & inner vertical surface of dirt wall including the heating the bitumen & cost of painting brush etc. 10.92 Sqm.	16.35	Rupees Sixteen & Paisa Thirty Five Only.	Per m ²
30	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 (Deck slab M25) 2.60 Cum.	7609.31	Rupees Seven Thousand Six Hundred Nine & Paisa Thirty One Only.	Per m ³
31	Supplying fitting and Placing HYSD bar reinforcement in super-structure 0.37 MT	53010.37	Rupees Fifty Three Thousand Ten & Paisa Thirty Seven Only.	Per MT

19/09/2019

Executive Engineer
Rural Works Department
Works Division, B. Sharif

Schedule XLV – Form No. – 61

32	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4 3.60 Cum.	6497.62	Rupees Six Thousand Four Hundred Ninety Seven & Paisa Sixty Two Only.
33	Plastering with cement mortar (1:4), 15 mm thick on brickwork in substructure as per technical specification Clauses 613.4 & 1204 76.68 Sqm.	155.93	Rupees One Hundred Fifty Five & Paisa Ninety Three Only.
34	Providing 1.5 mm thick neat cement Punning 24.96 Sqm.	54.85	Rupees Fifty Four & Paisa Eighty Five Only.
35	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 32.00 Nos.	127.27	Rupees One Hundred Twenty Seven & Paisa Twenty Seven Only.
36	1st Year Maintenance Cost 1.70 Km.	32880.59	Rupees Thirty Two Thousand Eight Hundred Eighty & Paisa Fifty Nine Only.
37	2nd Year Maintenance Cost 1.70 Km.	43182.35	Rupees Forty Three Thousand One Hundred Eighty Two & Paisa Thirty Five Only.
38	3rd Year Maintenance Cost 1.70 Km.	73683.53	Rupees Seventy Three Thousand Six Hundred Eighty Three & Paisa Fifty Three Only.
39	4th Year Maintenance Cost 1.70 Km.	102162.35	Rupees One Lakh Two Thousand One Hundred Sixty Two & Paisa Thirty Five Only.
40	5th Year Maintenance Cost 1.70 Km.	120650.00	Rupees One Lakh Twenty Thousand Six Hundred Fifty Only.

1979 ग्रेट यमि

Executive Engineer
Rural Work Department
Works Division

9. इस योजना की स्वीकृति सक्षम प्राधिकार सचिव, ग्रामीण कार्य विभाग से सचिका संख्या- मु0 अ0-4 (मु0) नाबार्ड-03-264/2015 में दिनांक 14.08.16 को सचिका के पृष्ठ 14/टि0 पर प्राप्त है।
10. यह आदेश वित्त विभाग के संकल्प संख्या-4-45/94-301 वि (2) दिनांक 31.01.1995 एवं वित्त विभाग के पत्रांक स्वीम (8)-11-2005-5090 वि (2) दिनांक 15.09.05 के आलोक में आंतरिक वित्तीय सलाहकार की सहमति प्राप्त कर निर्गत किया जा रहा है। आंतरिक वित्तीय सलाहकार की सहमति सचिका सं0- मु0 अ0-4 (मु0) नाबार्ड-03-264/2015 के पृष्ठ संख्या-21/टि0 पर दिनांक-03.08.16 को प्राप्त है।
11. वित्त विभाग के पत्रांक-770, दिनांक 20.09.11 के द्वारा सूचित किया गया है कि नाबार्ड से RADF के अन्तर्गत नई परियोजनाओं की प्रशासनिक अनुमोदन प्राप्त करने के उपरान्त ही स्वीकृति हेतु नाबार्ड को भेजी जाये।

विश्वासभाजन

ह0/-

(नरेन्द्र कुमार झा)

अपर सचिव

ज्ञापक- मु0 अ0-4 (मु0) नाबार्ड-03-264/2015

/पटना, दिनांक-

प्रतिलिपि- कोषागार पदाधिकारी, बिहारशरीफ को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

ह0/-

अपर सचिव

ज्ञापक- मु0 अ0-4 (मु0) नाबार्ड-03-264/2015 | 901

/पटना, दिनांक-08/08/16

प्रतिलिपि- माननीय मंत्री के आप्त सचिव, ग्रामीण कार्य विभाग/प्रधान सचिव, योजना एवं विकास विभाग/वित्त विभाग (आय-व्यय शाखा)/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/मंत्रिमंडल सचिवालय एवं समन्वय विभाग/कार्मिक एवं प्रशासनिक सुधार विभाग, प्रमण्डलीय आयुक्त, पटना/जिला पदाधिकारी, नालन्दा/उप विकास आयुक्त, नालन्दा/अभियंता प्रमुख ग्रा0 का0 वि0, बिहार, पटना/सचिव, BRRDA, ग्रा0 का0 वि0, बिहार, पटना/मुख्य अभियंता-1, पटना, ग्रामीण कार्य विभाग/मु0 अ0-4 (मुख्यालय), ग्रा0 का0 वि0/अधीक्षण अभियंता, ग्रा0 का0 वि0, कार्य अंचल, नालन्दा /कार्यपालक अभियंता, ग्रा0 का0 वि0 कार्य प्रमंडल, बिहारशरीफ/मुख्य महाप्रबंधक नाबार्ड, बिहार क्षेत्रीय कार्यालय, (मौर्या कम्प्लेक्स, पाँचवी मंजिल) डाक बगला रोड, पटना को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। आई0टी0 नोडल, ग्रामीण कार्य विभाग को विभाग के वेबसाइट पर अपलोड करने हेतु प्रेषित।

अपर सचिव