भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये ONE THOUSAND RUPEES

रु.1000 Rs.1000

सत्यमेव जयते INDIA

बिहार BIHAR

8 OCT 2019

AE 037775

सुधीर कुमार
मुद्रांक विक्रेता
अनुज्ञप्ति सं-08/2003
कचहरी, भागलपुर

AGREEMENT

This agreement, made the............ day of.................. Between The **Executive Engineer R.W.D.Works Division,Banka-II Bihar** [name and address of Employer] (here in after called "the Employee") of the one part, and **Dip Narayan Roy, Bhatta Road, Gumti No.-02, Bhikanpur Dist.-Bhagalpur Bihar (BID ID-349791)** (here in after called "the Contractor" of the other part.Whereas the employer is desirous that the contract execute the **Construction with Five Year Maintenance of Road From Suiya Borba PMGSY Road To Durgapur (Length in KM 1.790) Year 2018-2019 under Mukhya Mantri Gram Sampark Yojna (ST) (Tender ID-76760) Block-Chandan,** District–**Banka,** Bihar (here in after called the contract under **Chief Engineer-2 Rural Works Department Patna Letter No. 4114 (Attach)** Dated **31.10.2019** and the Employer has accepted the Bid by the Contractor for the execution and completion of Such works and the Routine maintenance of works for Five Years of the Contract Price remedying of any defects therein. at **Construction Cost Rs. 10847848.00 & Maintenance Cost** Rs. **1157974.00** with a Total Amount of **Rs. 1,20,05,822.00 (Rupees One Core Twenty Lacs Five Thousand Eight Hundred Twenty Two Only)** at bidder rate quoted **10 %(Ten)** below the estimated Cost. (i) BG No.-6/19-20 dated 02.12.2019 To 01.12.2020 Rs.7,50,500/- Total Rs. 750500/- Rupees Seven Laks Fifty Thousand Five Hundred Only) (Canara Banka Bhagalpur) The Commencement of work is 15/11/19.. and Completion of date up to .14/11/2020. i.e.(as Per letter No 2571 dted 15.11.2019)

Dip Narayan Roy

05/02/2020
EXECUTIVE ENGINEER
R.W.D. ...

Office of the Executive Engineer
R.W.D. Works Division, Banka-2

Letter of Acceptance

Letter No. :- 2571 ..... Date :- 15.11.19

To,

Dip Narayan Roy,
Bhatta Road, Gumti No.-02, Bhikanpur,
Dist.- Bhagalpur Bihar (BID ID-349791)

This is to notify you, that the Employer namely, **Executive Engineer R. W. D. Works Division, Banka-2** has accepted your **Bid Submitted Dated 27.03.2019 Bid ID-349791 in Compliance of Rural Works Department Govt. of Bihar, CE-2 Patna Letter No. 4114 (Attach) Dated 31.10.2019** for execution of the **Tender ID-76750, Block- Chandan,** Construction of Road From **Suiya Borba PMGSY Road To Durgapur (MMGSY ST)** for Construction & Routine Maintenance of the works for five years at the Contract Price of **Rs. 1,20,05,822.00 (Rupees One Core Twenty Lacs Five Thousand Eight Hundred Twenty Two Only)** in accordance with the Instructions to Bidders is hereby accepted by our Agency.

You are hereby requested to furnish Performance Security, (and additional security for unbalanced bids in terms of ITB Clause 26,) in the form detailed in Cl. 30 of ITB for an amount of **(a) Performance Security @ 2.5% Rs. 300146.00 & (b) Additional Performance Guaranty @ 3.75% Rs. 450219.00 with a Total Amount of Rs. 7,50,365.00 (Rupees Seven Lacs Fifty Thousand Three Hundred Sixty Five Only)** within 15 days of the receipt of this letter of acceptance valid up to 45 days from the date of expiry of Defects Liability Period i.e. up to .... and sign the contract, if the Performance Security is in the form of a Bank Guarantee, the period of validity of Bank Guarantee could be one year initially, however, the contractor would get this Bank Guarantee extended in such a way that an amount equal to requisite performance security is always available with the Employer until 45 days after the lapse of Defect Liability Period. Failing which action as stated in Cl. 30.3 of ITB will be taken. **In any circumstances no construction work will be done on private Land during execution of this work. You are directed to provide insurance in the name of employer (Executive Engineer) and yourself an insurance cover from the dated of start of work to the end of the defect of liability period equivalent to the amounts and deductible shown in contract data.**

Yours faithfully,

15/11/19

(Er.Krishna Kumar Sinh
Executive Engineer
R.W.D. Works Divisi
Banka-2

15.11.19

(i) Signature of Authorized Signatory :
(ii)Name and Title of Signatory : **E.E. R.W.D.(W).DIVISION BANKA-II**
(iii)Name of Agency : **Dip Narayan Roy**
Bhatta Road, Gumti No.-02, Bhikanpur, Bhagalpur

18/11/2019 Dip Narayan Roy

मुख्य अभियंता–2 का कार्यालय
ग्रामीण कार्य विभाग, पटना।

पत्रांक–
प्रेषक, /पटना, दिनांक–

ई० योगेश्वर पाण्डेय,
मुख्य अभियंता–2

सेवा में,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग, कार्य अंचल, भागलपुर।

विषय : शीर्ष **MMGSY** योजनान्तर्गत कार्य प्रमण्डल, बाँका–2 के अधीन **Suiya Borba PMGSY Road to Durgapur (Tender ID–76750)** कार्य की निविदा की स्वीकृति के संबंध में।

महाशय,

उपर्युक्त विषयक कार्य बिहार लोक निर्माण संहिता के कंडिका–163 के आलोक में इसके योग्य एवं दिनांक–30.10.2019 की लॉटरी में सफल न्यूनतम दरदाता **Dip Narayan Roy (Bid ID-349791)** को उनके द्वारा निविदित दर, जो परिमाण विपत्र के दर से –10.00% (दस प्रतिशत) कम है, को स्वीकृत करते हुए सम्पूर्ण कार्य कुल ₹ **1,20,05,822/–(एक करोड़ बीस लाख पांच हजार आठ सौ बाईस)** रुपये मात्र की लागत पर आपकी अनुशंसा एवं कार्यहित में आवंटित किया जाता है।

2. निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।
3. संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ जमा किये गये संबंधित एन०एस०सी०/**Fixed Deposit** आदि का सत्यापन संबंधित डाकघर/बैंक से कराकर प्रमंडलीय कार्यालय में अभिलेखित किया जायेगा। कार्यपालक अभियंता कार्य, प्रमंडल, बांका–2 कार्यादेश निर्गत करने के पूर्व अग्रधन की राशि के सत्यापन से संबंधित कागजात अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेगें।
4. एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जायेगा।
5. एकरारनामा से पूर्व कार्यपालक अभियंता यह सुनिश्चित कर लेंगे कि निविदाकार डिबार सूची/काली सूची या कार्य लंबित सूची में शामिल न हो।
6. कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य कराते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।
7. इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावैधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लेखित शर्त्त एकरारनामा का भाग होगा, जिसे विशेष शर्त्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।
8. अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वंय कर लेगें एवं त्रुटि पाये जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करायेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की जायेगी।
9. एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जांच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेगें कि इसमें कोई त्रुटि न हो।
10. कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपबंध से पूरी तरह आश्वस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावैधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये निदेश का अनुपालन सुनिश्चित करायेंगे। पथ का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, प्रशासनिक स्वीकृति की राशि, संवेदक द्वारा उद्धृत दर, पराक्रमित दर, **Bid Capacity** आदि का मिलान कर ही कार्य आवंटन आदेश निर्गत करेंगे। अधीक्षण अभियंता/कार्यपालक अभियंता कार्य आवंटन/**LOA** निर्गत करने से पूर्व मिलान कर लेंगे कि परिमाण विपत्र की राशि प्रशासनिक अनुमोदन की राशि के अनुज्ञेय सीमा के अन्दर है। यदि अनुज्ञेय सीमा से अधिक हो तो एकरारनामा के पूर्व पुनरीक्षित प्रशासनिक अनुमोदन प्राप्त कर लिया जाय।

E:\CE-2 Office\Office Work\All Scheme\Work Order\Lottery\Banka-2.Doc

Dip Narayan Roy

11. कार्यादेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु मासिक कार्य प्रोग्राम हस्ताक्षरित कराकर प्राप्त कर लेंगे जो की एकरारनामा का भाग होगा।
12. अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुरूप निर्धारित कार्य अवधि के अंदर पूरा की जायेगी।
13. कार्य समाप्ति की अवधि निविदा आमंत्रण सूचना के अनुसार होगी।
14. इस कार्य का व्यय शीर्ष **MMGSY** अन्तर्गत से मिलने वाले राशि अन्तर्गत उपबंधित राशि से विकलित होगा।
15. कार्य का प्रगति प्रतिवेदन प्रत्येक महीने की सातवीं तारीख तक निश्चित रूप से इस कार्यालय को समर्पित की जाय।
16. सभी निविदा कागजात एवं तुलनात्मक विवरणी की मूल प्रति आवश्यक कार्रवाई हेतु लौटाई जाती है। आप निविदा कागजातों एवं तुलनात्मक विवरणी के जांचोपरान्त आप आवश्यक निदेशों को अपने स्तर से निर्गत करेंगे।
17. एकरारनामा से पहले निविदाताओं द्वारा दिये गये कागजात का सत्यापन उनके मूल कागजात से मिलान कर लेगें। कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बांका–2 तुलनात्मक विवरणी की एक अभिप्रमाणित प्रति अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, भागलपुर को अभिलेख हेतु उपलब्ध करा देंगे। निदेश दिया जाता है कि संवेदक से कार्य प्रोग्राम प्राप्त कर लेंगे तथा उनका कार्यक्षमता कुशलता एवं पूर्व से आवंटित कार्यों की प्रगति से संतुष्ट हो लें।
18. इस निविदा की राशि में अगर कोई अंतर होता है तो इसकी सूचना तुरन्त इस कार्यालय को दी जाय।
19. कार्यपालक अभियंता, एकरारनामा करने के पूर्व संवेदक का निबंधन संख्या, पूर्ण पता एवं दूरभाष संख्या कार्यादेश में अंकित करेंगे तथा इस कार्यालय को सूचित करेंगे।
20. परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा निदेश के आलोक में अतिरिक्त वांछित परफॉरमेंस सिक्यूरिटी की राशि जमा कराना सुनिश्चित करेंगे।
21. किसी भी परिस्थिति में निजी जमीन पर निर्माण नहीं कराया जाय।
22. प्रत्येक 15 दिनों पर संवेदक से स्वहस्ताक्षरित विपत्र प्राप्त कर स्थल से मिलान कर मापी पुस्तिका में मापी दर्ज कर भुगतान सुनिश्चित करेंगे।
23. **कार्यपालक अभियंता कार्यावंटन आदेश प्राप्त होते ही संवेदक को अविलंब LOA (Letter of Acceptance) निर्गत करेंगे एवं SBD की ITB की कंडिका 30.1 में निहित प्रावधान के आलोक में 10 दिनों के अन्दर Performance Security प्राप्त कर लेंगे। LOA निर्गत करने की तिथि से 21 दिनों के अन्दर एकरारनामा की कार्रवाई सुनिश्चित करेंगे। निर्धारित अवधि के अन्दर Performance Security जमा नहीं करने की स्थिति में ITB की कंडिका 30.3 के आलोक में कार्रवाई करते हुए अधीक्षण अभियंता के माध्यम से प्रस्ताव अधोहस्ताक्षरी को समर्पित करेंगे। विशेष परिस्थिति में निर्धारित अवधि के पश्चात एकरारनामा करने हेतु Proper Justification के साथ प्रस्ताव उचित माध्यम से समर्पित करेंगे एवं अधोहस्ताक्षरी के अनुमति के उपरान्त ही एकरारनामा करेंगे।**

कृपया पत्र प्राप्ति की सूचना देंगे।

अनु0–यथा उपर्युक्त।

विश्वासभाजन
ह0/–
मुख्य अभियंता–2

ज्ञापांक 4114 / /पटना, दिनांक–31.10.19 /20

प्रतिलिपि:– कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, **बांका–2** को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

31.10.19
मुख्य अभियंता–2

Dib Narayan Ray

E:\CE-2 Office\Office Work\All Scheme\Work Order\Lottery\Banka-2.Doc

MUKHYA MANTRI GRAM SAMPRAK YOJANA (MMGSY)

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road :	Sulya Borba PMGSY Road TO Durgapur					
Block :	Chandan					
Length :	1.790 km	District :		Banka		
Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Providing & Fixing of Working benchmark/Refrence Pillars 01 nos. per km & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I				
	Benchmark Pillars 01 nos. per km	No	2	4,208.56	8417.12
	Refrence Pillars 04 nos. per km	No	7	1,929.56	13506.92
2	**Clearing and Grubbing Road Land** Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exeeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I **(By Manual Means) In area of non-thorny jungle**	Hect.	1.25	43,581.86	54477.33
3	**Box Cutting :-** Excavation for roadway in soil using manual means for carrying of cut earth to embankment site with a lift upto 1.5 m and lead upto 50 m as per Technical Specification Clause 302.3	Cum	3.75	88.42	331.58
4	**Construction of Embankment with Material Obtained from Roadway Cutting** Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet equirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5.	Cum	2.25	33.58	75.56
5	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a **lead upto 100** m as per Technical Specification Clause 301.5	Cum	1,788.06	147.3	263381.24
6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a **lead upto 1000 m** as per Technical Specification Clause 301.5	Cum	1,100.56	201.85	222148.04

DebNarayan Roy

Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
29	1st Year Maintenance cost	Year	1	70889.20	70889.20
30	2nd Year Maintenance cost	Year	1	92059.73	92059.73
31	3rd Year Maintenance cost	Year	1	443798.83	443798.83
32	4th Year Maintenance cost	Year	1	174006.24	174006.24
33	5th Year Maintenance cost	Year	1	505884.02	505884.02
				Total (B) =	1286638.02
	Grand Total Cost (A+B) =				13339802.18

Dib Narayan Ray