

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
4th year report on 4th Ball					
① Name of holder/maintenance of road from chandh					
Sobharai road to chand-					
pur Thakur Ashra					
② Name of Agency-smit					
Kumar					
③ Agreement No- 03/282/12-1					
④ Date of Mandi start 7/2/21					
⑤ Date of Mandi complete					
					09/3/22

① Restoration of rain cuts with soil, masonry etc. all complete 5/3					
3 x 7.50 x 1.05 x 0.30 = 7.08 m ³					
4 x 12.60 x 1.10 x 0.30 = 16.3 m ³					
2 x 10.90 x 1.10 x 0.30 = 7.19 m ³					
3 x 13.70 x 1.10 x 0.30 = 13.56 m ³					
5 x 9.90 x 1.05 x 0.30 = 15.59 m ³					
2 x 12.30 x 1.10 x 0.30 = 8.11 m ³					
3 x 11.70 x 1.10 x 0.30 = 11.55 m ³					
2 x 5.50 x 1.10 x 0.30 = 3.63 m ³					
				Qty	85.37 m ³
② Making up of berms soil etc. all complete 5/3					

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
3x	10.30x	1.00 =			30.90m
4x	12.50x	1.00 =			50.00m
2x	14.90x	1.00 =			29.80m
3x	12.90x	1.00 =			77.4m ²
5x	11.50x	1.00 =			57.5m ²
4x	12.50x	1.00 =			50.0m ²
3x	11.90x	1.00 =			35.70m ²
4x	12.50x	1.00 =			50.00m ²
5x	10.70x	1.00 =			53.50m
2x	13.00x	1.00 =			26.00m ²
				Qty	460.8m
③ Repair of pot holes					
Filled with 75mm etc.					
all completions					
1x	10.70x	1.20x	0.05 =		3.98m ²
2x	12.90x	3.00x	0.05 =		58.00m ²
4x	15.20x	2.90x	0.05 =		13.22
5x	14.70x	2.50x	0.05 =		13.78
4x	13.90x	2.70x	0.05 =		11.25
5x	15.50x	2.90x	0.05 =		16.85
6x	12.80x	3.00x	0.05 =		17.28
4x	13.50x	3.10x	0.05 =		12.35
5x	12.90x	2.80x	0.05 =		13.54
3x	15.00x	3.00x	0.05 =		70.29m
				Qty	115.52m ²
				Qty	105.43m

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
(6) Parished removed to existing bituminous surface etc. all complete job					
1x	10.70	1.20			12.84 m ²
1x	5.90	1.00			5.90 m ²
2x	4.90	1.20			11.76 m ²
1x	12.70	2.30			29.21 m ²
1x	14.50	2.20			31.90 m ²
2x	12.60	2.05			51.66 m ²
					143.27 m ²
					143.27 m ²
(7) Parished removed to two coat bitumen etc. all complete job, disposal etc. not T.M.B. para 54, item 6.					
					143.27 m ²
(8) Maintenance of concrete H/P culvert etc. all complete job.					
					143.27 m ²
(9) Maintenance of concrete slab culvert etc. all complete job.					
					1.100
(10) Cutting of branches of trees and shrubs etc. all					

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Completed by					
Dts 31.10					
(g) white washing of					
Parapet walls etc. all					
Completed by					
4 x 6.15 x 1.50 = 36.90 m ²					

ABSTRACT OF COST					
(1) Restoration of rain					
Cuts etc. all complete					
Job					
Dts vide TMS PWD 52					
Dts - 83.37 m ²					
@ Rs 351.06/m ²					29,26
(2) Making up of some					
etc. all complete					
Dts vide TMS PWD 53					
Dts 4108 m ²					
@ Rs 5238/m ²					24,136.44
(3) Repair of pot holes					
filled etc. all					
Continuation of 53,48 =					

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
			B. f B		53.482
Complete etc					
Qty vide Tms Pms 33					
Qty 105.47 m ²					
@ Rs 204.91/m ²					21,611.2
④ Periodical renewal to existing bitumens surface etc. all complete etc					
Qty vide Tms Pms 4					
Qty 105.47 m ²					
@ Rs 91.84/m ²					9686.2
⑤ Periodical renewal to existing bitumens Juss coat etc. all complete etc					
Qty vide Tms Pms 53					
Qty 105.47 m ²					
@ Rs 82.26/m ²					8676.2
⑥ Maintenance of concrete House Pipe Culvert etc. all complete etc					
Qty vide Tms Pms 54					
Qty 2110'					
@ Rs 1057.98/m ²					2116.2
					20575492

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
			bf-B		55.492
⑦ Maintenance of CD road glass culverts etc. all complete					
Qty mds 17854					
Qty 1110					
@ Rs 218-89/mt					2184
⑧ Cutting of branches and shrubs etc. all complete					
Qty mds 1055					
Qty 3110					
@ Rs 98-45/mt					295
⑨ white washing etc. all complete					
Qty mds 1055					
Qty 3690mt					
@ Rs 15-43/mt					571
					Total 98,542
(-) below 10% —					9854
					Total 88688
Chp					
for 30-0-0000					
12/4/23					
DE					
① EIW - 83.37 MT					
② Stone metre - 127.61 MT					
③ Bitumen - 0.089 MT					
Emulsion SS1 - 0.030 MT					
RS1 - 0.030 MT					