

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक- मु0अ0-4(मु0) 3054-01-05/2022-पार्ट-IV -02 /पटना, दिनांक:- 08/05/2024
प्रेषक,

उज्ज्वल कुमार सिंह, भा0प्र0से0
अपर मुख्य कार्यपालक पदाधिकारी
—सह— सचिव, ब्राडा।

सेवा में,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
सभी कार्य प्रमंडल।

विषय:- कार्य प्रमंडलों के PL खाते के CFMS Ledger ID-7069 से वापस लिये गये राशि के बराबर राशि MIS के माध्यम से प्रत्यर्पित करने के संबंध में।

प्रसंग:- ब्राडा का पत्रांक-68 दिनांक 06.05.2024

महाशय,


उपरोक्त विषयक प्रासंगिक पत्र के माध्यम से सभी कार्य प्रमंडलों के PL खाते के CFMS Ledger ID-7069 (बिहार ग्रामीण पथ अनुरक्षण नीति-2018) में उपलब्ध कराये गये राशि में से किये गये व्यय के उपरान्त अवशेष राशि को वापस लेकर कार्य प्रमंडलों से प्राप्त अन्य पथों के अधियाचना के विरुद्ध पत्रांक-69 दिनांक 06.05.2024 के माध्यम से आवंटन निर्गत किया गया है।

अतः सभी कार्यपालक अभियंता, कार्य प्रमंडल0 को निदेश दिया जाता है कि प्रासंगिक पत्र के माध्यम से वापस लिये गये राशि के बराबर राशि का पथवार प्रत्यर्पण MIS के माध्यम से तीन दिनों के अन्दर करना सुनिश्चित करेंगे।

कृपया इसे सर्वोच्च प्राथमिकता दे।

अनु0- यथोक्त।

विश्वासभाजन


(उज्ज्वल कुमार सिंह)

अपर मुख्य कार्यपालक पदाधिकारी
सह— सचिव, ब्राडा



Bihar Rural Road Maintenance Policy -2018

Division wise Surrender Amount though MIS against Pooled by H.O. from PIUs
Vide Letter No.- 68 dt 06.05.2024

(in Lakh)

SL. No.	PIU's Name	Pooled Amount	Surrender Through MIS by PIUs	Balance to be Surrender by PIUs through MIS
1	2	3	4	5
1	Arah	73.21762	11.98414	61.23348
2	Araria	57.77864		57.77864
3	Areraj	10.95814	6.21811	4.74003
4	Arwal	143.31692	34.78889	108.52803
5	Aurangabad	436.48638		436.48638
6	Bagaha-1	3.22831		3.22831
7	Bagaha-2	10.40361		10.40361
8	Baisi	263.81809		263.81809
9	Balia	54.42899		54.42899
10	Banka-1	15.44963		15.44963
11	Banka-2	136.60002		136.60002
12	Barh	3.52768		3.52768
13	Barsoi	158.89956		158.89956
14	Begusarai	0.09542	0.09542	-
15	Belsand	140.22281		140.22281
16	Benipatti	55.94552		55.94552
17	Benipur	174.24822		174.24822
18	Betia	71.81593		71.81593
19	Bhabhua	17.44156	17.44156	-
20	Bhagalpur	69.12097	58.42208	10.69889
21	Biharshariff	30.23183	11.49510	18.73673
22	Bikramganj	6.72571	6.72571	-
23	Biraol	89.78850		89.78850
24	Birpur	25.84356		25.84356
25	Buxar	17.71137		17.71137
26	Chakia	64.94615		64.94615
27	Chapra-1	15.21049		15.21049
28	Chapra-2	30.99714		30.99714
29	Dalsinghsarai	46.58175		46.58175
30	Danapur	97.67286	31.22505	66.44781
31	Darbhanga-1	732.30976	528.15824	204.15152
32	Darbhanga-2	82.20805		82.20805
33	Daudnagar	217.40224		217.40224
34	Dhamdaha	39.92249		39.92249
35	Dihri	16.94473		16.94473
36	Dumraon	3.48253		3.48253
37	Forbisganj	4.19905		4.19905
38	Gaya	155.43722	66.79095	88.64627
39	Gogri	2.21477		2.21477
40	Gopalganj-1	44.63785		44.63785
41	Gopalganj-2	20.92766		20.92766
42	Hajipur	52.66609		52.66609
43	Harnaut	89.17576		89.17576
44	Hathua	25.55777		25.55777
45	Hilsa	69.22734		69.22734
46	Imamganj	33.09959		33.09959
47	Jagdishpur	148.18175		148.18175
48	Jahanabad	254.07321		254.07321
49	Jamui	4.15847		4.15847
50	Jaynagar	70.51416	56.57940	13.93476

51	Jhajha	17.24378		17.24378
52	Jhanjharpur	276.24003		276.24003
53	Kahaigaon	171.21016	114.42802	56.78214
54	Katihar	47.27668		47.27668
55	Khagaria	37.12496	33.62011	3.50485
56	Kharagpur Tarapur	280.54447		280.54447
57	Kishanganj-1	330.12131		330.12131
58	Kishanganj-2	552.49051		552.49051
59	Lakhisarai	154.32664	144.29113	10.03551
60	Madhepura	134.33071		134.33071
61	Madhubani	1.90048		1.90048
62	Mahnar	235.88490		235.88490
63	Mahraiganj	11.62978	0.31390	11.31588
64	Mahua	53.18918		53.18918
65	Manihari	46.20030		46.20030
66	Manjhaul-Bakhari	0.00020		0.00020
67	Marhaura	28.28050		28.28050
68	Masaurhi	40.67222		40.67222
69	Mohaniya	250.43771		250.43771
70	Motihari	171.81642		171.81642
71	Munger	104.96023	21.08881	83.87142
72	Muzaffarpur (West)	61.33153	60.37533	0.95620
73	Muzaffarpur East- 2	72.49884	29.79015	42.70869
74	Muzaffarpur East-I	12.91404		12.91404
75	Narkatiaganj	32.76194		32.76194
76	Navgachiya	39.77552		39.77552
77	Nawada	134.72608	132.92516	1.80092
78	Ncemchak Bathani	19.31329	1.43079	17.88250
79	Pakridayal	85.79355	14.96238	70.83117
80	Paliganj	28.36929		28.36929
81	Patna	328.54418		328.54418
82	Patori	29.47574		29.47574
83	Phulparas	3.25747		3.25747
84	Piro	30.77480		30.77480
85	Pupari	57.42397		57.42397
86	Purnia	344.68591	124.39933	220.28658
87	Rajauli	23.67443		23.67443
88	Rajgir	83.35889	31.64273	51.71616
89	Raxaul	80.60515		80.60515
90	Rosera	222.57473		222.57473
91	Saharsa	155.29650		155.29650
92	Samastipur	118.68077		118.68077
93	Sasaram-1	32.91667		32.91667
94	Sasaram-2	2.14662	1.00554	1.14108
95	Shekhpura	46.91938		46.91938
96	Sherghati	45.36031		45.36031
97	Shivhar	132.57965		132.57965
98	Sikaharna (Dhaka)	60.37770		60.37770
99	Simri Bakhatiyarpur	64.56791	56.99681	7.57110
100	Sitamarhi	118.67603		118.67603
101	Siwan-1	172.59377		172.59377
102	Siwan-2	12.30308	8.90273	3.40035
103	Sonpur	1.83258		1.83258
104	Supaul	185.87800		185.87800
105	Teghara	12.89425	2.43784	10.45641
106	Tikari	33.78940		33.78940
107	Triveniganj	355.98077		355.98077
108	Udakishungani	146.21228		146.21228
		10,725.80006	1,608.53541	9,117.26465

कार्यपालक अभियंता का कार्यालय,

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, वीरपुर।

पत्रांक...1334.../

वीरपुर, दिनांक ...1.../...10.../2020

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, वीरपुर।

सेवा में,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मधेपुरा।

विषय :- परिमाण विपत्र अनुमोदन के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में कहना है कि FDR योजनान्तर्गत पथ Suryapur wale village me Raghua Razak Ke Ghar se Gopal Rajak Ke Ghar tak का परिमाण विपत्र अनुमोदन हेतु आवश्यक कार्रवाई हेतु समर्पित की जाती है।

Sl. No.	Block	Name of Road	BOQ Amount (In Lakh)
1	Partapganj	Suryapur wale village me Raghua Razak Ke Ghar se Gopal Rajak Ke Ghar tak	17.042

अनु०:-BOQ एक अदद में।

विश्वासभाजन

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, वीरपुर।

18/10/20



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

YEAR (2020 - 2021)

FDR

STATE :- BIHAR
DISTRICT :- Supaul
BLOCK :- Pratapganj

Bill Of Quantity

Restoration Of Traffic of Suryapurwale me raghuarazak Ke ghar togopalrazak house
takunder Pratapganj Block

TOTAL COST OF CONSTRUCTION :- Rs. 17.042 Lacs

SUBMITTED BY:

EXECUTIVE ENGINEER
RWD (w) DIVISION, VIRPUR
SUPAUL

FDR
YEAR(2020 - 2021)

GENERAL ABSTRACT OF COST

Block:--Pratapganj

District:--Supaul

Name of Road:--

Restoration Of Traffic of Suryapur waleme raghua razak Ke
ghar to gopal razak house tak under Pratapganj Block

SL. NO.	Item of work	Amount
A		
	TOTAL COST OF CONSTRUCTION	17.042 Lacs
	TOTAL cost of project	17.042 Lacs

Dr. Teluho
Executive Engineer
RWD (w) Division, Virpur

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :

Detailed Estimate For Restoration Of Traffic of Suryapur wale me
raghwa razak Ke ghar to gopal razak house tak under Pratapganj Block

DISTRICT

Supaul

BLOCK

Pratapganj

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	BRICK BAT & SAND FILLING	12.586
2	GSB	1.191
3	WBM GRADE III	1.194
	SUB TOTAL OF PAVEMENT COST IN LACS =	14.971
	12% GST on Total Amount :-	1.797
	1% Lab Cess :-	0.150
	Seigniorage Fee @ 10% on Material	0.124
	Total Restoration Cost (including GST and Labour Cess) (A) :-	17.042

dm T & Loko
Executive Engineer
RWD(w)
Division, Virpur

Sl. No.	Description	Unit	QUANTITY	RATE	AMOUNT (In Rs.)
1	Sand Filling Providing Local SAND filling bottom of both sides embankment	CUM	1132.5	554.03	627438.98
2	Brick Bats Laying Brick Bats on Prepared Soil Surface as per specifications and direction of E/L. Both side Damaged Flank (Brick bat upon earthwork) in 200 m damaged portion (ditch points)	cum	338.55	1864.35	631167.54
3	Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading I Material (With Stone Screening) Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	CUM	35.54	3351.45	119110.53
4	WBM Grading 3 (By Mechanical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	29.10	4101.79	119362.09
Sub Total					14,97,079.13
SUB TOTAL OF PAVEMENT COST IN LACS =					1497079.13
12% GST on Total Amount :-					179649.50
1% Lab Cess :-					14970.79
Seigniorage Fee @ 10% on Material					12500.80
Total Restoration Cost (including GST and Labour Cess) (A) :-					1704200.22

Line had to be
(den to all staff)
17,00,000 =
 Executive Engineer
 RWD Division Virpur

10.0.8 approved for Rs 17,00,000 = (Rupees seven
 ten lacs) only

Certified Copy
 10/06/21

अधीक्षण अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, मधेपुरा

पत्रांक ...515310/...

दिनांक ...15.10.2021/

प्रेषक,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मधेपुरा।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, वीरपुर।

विषय :- वित्तीय वर्ष 2020-21 में FDR के अंतर्गत मोटरेबुल कराये गये पथ का कोटेशन स्वीकृति के फलस्वरूप वापस करने के संबंध में।

प्रसंग :- कार्यपालक अभियंता, ग्रामीण कार्य विभाग कार्य प्रमंडल, वीरपुर का पत्रांक-1333/21 दिनांक-17.10.2020

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र द्वारा प्राप्त कार्य प्रमंडल, वीरपुर में FDR अंतर्गत मोटरेबुल कराये गये कुल 01 पथ का कोटेशन स्वीकृति के फलस्वरूप मूल में वापस किया जाता है।

अनु० :- यथोक्त।

विश्वासभाजन



अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल, मधेपुरा।

पत्रांक...517...9135.../

मधेपुरा, दिनांक 10...../06..../2024

प्रेषक,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मधेपुरा।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, वीरपुर।

विषय :- परिमाण विपत्र वापस करने के संबंध में।

प्रसंग:- कार्यपालक अभियंता ग्रामीण कार्य विभाग कार्य प्रमण्डल, वीरपुर को पत्रांक-1334 अनु0
दिनांक- 18.10. 2020


महाशय,

उपर्युक्त विषय के संबंध में कहना है कि FDR योजनान्तर्गत पथ Suryapur wale village me Raghua Razak Ke Ghar se Gopal Rajak Ke Ghar tak का परिमाण विपत्र अनुमादनोंपरांत वापस की जाती है।

Sl. No.	Block	Name of Road	BOQ Amount (In Lakh)
1	Partapganj	Suryapur wale village me Raghua Razak Ke Ghar se Gopal Rajak Ke Ghar tak	17.02 17.042 4.11

अनु0:-BOQ एक अदद में।

विश्वासभाजन


12/06/21
अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मधेपुरा।

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, वीरपुर।

पत्रांक 1333/2020

दिनांक 17/10/20

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, वीरपुर।

सेवा में,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मधेपुरा।

विषय :- वित्तीय वर्ष 2020-21 में FDR के अंतर्गत मोटरेबुल कराये गये पथों का कोटेशन स्वीकृति हेतु समर्पित करने के संबंध में।

महाशय,

उपर्युक्त विषयक संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमंडल, वीरपुर अंतर्गत वित्तीय वर्ष 2020-21 में FDR के अंतर्गत मोटरेबुल कराये गये पथों का कोटेशन स्वीकृति हेतु विहित प्रपत्र में तैयार कर आवश्यक कार्रवाई हेतु समर्पित।

अनु० :- कुल-01 अदद कोटेशन संलग्न।

विश्वासभाजन

17/10/20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग

कार्य प्रमंडल, वीरपुर

17/10/20

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, वीरपुर।

पत्रांक 1333/2020/

दिनांक 17/10/20

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, वीरपुर।

सेवा में,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मधेपुरा।

विषय :- वित्तीय वर्ष 2020-21 में FDR के अंतर्गत मोटरेबुल कराये गये पथों का कोटेशन स्वीकृति हेतु समर्पित करने के संबंध में।

महाशय,

उपर्युक्त विषयक संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमंडल, वीरपुर अंतर्गत वित्तीय वर्ष 2020-21 में FDR के अंतर्गत मोटरेबुल कराये गये पथों का कोटेशन स्वीकृति हेतु विहित प्रपत्र में तैयार कर आवश्यक कार्रवाई हेतु समर्पित।

अनु० :- कुल-01 अदद कोटेशन संलग्न।

विश्वासभाजन

Am
17/10/20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, वीरपुर

स.स. अभि०

17/10/20

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, वीरपुर।

पत्रांक 1333/2020/

दिनांक 12/12/20/

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, वीरपुर।

सेवा में,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, मधेपुरा।

विषय :- वित्तीय वर्ष 2020-21 में FDR के अंतर्गत मोटरेबुल कराये गये पथों का कोटेशन स्वीकृति हेतु समर्पित करने के संबंध में।

महाशय,

उपर्युक्त विषयक संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमंडल, वीरपुर अंतर्गत वित्तीय वर्ष 2020-21 में FDR के अंतर्गत मोटरेबुल कराये गये पथों का कोटेशन स्वीकृति हेतु विहित प्रपत्र में तैयार कर आवश्यक कार्रवाई हेतु समर्पित।

अनु० :- कुल-01 अदद कोटेशन संलग्न।

विश्वासभाजन

12/12/20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, वीरपुर

12/12/20

OFFICE OF THE EXECUTIVE ENGINEER, RURAL WORKS DEPARTMENT, WORKS DIVISION, BIRPUR COMPARATIVE STATEMENT
OF QUOTATION FOR TEMPORARY RESTORATION OF THE ROAD
QUOTATION CALL VIDE LETTER NO. DATED DATE OF RECEIPT :-

Name of Road :- Restoration work of road from Suryapur wale village me Raghua Razak Ke Ghar se Gopal Razak Ke Ghar tak.

Sl. No.	Name of Items	Unit	M/S RENUDEVI Add :- Er. Rajendra New Kunj Colony, Rajendra Nagar, Patna- 16 PAN-AYCPG9689B GST-10AYCPG9689B1ZM	M/S Mithun Kumar Add :- At+Po- Rampur, Via- Murliganj, Distt- Madhepura, Bihar, Pin-852122 GST- 10CXHPK2865F1ZP PAN-CXHPK2865F	RAM KUMAR Add :- At+Po- KALYANPUR, BHAPTIYAH, GST- 10BSIPK191F1ZS PAN-BSIPK8191F
			RATE	RATE	RATE
1	Sand Filling: Providing Local SAND filling	Cum	554.00	554.03	555.50
2	Brick Bats: Laying Brick Bats on Prepared Soil Surface as per specifications and direction of E/L. Both side Damaged Flank (Brick bat upon earthwork) in 200 m damaged portion (ditch points)	Cum	1864.30	1864.35	1865.50
3	GSB: Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading 1 Material (With Stone Screening) Construction of granular sub-base by providing well graded material, spreading	Cum	3351.43	3351.45	3352.65
4	WBM Grading 3 (By Mechanical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification	Cum	4101.75	4101.79	4102.60
			9871.48	9871.62	9876.25

C/S is forwarded to SE, RWD (W) The Lowest Rate Quoted by M/S RENUDEVI Circle, Madhepura for Approval. **CONSTRUCTION** is hereby Approved.

SM
13/10/20
C/S Prepared
by me

SM
17/10/20

Am
13/10/20
Executive Engineer
RWD, Works Division, Birpur

Approved
11/10/20
10/06/21
Superintending Engineer
RWD, Works Circle, Madhepura

OFFICE OF THE EXECUTIVE ENGINEER, RURAL WORKS DEPARTMENT, WORKS DIVISION, BIRPUR COMPARATIVE STATEMENT
OF QUOTATION FOR TEMPORARY RESTORATION OF THE ROAD
QUOTATION CALL VIDE LETTER NO..... DATED..... DATE OF RECIEPT :-

Name of Road :- Restoration work of road from Suryapur wale village me Raghua Razak Ke Ghar se Gopal Razak Ke Ghar tak.

Sl. No.	Name of Items	Unit	M/S RENUDEVI Add :- Er. Rajendra New Kunj Colony, Rajendra Nagar, Patna- 16 PAN-AYCPG9689B GST-10AYCPG9689B1ZM	M/S Mithun Kumar Add :- At+Po- Rampur, Via- Murliganj, Distt- Madhepura, Bihar, Pin-852122 GST- 10CXHPK2865F1ZP PAN-CXHPK2865F	RAM KUMAR Add :- At+Po- KALYANPUR, BHAPTIYAH, GST- 10BSIPK191F1ZS PAN-BSIPK8191F
			RATE	RATE	RATE
1	Sand Filling: Providing Local SAND filling	Cum	554.00	554.03	555.50
2	Brick Bats: Laying Brick Bats on Prepared Soil Surface as per specifications and direction of E/L. Both side Damaged Flank (Brick bat upon earthwork) in 200 m	Cum	1864.30	1864.35	1865.50
3	GSB: Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading 1 Material (With Stone Screening) Construction of granular sub-base by providing well graded material, spreading	Cum	3351.43	3351.45	3352.65
4	WBM Grading 3 (By Mechanical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification	Cum	4101.75	4101.79	4102.60
			9871.48	9871.62	9876.25

C/S is forwarded to SE, RWD (W) The Lowest Rate Quoted by M/S RENUDEVI Circle, Madhepura for Approval. CONSTRUCTION is hereby Approved.

[Signature]
17/10/20

C/S Prepared
by me

[Signature]
17/10/20

[Signature]
17/10/20
Executive Engineer
RWD, Works Division, Birpur

[Signature]
Approved
sd/-
Superintending Engineer
RWD, Works Circle, Madhepura

[Signature]
Approved
10/06/21

GSTIN : 10AYCPG9689B1ZM
PAN No.: AYCPG9689B



Date: 06/10/20

Ref.

Name Of Work - Restoration work of road from Suryapur wale village me Raghua Razak Ke Ghar se Gopal Razak Ke Ghar tak. Block-Pratapganj, Distt- Supaul. RWD Circle- Madhepura. RWD (W)- Birpur.					
Sl. No.	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1	Sand Filling Providing LocalSAND filling bottom of both sides embankment.	CUM	1132.50	554.00	627405.00
2	Brick Bats Laying Brick Batson Prepared Soil Surface as per specifications and direction of E/L. Both side Damaged Flank (Brick bat upom earthwork) in 200 m damaged portion (ditchpoints)	CUM	338.50	1864.30	631065.55
3	Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method)For Grading I Material (With Stone Screening) Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	CUM	35.54	3351.43	119109.8222
4	WBM Grading 3 (By Mechanical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	29.10	4101.75	119360.925
Sub Total					1496941.30
12% GST on Total Amount :-					179632.96
1% Lab Cess :-					14969.41297
Seigniorage Fee @ 10% on Material					23,421.22
Total Restoration Cost (including GST and Labour Cess) :-					1,714,964.88

Renu Devi Construction

Er. Rajendra Prasad, New Kunj Colony, Rajendra Nagar, Eastern, Patna-16
Mob.: 9504295151, 7979876321 | E-mail : renudeviconstruction@gmail.com



Mithun Kumar
Cust. Reg. Contractor
Reg No. 4103701

+919709327054
mkj271290@gmail.com
PAN NO- CXHPK2865F
GSTIN: 10CXHPK2865F1ZP

Date: 06/10/20

Name Of Work - Restoration work of road from Suryapur wale village me Raghua Razak Ke Ghar se Gopal Razak Ke Ghar tak. Block-Pratapganj, Distt- Supaul. RWD Circle- Madhepura. RWD (W)- Birpur.					
Sl. No.	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1	Sand Filling Providing Local SAND filling bottom of both sides embankment	CUM	1132.50	554.03	627438.98
2	Brick Bats Laying Brick Bats on Prepared Soil Surface as per specifications and direction of E/L. Both side Damaged Flank (Brick bat upom earthwork) in 200 m damaged portion (ditchpoints)	CUM	338.50	1864.35	631082.48
3	Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading I Material (With Stone Screening) Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	CUM	35.54	3351.45	119110.533
4	WBM Grading 3 (By Mechanical Means) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405	Cum	29.10	4101.79	119362.089
Sub Total					1496994.07
12% GST on Total Amount :-					179639.29
1% Lab Cess :-					14969.94072
Seigniorage Fee @ 10% on Material					23,421.22
Total Restoration Cost (including GST and Labour Cess) :-					1,715,024.52

Mithun Kumar

Mithun Kumar

AT-PO- Rampur, Via- Murliganj, Dist- Madhepura, Bihar, Pin-852122

RAM KUMAR

A - Kalyanpur,
Po+Ps- Bhaptiyahi
Dist- Supaul (Bihar)

Email: ramkumarmehta25@gmail.com

9939816551
7011695748

PAN: BSIPK8191F

GSTIN: 10BSIPK8191F1ZS

RWD Reg No- 4210039

Ref. No: 30 - The Executive Engineer
Bis Pur Date: 06/10/20

Name of Work - Restoration work of road from Suryapur wale village me Raghua Razak Ke Ghar se Gopal Razak Ke Ghar tak. Bloc (-Pratapganj), Distt- Supaul. RWI Circle-Madhepura. RWI (W)- Birpur.				
Sl. No.	Description	Unit	QUANTIT Y	AMOUNT (in Rs.)
	Sand Filling Providing Local SAND filling bottom of both sides embankment	CUM	1132.50	555.50
	Brick Bats Laying Brick Bats on Prepared Soil Surface as per specifications and direction of E/L. Both side Damaged Flank (Brick bat upon earthwork) in 200 m damaged portion (ditch points)	CUM	338.50	1865.50
3	Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading I Material (With Stone Screening) Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	CUM	35.54	3352.65
4	WBM Grading 3 (By Mechanical Means) Providing, laying, spreading and rompacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	Cum	29.10	4102.6
Sub Total				1499114.34
12% GST on Total Amount :-				179893.72
1% Lab Cess :-				14991.14341
Seigniorage Fee @ 10% on Material				23,421.22
Total Restoration Cost (including GST and Labour Cess) :-				1,717,420.42

10/10/20