

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

बिहार BIHAR

13 AUG 2024

4186/मोक-051081025 रजित कुमार को श्री परमेश्वर सिंह
(श्री परमेश्वर) ताता को रास्ता पटना को 1000 रु. 757152
का कागज

दिनांक: 13/08/24
आवेदन: 13/08/24
पृ. 80 3198-97

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

**SUPPLEMENTARY AGREEMENT NO:- 08/SBD/2024-25
of 08/SBD/2022-23**

This agreement, made 07th August Day of 2024 between Executive Engineer, RWD, Works Division, Lakhisarai, Munger, Govt. of Bihar Patna and **Sri. Ranjit Kumar, At+PO- Parsawan, PS- NTPC Barh, Dist- Patna.**

Whereas the Employer is desirous that the Contractor execute the Construction of Road and CD works for Kaandee se Mohiyaa of Block in Halsi, Under MMGSY in Lakhisarai District and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 1,24,17,355.00 (Rs. One Crore Twenty Four Lakh Seventeen Thousand Three Hundred Fifty Five) and five year maintenance cost Rs. 18,65,156.00 (Rs. Eighteen Lakh Sixty Five Thousand One Hundred Fifty Six) Total cost of Rs. 1,42,82,511.00 (Rs. One Crore Forty Two Lakh Eighty Two Thousand Five Hundred Eleven) only.

12/08/24

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमाण्डन, लखीसराय

12-8-24

-:Contractor's BID :-

Attached separately

NAME OF WORK:- Kaindee se Mohiyaa of Block in Halsi, Under MMGSY in Lakhisarai District.

District:- Lakhisarai

Block :- Halsi

Sl. No	Name of Road	Length (km)	Cost of const. (Rs. In lacks)	Maintenance cost (Rs. In lacks)
1.	Kaindee se Mohiyaa	2.050	124.17355	18.65156
Total		2.050	124.17355	18.65156

Rajesh Kumar

Rajesh Kumar
12/08/24

Rajesh Kumar
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, लखीसराय
12.8.24

SUPPLEMENTARY AGREEMENT NO:- 08/SBD/2024-25

NAME OF WORK: - Kaindee se Mohiyaa of Block in Halsi, Under MMGSY in Lakhisarai District.

NAME OF AGENCY: - Sri. Ranjit Kumar ,
At+PO- Parsawan,
PS- NTPC Barh,
Dist- Patna.

Reference :- Superintending Engineer,
R.W.D, Works Circle, Munger.
Vide Letter No. 734 Date . 23.07.2024

SUPPLEMENTARY AGREEMENT AMOUNT-

Main work:- 1,24,17,355.00
Maintenance work:- 18,65,156.00
Total Amount: - 1,42,82,511.00

Performance Security: - Deposited @ 2% Next 8% deducted from Bill

Supplementary Agreement Date :- 07.08.2024

Date of Commencement :-

Date of Completion :-

No. of Item of Work :- As per B.O.Q (Nos)

Rate Quoted :- 0.01% below (Zero Point zero one percent below only)


Signature of Contractor


12/08/24


कार्यपालक अभियंता
Executive Engineer
RWD, Works Division, Lakhisarai
12.8.24

Revised Bill of Quantity

Tender Inviting Authority: Engg-In Chief RWD Patna

Name of Work :- Kaindee Se Mohiyaa

Contract No: Civil Works/

Name of the
Bidder/ Bidding
Firm/ Company :


PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Providing & Fixing of Working benchmark Pillars 01 nos. per km. & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I Working benchmark Pillars	2.000	No.	3824.130	7648.26	INR Seven Thousand Six Hundred & Forty Eight and Paise Twenty Six Only
2	Providing & Fixing of Working benchmark Pillars 01 nos. per km. & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I Reference Pillars	8.000	No.	1747.650	13981.20	INR Thirteen Thousand Nine Hundred & Eighty One and Paise Twenty Only
3	Clearing and Grubbing Road Land (By manual means) Including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & removal of unserviceable material & stockpiling of soil	1.230	Ha	53879.810	66272.17	INR Sixty Six Thousand Two Hundred & Seventy Two and Paise Seventeen Only
4	Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross-sections, and transporting to the embankment location with a lift upto 1.5 m and lead upto 1000 m as per Technical Specification Clause 302.3 (Including Royalty & Labour Cess).	45.950	cum	75.610	3474.28	INR Three Thousand Four Hundred & Seventy Four and Paise Twenty Eight Only
5	Construction of embankment with approved material deposited from road way cutting and excavation from drain and foundation of other structures and excavated with an average lead of 100 m graded and compacted to meet requirement of tables 300.1 and 300.2 as per	27.570	cum	49.510	1364.99	INR One Thousand Three Hundred & Sixty Four and Paise Ninety Nine Only
6	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. (Including Royalty & Labour Cess).	1244.840	cum	190.410	237029.98	INR Two Lakh Thirty Seven Thousand & Twenty Nine and Paise Ninety Eight Only
7	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5. (Including Royalty & Labour Cess).	775.060	cum	166.100	128737.47	INR One Lakh Twenty Eight Thousand Seven Hundred & Thirty Seven and Paise Forty Seven Only
8	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m &	4593.100	cum	209.590	962667.83	INR Nine Lakh Sixty Two Thousand Six Hundred & Sixty Seven and Paise Eighty Three Only

Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
27	Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600	3.00	Sqm	2752.79	8258.37	INR Eight Thousand Two Hundred & Fifty Eight and Paise Thirty Seven Only
28	Providing and fixing of typical MR(3054) informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the	5.000	No	9326.910	46634.55	INR Forty Six Thousand Six Hundred & Thirty Four and Paise Fifty Five Only
29	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and	125.28	cum	283.94	35572.00	INR Thirty Five Thousand Five Hundred & Seventy Two Only
30	Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	22.800	cum	5074.110	115689.71	INR One Lakh Fifteen Thousand Six Hundred & Eighty Nine and Paise Seventy One Only
31	Plain/Reinforced cement concrete(M-20) in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	97.12	cum	5690.59	552670.10	INR Five Lakh Fifty Two Thousand Six Hundred & Seventy and Paise Ten Only
32	Providing and laying RCC pipe NP-3 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106	60.00	RM	2086.19	125171.40	INR One Lakh Twenty Five Thousand One Hundred & Seventy One and Paise Forty Only
33	ADD Labour Cess @ 1%	1.000	Rs	102722.060	102722.06	INR One Lakh Two Thousand Seven Hundred & Twenty Two and Paise Six Only
34	ADD GST @ 18%	1.000	Rs	1848996.010	1848996.01	INR Eighteen Lakh Forty Eight Thousand Nine Hundred & Ninety Six and Paise One Only
35	Seigniorage Fee @ 10%	1.000	Rs	194678.550	194678.55	INR One Lakh Ninety Four Thousand Six Hundred & Seventy Eight and Paise Fifty Five Only
	Total Cost Of Construction :-				12418596.70	INR One Crore Twenty Four Lakh Eighteen Thousand Five Hundred & Ninety Six and Paise Seventy Only
	MAINTENANCE					
36	1st Year Maintenance cost	2.050	KM	46892.200	96129.01	INR Ninety Six Thousand One Hundred & Twenty Nine and Paise One Only
37	2nd Year Maintenance cost	2.050	KM	81701.950	167489.00	INR One Lakh Sixty Seven Thousand Four Hundred & Eighty Nine Only
38	3rd Year Maintenance cost	2.050	KM	240585.850	493200.99	INR Four Lakh Ninety Three Thousand Two Hundred and Paise Ninety Nine Only

Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
39	4th Year Maintenance cost	2.050	KM	109591.710	224683.01	INR Two Lakh Twenty Four Thousand Six Hundred & Sixty Three and Paise One Only
40	5th Year Maintenance cost	2.050	KM	267435.120	548242.00	INR Five Lakh Forty Eight Thousand Two Hundred & Forty Two Only
41	ADD Labour Cess @ 1%	1.000	Rs	15297.240	15297.24	INR Fifteen Thousand Two Hundred & Ninety Seven and Paise Twenty Four Only
42	ADD GST @ 18%	1.000	Rs	275350.320	275350.32	INR Two Lakh Seventy Five Thousand Three Hundred & Fifty and Paise Thirty Two Only
43	Seigniorage Fee @ 10%	1.000	Rs	44972.000	44972.00	INR Forty Four Thousand Nine Hundred & Seventy Two Only
	Total Cost Of Maintenance :-				1865343.57	INR Eighteen Lakh Sixty Five Thousand Three Hundred & Forty Three and Paise Fifty Seven Only
Total in Figures					14283940.27	INR One Crore Forty Two Lakh Eighty Three Thousand Nine Hundred & Forty and Paise Twenty Seven Only
Quoted Rate in Figures			Less (-)	0.01%	14282511.68	INR One Crore Forty Two Lakh Eighty Two Thousand Five Hundred & Eleven and Paise Eighty Eight Only
Quoted Rate in Words		INR One Crore Forty Two Lakh Eighty Two Thousand Five Hundred & Eleven and Paise Eighty Eight Only				


 10/06/14
 Executive Engineer
 RWD Works Division
 Lakhisarai