

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये
रु.1000

ONE THOUSAND RUPEES
Rs.1000

OFFICE OF THE EXECUTIVE ENGINEER

RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 04/MBD/2024-25

This agreement, made the 10 July Day of 2024 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and Sri Pankaj Kumar Pawan, C/o- Sri Shyam Dev Prasad, Munger Road near Daryinpur Church, PO:- Jamalpur, Dist:- Munger.

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road Contract of the maintenance of road from MR-N/23-24/Lakhisarai/26 Package Under of Block in Chaman/Pipariya, Under M/R in Lakhisarai District and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 3,16,82,245.00 (Three Crore Sixteen Lakh Eighty Two Thousand Two Hundred Forty Five) only & five year Maintenance cost Rs. 88,64,824.00 (Eighty Eight Lakh Sixty Four Thousand Eight Hundred Twenty Four) only. Total Cost Rs. 4,05,47,069.00 (Four Crore Five Lakh Forty Seven Thousand Sixty Nine) only.

A. He has deposited Performance Security Deposit and Additional Performance Guarantee vide FD No. Rs.

B.

Sl. No.	Name of Road	Length (In km)	Const. Cost	Maintenance cost	Agreement Value
1	PMGSY Road Bhundar to Bagicha Tola Sangrampur	0.350	906135	389012	1295147
2	(LO38)Ramsir - Bichwa	0.660	1635399	770578	2405977
3	L058-L038 - Bichawya	0.350	898546	412856	1311402

Pankaj Kumar Pawan

Executive Engineer
RWD Works Division
Lakhisarai

4	PMGSY Bhandar to matar asthan tola	0.700	1656886	782870	2439756
5	PMGSY road to Balahpur gram via anasuchit jati	1.100	2618789	1227496	3846286
6	PMGSY road to south mandal tola	1.260	2830716	1307102	4137818
7	PMGSY shiv mandir to rewta Mushahari tola	0.350	1898353	246932	2145284
8	To2 To Basuachak	0.720	3669294	495954	4165248
9	L041 Aolipur Chowk To South Tola Aolipur	0.400	1641443	498442	2139886
10	Dih Pipariya to Basauna	1.070	4800236	1211478	6011714
11	Upgraded Primary School Aolipur to High school Aolipur	0.925	5183052	852623	6035675
12	Walipur library - walipur middle school (Rescind work)	0.726	3943395	669481	4612876
Total		8.611	3,16,82,245	88,64,824	4,05,47,069

NOW THIS AGREEMENT WITNESSTH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to and they shall be deemed to form and be read and construed as part of this agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the Execution adcompletion of the works and the remedying the defects hear in Contract price or such other sum as may become payable under the provision of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz
 - a. Letter of Acceptance
 - b. Contractor's Bid
 - c. Section VI -General Conditions
 - d. Section VII- Particular Condition
 - e. Section V - Technical Specification (General and Supplementary Technical Specification
 - f. Appendix A - Drawings
 - g. Section IV - Works Schedule
 - h. Quality plan for output and performance based road contract as per clause A14.1 of the technical specifications
 - i. Appendices of the contract
 - j. Addenda issued during bid period
 - k. Any other relevant documents listed in the particular conditions together with any post bid correspondence.

Pankaj Kumar Bhusan

[Signature]
10/07/24

[Signature]
Executive Engineer
RWD Works Division
Lakhisarai
10/07/24

-:Contractor's BID :-

Attached separately

NAME OF WORK:- MR-N/23-24/Lakhisarai/26 Package Under of Block in Chanan/Pipariya, Under M/R in Lakhisarai District.

District:- Lakhisarai

**Block :- Suryagarha
Chanan**

Sl. No	Name of Road	length (km)	Cost of Construction (Rs. In lacks)	Maintenance cost (Rs. In lacks)
1.	MR-N/23-24/Lakhisarai/26	8.611	316.82245	88.64824
Total		8.611	316.82245	88.64824

Pankaj Kumar Purohit

Pankaj
10/07/24

10/07/24
Executive Engineer
RWD Works Division
Lakhisarai

OFFICE OF THE EXECUTIVE ENGINEER
RURALWORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 04/MBD/2024-25

NAME OF WORK: - MR-N/23-24/Lakhisarai/26 Package Under of Block in Chanan/Pipariya, Under M/R in Lakhisarai District.

NAME OF AGENCY: Sri Pankaj Kumar Pawan,
C/o- Sri Shyam Dev Prasad,
Munger Road near Dariyapur Charch,
PO.- Jamalpur, Dist.- Munger.

Reference :- Chief Engineer-3,
R.W.D, Bhagalpur, Bihar, Patna
Vide Letter No. 379 Date :- 14.06.2024

AGREEMENT AMOUNT – Main work:- 3,16,82,245.00
Maintenance work:- 88,64,824.00
Total Amount: - 4,05,47,069.00

Performance Security :- Deposited @ 5 % & Next 5 % deducted from Bill
Date of Agreement :- 10.07.2024
Date of Completion :- 09.02.2025
No. of Item of Work :- As per B.O.Q (Nos)
Rate Quoted :- 1.11 % below (One Point one one percent below)

Contractor Signature

Pankaj Kumar Pawan.

[Signature]
10/07/24

[Signature] 10/07/24
Executive Engineer
RWD, Works Division, Lakhisarai
Rakhishri
10/07/24

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : **PMGSY ROAD BHANDAR To BAGICHA TOLA**
SANGRAMPUR
 Length of Road : **0.35**

District : **LAKHISARAI**
 Block : **CHANAN**

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
12	10.6	(II) Providing and Fixing 'Logo' of Maintenance				
		Providing and fixing of typical PMGSY informative sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing, arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of	No	3.000	12112.60	36337.80
13	13.9	Brick Masonry in C.M.(1:3) in parapet				
		Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	cum	2.880	6324.54	18214.88
14	12.3 (I)A	Plastering with cement mortar (1:4)				
		Plastering with cement mortar (1:4) on brick work in sub structure as per Technical Specifications	sqm	40.320	192.40	7757.57
15	12.13	Painting Two Coats on New Concrete Surfaces				
		Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	sqm	40.320	139.16	5610.93
16		1% Labour Cess	Rs	1.000	7623.22	7623.22
17		18% GST	Rs	1.000	137217.88	137217.88
18		Add 10% Seigniorage Fee :	Rs	1.000	9145.07	9145.07
Total Construction Cost :						916307.73
9		1st Year Maintenance cost	Year	1.000	41931	41931.00
0		2nd Year Maintenance cost	Year	1.000	43213	43213.00
1		3rd Year Maintenance cost	Year	1.000	121528	121528.00
2		4th Year Maintenance cost	Year	1.000	60141	60141.00
3		5th Year Maintenance cost	Year	1.000	62976	62976.00
1		1% Labour Cess	Rs	1.000	3297.89	3297.89
1		18% GST	Rs	1.000	59382.02	59382.02
1		Add 10% Seigniorage Fee :	Rs	1.000	928.52	928.52
Five Year Maintenance Cost :						393378.43
Total Estimated Cost in Figures						1309686.16
Amount						1,309,686.00


Executive Engineer
 Rural Work, Department
 Work, Div, Lakhisarai

EE
 RWD (w) DIV
 LAKHISARAI

Kad Kumar Pandey

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : L058-L038 To BICHAHYA

Length of Road : 0.35

District : LAKHISARAI
Block : CHANAN

SL No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
13	10.6	(I) Providing and Fixing 'Logo' of Maintenance				
		Providing and fixing of typical MMGSY informative sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of	No	3.000	13084.04	39252.12
14	13.9	Brick Masonry in C.M.(1:3) in parapet				
		Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	cum	2.880	6363.03	18325.53
15	12.3 (i)A	Plastering with cement mortar (1:4)				
		Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	sqm	20.160	196.25	3956.40
16	12.13	Painting Two Coats on New Concrete Surfaces				
		Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	sqm	20.160	139.16	2805.47
17		1% Labour Cess	Rs	1.000	7576.91	7576.91
18		18% GST	Rs	1.000	136384.35	136384.35
19		Add 10% Seigniorage Fee	Rs	1.000	6980.88	6980.88
Total Construction Cost :						908632.96
20		1st Year Maintenance cost	Year	1.000	39480	39480.00
21		2nd Year Maintenance cost	Year	1.000	59556	59556.00
22		3rd Year Maintenance cost	Year	1.000	118844	118844.00
23		4th Year Maintenance cost	Year	1.000	71917	71917.00
24		5th Year Maintenance cost	Year	1.000	60154	60154.00
25		1% Labour Cess	Rs	1.000	3500.51	3500.51
26		18% GST	Rs	1.000	63009.18	63009.18
27		Add 10% Seigniorage Fee	Rs	1.000	929.52	929.52
Five Year Maintenance Cost :						417490.21
Total Estimated Cost in Figures						1326123.17
Say Amount						1,326,123.00

(Signature)
Executive Engineer
Rural Work Department
Work, Div, Lakhisarai

(Signature)
Pradyumn Kumar Pandey

EE
RWD (w) D/V
LAKHISARAI

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road : PMGSY BHANDAR To MATAR ASTHAN TOLA

Length of Road : 0.7

District : LAKHISARAI

Block : CHANAN

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
13	10.6	(i) Providing and Fixing 'Logo' of Maintenance				
		Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.8 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos, 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of	No.	3.000	13114.14	39342.42
14	12.3 (i)A	Plastering with cement mortar (1:4)				
		Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	sqm	40.320	192.72	7770.47
15	12.13	Painting Two Coats on New Concrete Surfaces				
		Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	sqm	40.320	139.16	5610.93
16		1% Labour Cess	Rs	1.000	13978.78	13978.78
17		18% GST	Rs	1.000	251618.03	251618.03
18		Add 10% Seigniorage Fee :	Rs	1.000	12013.55	12013.55
Total Construction Cost :						1675488.28
19		1st Year Maintenance cost	Year	1.000	79651	79651.00
20		2nd Year Maintenance cost	Year	1.000	100873	100873.00
21		3rd Year Maintenance cost	Year	1.000	231422	231422.00
22		4th Year Maintenance cost	Year	1.000	130338	130338.00
23		5th Year Maintenance cost	Year	1.000	121412	121412.00
24		1% Labour Cess	Rs	1.000	6636.96	6636.96
25		18% GST	Rs	1.000	119465.28	119465.28
26		Add 10% Seigniorage Fee :	Rs	1.000	1859.04	1859.04
Five Year Maintenance Cost :						791657.28
Total Estimated Cost in Figures						2467145.56
Say Amount						2,467,146

Aditya
 DISCUSSING ENGINEER
 Public Works Department
 Work, Dist. Lakhisarai

forwards Kumar Singh

EE
 RWD (W) DIV
 LAKHISARAI

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

Name of Road

**PMGSY ROAD To BALAHPUR GRAM VIA
ANUSUCHIT JATI**

Length of Road **1.1**

District
Block

**LAKHISARAI
CHANAN**

SL No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
13	10.6	(I) Providing and Fixing 'Logo' of Maintenance				
		Providing and fixing of typical PMGSY informative sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of	No.	3.000	13103.84	39311.52
14	12.3 (i)A	Plastering with cement mortar (1:4)				
		Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	sqm	60.480	193.04	11675.06
15	12.13	Painting Two Coats on New Concrete Surfaces				
		Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	sqm	60.480	139.16	8416.40
16		1% Labour Cess				
18		18% GST	Rs	1.000	22077.41	22077.41
19		Add 10% Seigniorage Fee	Rs	1.000	397393.40	397393.40
		Total Construction Cost :	Rs	1.000	20978.07	20978.07
20		1st Year Maintenance cost				2648187.97
21		2nd Year Maintenance cost	Year	1.000	124567	124567.00
22		3rd Year Maintenance cost	Year	1.000	160836	160836.00
23		4th Year Maintenance cost	Year	1.000	358956	358956.00
24		5th Year Maintenance cost	Year	1.000	208252	208252.00
25		1% Labour Cess	Year	1.000	190022	190022.00
26		18% GST	Rs	1.000	10406.33	10406.33
27		Add 10% Seigniorage Fee :	Rs	1.000	187313.94	187313.94
		Five Year Maintenance Cost :	Rs	1.000	2921.35	2921.35
Total Estimated Cost in Figures						1241274.62
Say Amount						3889462.59
						3,889,463.00


Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

EE
RWD (W) DIV
LAKHISARAI

Rakesh Kumar Pandey

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

PMGSY ROAD To SOUTH MANDAL TOLA

District
Block

LAKHISARAI
CHANAN

1.26

Name of Road
Length of Road

No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
12	10.8	(i) Providing and Fixing 'Logo' of Maintenance board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of	No.	3.000	13107.83	39322.89
3	12.3 (IIA)	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	sqm	40.320	194.64	7847.88
4	12.13	Painting Two Coats on New Concrete Surfaces	sqm	40.320	139.16	5610.93
		Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701				
		1% Labour Cess	Rs	1.000	23682.30	23682.30
		18% GST	Rs	1.000	429881.33	429881.33
		Add 10% Seigniorage Fee	Rs	1.000	20500.11	20500.11
		Total Construction Cost :				2862493.33
		1st Year Maintenance cost	Year	1.000	139484	139484.00
		2nd Year Maintenance cost	Year	1.000	143424	143424.00
		3rd Year Maintenance cost	Year	1.000	406750	406750.00
		4th Year Maintenance cost	Year	1.000	204028	204028.00
		5th Year Maintenance cost	Year	1.000	214236	214236.00
		1% Labour Cess	Rs	1.000	11079.22	11079.22
		18% GST	Rs	1.000	199425.96	199425.96
		Add 10% Seigniorage Fee	Rs	1.000	3346.27	3346.27
		Five Year Maintenance Cost :				1321773.45
		Estimated Cost in Figures				4184266.78
		Amount				4,184,267.00

AB 29/11/24
Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

EE
RWD (w) DIV
LAKHISARAI

20/01/2025 Kumar Datta

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

85

Name of Road PMGSY SHIV MANDIR To REWTA MUSAHARI
TOLA
Length of Road 0.35

District LAKHISARAI
Block CHANAN

Sl. No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
10	12.3 (i)A	Plastering with cement mortar (1:4)				
		Plastering with cement mortar (1:4) on brick work in sub structure as per Technical Specifications	sqm	20.160	192.08	3872.33
11	12.13	Painting Two Coats on New Concrete Surfaces				
		Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	sqm	20.160	139.16	2805.47
12		1% Labour Cess	Rs	1.000	18112.18	18112.18
13		18% GST	Rs	1.000	290018.84	290018.84
14		Add 10% Seigniorage Fee :	Rs	1.000	2312.00	2312.00
Total Construction Cost :						1919658.75
15		1st Year Maintenance cost	Year	1.000	21019	21019.00
16		2nd Year Maintenance cost	Year	1.000	24110	24110.00
17		3rd Year Maintenance cost	Year	1.000	104545	104545.00
18		4th Year Maintenance cost	Year	1.000	29963	29963.00
19		5th Year Maintenance cost	Year	1.000	29963	29963.00
20		1% Labour Cess	Rs	1.000	2096.00	2096.00
21		18% GST	Rs	1.000	37728.00	37728.00
22		Add 10% Seigniorage Fee :	Rs	1.000	279.52	279.52
Five Year Maintenance Cost :						249703.52
Total Estimated Cost in Figures						2169362.27
Say Amount						2,169,362.27

EE
RWD (w) DIV
LAKHISARAI

Adh 21/11/23
Executive Engineer,
Rural Work, Department
Work, Div, Lakhisarai

E Letter No. 2421 Date 30.12.2023
Construction Cost Rs. 1919658.75
5 Yrs. Maintenance Cost Rs. 249703.52
Total Cost Rs. 2169362.27
BOQ Approved For Rs. 2169400.00
(Rupees) Twenty one Lakh Sixty nine
thousand four hundred
including 5 yrs m
Item no. 01 22

Prakash Kumar Prasad

Adh 21/11/23
Superintending Engineer,
Rural Works Department
District Circle, Munger

BILL OF QUANTITIES (BOQ) - CONSTRUCTION

37

Name of Road : T02 To BASUACHAK

Length of Road : 0.72

District : LAKHISARAI

Block : CHANAN

SL No.	SOR No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
14		1% Labour Cess	Rs	1.000	31153.15	31153.15 ✓
15		18% GST	Rs	1.000	560756.81	560756.81 ✓
16		Add 10% Seigniorage Fee :	Rs	1.000	3252.20	3252.20 ✓
Total Construction Cost :						3710476.46
17		1st Year Maintenance cost	Year	1.000	41801	41801.00 ✓
18		2nd Year Maintenance cost	Year	1.000	49553	49553.00 ✓
19		3rd Year Maintenance cost	Year	1.000	205162	205162.00 ✓
20		4th Year Maintenance cost	Year	1.000	62793	62793.00 ✓
21		5th Year Maintenance cost	Year	1.000	61576	61576.00 ✓
22		1% Labour Cess	Rs	1.000	4208.85	4208.85 ✓
23		18% GST	Rs	1.000	75759.30	75759.30 ✓
24		Add 10% Seigniorage Fee :	Rs	1.000	667.88	667.88 ✓
Five Year Maintenance Cost :						501521.03
Total Estimated Cost in Figures						4211997.49
Say Amount						4,211,997.00

EE
RWD (w) DIV
LAKHISARAI



Executive Engineer
Rural Work, Department
Work, Div, Lakhisarai

E. Letter No. 2421 Dt. 30.12.2023
Construction Cost Rs. 3710476.46
5 yrs. Maintenance Cost Rs. 501521.03
Total Cost Rs. 4211997.49
BOQ Approved For Rs. 4212000.00
(Rupees... Forty two lakh twelve thousand...
including 5% S.T.
Date 01/01/2024 24

Pankaj Kumar Panwar


Superintending Engineer,
Rural Works Department
Rural Works Circle, Munger
02/01/2024

23	Providing and fixing of typical MMSY Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.000 ✓	No.	10822.250	21644.50 ✓	INR Twenty One Thousand Six Hundred & Forty Four and Paise Fifty Only
24	GST @18% & LABOUR CESS @1%	1.000	Rs	263390.005	263390.31 ✓	INR Two Lakh Sixty Three Thousand Three Hundred & Ninety and Paise Ninety One Only
25	10% SEIGNIORAGE FEE	1.000	Rs	10207.876	10207.88 ✓	INR Ten Thousand Two Hundred & Seven and Paise Eighty Eight Only
26	1st Year Maintenance cost	0.400	km	79745.000	31898.00 ✓	INR Thirty One Thousand Eight Hundred & Ninety Eight Only
27	2nd Year Maintenance cost	0.400	km	138652.500	55461.00 ✓	INR Fifty Five Thousand Four Hundred & Sixty One Only
28	3rd Year Maintenance cost	0.400	km	309425.000	123770.00 ✓	INR One Lakh Twenty Three Thousand Seven Hundred & Seventy Only
29	4th Year Maintenance cost	0.400	km	174916.000	69964.00 ✓	INR Sixty Nine Thousand Nine Hundred & Sixty Four Only
30	5th Year Maintenance cost	0.400	km	354317.500	141687.00 ✓	INR One Lakh Forty One Thousand Six Hundred & Eighty Seven Only
31	GST @18% & LABOUR CESS @1%	1.000	Rs	80351.900	80351.00 ✓	INR Eighty Thousand Three Hundred & Fifty One Only
32	10% SEIGNIORAGE FEE	1.000	Rs	965.067	965.07 ✓	INR Nine Hundred & Six and Paise Seven Only
Total in Figures					2163905.05 ✓	Twenty One Lakh Sixty Three Thousand Nine Hundred & Five and Paise Five Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				


Executive Engineer
 Rural Work, Department
 Work, Dtr, Lakhisarai

28	10% SEIGNIORAGE FEE	1.000	Rs	18523.308	18523.31	Eighteen Thousand Five Hundred & Twenty Three and Paise Thirty One Only
29	1st Year Maintenance cost	1.070	km	73842.991	79012.00	INR Seventy Nine Thousand & Twelve Only
30	2nd Year Maintenance cost	1.070	km	117042.050	125235.00	INR One Lakh Twenty Five Thousand Two Hundred & Thirty Five Only
31	3rd Year Maintenance cost	1.070	km	298091.589	318958.00	INR Three Lakh Eighteen Thousand Nine Hundred & Fifty Eight Only
32	4th Year Maintenance cost	1.070	km	143089.720	153108.00	INR One Lakh Fifty Three Thousand One Hundred & Six Only
33	5th Year Maintenance cost	1.070	km	328700.935	351710.00	INR Three Lakh Fifty One Thousand Seven Hundred & Ten Only
34	GST @18% & LABOUR CESS @1%	1.000	Rs	195320.000	195320.00	One Lakh Ninety Five Thousand Three Hundred & Twenty Only
35	10% SEIGNIORAGE FEE	1.000	Rs	173.565	173.57	One Hundred & Seventy Three and Paise Fifty Seven Only
Total in Figures					6077631.28	Sixty Lakh Seventy Seven Thousand Six Hundred & Thirty One and Paise Twenty Eight Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				

E. Letter No. 244 Dt. 30.12.23
 Construction Cost Rs. 4854117 = ₹
 5 yrs. Maintenance Cost Rs. 1223575 = ₹
 Total Cost Rs. 6077632 = ₹
 BOO Approved For Rs. 6077600 = ₹
 (Rupees Sixty Lakh Seventy Seven Thousand
Six Hundred only)
 Including 5 yrs Maintenance Vide
 Item no. 10

AG
 29/12/23
 Executive Engineer
 Rural Work Department
 Work. Div, Lakhisarai

Rank of Junior Engineer

Superintending Engineer,
 Rural Works Department
 Works Circle, Munger

E. Letter No. 2421 Dt. 30.12.2023
 Construction Cost Rs. 5241229.98
 5 yrs. Maintenance Cost Rs. 862193.51
 Total Cost Rs. 6103423.49
 BOQ Approved For Rs. 6103400.00
 (Rupees Sixty one lakh three thousand
four hundred including 5 yrs M&C
 Item no. 01 28

Superintending Engineer,
 Rural Works Department
 District Circle, Munger

E. Letter No.....2421.....Dt.....30.12.2023
Construction Cost Rs.....39,87,658.48
5 yrs. Maintenance Cost Rs.....6,76,995.23
Total Cost Rs.....46,64,653.71
BOQ Approved For Rs.....46,64,700.00
(Rupees.....Forty Six Lakh Sixty four
thousand Seven hundred -
including 5 yrs maintenance
Item no.....01.....to.....26


Superintending Engineer,
Rural Works Department
A.M. Works Circle, Munger
05/01/2024

**मुख्य अभियंता-3, भागलपुर
ग्रामीण कार्य विभाग।**

पत्रांक- 379 /
प्रैक

/दिनांक- 14.6.24

ई0 श्रीप्रकाश,
मुख्य अभियंता-3

सेवा में

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, लखीसराय।

विषय: शीर्ष MR (3054) योजनान्तर्गत कार्य प्रमण्डल, लखीसराय के अधीन पैकेज संख्या-MR-N/23-24
Lakhisarai/26 (Tender ID-132195) कार्य की निविदा की स्वीकृति के संबंध में।

महोदय,

विभागीय पत्रांक-मु0अ0-(अ0उ0) 3054-01-124/2024-160 अनु0, दिनांक-14.06.2024

द्वारा संस्कृति आदेश के अनुपालन में उपर्युक्त विषयक कार्य बिहार लोक निर्माण संश्लेषण बोर्ड (लोक-163) के आलोक में इस कार्य को इसके योग्य एवं एकल Pankaj Kumar Pawan (BID ID-576091) को उसके द्वारा विधिदित दर, जो परिमाण विपत्र की दर से 1.11% (एक दशमलव एक-एक) प्रतिशत कम है, को स्वीकृत करते हुए सम्पूर्ण कार्य कुल ₹ 4,05,47,069/- (चार करोड़ पांच लाख सैंतालीस हजार चत्तर सैंतर) रुपये मात्र की लागत पर आपकी अनुमति एवं कार्यदित में आवंटित किया जाता है।

- निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधार नही होगा।
- संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ जमा किये गये संबंधित एन0एस0सी0/Fixed Deposit आदि का सत्वापन संबंधित आकधर/बैंक से कराकर प्रमंडलीय कार्यालय में अभिलेखित किया जायेगा। कार्यपालक अभियंता, कार्य प्रमंडल, लखीसराय कार्यदित निर्मात करने के पूर्व अध्ययन की राशि के सत्वापन से संबंधित कागजात अद्योहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।
- एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्ययन स्वच्छ एवं सत्थापित प्रति निश्चित रूप से प्राप्त कर दिया जायेगा।
- एकरारनामा से पूर्व कार्यपालक अभियंता, यह सुनिश्चित कर लेंगे कि निविदाकार दिवार सूची/कांसी सूची या कार्य संबंधित सूची में शामिल न हो।
- कार्य में व्यवहृत सामग्रियों को बर, प्रमण्डल में स्वीकृत लीज के अन्तर्गत पर दिया गया है, कार्य करते समय अगर इसमें कमी पाई जाती है तो उसके बर में संपूर्ण कमी कर दी जायेगी।
- इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गता प्रशासनिक स्वीकृति एवं प्रावधिक स्वीकृति तथा निविदा आनर्षा सूचना में उल्लेखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।
- अनुमोदित किये गये मुल्यनात्मक विवरणों के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं नुति पाये जाने की स्थिति में दस्तुस्थिति से तत्क्षण अद्योहस्ताक्षरी को अद्ययत करायेंगे। नुति के सुधारोपरान्त एकरारनामा को कार्यवाई की जायेगी।
- एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जांच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई नुति न हो।
- कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राकलन में किये गये उपबंध से पूरी तरह आश्चरत हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावधिक स्वीकृति के अद्यसाधन प्राकप में दिये गये निदेश का अनुपालन सुनिश्चित करायेंगे। प्रश्न का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, प्रशासनिक स्वीकृति की राशि, संवेदक द्वारा उद्धृत दर, परकर्मित दर, Bid Capacity आदि का मिलान कर ही कार्य आधटन आदेश निर्गत करेंगे। अधीक्षण अभियंता/कार्यपालक अभियंता कार्य आधटन/LOA निर्गत करने से पूर्व मिलान कर लेंगे कि परिमाण विपत्र की राशि प्रशासनिक अनुमोदन की राशि के अनुज्ञेय सीमा के अन्दर है। यदि अनुज्ञेय सीमा से अधिक हो तो एकरारनामा के पूर्व पुनरीक्षित प्रशासनिक अनुमोदन प्राप्त कर लिया जाय।

Govt. of Bihar
Rural Works Department
Office of the Executive Engineer, Rural Works Department,
Works Division, Lakhisarai

(बिहार ग्रामीण पथ अनुपकरण नीति, 2018)

Notice Inviting Re-Tender for Rural Roads Maintenance based on Output and performance based Contract through e-procurement mode on Model Bidding Document (MBCD).

(Short Notice Inviting No. - Re-Tender -MR-1034-11/2023-24)

1. Designation and Address of the Advertiser
2. Date of Issue of Notice Inviting Tender
3. Period for downloading of Tender documents

Executive Engineer, Rural Works Department, Works Division Lakhisarai
06/02/2024
From 16.02.2024 (9.00) to 23.02.2024 up to 13.00 hrs. From
website-<http://www.bidsolbhar.gov.in>

4. Date, Time & Place of Pre-Bid Meeting

Date 12.02.2024 Time 13.00 hrs.
Place O/o Concerned Superintending Engineer

5. Last Date & Time for uploading tender Documents by bidder

Date 23.02.2024 up to: 13.00 hrs.

6. Date, Time for online opening of Technical bid

<http://www.bidsolbhar.gov.in>

7. Last date, time and place for submission of Original instrument of EMD, Cost of BQO and Affidavit regarding correctness of information provided with bid document

Date 23.02.2024 up to Time 13.30 hrs.

Till 13.00 hrs on 23.02.2024

Place: O/o concerned

(i) Executive Engineer

Or

(ii) Superintending Engineer

Or

(iii) Chief Engineer

8. The Engineer in chief, Rural Works Department on behalf of Governor of Bihar invites bids from the eligible bidders for the works detailed below.

Project Scope & Conditions

- I. To undertake, Initial Rectification Works including surface removal and Ordinary Maintenance for a period of 5 years after completion of initial rectification works including surface removal Works on selected roads as described in para 9.
- II. The Initial Rectification may include improvement and pavement strengthening and widening work, road safety measures and tree plantation in Banks as per contract document. The initial rectification including surface removal of works will be done in such a way that after rectification it complies all technical standards and safety measures to bring the road under prescribed service level. The time of completion for initial rectification works including surface removal shall be 09 months from the date of issue of LOA.
- III. After completion of initial rectification with surface removal the selected roads will be maintained for next five years to comply the prescribed service level, to maintain road for traffic worthy. The ordinary maintenance work will also include drain drainages works, minor works on bridges and road maintenance within road side maintenance within selected roads.
- IV. The Ordinary Maintenance works will be carried out under performance based road maintenance on a lump sum basis paid Quarterly.
- V. Initial Rectification Works including surface removal will be paid on measured quantity to the value of contract.
- VI. There is a requirement for specialized maintenance equipment and the contract obligation is for continuous input over the contract period i.e. Initial rectification including surface removal and ordinary maintenance period.
- VII. To undertake emergent repair due to natural calamities like flood, earthquake, etc.
- VIII. Bidders are strongly encouraged to download the bidding documents prior to the pre-bid meeting in order for bidders to have a good understanding of the scope of work under this contract for discussion and clarification at the pre-bid meeting. Bidders are also advised to visit each road, be acquainted with the physical condition of road, satisfy themselves and then participate in the bid.

9. Details of Work:-

Sl. No	Package No.	District	Division	Block	Name of Road	Length (In KM)	Cost of Initial Rectification Works with Surface Removal (In Lakhs)	Cost of 5-years Maintenance (In Lakhs)	Total Estimated Cost (In Lakhs)	Cost of BQO (In Rs.)	Bid Security (In Rs. In Lakhs)	Amount Payable to works Division
1	2	3	4	5	6	7	8	9	10	11	12	13
1	MR-1034-24 Lakhisarai/26	Lakhisarai	Lakhisarai	Chausi	PMCSY Road Bharhar to Bagicha Tola Sangrahar	8.300	11.400	4.734	16.130	10000	5.500	R.E. RWD Works Division Lakhisarai
		Lakhisarai	Lakhisarai	Chausi	GLOR/Ramair - Tichwa	8.640	11.760	9.318	21.078			
		Lakhisarai	Lakhisarai	Chausi	1258-1258 - Bichwary	6.390	16.390	3.350	19.740			
		Lakhisarai	Lakhisarai	Chausi	Pargay Bharhar to mairi aroria tola	8.700	19.300	9.808	29.108			
		Lakhisarai	Lakhisarai	Chausi	Pargay road to Belaapur gram via arunachil jai	7.100	31.340	15.240	46.580			
		Lakhisarai	Lakhisarai	Chausi	Pargay road to acoli mandal tola	1.200	33.200	12.900	46.100			
		Lakhisarai	Lakhisarai	Chausi	Pargay shiv mandir to mawa Mushkauri tola	8.300	17.470	3.420	20.890			

For Key Kirmar Pawan