



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2024-25)

ROAD NAME :- PIPAL TOLA SHEKHPURA TO PMGSY ROAD

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0.990 KM	
DISTRICT	KATIHAR	
BLOCK	KADWA	
DIVISION	BARSOI	
TOTAL DAMAGE LENGTH OF ROAD	0.124	KM
TOTAL COST OF F.D.R. PART - A	Rs. 9.416	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

तकनीकी प्रतिवेदन

योजना का नाम:- *pipal Tdg Shekhpura to PMBSY Road*

क्षतिग्रस्त पथ की लम्बाई:- *0.124 K.M.*

प्राक्कलित राशि:- *9.416 लाख*

योजना शीर्ष :- **3054/2245 F.D.R.**

प्राधिकार :- सचिव, ग्रामीण कार्य विभाग, बिहार, पटना का मु0अ0-4(मु0) विविध
(कार्य)-06-109 / 2024-1956 दिनांक-28-05-2024

प्रतिवेदन

प्रस्तुत प्राक्कलन अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथ के पथांश का प्राक्कलन

मात्र के लिए ग्रामीण कार्य विभाग, कार्य प्रमण्डल *खारसोई* के
द्वारा शीर्ष F.D.R. 3045 के अन्तर्गत तैयार किया गया है।

पथ के आवस्मिक मरम्मत हेतु पथांशों में मिट्टी भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, बॉस का चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट इत्यादि से भरकर बचाव कार्य करते हुए यातायात पुर्नस्थापित किया गया है।।

पथ मरम्मत कार्य का प्राक्कलन वर्तमान अनुसूचित दर एवं सामग्री की दुलाई निकटतम खदान से प्रावधान कर बनाया गया है। दर गणना में संवेदक लाभांश सम्मिलित नहीं है।

प्राक्कलन तकनीकी स्वीकृति हेतु अपेक्षित है।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य 4211141-कदवा

15/11/2024
सहायक अभियंता
ग्रामीण कार्य विभाग
का0 अ0 प्र0-कदवा

28/11/24
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, *खारसोई*

Block:- Kadwa

FDR.
Division - Barsoi


AD NAME :- PIPAL TOLA SHEKHPURA TO PMGSY ROAD

Year - 2024-25


Description	Unit	Length (In Mtr.)	Width (In Mtr.)	Depth/ Height (In Mtr.)	Qty.	Rate (In Rs.)	Amount (In Rs.)
Empty Cement Bags (Supply of Empty Cement Bag Capacity 1.2 CFT in Good condition And As per Specification)	No	-	-	-			
100 mm Dia 6m to 8m Long	No	-	-	-	0.00	3.35	0.00
Brick Bats (Brick Bats of Well Burnt Bricks)	Cum	-	-	-	0.00	20.28	0.00
Local Sand (As per Specification)	Cum	-	-	-	431.78	990.00	427462.20
Kiln Rubbish (is Should be clean & Free from other impurities)	Cum	-	-	-	0.00	65.02	0.00
Hume Pipe (NP3) 1000mm Dia (NP3 Rcc Hume Pipe)	Mtr.	-	-	-	151.00	820.00	123820.00
Granular Sub Base material Gradding-ii (Granular Sub Base Material Gradding-ii as per Specification)	Cum	-	-	-	0.00	2400.00	0.00
Unskilled Labour (8 hrs/ Day)	Hrs/ Day	-	-	-	0.00	82.00	0.00
Semi Skilled Labour (8 hrs/ Day)	Hrs/ Day	-	-	-	432.00	320.00	138240.00
Skilled Labour (8 hrs/ Day)	Hrs/ Day	-	-	-		270.00	0.00
Mason (8 hrs/ Day)	Hrs/ Day	-	-	-	86.00	380.00	32680.00
Head Mason (8 hrs/ Day)	Hrs/ Day	-	-	-		350.00	0.00
Bhisti (8 hrs/ Day)	Hrs/ Day	-	-	-		370.00	0.00
Carpenter (8 hrs/ Day)	Hrs/ Day	-	-	-		310.00	0.00
Front End Loader 1.0 cum (Soil Loading/ Aggregate Loading) Cum/Hour 60/25	Per Hour	-	-	-	58.00	1400.00	81200.00
8-10 Ton smooth Wheeled (Compaction / Consolidation) Cum/hour 70/25	Per Hour	-	-	-	0.00	850.00	0.00
Tractor With Trolley (Transportation of Material) Cum 3 to 5 ton	Ton / Trip	-	-	-	230 230.28	600.00	138000 138169.60
Tipper (Transportation of Material) Cum 5.5	Per Day	-	-	-		1100.00	0.00
Generator Set With Fuel (Generation of Electecal Energy) KVA 5	Per Day	-	-	-		296.00	0.00
Total Amount (In Rs.) =							941571.80



P. K. Singh



P. K. Singh



P. K. Singh

Technically sanctioned for Rs 9,41,402/-
< Rupees nine lakh forty one thousand
four hundred two > only.

29/11/24

अधीक्षण अभियंता

ग्रामीण कार्य विभाग

कार्य अंचल, पूर्णिया

29/11/24

ROAD NAME :- PIPAL TOLA SHEKHIPURA TO PMGSY ROAD

SL. No.	SDB SL.NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY
1	4.5		Brick Bats						
			Placing tractor at loading point loading with front end loader dumping /turning for return trip						
			C/O To Calculation Sheet						
				Cum					431.780
2	5.7.7 WRD		Labour for driving 62 MM to 75 MM dia Bamboo Piles Including cutting to in proper size and shoes etc complete job. (Bamboo Piles c/c 0.3 m)						431.780
			One Pile No. x Pile Height = Rm / 6 = Nos. ((230*2.50))/6						575.00
			Total Bamboo =						96.00

11/11/22
S. J. J. J.

11/11/22
S. J. J. J.

ROAD NAME :- PIPAL TOLA SHEKHPURA TO PMGSY ROAD
ANNEXURE "B"

Sl. No.	Chainage At (Mtr.)	NO.	Length (in mt.)	Top Width (in mt.)	Avg. Top Width + Bottom Width) / 2	Height (in mt.)	Qty. (in Cum)	Remarks
		1	5.00	(2.0+2.30)/2	(2.0+2.30)/2	(2.0+2.40)/2	23.65	
		1	7.10	(2.0+2.10+2.30)/3	(2.0+2.10+2.30)/3	(2.40+2.60+2.30)/3	36.86	
		1	4.00	1.500	1.500	0.500	3.00	
		1	4.00	3.750	3.750	0.500	7.50	
		1	2.00	3.750	3.750	0.300	2.25	
		1	3.80	2.000	2.000	2.100	15.96	
		1	69.00	(2.0+1.80+1.50+1.70)/4	(2.0+1.80+1.50+1.70)/4	(2.20+2.0+1.50)/3	229.43	
		1	29.50	(2.0+1.80+2.10)/3	(2.0+1.80+2.10)/3	(2.0+1.90)/2	113.13	
						Total=	431.78	

J.E

A.E.

[Signature]
E.E.