



बिहार BIHAR  
 06 SEP 2024  
 जयदेव खंहरा पदाधिकारी  
 पूर्वी चम्पारण, मोतिहारी

149/11/9/2024  
 बापू धाम कान्स्ट्रक्शन् प्रा प्राइडर एग्जिक्यूटिव  
 श्री अरुण प्रसाद पादय सा-मोतिहारी AX 833226  
 अरिशा सुलताना निवासी पोस्ट/वार्ड/मोतिहारी  
 2000/1000/1000/1000  
 AGREEMENT  
 मोतिहारी  
 L.N.-81/81

Work has been allotted by Chief Engineer-5, R.W.D, Bihar Patna. vide letter no. 2547, dt. 15.09.2024

Below 4.66% on BOQ Rate

PAN- EYBPK1827C  
 Reg.- 1230300/21.09.2028  
 GST No- 10EYBPK1827C125

1. Agreement No- 01/3054/M.B.D/2024-25
2. Estimated Cost Rs. 3,91,61,767.00 (Three crore Ninty One lar Sixty One thousand Seven hundred Sixty Seven only.)
3. Agreement value:- 3,75,71,799.00 (Three Crore Seventy Five lar Seventy One thousand Seven hundred Sixty Nine only)
4. Performance security Rs. 23.56 Lac. PSi2 in shape of FDR
5. Date of commencement of work: 24/09/2024
6. Date of completion of work: 23/06/2025

This agreement, made the... day of ... 2023 Between Executive Engineer, R.W.D. Works Division, Gopalganj-2, of the one part, and Bapu Dham Construction, At- Mathiya Barharpur PO- Mathurapur PS- Piprakothi Dist- East Champaran Where as the Employer is desirous that Contractor execute construction of Road from MR-3054, Package No- MR-N/23-24/Gopalganj-203, Under- 3054-New Maintenance Policy-2018 (Length- 5.548 km.) and the employer has accepted the bid by the contractor for the execution and completion of such works and the remedying of any defects there in at total cost of Rupees.

| Road                                                            | Length (In K.M) | Construction Cost | Maintenance Cost | Total Cost. |
|-----------------------------------------------------------------|-----------------|-------------------|------------------|-------------|
| T06 to Rampur                                                   | 2.50            | 17068035.00       | 3253856.00       | 20261891.00 |
| Janak Singh Ke Khaliha to Chanaparan Shih Mandir Via Sakul Tola | 3.048           | 13368141.00       | 3941767.00       | 17309908.00 |

BAPU DHAM CONSTRUCTION  
 बपु धाम  
 Proprietor

24.09.24

24.09.24  
 Executive Engineer  
 RWD (W) Division  
 Gopalganj-2

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS

1. In this Agreement, words and expression shall have the same meanings as are respectively as are respectively assigned to them in the condition of contract here in after referred to, and they shall be deemed to from and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the employer to the contractor as here in after mentioned, the contractor the works and remedy any defects there in conformity in all aspects with the provision of the contract.
3. The Employer here by covenants to pay contractor in consideration of the execution of the execution and completion of the works and the remedying the defects where in the contract price of such other sum as may become payable under the provisions the contract.
4. The following documents shall be deemed to from and be read and construct as part of this Agreement, Viz:-
  - I. Letter of Acceptance
  - II. Notice to proceed with the works
  - III. Contractor's Bid
  - IV. Contract Data
  - V. Special conditions of contract and general conditions of contract
  - VI. Specifications
  - VII. Drawings
  - VIII. Any other document listed in the contract date as forming part of the contract.

In witness where of the parties there to have caused this Agreement to be executed the day and year first before written.

The common seal of.....

In the presence of:-

Binding signature of employer.....

*[Signature]*  
29.05.24  
Executive Engineer  
RWD (W) Division  
Gadgaon-2

Binding signature of contractor.....

*[Signature]*  
RUP DHAM CONSTRUCTION  
Proprietor

*[Signature]*  
24.09.24




# SYNOPSIS OF AGREEMENT

(Agreement Below on - 4.06%)

Name of Works :- MR-3054, Package No- MR-N/23-24/Gopalganj-2/03, Under-3054-New Maintenance Policy-2018 (Length- 5.548 km.)

1. Estimated Cost. : 3,91,61,767.00
- Ref. of NIT : PR No- MR3054/01/2023-24
2. AA Amount : Mentioned in Cost Sheet
3. TS Amount : Mentioned in Cost Sheet
4. Agreement Value : 3,75,71,799.00
5. Date of Tender : 10.11.2023
6. Details of Earnest Money : 23.56 Lac. PSD in shape of FD
7. Date of Works Order : 24/03/2024
8. Date of Completion : 23/06/2025
9. Actual Date of Completion :
- 10.No. of Items Tender for : 131 Nos in Three Road

  
24.09.24  
D.A.O.  
R.W.D. Works Division  
Gopalganj-2

BAPU DHAM CONSTRUCTION  
  
Proprietor

  
29.09.24  
Executive Engineer  
R.W.D. Works Division  
Gopalganj-2  
2024



Office of the Executive Engineer, R.W.D. Works Division, Gopalganj-2.

Issue of Notice to proceed with the work

Memo No.

Dated:.....

To- Bapu Dham Construction,  
At- Mathiya Bariyarpur PO- Mathurapur PS- Piprakothi  
Dist- East Champaran

Dear Sir,

Pursuant to your furnishing the requisite performance security as stipulated in ITB Clause 32.1 and signing of the contract for the construction from MR-3054, Package No- MR-N/23-34 Gopalganj-2/03, Under- 3054-New Maintenance Policy-2018 (Length-5.548 km.) you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours Faithfully.

Executive Engineer,  
R.W.D. Works Division,  
Gopalganj

ज्ञापांक-

दिनांक-

प्रतिलिपि- संबंधित सहायक अभियंता, ग्रामीण कार्य विभाग कार्य अवर प्रमंडल, बरौली, / कनीय अभियंता बरौली को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित/ निर्देश दिया जाता है कि संवेदक द्वारा कार्य आरंभ करने के पूर्व कार्य स्थल का फोटो एवं कार्य पूर्ण होने पर कार्य स्थल का फोटो प्रमंडलीय कार्यालय में ससमय समर्पित करना सुनिश्चित करें साथ ही निर्माण से संबंधित यंत्र-संयंत्र तथा प्रयोगशाला कार्य स्थल पर स्थापित कराना सुनिश्चित करेंगे एवं उसका फोटोग्राफ प्रमंडलीय कार्यालय में समर्पित करेंगे। कार्य में प्रयुक्त होने वाले सभी सामग्रियों का गुण-नियंत्रण जॉच प्रतिवेदन एवं अन्य वांछित जॉच प्रतिवेदन प्रत्येक चालु विपत्र के साथ संलग्न कर समर्पित करना सुनिश्चित करें। कार्य में पी०सी०सी० पथांश का Mix Design AICTE approved Engineering College से लेना सुनिश्चित करेंगे।

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल गोपालगंज-2

ज्ञापांक-

दिनांक-

प्रतिलिपि- कार्यपालक अभियंता, ग्रामीण कार्य, विभाग, गुण नियंत्रण प्रमंडल ग्रामीण कार्य विभाग छपरा को सूचनार्थ एवं आवश्यक कार्रवाई हेतु समर्पित/ अनुरोध है कि संबंधित कार्य के गुण नियंत्रण प्रणाली का टेस्ट रिपोर्ट भुगतान के पूर्व इस प्रमंडलीय कार्यालय को ससमय उपलब्ध कराना सुनिश्चित करेंगे।

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल गोपालगंज-2

ज्ञापांक-

दिनांक-

प्रतिलिपि- मुख्य अभियंता-5 ग्रामीण कार्य विभाग, बिहार पटना/ अपीक्षक अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, सिवान को आवश्यक कार्रवाई हेतु सूचनार्थ समर्पित।

BAPU DHAM CONSTRUCTION  
बहुल धाम  
Proprietor

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल गोपालगंज-2

MR-N-23-24/Gopalganj-203  
Tender ID- 129070

Date of Tender - 30.10.2023 to 10.11.2023

Date of Receipt of Tender - 10.11.2023

| As per BOQ Cost.                                                 |                                  |                             |                             |                      |                      |
|------------------------------------------------------------------|----------------------------------|-----------------------------|-----------------------------|----------------------|----------------------|
| Name of Work                                                     | AA Amount<br>In Lac              | TS Amount                   | Maintenance<br>Quarter Wise | Total<br>Maintenance | Construction<br>Cost |
| T06 to Rampur                                                    | 225.76 Lac<br>1970 dt 31.03.2023 | 211.20 Lac<br>dt 04.05.2023 | 100.578.00                  | 3991553.00           | 57727780.00          |
| Jank Singh ke Khalihan to Chanapurana Shiv Mandir Via Sukul Tola | 176.19 Lac<br>1970 dt 31.03.2023 | 180.43 Lac<br>dt 04.05.2023 | 205429.00                   | 4108575.00           | 13013896.00          |
| Total.                                                           |                                  |                             | 315997.00                   | 7500128.00           | 31661679.00          |

| As per Agreement on 4.06%                                        |                                  |                             |                         |                      |                      |
|------------------------------------------------------------------|----------------------------------|-----------------------------|-------------------------|----------------------|----------------------|
| Name of Work                                                     | AA Amount                        | TS Amount                   | 1st Year<br>Maintenance | Total<br>Maintenance | Construction<br>Cost |
| T06 to Rampur                                                    | 225.76 Lac<br>1970 dt 31.03.2023 | 211.20 Lac<br>dt 04.05.2023 | 162693.00               | 3253896.00           | 17008035.00          |
| Jank Singh ke Khalihan to Chanapurana Shiv Mandir Via Sukul Tola | 176.19 Lac<br>1970 dt 31.03.2023 | 180.43 Lac<br>dt 04.05.2023 | 170949.00               | 2011797.00           | 12368141.00          |
| Total.                                                           |                                  |                             | 333642.00               | 7165693.00           | 30376176.00          |
| Say Rs.                                                          |                                  |                             | 333642.00               | 7165693.00           | 30376176.00          |

*[Signature]*  
24.09.24  
D.A.O  
R.W.D. Works Division  
Gopalganj-2

*[Signature]*  
Executive Engineer,  
R.W.D. Works Division Gopalganj-2  
24.09.24

BAHU DHAM CONSTRUCTION  
*[Signature]*  
Proprietor



## Term & Condition

- 1-Deduction from running bill will be made as per Government notification.
- 2-Terms and Conditions of 3054 New Maintenance Policy-2018 will be applicable to the Contractor
- 3- Contractor will have to strictly follow rules & regulation which issued time to time by the department and Government of Bihar. Regarding the execution contract work.
- 4-The Terms and Conditions of the NIT will be the part of this Agreement.
- 5-Neither any type of construction works nor excavation of earth in private land will be made.
- 6-Contractor must purchase/use road construction material to complete the road as mentioned in sanctioned estimate of the road.
- 7-Notice proceed to work, Contractor Bid, Contract Data, Special conditions of contract & general conditions of contract and any other document listed in the contract data in 3054 NMP-2018 will be the part & parcel of the this agreement.
- 8-Clause of C.E. 5, RWD, Bihar Patna Letter No. 2547 dated 15.09.24 also the part of agreement.

RAPUDHAM CONSTRUCTION

Sing. Of Contractor

  
Proprietor

  
24.09.24

  
Executive Engineer,  
R.W.D. Works Division

Gopalganj-24/09/24

PA B 176.19.000

158 180.43.000

Excavation 300

Tender Inviting Authority: Engg-in Chief RWD Patna

Name of Work: JANAK SINGH KE KHALHA TO CHANAPURANA SHIV MANDIR VIA SIKUL TOLA (BLOCK BRIDGE)

Contract No: Civil Work

Name of the Bidder/  
Bidding Firm /  
Company :

(This BOD template must not be modified/replaced by the bidder and the same should be uploaded after filling the price column else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder

PRICE SCHEDULE

Name and (Value only) :  
NUMBER  
ESTIMATED  
TOTAL AMOUNT  
IN WORDS

| Sl. No. | TEXT #<br>Item Description | NUMBER #<br>Quantity | TEXT #<br>Units | ESTIMATED<br>NUMBER #<br>Estimated Rate | NUMBER #<br>TOTAL AMOUNT<br>IN WORDS |
|---------|----------------------------|----------------------|-----------------|-----------------------------------------|--------------------------------------|
|---------|----------------------------|----------------------|-----------------|-----------------------------------------|--------------------------------------|

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                     |   |     |        |                                                                   |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----|--------|-------------------------------------------------------------------|
| 1 | Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of unserviceable materials & earlier & disposal of serviceable materials to be used or stacking of serviceable materials to be used or stacking of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E1 | 4 | Sqm | 26.300 | 105 Four Thousand Three Hundred & Two and Paise Thirty Seven Only |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----|--------|-------------------------------------------------------------------|

|   |                                                                                                                                                                                                |         |     |        |                                                              |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|-----|--------|--------------------------------------------------------------|
| 2 | Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4. | 443.750 | Sqm | 26.300 | 11685 Four Thousand Seven Hundred Sixty and Paise Eight Only |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|-----|--------|--------------------------------------------------------------|

|   |                                                |          |     |        |                                                                 |
|---|------------------------------------------------|----------|-----|--------|-----------------------------------------------------------------|
| 3 | Construction of Subgrade and Earthen Shoulders | 1690.200 | Cum | 26.300 | 44659 Four Thousand Six Hundred Sixty Nine and Paise Eight Only |
|---|------------------------------------------------|----------|-----|--------|-----------------------------------------------------------------|

|   |                                                                                                                                                                                                                                                                                                          |          |     |        |                                                                 |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----|--------|-----------------------------------------------------------------|
| 4 | Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 301.1. | 1690.200 | Cum | 26.300 | 44659 Four Thousand Six Hundred Sixty Nine and Paise Eight Only |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----|--------|-----------------------------------------------------------------|

|   |                                                           |          |     |        |                                                                 |
|---|-----------------------------------------------------------|----------|-----|--------|-----------------------------------------------------------------|
| 5 | Granular Sub-base with Well Graded Material (Table 400.1) | 1690.200 | Cum | 26.300 | 44659 Four Thousand Six Hundred Sixty Nine and Paise Eight Only |
|---|-----------------------------------------------------------|----------|-----|--------|-----------------------------------------------------------------|

|   |                                                  |          |     |        |                                                                 |
|---|--------------------------------------------------|----------|-----|--------|-----------------------------------------------------------------|
| 6 | (By mix in place method) For Grading II Material | 1690.200 | Cum | 26.300 | 44659 Four Thousand Six Hundred Sixty Nine and Paise Eight Only |
|---|--------------------------------------------------|----------|-----|--------|-----------------------------------------------------------------|

CONSTRUCTION

M. A. S. B.

24.07.24

24.07.24



|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |             |     |          |            |                                                                                         |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|-----|----------|------------|-----------------------------------------------------------------------------------------|
| 7  | Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.                                                                                                                                           | 45.100      | Cum | 2114.829 | 16251.05   | INR One Lakh Forty Thousand Two Hundred & Fifty One and Paise Five Only                 |
| 8  | WBM Grading 2 (By Mechanical Means)                                                                                                                                                                                                                                                                                                                                                                                                                                |             |     |          |            |                                                                                         |
| 9  | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 403. | 63.830      | Cum | 6455.310 | 42655.43   | INR Four Lakh Twenty Three Thousand Six Hundred & Fifty Five and Paise Forty Three Only |
| 10 | WBM Grading 3 (By Mechanical Means)                                                                                                                                                                                                                                                                                                                                                                                                                                |             |     |          |            |                                                                                         |
| 11 | Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 403.           | 179.440     | Cum | 8966.070 | 1603900.37 | INR Ten Lakh Thirty Three Thousand Nine Hundred and Paise Ninety Seven Only             |
| 12 | SUB HEAD : BITUMINOUS ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                                        |             |     |          |            |                                                                                         |
| 13 | Prime Coat (Low Porosity)                                                                                                                                                                                                                                                                                                                                                                                                                                          |             |     |          |            |                                                                                         |
| 14 | Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 592.                                                                                                                                                                                                       | 2272.500    | Sqm | 59.310   | 136145.48  | INR One Lakh Thirty Six Thousand One Hundred & Forty Five and Paise Forty Eight Only    |
| 15 | Patch work over WBM using Mix seal surface for bituminous and Existing CC Pavement                                                                                                                                                                                                                                                                                                                                                                                 |             |     |          |            |                                                                                         |
| 16 | Providing, laying and rolling of close graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2                                                                                                                                                                                                                                                                                                                          | 2272.530    | Sqm | 102.550  | 46764.89   | INR Six Lakh Eighty Seven Thousand Six Hundred & Forty Four and Paise Eighty Five Only  |
| 17 | Tack Coat                                                                                                                                                                                                                                                                                                                                                                                                                                                          |             |     |          |            |                                                                                         |
| 18 | Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared                                                                                                                                                                                                                                                                                                                  | 11.117 (RM) | Sqm | 20.346   | 132226.48  | INR Two Lakh Thirty Two Thousand Two Hundred & Twenty Six and Paise Forty Eight Only    |

BAPU DHAM CONSTRUCTION

Proprietor

11.117 (RM)

24.07.24

Agreed 24.07.24

24.07.24



|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |         |     |           |            |                                                                                         |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|-----|-----------|------------|-----------------------------------------------------------------------------------------|
| 19 | Semi-Dense Bituminous Concrete                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |         |     |           |            | INR Thirty Three Lakh Ninety Thousand Seven Hundred & Sixty and Paise Seventy Nine Only |
| 20 | Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per M&RTM specification clause No. 508 complete in all respects.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 226.118 | Cum | 16661.258 | 3319702.79 |                                                                                         |
| 21 | Construction of dry lean cement concrete sub-base over a prepared sub-grade with coarse and fine aggregates conforming to IS-383, the size of coarse aggregate not exceeding 25mm, aggregate cement ratio not to exceed 15:1 aggregate gradation after blending to be as per table 600-1 cement content not to be less than 150kg/cum optimum moisture content to be determined during trial length construction, concrete strength not be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 24.150  | Cum | 2471.980  | 61173.53   | INR Sixty One Thousand One Hundred & Seventy Nine and Paise Fifty Three Only            |
| 22 | Construction of un-reinforced plain cement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete or not less than 0.25cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side formwork (steel channel, jacking and fixing of 125 micron thick polythene film, wedges, steel plates, including levelling the formwork as per drawing) spreading the concrete with shovels, rakes, spreading using needle, screed and plate vibrators compacted using needle, screed and plate vibrators and finished in continuous operation strip, provision of contraction and expansion joints, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge, culvert and construction joints, admixtures as approved, curing of concrete slab for 14 days as approved, (where specified) and water curing compound (where specified) and water finishing to lines and grade as per drawing and finishing to lines and grade as per drawing. | 393.950 | Cum | 9751.100  | 3014920.46 | INR Thirty Nine Lakh Fourteen Thousand Nine Hundred & Sixty and Paise Forty Six Only    |
| 23 | SUB HEAD : ROAD FURNITURES, K&A STONE'S, TRAFFIC & DIRECTION SIGN, MAMSY LOGO                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |         |     |           |            |                                                                                         |
| 24 | Kilometre stone                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |         |     |           |            |                                                                                         |

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                               |         |                  |           |          |                                                                                 |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------|-----------|----------|---------------------------------------------------------------------------------|
| 25 | Reinforced cement concrete M15 grade hexametric local stone of standard design as per IRC:8 fitting in position including painting and printing, etc as per drawing and technical specification clause 1703.                                                                                                                                                                                                                                  |         |                  |           |          | INR Eighty Four Thousand One Hundred & Eighty Seven and Paise Thirty Six Only   |
| 26 | sq. Km stone                                                                                                                                                                                                                                                                                                                                                                                                                                  | 5.000   | Nos.             | 8273.000  | 8315.45  | INR Eighty Four Thousand One Hundred & Eighty Seven and Paise Forty Five Only   |
| 27 | sq. 200 m stone                                                                                                                                                                                                                                                                                                                                                                                                                               | 12.000  | Nos.             | 891.850   | 8702.20  | INR Ten Thousand Seven Hundred & Twenty and Paise Twenty Only                   |
| 28 | Direction and Place Identification signs with size more than 1.9 sqm size board                                                                                                                                                                                                                                                                                                                                                               |         |                  |           |          |                                                                                 |
| 29 | Retro-reflective Traffic Signs Providing and erecting direction and place identification retro-reflective signs as per IRC:57 made of                                                                                                                                                                                                                                                                                                         | 1.950   | Sqm              | 12943.560 | 2047.64  | INR Thirty Six Thousand Nine Hundred & Fifty Seven and Paise Sixty Four Only    |
| 30 | Retro-reflective Traffic Signs                                                                                                                                                                                                                                                                                                                                                                                                                |         |                  |           |          |                                                                                 |
| 31 | Providing and fixing of retro-reflective standard, mandatory and informative sign as per IRC:67 made of encapsulated lens type reflective sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 450 mm below ground level as per drawings and Technical Specification Clause 301 |         |                  |           |          |                                                                                 |
| 32 | 600 mm equilateral & triangle                                                                                                                                                                                                                                                                                                                                                                                                                 | 16.000  | Nos.             | 5183.710  | 8418.35  | INR Eighty Four Thousand One Hundred & Eighty Seven and Paise Thirty Six Only   |
| 33 | 600 mm circular                                                                                                                                                                                                                                                                                                                                                                                                                               | 14.500  | Nos.             | 5503.480  | 78168.72 | INR Seventy Eight Thousand One Hundred & Sixty Eight and Paise Seventy Two Only |
| 34 | 600 mm x 450 mm rectangular                                                                                                                                                                                                                                                                                                                                                                                                                   | 8.050   | Nos.             | 3038.930  | 63191.86 | INR Forty Three Thousand One Hundred & Eleven and Paise Eighty Four Only        |
| 35 | 900 mm octagon stop board                                                                                                                                                                                                                                                                                                                                                                                                                     | 6.000   | Nos.             | 11403.730 | 68422.38 | INR Sixty Eight Thousand Four Hundred & Twenty Two and Paise Thirty Eight Only  |
| 36 | Boundary Pillar/Guard Post                                                                                                                                                                                                                                                                                                                                                                                                                    |         |                  |           |          |                                                                                 |
| 37 | Reinforced cement concrete M15 grade boundary pillar/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704                                                                                                                                                                                                          | 16.000  | Nos.             | 828.678   | 44461.52 | INR Forty Six Thousand Four Hundred & Sixty One and Paise Fifty Two Only        |
| 38 | Printing New Letters and Figures of any shade with synthetic cement paint black or any other approved colour to give an even shade as per PRACTICE DRAWING                                                                                                                                                                                                                                                                                    | 332.000 | cm height per ft | 0.710     | 260.48   | INR Two Hundred & Sixty and Paise Forty Eight Only                              |

प्रोप्रीटर

१

११/०१/२३


Executive Engineer  
RWD (W) Division  
Gopalganj-2



|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |         |      |           |           |                                                                                         |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|-----------|-----------|-----------------------------------------------------------------------------------------|
| 43 | Planting of Trees and their Maintenance for one Year                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |         |      |           |           | INR One Lakh Eight Five Thousand Seven Hundred & Twenty and Paise Sixty Only            |
| 41 | Planting of trees by the road side (average trees) in @ 80 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/dung manure, sloping the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 119,200 | Each | 1124,400  | 4973.60   |                                                                                         |
| 42 | Road Marking with Hot Applied Thermoplastic Compound with Reflecting Glass Beads on Bituminous                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |         |      |           |           |                                                                                         |
| 43 | Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflecting glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per JRC:35. The finished surface to be level, uniform and free from streaks and holes.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |         |      |           |           |                                                                                         |
| 44 | At Edge for DT Portion                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 417,600 | Sqm  | 856,670   | 422915.99 | INR Four Lakh Twenty Two Thousand Nine Hundred & Twenty Five and Paise Ninety Nine Only |
| 45 | At Edge for CC Portion                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 123,800 | Sqm  | 946,530   | 120748.64 | INR One Lakh Thirty Thousand Seven Hundred & Forty Eight and Paise Sixty Four Only      |
| 46 | Providing and Fixing Logo of Maintenance Project                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |         |      |           |           |                                                                                         |
| 47 | Providing and fixing of typical MMSV Information sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.5 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edge. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet metal posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most standard plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tabs. All M.S. will be slope finished on both sides. Lettering and printing arrows, border etc. will be printed with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1101 and Appendix 1105.1 |         |      |           |           |                                                                                         |
| 48 | Providing and Fixing Logo of Maintenance Project                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 2,800   | Msq  | 11275,600 | 21151.00  | INR Twenty One Thousand One Hundred & Fifty One and Paise Eighty Only                   |
| 49 | Brick masonry work in cement mortar 1:2 in parapet excluding pointing and plastering as per drawing and technical specifications Clause 610, 611 and 612                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 6,518   | Sqm  | 7101,600  | 8327.16   | INR Sixty Three Thousand Nine Hundred & Seventy Eight and Paise Sixteen Only            |
| 50 | Plastering with cement mortar 1:4 on brick work in sub-structure as per Technical Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 60,190  | Sqm  | 330,050   | 14464.03  | INR Fourteen Thousand Four Hundred & Ninety Four and Paise Three Only                   |

RAJU SWAMI CONSTRUCTION  
  
 Proprietor

  
 24.09.24

  
 EXECUTIVE ENGINEER  
 RYD (W) DIVISION  
 GOVT. OF KARNATAKA  
 24.09.24

|                        |                                                                                                                                                       |               |           |             |             |                                                                                            |
|------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|-----------|-------------|-------------|--------------------------------------------------------------------------------------------|
| 51                     | Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as | EQ / SQ       | Sum       | 133.208     | 8951.28     | INR Eight Thousand Eighty One and 20/100 Twenty Eight Paise Only                           |
| 52                     | Add GST @ 18%                                                                                                                                         | 1.800         | RS        | 2035651.187 | 2095641.19  | INR Twenty Lakh Twenty Five Thousand Six Hundred & Twenty One and Paise Ninety One Only    |
| 53                     | Add Labour Cost @ 1%                                                                                                                                  | 1.809         | RS        | 116424.518  | 116424.51   | INR One Lakh Sixteen Thousand Four Hundred & Twenty Four and Paise Four Five One Only      |
| 54                     | SEIGNIORAGE FEE                                                                                                                                       | 1.809         | RS        | 79339.628   | 79339.62    | INR Seventy Nine Thousand Three Hundred & Twenty Nine and Paise Sixty Two Only             |
| 55                     | Maintenance cost                                                                                                                                      | 30.000        | Quarterly | 172339.750  | 3446795.00  | INR Thirty Four Lakh Forty Six Thousand Seven Hundred & Ninety Five Only                   |
| 56                     | Add GST @ 18%                                                                                                                                         | 1.809         | RS        | 518421.100  | 526423.10   | INR Six Lakh Twenty Thousand Four Hundred & Twenty Three and Paise Two One Only            |
| 57                     | Add Labour Cost @ 1%                                                                                                                                  | 1.810         | RS        | 34467.958   | 34467.95    | INR Thirty Four Thousand Four Hundred & Twenty Seven and Paise Ninety Five One Only        |
| 58                     | Maintenance SEIGNIORAGE FEE                                                                                                                           | 1.800         | RS        | 6884.610    | 6884.63     | INR Six Thousand Eight Hundred & Eighty Eight and Paise Sixty Three Only                   |
| Total in Figures       |                                                                                                                                                       |               |           |             | 18042431.04 | One Crore Eighty Lakh Forty Two Thousand Four Hundred & Thirty One and Paise Four One Only |
| Quoted Rate in Figures |                                                                                                                                                       |               | Per Sq    |             | 0.00        | INR Zero Only                                                                              |
| Quoted Rate in Words:  |                                                                                                                                                       | INR Zero Only |           |             |             |                                                                                            |

for approved for Rs 18042431.00 / Rupees *Placed*  
 one crore eighty four lakh forty two thousand  
 four hundred & thirty one) only from  
 Serial No. 7 to 58.

BEAU DHAN CONSTRUCTION  
*Beau Dhan*  
 Proprietor

Superintending Engineer  
 RWD Works *Beau Dhan* SINGAR

*Beau Dhan*  
 21/05/2023

*Beau Dhan*  
 EXECUTIVE ENGINEER  
 RWD (W) DIVISION  
 GODOLLA + 26/2/2023