



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD F.D.R. PART - A (2023 - 24)

DETAILED ESTIMATE For F.D.R. Motrable Work

DISTRICT :	BHAGALPUR	BLOCK :	Pirpainti
NAME OF ROAD :	Jagdispur More Barahat PWD Path To Gauripur Via Bhagaiya Path		
Restoration Length :	30 meter		
Cost of Road Motorable work :	36.168		Lakh
Add GST @ 18% :	6.510		Lakh
Add LC @ 1% :	0.362		Lakh
Add S.F :	2.090		Lakh
Drone Photograpy @ 5000/ per Stage + Still Photography of Damaged and Restoration Work. $5500 \times 3 = 16500 + 5000 = 21500/-$ Per	0.430		Lakh
Total Cost :	45.560	45.123	Lakh

SUBMITTED BY
The Executive Engineer
Works Division, Kahalgaon

INSPECTION REPORT FOR MOTORABLE WORK

Name of PIUs :- E.E. RND Works Division, Kahalgouri.	
Name of Block / Road :- Jagdishpur More Barabati PWD from to Gauripur via Bhaguniya Pat.	
A. For Road	
1. Damage Location / Chainage :	
2. Damage Length : 30 m.	
3. Nature of Damage (length wise)	(i) Breach :- 30 m.
	(ii) Crust Damage :- 30 m.
	(iii) Only Flank Damage —
whether traffic fully/Partially obstructed - Fully obstructed.	
4. Details of Restoration ;	
(i) Material Being Used in Restoration : Brice bats, sand filled bags.	
(ii) Equipment / Tools being Used in Restoration Works : Front-end loader, Tractor-hauled screw assisted roller.	
(iii) Restored length	In open Area :- 30 m.
	In habitation Area :- —
(iv) if Restoration work done in habitation Area give Reason :- —	
B. For Bridge (Size of Bridge / Culvert)	
1. Damage Location / Chainage : / N/A	
2. No. of Span Damage :-	
3 Length of Span	
4 Nature of Damage (Pier / Abutment/Wing wall/Approach Road Damage)	
5. Details of Restoration :	
(i) Material Being Used in Restoration :	
(ii) Equipment / Tools being Used in Restoration Works : N/A	
(iii) Restored length	In open Area :-
	In habitation Area :-
Overall Grade of Restoration Work (Satisfactory / Unsatisfactory) Satisfactory.	

Signature of Inspector
(Official Seal)

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, २

FDR 2023-24

प्रतिवेदन

पथ का नाम — Jagdishpur More Barahat PWD Path to Gauripur via Bhagaiya
प्रखण्ड का नाम — Pirpainti
पथ की लम्बाई — 10.20 Km
प्राक्कलित राशि — 45.560 Lakh

वर्ष 2023 में गंगा नदी में आयी भयंकर बाढ़ / अतिवृष्टि से ग्रामीण कार्य विभाग, कार्य प्रमण्डल, कहलगौव अन्तर्गत पीरपैती प्रखण्ड में Jagdishpur More Barahat PWD Path to Gauripur via Bhagaiya पथ के क्षतिग्रस्त पथार्शों में यातायात पूर्ववहाल कराने हेतु प्राक्कलन तैयार किया गया है। पथ के क्षतिग्रस्त पथार्शों को तत्काल Brick bat से भरकर मोटरेबुल किया गया है। मोटरेबुल कार्य अधीक्षण अभियन्ता, ग्रामीण कार्य विभाग, कार्य अंचल भागलपुर के पत्रांक 700 दिनांक 25.07.2023 के द्वारा कार्य प्रमण्डल कहलगौव के लिये चयनित एजेन्सी द्वारा कराया गया है।

कराये गये कार्य का प्राक्कलन स्वीकृत अनुसूचित दर पर तैयार किया गया है तथा कार्य का विवरण MIS के FDR Module में प्रविष्टि किया गया है।

कार्य पूर्ण कराये जाने के उपरान्त प्राक्कलन की तकनीकी अनुमोदन सह तकनीकी स्वीकृति अपेक्षित है।

कनीय अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रशाखा कहलगौव

सहायक अभियन्ता
ग्रामीण कार्य विभाग
कार्य अवर प्रमण्डल कहलगौव

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल कहलगौव

GENERAL ABSTRACT OF COST

Name of Road : Jagdispur More Barahat PWD Path To
Gauripur Via Bhagaiya Path

District : BHAGALPUR

Length of Road : 10.200 Km

Block : Pirpainti

Restoration Length : 30 meter

Sl. No	Particulars		Details	Total Cost (in Rs.)
A	Cost of Road Motorable work	:		36,16,808.00
B	Add GST @ 18%	:		6,51,025.44
C	Add LC @ 1%	:		36,168.08
D	Add S.F	:		2,08,984.33
E		:		
	Total Cost of Restoration work	:		45,12,985.85
			Say, Rs in Lakh	45.129 lacs

J. E.

A. E.

E. E.

Post facto technically sanctioned for Rs. 45.129 lacs (Rupees Forty five lakh twelve thousand nine hundred) only.

Superintending Engineer
Rural Works Department
Works Circle, Bhagalpur