



बिहार BIHAR

परिचाय कोषगार बज्रगृह
निर्गत तिथि:-

17 OCT 2023

कोषगार पदाधिकारी

E.E.R.W.D. WORKS DIVISION. BAISI. PURNEA

AU 262259

Ag

Md. Shamim Ahmad Ansari
S. V. BAISI, PURNEA
L.No.-230/95

Supplementary Agreement of 98 SBD/2020-21

This Supplementary agreement made on _____ between Executive Engineer, R.W.D. works Division Baysi of the one part and Rameez Raza, At Kohbara Adhang, Distt :- Purnea (Bihar) Herein after called the contractor of the other part. Whereas the Employer has accepted the Difference amount of sanctioned GST revised rate @ 18% sanctioned by the Superintending Engineer, Rural works department, Works circle Purnera via Letter Number 1726 (अनु) Dated:-16.12.2023 for Rupees 2,86,509.00 (Rupees Two Lakhs Eighty Six Thousand Five Hundred Nine Only) as illustrated below:-

SI NO	Name of the road	Previously Approved Agreement	Approved Agreed Value including 18 % GST
1	Baraili More to Ghat Baraili	Rs 67,34,352.00	Rs 70,20,861.00
		Rs 67,34,352.00	Rs 70,20,861.00
Total		2,86,509.00	
Difference Amount			
Total Value of Agreement After Approval of 18% GST for the Above Road(1+2) [Original +Suppl.]Agreement			70,20,861.00

i.e Rupees Seventy Lakhs Twenty Thousand Eight hundred Sixty One Only

In this Agreement, Words and expression shall have the same meanings as are respectively assigned to them in the Condition of contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.

Rameez Raza

10/11/24

Executive Engineer
R.W.D. Works Division
Baisi

NOW THIS AGREEMENT WITNESSETH as follows :-

1. The following documents shall be deemed to form and be ready and construed as part of this Agreement, Viz.

- Letter of Superintending Engineer RWD works Circle, Purnea
- BOQ Approved
- Original Agreement

It is expressly acknowledged and agreed by both parties that this supplementary agreement is intended to address specific aspects related to the GST claim, rest portion of execution, and maintenance of road, and it shall not in any way alter, modify, or affect the terms and conditions stipulated in the original agreement dated [Original Agreement Date] _____.

The original agreement remains in full force and effect, and any provisions not explicitly addressed in this supplementary agreement shall be governed by the terms of the original agreement.

In witness where of, the parties hereto execute this non-impact statement on the date first above written.

2. Deduction :- I.T, GST, Royalty & all other deduction will be deduced form each bill as per Govt. rule.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written

The Common Seal of

Was hereunto affixed in the presence of

Signed Sealed and Delivered by the said

In the presence of :



Binding Signature of Contractor


10/11/24


10/11/24

Executive Engineer

Binding Signature of Employer


10/11/24 Baisi



STATE BANK OF INDIA
KASBA (DIST. PURNEA) (02960)

Special Term Deposit Advice
(in lieu of Special Term Deposit Receipt)

Date: 21/12/2023

Dear Sir/Madam,

We have pleasure in confirming your deposit held with us, the details of which are as shown below.

Your FD account number is 42543025538 . Please quote this in all correspondences.

Thank you for banking with SBI.

A. Customer Name - RAMEEZ RAZA

CIF Number
85468616877

Mode of Operation
SINGLE

Scheme
STD-PUB IND UNI 181D-10YRS
Credit Interest & Maturity Proceeds to (A/c)
30702479311

Maturity Instruction
Auto Renewal

Frequency of Interest Payment
At Maturity

Nomination
Registered

Nominee(s), if any
MD RAHBER ALAM

TDR/STDR A/c No.	Tenure	Interest Rate	Principal Amt.	Value Date	Maturity Date	Maturity Value
42543025538	3 Year(s), 0 Month(s), 0 Days(s)	6.5 %	INR 10000	21/12/2023	21/12/2026	INR 12134

B. Terms & Conditions for TDR/STDR

- Pledge to E.E.R.W.D. works division*
- Please inform us of any change in your Resident/Non-Resident status as and when change takes place. The status declaration on the account opening form shall remain in force until such time as you are advised to us.
 - In case of premature payment the deposit represented by this advice shall be subject to penalty provisions at the rates decided by the bank from time to time.
 - Bank will deduct Income Tax as per the law applicable. No tax is to be deducted, Form 15G/H has to be submitted by the depositor to the branch just after opening the FD and at the beginning of each financial year in the subsequent financial years. The facility for online submission of Form 15G/H is also available in the INB platform (inbasbi.com) of the bank.
 - FD with additional rate of interest for senior citizens will be issued if option for "Senior Citizen" is given by the customer and age of customer is 60 Yrs or above, on the date of creating the fixed deposit, as per date of birth recorded with the Bank. The minimum days and minimum amount applicable for additional rate of interest for senior citizen will be as per Bank's policy.
 - FD will be disposed of according to the Maturity Instruction given at the time of opening the deposit. In case of auto renewal, the deposit will be renewed for the same duration for which it was originally kept, at the rate of interest prevailing on the date of renewal for that duration. If auto renewal instruction are given, the instructions will continue to be executed till terminated by the account holder.
 - As per section 206AA introduced by Finance (No. 2) Act, 2009 effective April 01, 2010, every person who receives income on which TDS is deductible shall furnish his PAN, failing which TDS shall be deducted at the rate of 20% in case of Domestic deposits and 30.90% in case of NRO deposits.
 - Additionally, in the absence of PAN, Form 15G/H and other exemption certificates will be invalid even if submitted & partial TDS will be applicable. Kindly visit your SBI branch with PAN card (original & copy) to get the same updated on the bank records.

Rameez Raza

6860
10/1/24

10/1/24
Executive Engineer
R W Works Division
Baisi

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बायसी।

पत्रांक.....63...../

Email: ID-rwdbaysi@gmail.com

बायसी, दिनांक.....09/01/24.....

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बायसी।

सेवा में,

Branch Manager,
State Bank Of India,
Kasba Purnea.

विषय:- FD के सत्यापन के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में कहना है कि संवेदक Rameez Raza ने कार्य का इनके द्वारा Earnest Money के रूप में आपके शाखा से निर्गत किया गया है।

अतः अनुरोध है कि टेबल में अंकित FD आपके शाखा से निर्गत एवं अधोहस्ताक्षरी के पदनाम से प्रतिष्ठित किया गया है या नहीं को सत्यापित कर इस कार्यालय को सूचित करने की कृपा की जाय, ताकि अग्रेत्तर कार्रवाई किया जा सके।

क्रम स0	FD/BG	Amount	Date of Issue	Date of Expire/Maturity
1	42543025538	10,000.00	21-12-2023	21-12-2026



विश्वासभाजन

Handwritten signature and date: 09/01/24

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बायसी।

Handwritten signature and date: 09/01/24

Handwritten signature: Rameez Raza

Handwritten signature and date: 10/1/24

Executive Engineer
RWA Works Division
Baisi

बिहार सरकार
अधीक्षण अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णियाँ।

प्रेषक,

पत्रांक1726 (अनु.)

पूर्णियाँ/दिनांक ...16/12/2023

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, पूर्णियाँ।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बायसी।

विषय :- पुनरीक्षित परिमाण विपत्र स्वीकृत करने के संबंध में।

प्रसंग :- आपका पत्रांक 2060 दिनांक 06.12.2023

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र के आलोक में सूचित करना है कि निम्नांकित पथ के स्वीकृत प्राक्कलन में 12% GST प्रावधान था, जबकि सरकार के पत्रांक 3322 दिनांक 05.12.2022 द्वारा GST 12% से बढ़ाकर 18% GST किए जाने के फलस्वरूप आपके द्वारा समर्पित GST प्रस्ताव की स्वीकृति दी जाती है। कार्यपालक अभियंता यह सुनिश्चित करेंगे की संवेदक द्वारा GST का भुगतान ससमय किया गया हो।

क्र०सं०	पथ का नाम	पुनरीक्षित परिमाण विपत्र की राशि (लाख में)	पूर्व में स्वीकृत परिमाण विपत्र की राशि (लाख में)	अंतर राशि (लाख में)
1	Baraili More to Ghat Baraili	7020861.00	6734352.00	286509.00

विश्वासभाजन

[Signature]
अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, पूर्णियाँ।

[Signature]
10/1/24

[Signature]
10/1/24

Executive Engineer
R W Works Division
Baisi

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बायसी

पत्रांक.....२०६० /
प्रेषक,

बायसी, दिनांक ६.१२.२३

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बायसी।

सेवा में,

अधीक्षक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल, पूर्णिया।

विषय :- MMGSY(SC) योजनान्तर्गत स्वीकृत योजनाओं में GST दर 12% से बढ़ाकर 18% करने के संबंध में।

प्रसंग:- अपर मुख्य कार्यपालक पदाधिकारी-सह-सचिव, बिहार ग्रामीण पथ विकास अभिकरण, पटना के पत्रांक 3322 पटना/दिनांक 05.12.2022

महाशय,

उपर्युक्त विषय के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमंडल, बायसी अधीन MMGSY(SC) योजनान्तर्गत निम्नलिखित पथ का GST दर 12% से बढ़ाकर 18% पूर्व के परिमाण विपत्र का पुनरीक्षित परिमाण विपत्र तैयार कर अनुमोदनार्थ समर्पित की जाती है।

क्रमांक	योजना का नाम	पुनरीक्षित परिमाण विपत्र की राशि (लाख में)	पूर्व की स्वीकृत परिमाण विपत्र की राशि (लाख में)	अंतर राशि (लाख में)
1	BARAILI MORE TO GHAT BARAILI	7020861.00	6734352.00	286509.00

अनु०-यथोक्त।

विश्वासभाजन

[Signature]
६/१२/२३

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बायसी।

[Signature]
20/11/24

Executive Engineer
R W & Works Division

[Signature]
Baisi

[Signature]
18/12/23

Tender Inviting Authority: Engg-in Chief RWD Patna

BARAILI MORE TO
GHAT BARAILI

Name of Work: Construction of Road & CD Works Under :

BLOCK :- AMOUR

DIVISION:- BAISI

Excess (+)

%

Bidder
Name:**SCHEDULE OF WORKS**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

AMOUNT
Rs. P

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate Figure	
WORK DONE					
1	Providing & Fixing of Working benchmark/Reference Pillars 02 nos. per km & 06 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I	0.550	Km	35804.960	19693.000
2	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass ,bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I	0.193	Hac	51137.380	9870.000
3	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 . (Including Royalty & Labour Cess).For 1000 m Lead	210.150	Cum	190.450	40023.000
28	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	90.960	Cum	294.730	26809.000
29	Sand filling Foundation Trenches as per drawing and technical specification Clause 1108	1.310	Cum	487.590	639.000
30	Providing PCC Grade M 25 for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	11.650	Cum	6276.110	73117.000
31	Providing PCC Grade M 25 for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	52.240	Cum	6276.110	327864.000

Executive Engineer
Works Division
Baishi

10/11/24

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	AMOUNT Rs. P
				Figure	
32	Providing RCC Grade M 25 for Plain/reinforced cement concrete in substructure (Boc Cell) complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	32.090	Cum	7501.480	240722.000
33	Providing RCC Grade M 25 for Plain/reinforced cement concrete in Superstructure (Deck Slab M-25) complete as per drawings and technical specification Clauses 800, 1205.4, 1205.5	8.150	Cum	7661.850	62444.000
34	Providing Bitumen painting over top surface of Abutment Cap & Inner Vertical Surface of Dirt Wall including Heating the Bitumen & Cost of Painting Brush etc. all Complete.	0.000	Sqm	15.010	0.000
35	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in superstructure complete as per drawings and technical specification Clauses 1002, 1002, 1010 & 1202	0.722	MT	57475.770	41498.000
36	Providing and filling joint sealing compound as per drawings and technical specifications with coarse sand and 6 per cent bitumen by weight.	15.000	Rm	40.490	607.000
37	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	16.000	Nos.	241.440	3863.000
38	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	29.800	Cum	294.730	8783.000
39	Providing PCC M -15 (1:2.5:5) concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M -15	4.595	Cum	5626.040	25852.000
40	Plain/reinforced cement concrete in (M-20) substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	34.710	Cum	6603.700	229214.000
41	Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in double row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets as per Clause 1106.	7.500	Rm	3273.789	24553.000
Total Cost of Construction =			Rs		1135551.000
As per Aggrement Below 0.10 %			Rs		1134415.00
Add GST @ 12%			Rs		136130.000

[Signature]
10/11/24

[Signature]
10/11/24
Executive Engineer
R. M. L. Works Division
Baisi

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	AMOUNT Rs. P
				Figure	
					11344.000
	Add Labour Cess @ 1%		Rs		1281889.000
	Total Cost of Construction =		Rs		
WORK TO BE DONE					
4	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess).	482.300	Cum	192.130	92664.300
5	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	208.310	Cum	2980.410	620849.210
6	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	156.230	Cum	3661.600	572051.770
7	Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical	333.300	Cum	6875.540	2291617.480

4860
18/11/24

Executive Engineer
Works Division
Baisi
18/11/24

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate Figure	AMOUNT Rs. P
8	Providing and laying of a reinforced cement concrete pipe duct.300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills,constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:981997,bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	15.000	Rm	1658.920	24883.800
9	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703.				
10	Ordinary Kilometer Stone (Precast)	2.000	Nos.	2296.710	4593.420
11	200 m Stone (Precast)	2.000	Nos.	626.470	1252.940
12	Providing and fixing of Semi reflective cautionary, mandatory and informatory sign board :- Providing and fixing of Semi reflective cautionary, mandatory and informatory sign board as per IRC:67 made of 1.5 mm thick MS Sheet duly stove white colour in front and gray colour on back with red reflective border of 65 mm width and required letters and figures with reflective tape engineering grade as per Clause 1701.3.9 of MORD for Rural Roads of required shade and colour supported and welded on 47mm x 47 mm x 12 SWG sheet tube firmly fixed to the ground by mean of properly designed foundations with M-15 grade cement concrete 450x450x600 mm, 600 mm below ground level as per approved drawing Clause 1701.2.2				
13	600 mm equilateral & triangle	2.000	Nos.	3553.886	7107.770
14	600 mm Circular	1.000	Nos.	4734.200	4734.200
15	800mm X 600 mm rectangular	2.000	Nos.	6565.083	13130.170
16	600mm X 450 mm rectangular	1.000	Nos.	4613.381	4613.380
17	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.				
18	Road Marking on CC	110.000	Sqm	821.810	90399.100

[Signature]
10/11/24

[Signature]
10/11/24
Executive Engineer
R.H. Works Division
Baisi

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	AMOUNT Rs. P
				Figure	
19	Reinforced cement concrete M15 grade Boundary Pillar / local stone of standard design as per IRC:25 fixing in position including finishing and lettering but excluding painting as per drawing and technical specification clause 1704.	16.000	Nos.	476.484	7623.740
20	Providing and erecting direction and place identifications of semi reflective sign boards as per IRC:67 made of 2 mm thick M.S. Sheet duly stove enameled paint in white colour in front and grey colour on back with red reflective border of 70 mm width and required message, letters, figures with reflective engineering grade tape as per MORD specifications of required shade and colour. Supported and welded on 47 mm x 47mm of 12 SWG Square tube of 3050 mm height duly strengthened by 25 mm x 5 mm M/s flat iron on edges on back firmly fixed to the ground by means of properly designed foundations with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	2.000	Nos.	11431.370	22862.740
21	Providing and Fixing 'Logo' of MMGSY Project Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	3.000	Nos.	3558.290	10674.870
22	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	67.500	Cum	294.730	19894.280

[Signature]

[Signature]
10/11/24

[Signature]
10/11/24

Executive Engineer
R.W. Works Division
Baisi
10/11/24



Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	AMOUNT Rs. P
				Figure	
23	Providing PCC M -15 (1:2.5:5) concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M -15	7.000	Cum	5626.040	39382.280
24	Brick masonry work in cement mortar (CM 1:4) in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 602, 603, 604, 1202 & 1203	65.500	Cum	6712.890	439694.300
25	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M -20	1.500	Cum	6603.700	9905.550
26	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	50.000	Nos.	241.440	12072.000
27	Plastering with cement mortar (1:4), 15 mm thick on brickwork in substructure as per technical specification Clauses 613.4 & 1204	70.000	Sqm	392.640	27484.800
28	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	13.612	Cum	294.730	4011.510
29	Sand filling Foundation Trenches as per drawing and technical specification Clause 1108	0.227	Cum	487.590	110.430
30	Providing PCC Grade M 25 for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	1.757	Cum	6276.110	11026.810
31	Providing PCC Grade M 25 for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	6.856	Cum	6276.110	43029.000
32	Providing RCC Grade M 25 for Plain/reinforced cement concrete in substructure (Boc Cell) complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	2.180	Cum	7501.480	16353.720
33	Providing RCC Grade M 25 for Plain/reinforced cement concrete in Superstructure (Deck Slab M-25) complete as per drawings and technical specification Clauses 800, 1205.4, 1205.5	1.628	Cum	7661.850	12473.570
34	Providing Bitumen painting over top surface of Abutment Cap & Inner Vertical Surface of Dirt Wall including Heating the Bitumen & Cost of Painting Brush etc. all Complete.	16.920	Sqm	15.010	253.970



[Signature]
10/11/24

[Signature]
10/11/24
Executive Engineer
Works Division
Baisi

B.O.D. revised due to G.S.T. enhancement 12% Dec 18.

Revised B.O.D. approved for amount Rs 70,20,861.00 (Rupees seventy two thousand eight hundred & sixty one) only.


अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, पूर्णिया

16/12/23


Executive Engineer
R.W.C. Works Division
Baisi

10/1/24

RURAL WORKS DEPARTMENT

GOVERNMENT OF BIHAR

GST Claim Under Change in Law

NAME OF WORK :- BARAILI MORE TO GHAT BARAILI

Executive Engineer. RWD WORKS DIVISION, BAISI , PURNEA

CONTRACTOR NAME :- RAMEEZ RAZA

GSTN:- 10BFOPR9391R1ZD

[Signature]
10/11/24

Executive Engineer
R W Works Division
Baissi

[Signature]
10/11/24