



बिहार BIHAR



क्र.सं. 6819 ता. 26/12/23 मु. 1000 सीट सं. 14 सीट AS 945556
क्रेता का नाम एवं पता पंडित रविशंकर सिन्हा पता 39 इन्द्रपुरी

प्रसाद
ता. 17/86
पटना

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 52/MBD/2023-24

This agreement, made the 26 December Day of 2023 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and M/S Pandey Ravikant Sinha, 39 Indrapuri Road no.-2 Keshri Nagar, Phulwari, Patna- 800024

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road Contract of the maintenance of road from MR-N/23-24/Lakhisarai/15 Package Under of Block in Chanan, Under M/R in Lakhisarai District and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 2,05,15,675.00 (Two Crore Five Lakh Fifteen Thousand Six Hundred Seventy Five) only & five year Maintenance cost Rs. 50,58,374.00 (Fifty Lakh Fifty Eight Thousand Three Hundred Seventy Four) Total Cost Rs. 2,55,74,049.00 (Two Crore Fifty Five Lakh Seventy Four Thousand Forty Nine) only.

PRASINHA

प्रसाद
26/12/23

Executive Engineer
RWD Works Division
Lakhisarai

SL No.	Name of Road	Length in km	Const. Cost	Maintenance cost	Agreement Value
1	L058- L038 to Bichchhawe	0.611	22.55290	8.72198	31.27488
2	PMGSY Sadak Se Sudamadih	2.600	126.80940	33.65949	160.46889
3	RCD Road Kundar Mandal Tola to Chandrabansi tola Kundar	0.900	55.79445	8.20227	63.99672
Total		4.111	205.15675	50.58374	255.74049

NOW THIS AGREEMENT WITNESSTH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to and they shall be deemed to from and be read and construed as part of this agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the Execution adcompletion of the works and the remedying the defects hear in Contract price or such other sum as may become payable under the provision of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz
 - a. Latter of Acceptance
 - b. Contractor's Bid
 - c. Section VI –General Conditions
 - d. Section VII- Particular Condition
 - e. Section V – Technical Specification (General and Supplementary Technical Specification
 - f. Appendix A – Drawings
 - g. Section IV – Works Schedule
 - h. Quality plan for output and performance based road contract as per clause A14.1 of the technical specifications
 - i. Appendices of the contract
 - j. Addenda issued during bid period
 - k. Any other relevant documents listed in the particular conditions together with any post bid correspondence.

In witness whereof the parties thereto have caused this agreement to be executed the day and year first before written

The Common Seal of was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said

..... in the presence of:

Binding Signature of Employer

Binding Signature of Contractor

PPK3intha

24/12/23

Executive Engineer
RWD Works Division
Lakhisarai
26/12/23

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:-52/MBD/2023-24

NAME OF WORK: - MR-N/23-24/Lakhisarai/15 Package Under of Block in Chanan, Under M/R in Lakhisarai District.

NAME OF AGENCY: M/S Pandey Ravikant Sinha,
39 Indrapuri Road no.-2 Keshri Nagar,
Phulwari, Patna- 800024

Reference :- Chief Engineer-2,
R.W.D, Bihar, Patna
Vide Letter No. 4144 Date :- 09.12.2023

AGREEMENT AMOUNT – Main work:- 2,05,15,675.00
Maintenance work:- 50,58,374.00
Total Amount: - 2,55,74,049.00

Performance Security :- Deposited @ 5 % & Next 5 % deducted from Bill
Date of Agreement :- 26-12-2023
Date of Completion :- 25-09-2024
No. of Item of Work :- As per B.O.Q (Nos)
Rate Quoted :- 1.01 % below (One five Point zero zero percent below)

PRK Sinha
Contractor Signature

Prasad
24/12/23

A. B. Sinha
Executive Engineer
R.W.D. Works Division
Lakhisarai

Rakshita
26/12/23

Tender Inviting Authority: Engr-in Chief RWD Patna

Name of Work: Construction of Road & CD Works for L058 - L038 To Bichchhawa in Suryagarha Block Under MR-3954

Contract No: Civil Works

Bidder
Name:

Excess (+)

VALIDATE

PRINT

HELP


Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.12	Hect	75573.34	Rupees Seventy Five Thousand Five Hundred & Seventy Three and Paise Thirty Four Only	9063.00
2	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	522.45	Cum	262.74	Rupees Two Hundred & Sixty Two and Paise Seventy Four Only	137269.00
3	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	19.95	Cum	1734.81	Rupees One Thousand Seven Hundred & Thirty Four and Paise Eighty One Only	34609.00
4	WBM Grading 2 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	25.51	Cum	3562.84	Rupees Three Thousand Five Hundred & Sixty Two and Paise Eighty Four Only	90885.00
5	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	41.16	Cum	3257.65	Rupees Three Thousand Two Hundred & Fifty Seven and Paise Sixty Five Only	134085.00
6	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	548.80	Sqm	59.84	Rupees Fifty Nine and Paise Eighty Four Only	32840.00

pkksinha

Signature of Tenderer with seal

Executive Engineer
RWD Works Division
Lakhisargaj

E. Letter No. 1163 Dt. 15/7/23
Construction Cost Rs. 22,78,300.76
5 yrs. Maintenance Cost Rs. 8,81,096.79
Total Cost Rs. 31,59,397.55
BOQ Approved For Rs. 31,59,400.00
(Rupees Thirty one lakh fifty nine
thousand four hundred only)
including 5 yrs Maintenance Vide
Item no. 01 to 24


Superintending Engineer
Rural Works Department
Anwar Circle, Munger

21/07/23

Tender Inviting Authority: Engg-in Chief RWD Patna



Name of Work: Construction of Road & CD Works for PMOSY Sadak Se Sudamedih



Panah Block Under/ MR-3054

Contract No: Civil Works/



Bidder Name: Excess (+) %

SCHEDULE OF WORKS						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	1.04	Hect	75573.34	Rupees Seventy Five Thousand Five Hundred & Seventy Three and Paise Thirty Four Only	78596.00
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	891.00	Cum	259.20	Rupees Two Hundred & Fifty Nine and Paise Twenty Only	230947.00
3	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1294.10	Cum	262.74	Rupees Two Hundred & Sixty Two and Paise Seventy Four Only	340012.00
4	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	91.86	Cum	2018.32	Rupees Two Thousand & Eighteen and Paise Thirty Two Only	185443.00
5	WBM Grading 2 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	68.93	Cum	4126.52	Rupees Four Thousand One Hundred & Twenty Six and Paise Fifty Two Only	284441.00
6	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	92.53	Cum	3792.92	Rupees Three Thousand Seven Hundred & Ninety Two and Paise Ninety Two Only	350959.00
7	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (55-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	1233.73	Sqm	60.00	Rupees Sixty Only	74024.00

PRK Sinha

Signature of Tenderer with seal

Executive Engineer
RWD Works Division
Lakhisarai

S. E. Letter No. 1162 Dt. 15.07.2023
Construction Cost Rs. 12810323.82
5 yrs. Maintenance Cost Rs. 3400291.49
Total Cost Rs. 16210615.31
BOG Approved For Rs. 16210600 = 0
(Rupees One crore sixty two lakhs
Ten thousand six hundred — only)
including 5 yrs Maintenance Vide
Memo No. 01 to 32


Superintending Engineer
Rural Works Department
Avesh
27/07/23
Circle, Munger

Order Inviting Authority: Engg-in Chief RWD Patna

Line of Work: Construction of Road & CD Works for RCD Road Kunder Mandal To Chandrabansi To Kunder

Sanction Block Under: MR-3054

Contract No: Civil Works

Bidder Name: Excess (+) %

SCHEDULE OF WORKS						
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
6	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. Km stone	2.00	Each	2873.39	Rupees Two Thousand Eight Hundred & Seventy Three and Paise Thirty Nine Only	5747.00
7	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. 200 m stone	4.00	Each	816.60	Rupees Eight Hundred & Sixteen and Paise Sixty Only	3266.00
8	Direction and Place Identification signs with size more than 0.9 sqm size board > Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	1.92	Sqm	15007.08	Rupees Fifteen Thousand & Seven and Paise Eight Only	28814.00
9	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600 mm equilateral & triangle)	6.00	Each	4445.38	Rupees Four Thousand Four Hundred & Forty Five and Paise Thirty Eight Only	26672.00
10	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600 mm circular)	6.00	Each	4318.40	Rupees Four Thousand Three Hundred & Eighteen and Paise Forty Only	25910.00
11	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600 mm rectangular)	3.00	Each	4173.87	Rupees Four Thousand One Hundred & Seventy Three and Paise Eighty Seven Only	12522.00

Signature of Tenderer with seal

Executive Engineer
RWD Works Division
Lakhisarai

S. E. Letter No. 1163 Dt. 15.7.23
Construction Cost Rs. 56,36,272.31
5 yrs. Maintenance Cost Rs. 82,85,95.90
Total Cost Rs. 64,64,968.21
BOQ Approved For Rs. 64,65,000.00
(Rupees sixty four lakh
sixty five thousand only)
Including 5 yrs Maintenance Vide
Mem no. 01 to 17


Superintending Engineer
Rural Works Department
Amd
21/3/23
Circle, Munger

**मुख्य अभियंता-2 का कार्यालय
ग्रामीण कार्य विभाग, पटना।**

/ पटना, दिनांक-

पत्रांक-
प्रेषक,


ई० श्रीप्रकाश
मुख्य अभियंता-2

सेवा में,
कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, लखीसराय।

विषय : शीर्ष 3054 (MR) अंतर्गत कार्य प्रमण्डल, लखीसराय के अधीन पैकेज सं०-MR-N/23-24
Lakhisari/15 (Tender Id-127180) कार्य की निविदा की स्वीकृति के संबंध में।

- महोदय,
- उपरोक्त विषयक कार्य बिहार लोक निर्माण संहिता के कड़िका-163 के आलोक में इस कार्य के लिए न्यूनतम दरदाता Pandey Ravikant Sinha (Bid ID- 554022) को उनके द्वारा निविदित दर, जो परिमाण विपत्र की दर से 1.01% (एक दशमलव शून्य एक प्रतिशत) कम है, को स्वीकृत करते हुए सम्पूर्ण कार्य कुल 2,55,74,049/- (दो करोड़ पचपन लाख चौहत्तर हजार उनचास) रुपये मात्र की लागत पर आप ही अनुज्ञा एवं कार्यहित में आवंटित किया जाता है।
- निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।
 - संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ जमा किये गये संबंधित एन०एस०सी० / Fixed Deposit/BG आदि का सत्यापन संबंधित डाकघर/बैंक से कराकर प्रमंडलीय कार्यालय में अभिलेखित किया जायेगा। कार्यपालक अभियंता, कार्य प्रमंडल, लखीसराय कार्यदेश निर्गत करने के पूर्व अधधन की राशि के सत्यापन से संबंधित कागजात अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।
 - एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जायेगा।
 - एकरारनामा से पूर्व कार्यपालक अभियंता यह सुनिश्चित कर लेंगे कि निविदाकार डिबार सूची/काली सूची या कार्य लंबित सूची में शामिल न हों।
 - कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत रीड के आधार पर दिया गया है, कार्य करते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।
 - इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रादेशिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लेखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।
 - अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में यत्सुस्थिति से तात्क्षण अधोहस्ताक्षरी को अवगत करायेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्यवाई की जायेगी।
 - एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जांच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।
 - कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपबंध से पूरी तरह आश्चस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रादेशिक स्वीकृति के अप्रसारण प्राप्त होने पर कार्यारम्भ का अनुपालन सुनिश्चित करायेंगे। पथ का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, प्रशासनिक स्वीकृति की राशि, संवेदक द्वारा उद्धृत दर, परकर्मित दर, Bid Capacity आदि का मिलान कर ही कार्य आवंटन आदेश निर्गत करेंगे। कार्यपालक अभियंता कार्य आवंटन/LOA निर्गत करने से पूर्व मिलान कर लेंगे कि परिमाण विपत्र की राशि प्रशासनिक अनुमोदन की राशि के अनुज्ञेय सीमा के अन्दर है। यदि अनुज्ञेय सीमा से अधिक हो तो एकरारनामा के पूर्व पुनरीक्षित प्रशासनिक अनुमोदन प्राप्त कर लिया जाय।
 - कार्यदेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु मासिक कार्य प्रोग्राम हस्ताक्षरित कराकर प्राप्त कर लेंगे जो की एकरारनामा का भाग होगा।
 - अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुसार निर्धारित कार्य अवधि के अंदर पूरा की जायेगी।


Executive Engineer
RWO Works Division
Lakhisari