



21/12/23 29-12-23 सुबेश कुमार  
ए. रा. व. 513/2 MR-ए. रा. व. 513/2  
पुरानी बजार लखिसरई, भागलपुर जिला।  
उक्त 1000 रुपये, नए-पुराने  
कलकत्ता जिल्ला, भारत  
90-12-23

AT 658246

**OFFICE OF THE EXECUTIVE ENGINEER  
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI**

**AGREEMENT NO:- 54/MBD/2023-24**

This agreement, made the 30 December day of 2023 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and **Sri Subesh Kumar, Karyanand Nagar, Purani Bazar Lakhisari, Bihar.**

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road contract for the maintenance of road from MR-N/23-24/Lakhisarai/21 Package Under of Block in Suryagarha, Under M/R in Lakhisarai District and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 2,90,98,346.00 (Two Crore Ninety Lakh Ninety Eight Thousand Three Hundred Forty Six) only & five year Maintenance cost Rs. 74,06,801.00 (Seventy Four Lakh Six Thousand Eight Hundred One) only total cost Rs. 3,65,05,147.00 (Three Crore Sixty Five Lakh Five Thousand One Hundred Forty Seven) only.

उत्तर

Subesh Kumar  
30/12/23

30/12/23  
Executive Engineer  
RWD Works Division  
Lakhisarai  
30-12-23



		<u>issu Date</u>	<u>end Date</u>
FDA/C-	42202280677 ⇒ Amt ⇒ 8,60,000/-	23/08/23	23/08/25
BGA/C-	0296823BG0600008 Amt ⇒ 36,76,600	30/12/23	26/09/24

OFFICE OF THE EXECUTIVE ENGINEER  
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI  
**AGREEMENT NO:- 54/MBD/2023-24**

This agreement, made the 30 December day of 2023 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and **Sri Subesh Kumar, Karyanand Nagar, Purani Bazar Lakhisari, Bihar.**

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road contract for the maintenance of road from **MR-N/23-24/Lakhisarai/21 Package Under of Block in Suryagarha, Under M/R in Lakhisarai District** and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 2,90,98,346.00 (Two Crore Ninety Lakh Ninety Eight Thousand Three Hundred Forty Six) only & five year Maintenance cost Rs. 74,06,801.00 (Seventy Four Lakh Six Thousand Eight Hundred One) only total cost Rs. 3,65,05,147.00 (Three Crore Sixty Five Lakh Five Thousand One Hundred Forty Seven) only.

17/12/23

30/12/23

*[Signature]*  
30/12/23  
Executive Engineer  
RWD Works Division  
Lakhisarai

SI	Name of Road	Length (in km)	Const. Cost.	Maint. Cost.	Agree. Value
1	Kajra- Jalappa Asthan to Belaunja	3.000	110.99788	38.04279	149.04067
2	NH-80 to Shah tola via Chaundi Asthan Banhipur	0.825	45.94807	8.18376	54.13183
3	NH-80 to Nanhki tola Khawa	2.015	107.49618	19.73831	127.23449
4	Manikpur se Tinmohani	0.630	26.54133	8.10316	34.64448
	<b>Total</b>	<b>6.470</b>	<b>290.98346</b>	<b>74.06801</b>	<b>365.05147</b>

NOW THIS AGREEMENT WITNESSTH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to and they shall be deemed to from and be read and construed as part of this agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the Execution adcompletion of the works and the remedying the defects hear in Contract price or such other sum as may become payable under the provision of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz
  - 1 Latter of Acceptance
  - 2 Contractor's Bid
  - 3 Section VI -General Conditions
  - 4 Section VII- Particular Condition
  - 5 Section V - Technical Specification (General and Supplementary Technical Specification
  - 6 Appendix A - Drawings
  - 7 Section IV - Works Schedule
  - 8 Quality plan for output and performance based road contract as per clause A14.1 of the technical specifications
  - 9 Appendices of the contract
  - 10 Addenda issued during bid period
  - 11 Any other relevant documents listed in the particular conditions together with any post bid correspondence.

*[Handwritten signature]*

*[Handwritten signature]*  
30/12/23

*[Handwritten signature]*  
30/12/23  
Executive Engineer  
RWD Works Division  
Lakhisarai



OFFICE OF THE EXECUTIVE ENGINEER  
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

**AGREEMENT NO:- 54/MBD/2023-24**

**NAME OF WORK: - MR-N/23-24/Lakhisarai/21 Package Under of Block in  
Suryagarha, Under M/R in Lakhisarai District.**

**NAME OF AGENCY: -** Sri Subesh Kumar,  
Karyanand Nagar, Purani Bazar,  
Lakhisarai.

**Reference :-** Chief Engineer -2  
R.W.D Bihar, Patna  
Vide Letter No.- 4121 Date :- 06.12.2023

<b>AGREEMENT AMOUNT – Main work:-</b>	<b>2,90,98,346.00</b>
<b>Maintenance work:-</b>	<b>74,06,801.00</b>
<b>Total Amount: -</b>	<b>3,65,05,147.00</b>

**Performance Security: -** Deposited @ 5 % Next 5 % deducted from Bill

**Date of Agreement :-** 30.12.2023

**Date of Completion :-** 29.09.2024

**No. of Item of Work :-** As per B.O.Q ( Nos)

**Rate Quoted :-** 15.09% below (One five point f zero nine percent below)

  
Contractor Signature

  
30/12/23

  
Executive Engineer  
R.W.D. Works Division  
Lakhisarai  
30/12/23

Tender Inviting Authority: Engg-In Chief RWD Patna

VALIDATE

Name of Work: Construction of Road &amp; CD Works for Kajra-Jalappa Asthan To Belaunja in Suryagarha Block Under/ MR-305

PRINT

Contract No: Civil Works/

HELP

Bidder Name:		Excess (+)	%
--------------	--	------------	---

SCHEDULE OF WORKS							AMOUNT Rs. P
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate			
				Figure	Words		
1	CleB2:E28aring and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.60	Hect	75573.34	Rupees Seventy Five Thousand Five Hundred & Seventy Three and Paise Thirty Four Only		45344.00
2	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1780.50	Cum	262.74	Rupees Two Hundred & Sixty Two and Paise Seventy Four Only		467809.00
3	Granular Sub-base Gr - II with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	106.01	Cum	2736.46	Rupees Two Thousand Seven Hundred & Thirty Six and Paise Forty Six Only		290092.00
4	WBM Grading 2 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	74.30	Cum	3999.60	Rupees Three Thousand Nine Hundred & Ninety Nine and Paise Sixty Only		297170.00
5	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	191.42	Cum	3668.05	Rupees Three Thousand Six Hundred & Sixty Eight and Paise Five Only		702138.00
6	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	2552.27	Sqm	59.94	Rupees Fifty Nine and Paise Ninety Four Only		152983.00

Signature of Tenderer with seal

Executive Engineer  
RWD Works Division  
Lakhisarai



Bidder Name:				Excess ( + )			%
SCHEDULE OF WORKS							
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P	
				Figure	Words		
17	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (900 mm octagon stop board)	2.00	Each	8744.96	Rupees Eight Thousand Seven Hundred & Forty Four and Paise Ninety Six Only	17490.00	
18	Boundary Pillar/Guard Post :- Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC-25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	24.00	Each	798.12	Rupees Seven Hundred & Ninety Eight and Paise Twelve Only	19155.00	
19	Printing New Letters and Figures of any Shade :- Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	138.00	m height per	0.75	Rupees and Paise Seventy Five Only	102.00	
20	Planting of Trees and their Maintenance for one Year :- Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	115.00	Each	1288.76	Rupees One Thousand Two Hundred & Eighty Eight and Paise Seventy Six Only	148207.00	
21	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	460.00	Sqm	888.46	Rupees Eight Hundred & Eighty Six and Paise Forty Six Only	407772.00	
22	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Concrete Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	140.00	Sqm	994.60	Rupees Nine Hundred & Ninety Four and Paise Sixty Only	139244.00	

Executive Engineer  
RWD Works Division  
Lakhisarai

Signature of Tenderer with seal

E. Letter No. 1163 Dt. 15/7/23  
Construction Cost Rs. 13072414.50  
5 yrs. Maintenance Cost Rs. 4480366.61  
Total Cost Rs. 17552781.11  
BOQ Approved For Rs. 17552800 = 00  
(Rupees *one crore seventy five lakh*  
*fifty two thousand eight hundred only*)  
including 5 yrs Maintenance Vide  
sam no. 01 to 32

*[Signature]*  
Superintending Engineer  
Rural Works Department  
*[Signature]* Circle, Munger  
21/07/23

*[Signature]*

Tender Inviting Authority: Engg-in Chief RWD Patna

☒ VALIDATEName of Work: Construction of Road & CD Works for NH-80 To Shah Tola Via Chaudh Asthan Banshipur  
uryagarha Block Under MR-3054☐ PRINT

Contract No: Civil Works/

☐ HELPBidder  
Name:

Excess (+)

%

## SCHEDULE OF WORKS



Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. p
				Figure	Words	
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.17	Hect	75573.34	Rupees Seventy Five Thousand Five Hundred & Seventy Three and Paise Thirty Four Only	12847.00
2	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	321.75	Cum	262.74	Rupees Two Hundred & Sixty Two and Paise Seventy Four Only	84537.00
3	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	112.50	Cum	3658.05	Rupees Three Thousand Six Hundred & Sixty Eight and Paise Five Only	412656.00
4	Dry Lean Cement Concrete Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregates conforming to IS:383, the size of coarse aggregate not exceeding 25mm, aggregate cement ratio not to exceed 15:1 aggregate gradation after blending to be as per table 600-1 cement content not to be less than 150kg/cum optimum moisture content to be determined during trial length construction, concrete strength not be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing.	9.56	Cum	6977.26	Rupees Six Thousand Nine Hundred & Seventy Seven and Paise Twenty Six Only	66720.00

  
Executive Engineer  
RWD Works Division  
Lakhisarai

  
Signature of Tenderer with seal



W. E. Letter No. 1163 Dt. 15/7/23  
Construction Cost Rs. 5411279.95  
5 yrs. Maintenance Cost Rs. 963816.23  
Total Cost Rs. 6375196.18  
BOQ Approved For Rs. 6375200.00  
(Rupees Sixty three lakh seventy five  
thousand two hundred only)  
including 5 yrs Maintenance Vide  
item no. 01 to 17

  
Superintending Engineer  
Rural Works Department  
District Circle, Munger  
  
21/07/23

21/7/23

Tender Inviting Authority: Engg-In Chief RWD Patna

☒ VALIDATE

Name of Work: Construction of Road &amp; CD Works for NH-80 To Nanhki Tola Khawa in Suryagarha Block Under MR-3054

☐ PRINT

Contract No: Civil Works/

☐ HELPBidder  
Name:

Excess ( + )

%

## SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.40	Hect	75573.34	Rupees Seventy Five Thousand Five Hundred & Seventy Three and Paise Thirty Four Only	30229.00
2	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	302.25	Cum	262.74	Rupees Two Hundred & Sixty Two and Paise Seventy Four Only	79413.00
3	Granular Sub-base Gr - II with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	206.25	Cum	2658.30	Rupees Two Thousand Six Hundred & Fifty Eight and Paise Thirty Only	548274.00
#REF! 4	WBM Grading 3 - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	337.50	Cum	3409.54	Rupees Three Thousand Four Hundred & Nine and Paise Sixty Four Only	1150754.00
#REF! 5	Dry Lean Cement Concrete Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregates conforming to IS-383, the size of coarse aggregate not exceeding 25mm, aggregate cement ratio not to exceed 15:1 aggregate gradation after blending to be as per table 800-1 cement content not to be less than 150kg/cum optimum moisture content to be determined during trial length construction, concrete strength not be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing.	4.58	Cum	6815.36	Rupees Six Thousand Eight Hundred & Sixteen and Paise Thirty Six Only	31219.00

Signature of Tenderer with seal

*A92*  
 Executive Engineer  
 RWD Works Division  
 Lakhisarai



S. E. Letter No. 1088 Dt. 06-07-2023  
Construction Cost Rs. 12659694 = 0  
5 yrs. Maintenance Cost Rs. 2324616 = 0  
Total Cost Rs. 14984230 = 0  
BOG Approved For Rs. 14984200 = 0  
(Rupees one crore forty nine lakh  
eighty four thousand two hundred only)  
Including 5% Maintenance Vide  
Sanction No. 01 17

  
Superintending Engineer  
Rural Works Department  
Muzaffarpur Circle, Munger  
  
23/07/2023

23/7/2023

Tender Inviting Authority: Engg-in Chief RWD Patna

☒ VALIDATE

Name of Work: Construction of Road &amp; CD Works for Manikpur Se Timmohani In Suryagarha Block Under/ MR-3054

☐ PRINT

Contract No: Civil Works/

☐ HELPBidder  
Name:


Excess ( + )

%

## SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.25	Hect	75573.34	Rupees Seventy Five Thousand Five Hundred & Seventy Three and Paise Thirty Four Only	18893.00
2	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	453.00	Cum	262.74	Rupees Two Hundred & Sixty Two and Paise Seventy Four Only	119179.00
3	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	33.02	Cum	1979.21	Rupees One Thousand Nine Hundred & Seventy Nine and Paise Twenty One Only	65354.00
4	WBM Grading 2 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	19.84	Cum	4045.97	Rupees Four Thousand & Forty Five and Paise Ninety Seven Only	80272.00
5	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	27.87	Cum	3719.08	Rupees Three Thousand Seven Hundred & Nineteen and Paise Eight Only	103851.00
6	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	371.60	Sqm	59.84	Rupees Fifty Nine and Paise Eighty Four Only	22237.00

Signature of Tenderer with seal

  
Executive Engineer  
RWD Works Division  
Lakhisaraj



Inviting Authority: Engg-in Chief RWD Patna

Name of Work: Construction of Road & CD Works for Manikpur Se Timmohani in Suryagarha Block Under/ MR-3054

☒ VALIDATE

☐ PRINT

☐ HELP

Contract No: Civil Works/

Bidder Name: Excess (+) %

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
19	Planting of Trees and their Maintenance for one Year :- Planting of trees by the road side (Avenue trees) in 0.50 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/slugd manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	32.00	Each	1288.76	Rupees One Thousand Two Hundred & Eighty Eight and Paise Seventy Six Only	41240.00
20	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	126.00	Sqm	886.46	Rupees Eight Hundred & Eighty Six and Paise Forty Six Only	111694.00
21	(I) Providing and Fixing "Logo" of Maintenance Project :- Providing and fixing of typical informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	3.00	Each	11665.44	Rupees Eleven Thousand Six Hundred & Sixty Five and Paise Forty Four Only	34996.00
22	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	90.00	Cum	398.62	Rupees Three Hundred & Ninety Eight and Paise Sixty Two Only	35876.00
23	Providing M15 (PCC 1:2.5:5) as levelling course in foundation :- Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	9.20	Cum	6918.54	Rupees Six Thousand Nine Hundred & Eighteen and Paise Fifty Four Only	63651.00
24	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	48.96	Sqm	212.35	Rupees Two Hundred & Twelve and Paise Thirty Five Only	10397.00
25	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	7.20	Cum	6354.05	Rupees Six Thousand Three Hundred & Fifty Four and Paise Five Only	45749.00
26	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	48.96	Sqm	136.22	Rupees One Hundred & Thirty Six and Paise Twenty Two Only	6669.00


Signature of Tenderer with seal



  
Executive Engineer  
RWD Works Division

S. E. Letter No. 1163 Dt. 15/7/23  
Construction Cost Rs. 3125819.14  
5 yrs. Maintenance Cost Rs. 954322.12  
Total Cost Rs. 4080141.26  
EOQ Approved For Rs. 4080100.00  
(Rupees forty lakh eighty thousand  
one hundred only)  
Including 5 yrs Maintenance Vide  
Ser. no. 01 to 29

  
Superintending Engineer  
Rural Works Department  
Amraoti Circle, Munger  



मुख्य अभियंता-2 का कार्यालय  
ग्रामीण कार्य विभाग, पटना।

/पटना, दिनांक-

पत्रांक-  
प्रेषक,

ई० श्रीप्रकाश  
मुख्य अभियंता-2

सेवा में,

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, लखीसराय।

विषय : शीर्ष MR-3054 योजनान्तर्गत कार्य प्रमण्डल, लखीसराय के अधीन पैकेज संख्या-MR-N/23-24  
Lakhisarai/21 (Tender ID-127186) कार्य की निविदा की स्वीकृति के संबंध में।

महाशय,

विभागीय पत्रांक-मु0अ0-4(मु0)-निविदा-04-406 पार्ट-1/2023-6156 अनु0, दिनांक-05.12.2023 द्वारा संसूचित आदेश के अनुपालन में उपर्युक्त विषय के संबंध में बिहार लोक निर्माण संहिता के कडिका-163 के आलोक में इस कार्य को इसके योग्य एवं सफल निविदाकार Subesh Kumar (बीड आईडी-552485) को उनके द्वारा निविदित दर, जो परिमाण विपत्र की दर से 15.09 (पन्द्रह दशमलव शून्य नौ प्रतिशत) कम है, को स्वीकृत करते हुए सम्पूर्ण कार्य कुल 3,65,05,147/- (तीन करोड़ पैंसठ लाख पाँच हजार एक सौ सैंतालीस) रुपये मात्र की लागत पर आपकी अनुशंसा एवं कार्यहित में आवंटित किया जाता है।

2. निविदा की स्वीकृति सिर्फ इसी कार्य के लिए है, जो भविष्य में पूर्वाधारण नहीं होगा।
3. संवेदक के द्वारा एकरारनामा के लिए जमा की गई राशि एवं निविदा के साथ जमा किये गये संबंधित एन0एस0सी0 / Fixed Deposit/BG आदि का सत्यापन संबंधित डाकघर/बैंक से कराकर प्रमंडलीय कार्यालय में अभिलेखित किया जायेगा। कार्यपालक अभियंता, कार्य प्रमंडल, लखीसराय कार्यादेश निर्गत करने के पूर्व अग्रधन की राशि के सत्यापन से संबंधित कागजात अधोहस्ताक्षरी को उपलब्ध कराया जाना सुनिश्चित करेंगे।
4. एकरारनामा के पूर्व निविदा सूचना के अनुसार सभी वांछित कागजातों की अद्यतन स्वच्छ एवं सत्यापित प्रति निश्चित रूप से प्राप्त कर लिया जायेगा।
5. एकरारनामा से पूर्व कार्यपालक अभियंता यह सुनिश्चित कर लेंगे कि निविदाकार डिबार सूची/काली सूची या कार्य लंबित सूची में शामिल न हो।
6. कार्य में व्यवहृत सामग्रियों का दर प्राक्कलन में स्वीकृत लीड के आधार पर दिया गया है, कार्य कराते समय अगर इसमें कमी पाई जाती है तो उसके दर में सापेक्ष कमी कर दी जायेगी।
7. इस कार्य के संबंध में ग्रामीण कार्य विभाग, बिहार सरकार द्वारा निर्गत प्रशासनिक स्वीकृति एवं प्रावधिक स्वीकृति तथा निविदा आमंत्रण सूचना में उल्लेखित शर्त एकरारनामा का भाग होगा, जिसे विशेष शर्त में जोड़कर संवेदक के साथ एकरारनामा किया जायेगा।
8. अनुमोदित किये गये तुलनात्मक विवरणी के प्रत्येक बिन्दु की जाँच अपने स्तर से स्वयं कर लेंगे एवं त्रुटि पाये जाने की स्थिति में वस्तुस्थिति से तत्क्षण अधोहस्ताक्षरी को अवगत करायेंगे। त्रुटि के सुधारोपरान्त एकरारनामा की कार्रवाई की जायेगी।
9. एकरारनामा के समय प्रत्येक मद के भाषा की शुद्धता की जांच कार्यपालक अभियंता स्वयं कर लेंगे एवं यह सुनिश्चित करेंगे कि इसमें कोई त्रुटि न हो।
10. कार्यारम्भ के पूर्व कार्यपालक अभियंता कार्य स्थल के निरीक्षणोपरान्त स्थल की स्थिति एवं प्राक्कलन में किये गये उपबंध से पूरी तरह आश्वस्त हो लेंगे एवं प्रशासनिक स्वीकृति तथा प्रावधिक स्वीकृति के अग्रसारण प्रारूप में दिये गये निर्देश का अनुपालन सुनिश्चित करायेंगे। पथ का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, प्रशासनिक स्वीकृति की राशि, संवेदक द्वारा उद्धृत दर, परक्रमित दर, Bid Capacity आदि का मिलान कर ही कार्य आवंटन आदेश निर्गत करेंगे। कार्यपालक अभियंता कार्य आवंटन/LOA निर्गत करने से पूर्व मिलान कर लेंगे कि परिमाण विपत्र की राशि प्रशासनिक अनुमोदन की राशि के अनुज्ञेय सीमा के अन्दर है। यदि अनुज्ञेय सीमा से अधिक हो तो एकरारनामा के पूर्व पुनरीक्षित प्रशासनिक अनुमोदन प्राप्त कर लिया जाय।
11. कार्यादेश निर्गत करने से पहले संबंधित संवेदक से एकरारित अवधि के अन्दर कार्य समाप्त करने हेतु मासिक कार्य प्रोग्राम हस्ताक्षरित कराकर प्राप्त कर लेंगे जो की एकरारनामा का भाग होगा।

*[Signature]*

Executive Engineer  
RWD Works Division  
Lakhisarai

*[Signature]*  
30/12/23



12. अधीक्षण अभियंता एवं कार्यपालक अभियंता विशेष रूप से ध्यान देंगे कि कार्य मानक विशिष्टियों के अनुरूप निर्धारित कार्य अवधि के अंदर पूरा की जायेगी।
13. कार्य समाप्ति की अवधि निविदा आमंत्रण सूचना के अनुसार होगी।
14. इस कार्य का व्यय शीर्ष MR-3054 योजनान्तर्गत से मिलने वाले राशि अन्तर्गत उपबंधित राशि से विकलित होगा।
15. कार्य का प्रगति प्रतिवेदन प्रत्येक महीने की सातवीं तारीख तक निश्चित रूप से इस कार्यालय को समर्पित की जाय।
16. सभी निविदा कागजात एवं तुलनात्मक विवरणी की मूल प्रति आवश्यक कार्रवाई हेतु लौटाई जाती है। आप निविदा कागजातों एवं तुलनात्मक विवरणी के जांचोपरान्त आप आवश्यक निदेशों को अपने स्तर से निर्गत करेंगे।
17. एकरारनामा से पहले निविदाताओं द्वारा दिये गये कागजात का सत्यापन उनके मूल कागजात से मिलान कर लेंगे। कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय तुलनात्मक विवरणी की एक अभिप्रमाणित प्रति अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर को अभिलेख हेतु उपलब्ध करा देंगे। निदेश दिया जाता है कि संवेदक से कार्य प्रोग्राम प्राप्त कर लेंगे तथा उनका कार्यक्षमता कुशलता एवं पूर्व से आवंटित कार्यों की प्रगति से संतुष्ट हो लें।
18. इस निविदा की राशि में अगर कोई अंतर होता है तो इसकी सूचना तुरन्त इस कार्यालय को दी जाय।
19. कार्यपालक अभियंता, एकरारनामा करने के पूर्व संवेदक का निबंधन संख्या, पूर्ण पता एवं दूरभाष संख्या कार्यादेश में अंकित करेंगे तथा इस कार्यालय को सूचित करेंगे।
20. परिमाण विपत्र की दर से कम दर उद्धृत करने वाले संवेदक से विभाग द्वारा पूर्व में निर्गत दिशा निदेश के आलोक में अतिरिक्त वांछित परफॉर्मंस सिक्यूरिटी की राशि जमा कराना सुनिश्चित करेंगे।
21. किसी भी परिस्थिति में निजी जमीन पर निर्माण नहीं कराया जाय।
22. प्रत्येक 15 दिनों पर संवेदक से स्वहस्ताक्षरित विपत्र प्राप्त कर स्थल से मिलान कर मापी पुस्तिका में मापी दर्ज कर भुगतान सुनिश्चित करेंगे।
23. कार्यपालक अभियंता कार्यावंटन आदेश प्राप्त होते ही संवेदक को अविलंब LOA (Letter of Acceptance) निर्गत करेंगे एवं MBD की ITB की कंडिका 34.1 में निहित प्रावधान के आलोक में निर्धारित 21 दिनों के अन्दर एकरारनामा की कार्रवाई सुनिश्चित करेंगे। विशेष परिस्थिति में उक्त निर्धारित अवधि के पश्चात् एकरारनामा करने हेतु Proper Justification उचित माध्यम से समर्पित करेंगे एवं अधोहस्ताक्षरी के अनुमति के उपरान्त ही एकरारनामा करेंगे।
24. विभागीय पत्रांक-मु0अ0-4 (मु0) विविध-23-291/2014-131, दिनांक 13.12.2019 के आलोक में पत्र प्राप्ति के 24 घंटे के भीतर Letter of Acceptance (LOA) संबंधित संवेदक को निर्गत करेंगे।

कृपया पत्र प्राप्ति की सूचना देंगे।

अनु0-यथा उपर्युक्त।

विश्वासभाजन

ह0/-

मुख्य अभियंता-2

झापांक- 4121 /

/पटना, दिनांक- 06.12.23/23

प्रतिलिपि :

1. अभियंता प्रमुख, ग्रामीण कार्य विभाग, पटना को सूचनार्थ समर्पित।
2. अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।
3. सहायक आई0टी0 मैनेजर को सूचनार्थ एवं संबंधित अधीक्षण अभियंता/कार्यपालक अभियंता के ई-मेल आई0डी0 पर अपलोड करने हेतु प्रेषित।

मुख्य अभियंता-2

अधीक्षण

Rakshin  
30.12.23



**Govt. of Bihar**  
**Rural Works Department**  
Office of the Engineer-in-Chief, Rural Works Department, Bihar  
Vishweshwaraiya Bhawan, 5<sup>th</sup> Floor, Rural Works Department, Bailey Road, Patna, Bihar -800015  
**(बिहार ग्रामीण पथ अनुरक्षण नीति, 2018)**

Notice Inviting Tender for Rural Roads Maintenance based on Output and performance based Contract through e-procurement mode on Model Bidding Document (MBD).

**(Notice Inviting Tender No. - MR-3054-14/2023-24)**

- |   |  |
|---|--|
| 1. Designation and Address of the Advertiser  | : Office of Engineer-in-Chief, Rural Works Department, Bihar, Patna  |
| 2. Date of Issue of Notice Inviting Tender  | : 24.07.2023   |
| 3. Period for downloading of Tender documents   | : From 16.08.2023 (9:00) to 30.08.2023 up to 15:00 hrs. From website- <a href="http://pingsytenderbih.gov.in">http://pingsytenderbih.gov.in</a>        |
| 4. Date, Time & Place of Pre- Bid Meeting   | : Date 22.08.2023 time 15:00 hrs.<br>Place O/o Concerned Superintending Engineer   |
| 5. Last Date & Time for uploading tender Document by bidder   | : Date 30.08.2023 up to: 15:00 hrs.<br><a href="http://pingsytenderbih.gov.in">http://pingsytenderbih.gov.in</a>                                       |
| 6. Date, time for online opening of Technical bid   | : Date 30.08.2023 up to Time: 15:30 hrs.   |
| 7. Last date, time and place for submission of Original instrument of EMD, Cost of BOQ, Bank credit facility certificate and an Affidavit regarding correctness of Information provided with bid document | : Till 15:00 hrs on 30.08.2023<br>: Place- O/o-concerned<br>(i) Executive Engineer<br>Or<br>(ii) Superintending Engineer<br>Or<br>(iii) Chief Engineer |
| 8. The Engineer in chief, Rural Works Department on behalf of Governor of Bihar invites bids from the eligible bidders for the works detailed below.  |  |

**Project Scope & Duration:**

- I. To undertake, Initial Rectification Works including surface renewal and Ordinary Maintenance for a period of 5 years after completion of initial rectification works including surface renewal Works on selected roads as described in para 9.
- II. The Initial Rectification may include improvement and pavement strengthening and widening work , road safety measures and tree plantation in flanks as per contract document. The initial rectification including surface renewal of works will be done in such a way that after rectification it complies all technical standards and safety measures to bring the road under prescribed service level. The time of completion for initial rectification works including surface renewal shall be 09 months from the date of issue of LOA.
- III. After completion of initial rectification with surface renewal the selected roads will be maintained for next five years to comply the prescribed service level, to maintain road for traffic worthy. The ordinary maintenance work will also include cross drainage works, minor works on bridges and road maintenance within road side maintenance within selected roads.
- IV. The Ordinary Maintenance works will be carried out under performance based road maintenance on a lump sum basis paid Quarterly.
- V. Initial Rectification Works including surface renewal will be paid on measured quantity to the value of contract.
- VI. There is a requirement for specialised maintenance equipment and the contract obligation is for continuous input over the contract period i.e. initial rectification including surface renewal and ordinary maintenance period.
- VII. To undertake emergent repair due to natural calamities like flood, earthquake, etc
- VIII. Bidders are strongly encouraged to download the bidding documents prior to the pre-bid meeting in order for bidders to have a good understanding of the scope of work under this contract for discussion and clarification at the pre-bid meeting. Bidders are also advised to visit each road, be acquainted with the physical condition of road, satisfy themselves and then participate in the bid.

9. Details of Works:-