

# RURAL WORK DEPARTMENT


## GOVERNMENT OF BIHAR

1. NAME OF OFFICE:- OFFICE OF EXECUTIVE ENGINEER  
Rural Works Department Works Division Baisi
2. NAME OF WORK:- MMGSY - NDB - AWSESH - 337 - BAISE  
Kabristan to Kumbharwa.
3. NAME OF AGENCY :- Rameez Raza
4. ADDRESS
5. AGREEMENT NO. :- 09SBD/2023-24
6. TENDER VALUE :-
7. RATE APPROVED :-
8. CONSTRUCTION COST :-
9. MAINTENANCE COST :-
10. AGREEMENT VALUE :-
11. DATE OF COMMENCEMENT:-
12. DATE OF COMPLETION :-

  
Signature of Contractor

EXECUTIVE ENGINEER  
Rural Works Department  
Works Division Baisi





बिहार BIHAR

EERWD WORKS DIVISION Baisi Purnea

AV 808317

1000x1 = 1000/-

Ag. Shamim Ahmad Ansari  
29-2-24

Md. Shamim Ahmad Ansari  
S. V. BAISI, PURNEA  
L.No.-230/95

पूर्णियाँ कोषगार बज्रगृह  
निर्गत तिथि:-

03 JAN 2024

कोषगार पदाधिकारी

09 SBD /2023-24  
**MMGSY(NDB) AWSESH  
AGREEMENT**

This agreement made on the 13<sup>th</sup> March of 2024  
between concerned **Executive Engineer R.W.D Works Division ,Baisi (Purnea)**  
[name an address of Employer] (hereinafter called "the Employer") of the one part] **Rameez  
Raza(BID ID:-562152),At Kohbara Adhang Jalalgarh,Purnea Bihar Pin  
854330, Email id:- raza.rameez3@gmail.com address of Contractor](hereinafter called  
"the Contractor") of the other part]**

Whereas the employer is desirous that contractor  
execute the **MMGSY-NDB(AWSESH)-BRRP2-337-Baisi [Kabristan to  
Kumaharwa ] {Tender ID:- 128899}** [name and identification number of contract] (here  
in after the work)& the employer has accepted the Bid by the Contractor with for the  
execution and completion of such Work's and Routine maintenance of work for 5  
years of the contract Price remedying of any defects therein at a cost of Rupees  
1,38,74,812.00. (One Crore Thirty Eight Lakhs Seventy Four Thousand Eight Hundred  
Twelve Only).

Rameez Raza

Executive Engineer  
R W D Works Division  
Baisi





बिहार सरकार

**NOW THIS AGREEMENT WITNESSETH AS FOLLOWS:-**

1. In this Agreement , words and expression shall have the same meanings as Are respectively assigned to them in the conditions of contract hereinafter Referred to and they shall be deemed to form and be read and construed As part of this Agreement.
2. In Consideration of the payments to be made by the Employer to the contractor as herein-after mentioned, the contractor hereby covenants with the Employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the Provision of the contract and Under taking routing maintenance for **five years** .
3. The Employer hereby covenants to pay the contractor in consideration of the Execution and completion of the works and the remedying the defect wherein the contract price or such other sum as may become payable under the provisions of the contract at the time and in the manner prescribed by the contract.

**4. The Following documents shall be deemed from and be ready and construed as part of This agreement Viz .**

- (I) Letter of acceptance.
- (II) Notice to proceed with the works.
- (III) Contractor's Date
- (IV) Contract Date.
- (V) Special conditions of contract and General conditions of contract.
- (VI) Drawings.
- (VII) Specifications.
- (VIII) Bill of Quantity and
- (IX) Any other documents listed in the contract Data as forming part of the contract In witness whereof the parties there to have caused this Agreement executed the day and year first before written .

5. Deduction : I.T , G.S.T, Royalty & all other deduction will be deducted from each bill as applicable

In witnessed where of the parties there to have caused this Agreement to be executed the day and year first before written.

The common seal of contractor was hereunto affixed in the presence of :-

Signed , Sealed and delivered by the said.....

In the Presence of :

**Binding signature of Employer .....**

Binding signature of Contractor Rameez Raza.....

13/12/24

**EXECUTIVE ENGINEER  
RURAL WORK DEPARTMENT  
WORK DIVISION BAYSI**

## STATE BANK OF INDIA



FD Number  
42387839328

KASBA (DIST. PURNEA)(02960)

e-Special Term Deposit Advice

(In lieu of term deposit receipt)

Date : 28-Oct-2023

Dear Sir/Madam

We have pleasure in confirming details of the following amount held in deposit with us. Please quote the Account Number in all correspondence. Thank you for Banking with us.

Name

Customer Number

Mr. RAMEEZ RAZA

85468616877

Debit Account Number :

Mode of operation : Single

Scheme : STD-PUB IND UNI 181D-10YRS

Nominee(s) : NA

Maturity Instruction : Auto Renewal

e-TDR/e-STD Account No.	Tenure	Fixed Rate Interest @	Principal Amt	Value Date	Maturity Date	Maturity Value
42387839328	3 Year(s) 0 Month(s) 0 Day(s)	6.5%	INR280000.00	27/10/2023	27/10/2026	INR339754.00

Terms and Conditions for e-TDR / e-STD

Pledged to EERWD Works division Baisi.

Terms and Conditions for Fixed Deposit

- The mode of Operation of the Fixed Deposit account created in INR would be single only and would be generated in the name that would be same as that of the CIF of the user making the request.
- The interest proceeds on the FD will be credited by default to the account from which the FD was funded.
- The maturity proceeds of principal and interest in case of FD will be credited by default to the account from which the FD was funded.
- In case of pre-mature closure, depositor will be able to select the account from where she wishes the pre-mature closure proceeds to be credited
- Bank will deduct the income tax as per the law applicable and in case no tax is to be deducted, form 15H/G has to be submitted by the depositor to the branch just after opening the FD and at the beginning of the Financial Year in the subsequent Financial Years. The facility for online submission of form 15 G/H is also available in the INB platform (onlinesbi.com) of the bank.
- FD with additional rate of interest for senior citizens will be issued if option for "Senior Citizen" is selected by the customer and age of customer is 60 yrs. or above, on the date of creating the fixed deposit, as per date of birth recorded with the Bank. The minimum days and minimum amount applicable for additional rate of interest for senior citizen will be as per Bank's policy.
- If you choose the Senior Citizen option, then you must ensure that your age as on the date of making the deposit is 60 years or more. If at any time the Bank discovers that you did not qualify for the Senior Citizen benefit, the Bank reserves the right to recover from you any additional amount of interest that the Bank might have paid to you and take any other action as permitted by law.
- In case of joint accounts, the Senior Citizen benefit can be availed only if the first account holder qualifies for this benefit.
- FD will be disposed of according to the Maturity Instruction given at the time of opening the deposit. In case of auto renewal, the deposit will be renewed for the same duration for which it was originally kept, at the rate of interest prevailing on the date of renewal for that duration. If auto renewal instructions are given, the instructions will continue to be executed till terminated by the account holder.
- As per section 206AA introduced by Finance (No. 2) Act, 2009 effective April 01, 2010, every person who receives income on which TDS is deductible shall furnish his PAN, failing which TDS shall be deducted at the rate of 20% in case of Domestic deposits and 30.90% in case of NRO deposits.
- 11 Additionally, in the absence of PAN, Form 15G/H and other exemption certificates will be invalid even if

Rameez Raza

28/10/2023

Executive Engineer  
R.W.D. Works Division  
Baisi





**STATE BANK OF INDIA**  
KASBA (DIST. PURNEA) ( 02960 )

Special Term Deposit Advice  
(In lieu of Special Term Deposit Receipt)

Date: 02/03/2024

Dear Sir/Madam,

We have pleasure in confirming your deposit held with us, the details of which are as shown below.

Your FD account number is 42755247551 . Please quote this in all correspondences.

Thank you for banking with SBI.

**A. Customer Name - RAMEEZ RAZA**

CIF Number  
85468616877

Mode of Operation  
**SINGLE**

Scheme  
**STD-PUB IND UNI 181D-10YRS**

Maturity Instruction  
**Auto Renewal**

Frequency of Interest Payment  
**At Maturity**

Credit Interest & Maturity Proceeds to (A/c)  
**37718126517**

Nomination  
**Registered**

Nominee(s), if any  
**MD RAHBER ALAM**

TDR/STDR A/c No.	Tenure	Interest Rate	Principal Amt.	Value Date	Maturity Date	Maturity Value
42755247551	03 Year(s), 0 Month(s), 0 Days(s)	6.75 %	INR 105000	02/03/2024	02/03/2027	INR 128351

**B. Terms & Conditions for TDR/STDR**

1. Please inform us of any change in your Resident/Non-Resident status as and when such change takes place. The status declaration on the account opening form shall remain in force until such time as a change is advised to us.
2. In case of premature payment the deposit represented by this advice shall be subject to penalty provisions at the rates decided by the bank from time to time.
3. Bank will deduct Income Tax as per the law applicable and in case no tax is to be deducted, Form 15G/H has to be submitted by the depositor to the branch just after opening the FD and at the beginning of the Financial Year in the subsequent Financial Years. The facility for online submission of Form 15G/H is also available in the INB platform (onlinesbi.com) of the bank.
4. FD with additional rate of interest for senior citizens will be issued if option for "Senior Citizen" is given by the customer and age of customer is 60 Yrs or above, on the date of creating the fixed deposit, as per date of birth recorded with the Bank. The minimum days and minimum amount applicable for additional rate of interest for senior citizen will be as per Bank's policy.
5. FD will be disposed of according to the Maturity Instruction given at the time of opening the deposit. In case of auto renewal, the deposit will be renewed for the same duration for which it was originally kept, at the rate of interest prevailing on the date of renewal for that duration. If auto renewal instruction are given, the instructions will continue to be executed till terminated by the account holder.
6. As per section 206AA introduced by Finance (No. 2) Act, 2009 effective April 01, 2010, every person who receives income on which TDS is deductible shall furnish his PAN, failing which TDS shall be deducted at the rate of 20% in case of Domestic deposits and 30.90% in case of NRO deposits.
7. Additionally, in the absence of PAN, Form 15G/H and other exemption certificates will be invalid even if submitted & penal TDS will be applicable. Kindly visit your SBI branch with your PAN card (original & copy) to get the same updated on the bank records.

*Rameez Raza*

*13/3/24*  
**Executive Engineer**  
**R W D Works Division**  
**Baisi**

440



KASBA (DIST. PURNEA) 4 | Saka Phalguna 15 1945 | 05/03/2024 | Welcome ARJUN G  
(2960) TAPEY (5240743)

INPUT REFERENCE

Account Number:	4275524755-1	Product:	STD-PUB IND UNI 181D-1
Home Branch:	02960	User Codes:	0.....10
District:	0	Rel Manager:	0
Account Name:	Mr. RAMEEZ RAZA		
Customer Name:	S/O MD RAHBAR ALAM		
Door/FlatNo;Building/Society:	VILL- KOHBARA P O-ADANG		
Street/Road Name/Block:	VIA- KASBA DIST- PURNEA		
Locality/Village/Tehsil:	Purnia		
District:	854330		
Open Dt:	02/03/2024	Cr Int Rate:	6.7500
Balance:	105000.00 CR	Od Limit:	0
Unclear:	0	Hold Value:	105000.00
Cls Int:	0	Cr Int Incr:	19.25951
Cls Tax:	0	Cr Int Proj:	23351.25600
Od Int:	0	Int Avail:	57.77853 CR
Avl Bal:	0	Matched Rate:	0
Comp Freq:	3A	Comp Amt:	0
Comp SOP Dt:	02/03/2024	Comp EOP Dt:	01/06/2024

Int Type:	0
Status:	OPEN
Mail Ind:	1
Account Maintained At:	
Int Paid 1:	0
Int Paid 2:	0
Int Paid 3:	0
Int Paid 4:	0
Int Paid 5:	0
Dr Int Rate:	0
Od Exp:	99/99/9999
Term Receipt No :	
Int From:	02/03/2024
Int To:	01/03/2027
Last Txn:	02/03/2024
LastAcc TypeChange:	
Int.Monthly Basis	Y
Renewal Date:	

Type	Post-Dt	Jrnl.No.	Value-Dt	Txn-Amount	Curr-Balance	Chq-No.	Txn-
31	05/03/24	309351490	05/03/24	105000.00	000000000	22-PLEDGE LNO 460	9093 2920

**MUKHYA MANTRI GRAM SAMPARK YOJNA (MMGSY)  
NDB (AWSESH) TRANCHE -I**

**BILL OF QUANTITIES (BOQ) - CONSTRUCTION**

PRICE OF WORK

Name of Road :	Kabristan To Kumharwa		District	Purnea	
Block :	Amaur				
Length :	1.100 km				
Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Providing & Fixing of Working benchmark/Reference Pillars 01 nos. per km & 04 Nos. of reference pillars required for 1 Km. as per drawings given and direction of E/I				
	Benchmark Pillars 01 nos. per km	No	2.00	5376.44	10752.88
	Reference Pillars 04 nos. per km	No	4.00	2503.74	10014.96
2	<b>Clearing and Grubbing Road Land</b> Cleaning and Grubbing Road Land ( By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I ( By Manual Means) <del>In area of non-thorny jungle</del>	Hect.	0.77	75573.34	58191.47
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	Cum	388.03	261.09	101310.75
4	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100 m as per Technical Specification Clause 301.5	Cum	1070.39	177.64	190144.08
5	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m & 100 m as per Technical Specification Clause 303.1. (Including Royalty & Labour Cess).	Cum	2718.96	264.63	719518.38

*Am*

Executive Engineer  
R W D Works Division  
Baisi

*Rameez Raja*



Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
6	<b>Granular Sub-base with Well Graded Material (Table 400.1) :-</b> Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 (For Grading I Material)	Cum	797.90	3882.76	3098054.20
7	<b>WBM Grading 3 :-</b> Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405	Cum	315.56	5491.30	1732834.63
8	<b>Prime Coat (Low Porosity) :-</b> Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 502	Sqm	3251.25	58.45	190035.56
9	<b>Tack Coat:-</b> Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	Sqm	3251.25	20.02	65090.03
10	<b>Mix Seal Surfacing Type B</b> Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509.	Sqm	3251.25	282.78	919388.48

*Dr*

*Rameez Raza*

Executive Engineer  
R W L Works Division  
Baisi



Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
11	<b>Cement Concrete Pavement M30</b> Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and	Cum	153.00	9372.83	1434042.99
12	<b>Hard Shouldering</b> :- Laying brick soling layer on prepared sub-grade with brick on end edging according to lines, graded and cross-section shown on the drawing filling joints with sand and earth, spreading 25 mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kN as per Technical Specification Clause 412	sqm	125.00	540.29	67536.25
13	<b>TRAFFIC SIGNS, MARKINGS &amp; OTHER ROAD APPURTENANCES</b>				
	<b>Kilometre Stone</b> :- Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703				
ii	Ordinary Kilometer Stone (Precast)	Each	3.00	3204.21	9612.63
iii	200 m stone (precast)	Each	4.00	872.09	3488.36

*Am*

*Rameez Raza*

Executive Engineer  
R W T W. Division  
Baisi

Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
14	<b>(I) Providing and Fixing 'Logo' of MMGSY Project</b> :- Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 16 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tube posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and 1704.	Each	4.00	11907.66	47630.64
15	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	per cm height per letter	88.00	0.75	66.00
16	<b>Boundry Pillar/ Guard Post</b> Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	No	16.00	789.37	12629.92
17	<b>Retro-reflectorised Traffic Signs</b> :- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801				
	600 mm equilateral & triangle	Each	6.00	4464.60	26787.60
	600 mm circular	Each	4.00	5914.22	23656.88
	600 mm x 450 mm rectangular	Each	2.00	5765.83	11531.66
	900 mm side octagon, OR	Each	2.00	10354.38	20708.76
	900 mm x 300 mm, Hazard Marker	Each	8.00	4533.03	36264.24

*Signature*

*Rameez Raza*

Executive Engineer  
R W L Works Division  
Baisi



Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
18	<u>Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface</u> :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	Sqm	170.00	886.46	150698.20
19	<u>Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Concrete Surface</u> :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	Sqm	50.00	1005.35	50267.50
20	<u>Planting of tree &amp; there maintainance for one Year</u> :- Planting of tree by the road side (Avenue Tree) in 0.6 m dia holes, 1 m deep dug in the Ground, Mixing the soil with decayed farm yard/ slug manure, planting the saplings back filling the trench, watering, fixing the tree guard & maintain the Plant for One Year.	No.	85.00	1288.76	109544.60
21	<u>Cable Duct Across the Road</u> :- Providing and laying of a reinforced cement concrete pipe duct, 300 mm dia, across the road (new construction), extending from drain to drain in cuts and toe of slope to toe of slope in fills, constructing head walls at both ends, providing a minimum fill of granular material over top and sides of RCC pipe as per IRC:98:1997, bedded on a 0.3 m thick layer of granular material free of rock pieces, outer to outer distance of pipe at least half dia of pipe subject to minimum 450 mm in case of double and triple row ducts, joints to be made leak proof, invert level of duct to be above higher than ground level to prevent entry of water and dirt, all as per IRC: 98 - 1997 and approved drawings.	Rm	20.00	1034.07	20681.40
	<u>Hume Pipe Culvert</u>				
22	<u>Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104</u>	Cum	29.80	427.09	12727.28
23	<u>Providing M15 (PCC 1:2.5:5) as levelling course in foundation</u> :- Providing PCC M 15 (1:2.5:5) concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	Cum	4.60	8058.24	37067.90
24	<u>Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 ( M20 )</u>	Cum	33.74	9157.18	308963.25

*du*

*Ramsey Raja*

Executive Engineer  
R W L Works Division  
Baisi

Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
25	Providing and laying RCC pipe NP-3 for culverts on first class bedding of PCC M10 material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling concrete and masonry works in head walls and parapets as per clause 1106 (1000 mm dia)	RM	7.50	7713.11	57848.33
26	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	Sqm	20.64	137.83	2844.81
<b>Box Culvert</b>					
27	Earth work in excavation for foundation of structures upto 3.0 m depth as per drawing and technical specification clause 1104	Cum	111.71	427.09	47710.22
28	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15 Grade	Cum	7.92	8058.24	63821.26
29	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-20 Grade	Cum	33.40	8827.08	294824.47
30	Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202	MT	0.16	80140.33	12822.45
<b>Sub Structure</b>					
31	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 PCC M-20 Grade	Cum	16.25	9157.18	148804.18
32	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	no	36.00	158.11	5691.96
33	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 RCC M-25 Grade	Cum	10.02	9893.81	99135.98
34	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	mt	0.85	80363.86	68309.28
35	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (With Sandy Materials)	Cum	34.29	996.40	34166.56

*Signature*

*Rameez Raza*

Executive Engineer  
R W L Works Division  
Baisi



Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
36	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8	Cum	19.82	4419.95	87603.41
	<b>Superstructure</b>				
37	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 RCC M-30 Grade	Cum	4.13	10744.75	44375.82
38	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202	mt	0.35	81995.51	28698.43
39	Parapet Construction Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 (M20)	Cum	2.51	9157.18	22984.52
40	Painting on Parapet Wall (Black & White Strips) Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	sqm	24.79	137.83	3416.81
41	Drainage spouts complete as per drawing and technical specifications Clause 1209	no	4.00	711.29	2845.16
				<b>Total =</b>	<b>10505145.13</b>
				GST @ 18%	<b>1890926.12</b>
				Labour cess @ 1 %	<b>105051.45</b>
				Seigniorage Fee @ 10%	<b>147995.59</b>
				<b>Total Construction Cost (A) =</b>	<b>12649118.29</b>

*Am*

*Rameez Raza*

Executive Engineer  
R W & Works Division  
Baisi

Sl. No.	Description of Items	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
42	1st Year Maintenance cost	Year	1	50448.00	50448.00
43	2nd Year Maintenance cost	Year	1	155954.00	155954.00
44	3rd Year Maintenance cost	Year	1	394422.00	394422.00
45	4th Year Maintenance cost	Year	1	203079.00	203079.00
46	5th Year Maintenance cost	Year	1	233360.00	233360.00
				<b>Total</b>	<b>1037263.00</b>
				GST @ 18%	<b>186707.34</b>
				Labour cess @ 1 %	<b>10372.63</b>
				Seigniorage Fee @ 10%	<b>5239.84</b>
				<b>Total Maintenance cost (B) =</b>	<b>1239582.81</b>
				<b>Grand Total Cost (A+B)</b>	<b>1388701.10</b>

Say

1388701.10

16/10/23  
SE Baisi

B.O.G. approved for amount Rs 1,38,88,701.00 (Rupees one crore thirty eight lac eighty eight thousand seven hundred & one) only.

अधीक्षण अभियंता  
ग्रामीण कार्य विभाग  
कार्य अंचल, पूर्णिया

17/10/23

Rameez Baisi

Executive Engineer  
R W L Works Division  
Baisi



कार्यपालक अभियंता का कार्यालय,  
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बायसी

बायसी, दिनांक 16/10/23

पत्रांक 1516 /

प्रेषक,

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, बायसी।

सेवा में,

अधीक्षक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य अंचल, पूर्णिया।

विषय :-

शीर्ष MMGSY-NDB (AWSESH) योजनान्तर्गत स्वीकृत 01 (एक) अदद पथ का  
परिमाण विपत्र समर्पित करने के संबंध में।

महाशय,

उपर्युक्त विषयक के संबंध में कहना है कि विषयांकित शीर्ष योजनान्तर्गत Kabristan  
To Kumharwa पथ का परिमाण विपत्र अनुमोदन हेतु समर्पित की जाती है।

SL NO.	Name of Road	Length (in k.m)	Amount (Rs)
1	Kabristan To Kumharwa	1.100	13888701

अनु०-दो प्रति में।

विश्वासभाजन

*[Signature]*  
16/10/23

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, बायसी।

Executive Engineer  
R W L Works Division  
Baisi

*[Signature]*

बिहार सरकार  
अधीक्षण अभियंता का कार्यालय,  
ग्रामीण कार्य विभाग, कार्य अंचल, पूर्णियाँ।

पत्रांक 1214(345)

पूर्णियाँ/दिनांक 17/10/2023

प्रेषक,

अधीक्षण अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य अंचल, पूर्णियाँ।

सेवा में,

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल, बायसी।

विषय :- MMGSY (NDB) Awasesh योजनान्तर्गत पथ के BOQ अनुमोदन के संबंध में।

प्रसंग :- आपका पत्रांक 1516 (अनु0) दिनांक 16.10.23

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र द्वारा MMGSY (NDB) Awasesh योजनान्तर्गत निम्नलिखित पथों का BOQ अनुमोदनोपरान्त आवश्यक कार्रवाई हेतु वापस की जाती है।

क्र० सं०	पथ का नाम	लम्बाई (कि०मी०)	राशि (लाख में)
1	Kabristan to Kumharwa	1.100	13888701

अनु० :- यथोक्त।

विश्वासभाजन

अधीक्षण अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य अंचल, पूर्णियाँ।

17/10/23

Rameez Raza

Executive Engineer  
R W D Works Division  
Baisi



**Rural Works Department**  
**Notice Inviting Tender (No.-RWD/MMGSY(AWSESH)/JQ/ET/2023-24/15)**

The Government of Bihar has applied for a loan/credit through the Govt. of India (GoI), to the New Development Bank (NDB), for Bihar Rural Roads Project (Phase-II) (Mukhya Mantri Gram Sampark Yojana-AWSESH) and intends to apply the funds to cover eligible payments under the contracts for construction of works as detailed in the Table-1.

Engineer-in-Chief, Rural Works Department, on behalf of Governor of Bihar invites, **SBD based** Percentage rate tender in electronic tendering system under **Mukhya Mantri Gram Sampark Yojana-AWSESH** for each of the following works including their maintenance for five years from the eligible and approved Contractors registered with RWD/RCD/CPWD/MES Railways/Other State/Central Govt. departments.

Table-1									
Sl. No.	Package	Description of the Works (CONSTRUCTION AND MAINTENANCE OF ROADS (A) / BRIDGES (B))		Length (KM)	Construction Amount (In Lacs)	Maintenance Amount (In Lacs)	Total Amount (In Lacs)	Earnest Money Payable* (In Lacs)	Amount Payable to Works Division
		From	To						
1	2		3	4	5	6	7	8	9
1	MMGSY(AWSESH) -NDB-BRRP2-313- KATHAR	A 1	Part-A:- Katihar Danddhora Road Parjani Pul	Kurbani Bhitta	0.440	28.309	5.238	33.547	8.808
		B 1	Part-B:- Construction of HL RCC Bridge Span 2x14.50m Across Water Logging Area on Kurbani Bhitta at CH- 70m with Protection work & Approach Road=100m		30.26 m	402.147	4.702	406.849	
		Total		1	0.570	430.456	9.940	440.396	
2	MMGSY(AWSESH) -NDB-BRRP2-314- BANKA-1	A 1	Swasthya Upkendra Rajapur	Paswan Tola Rajapur	0.200	22.274	1.443	23.717	2.761
		A 2	English More Shambhuganj RCD Road	Paswan Tola	0.300	29.980	2.001	31.981	
		A 3	Salpur Katoria Road	Balua	0.200	23.035	1.443	24.478	
		A 4	Salpur Katoria Road	Balua Harjan Tola	0.230	25.773	1.822	27.595	
		A 5	Amarpur Bhagalpur to Mahagama	Mahagama Tola	0.260	28.522	1.750	30.272	
Total		5			1.190	129.584	8.459	138.043	
3	MMGSY(AWSESH) -NDB-BRRP2-315- BANKA-1	A 1	Nahar Pul	Middle School	0.210	24.194	1.437	25.631	2.760
		A 2	Khajur Road	Anusuchit Jat Tola	0.175	19.101	1.477	20.578	
		A 3	Sahdhopur Road	Bathan	0.200	23.041	1.374	24.415	
		A 4	Narsandi Road	Chotara Bind Tola School	0.575	63.414	3.983	67.397	
Total		4			1.160	129.750	8.271	138.021	
4	MMGSY(AWSESH) -NDB-BRRP2-316-	A 1	Namua	Changari	1.315	143.962	15.287	159.249	7.053
									Banka-2

*Samir Ray*

Standard Bidding Document for MMGSY(AWSESH)

Accounting document for MMGSY(AWSESH)									
BANKA-2	A	Navoliya	Chachara Harpur Nahar Path	0.660	72.449	7.746	80.195		
	2	Mahadhi Path to Dharma Tola Path	Dharmatola Ghatwar Basti	0.970	103.080	10.103	113.183		
Total	3			2.945	319.491	33.136	352.627		
5	MMGSY(AWSESH) -NDB-BRRP2-317- BANKA-2	1	Dharpurath	Bagicha Munda Tola	2.250	249.187	25.079	274.266	Banka-2
	2	Kali Mandir	Dumaria	3.900	408.698	44.426	453.324	14.552	
Total	2			6.150	658.085	69.505	727.590		
6	MMGSY(AWSESH) -NDB-BRRP2-318- BANKA-2	1	Rampur Pabra	Dulhandih	2.350	226.597	30.337	256.934	
	2	Bhadiaha	Palampur	1.800	188.168	19.830	207.998		Banka-2
	3	Karjhousa Sathiyari Raod	Kubibel	1.075	115.412	10.518	125.930	13.461	
	4	Maruwaran	Mahadalit Tola	0.500	77.072	5.114	82.186		
Total	4			5.725	607.249	65.799	673.048		
7	MMGSY(AWSESH) -NDB-BRRP2-319- BANKA-2	1	Triukura Mor	Barakola	1.200	144.376	14.845	159.221	
	2	Tonpathar Belhar Katorya PWD Road	Tonpathar Das Tola	1.200	117.768	10.995	128.763	8.332	Banka-2
	3	Bagra Kalimandir	Brijapur	0.775	119.016	9.585	128.601		
Total	3			3.175	381.160	35.425	416.585		
8	MMGSY(AWSESH) -NDB-BRRP2-320- BANKA-2	1	Sanhaula Panjwara RCD Road (Ramkol, Anganwari Kendra)	Near Tunar Yadav and Gopal Yadav House	0.575	65.027	7.242	72.269	Banka-2
Total	1			0.575	65.027	7.242	72.269		
	A	Tetariya Jharkhand Border Road	Ostabazar	0.875	90.565	11.363	101.928		
	2	Chiraiya More Indodih Road	Nauwadhi	1.000	103.559	12.338	115.897		
9	MMGSY(AWSESH) -NDB-BRRP2-321- BANKA-2	3	Malbathan Jamdaha Road	Daddubagha t	1.000	100.035	11.268	111.303	Banka-2
	4	Jajpur Jamdaha RCD Road	Mahesmara	0.900	114.747	12.005	126.752		
	5	Jajpur Jamdaha RCD Road	Dabrakol	1.135	204.779	13.691	218.470		
Total	5			4.910	613.685	60.665	674.350	13.487	
10	MMGSY(AWSESH) -NDB-BRRP2-322- BANKA-2	1	Jajpur Jamdaha RCD Road	Thamhan	1.600	178.875	20.587	199.462	
	2	Jajpur Jamdaha RCD Road	Mohipur Kurawa	0.700	78.612	7.054	85.666	17.445	Banka-2



Standard Bidding Document for MMGSY(AWSESH)

11	MMGSY(AWSESH) -NDB-BRRP2-323- BANKA-2	A 3	Jaipur Jamdaha RCD Road	Mahadeva Varan	0.750	83.140	8.152	91.292	13.373	Banka-2
		A 4	Malbadhan Jamdaha Road	Barakola	1.230	125.088	14.881	139.969		
		A 5	Malbadhan Jamdaha Road	Jamua Tilha	0.600	65.115	6.478	71.613		
		A 6	Jaipur Jamdaha RCD Road	Dughband h Suman Tola	0.775	84.894	9.542	94.436		
		A 7	Malhorichak Hebhadhiya Road	Bengal Gaith	0.525	57.699	6.094	63.793		
		A 8	Logat Path Toamihar	Kosht Dole	0.700	119.763	6.232	125.995		
		8			6.880	793.206	79.020	872.226		
		Total								
12	MMGSY(AWSESH) -NDB-BRRP2-324- BANKA-2	A 1	Jakajore, Pipra More	Khakma Village	1.700	182.605	21.044	203.649	5.865	Banka-2
		A 2	Deoghar to Katoriya Road Om Nagar	Hima	1.425	226.751	19.137	245.888		
		A 3	Madhura More to Kenduwar Road	Khawa Aadiwashi Tola	1.850	197.370	21.735	219.105		
		3			4.975	606.726	61.916	668.642		
13	MMGSY(AWSESH) -NDB-BRRP2-325- GOGARI	A 1	BGP Dumka Road to Bhawanipur	Near Sheo Temple	1.050	96.619	11.944	108.563	6.964	Gogari
		A 2	BGP Dumka RCD Road	Kapildeo Yadav	0.850	90.392	9.440	99.832		
		A 3	Near House of Manoj Paswan	Near House of Manoj Mandal	0.720	79.927	4.944	84.871		
		3			2.620	266.938	26.328	293.266		
14	MMGSY(AWSESH) -NDB-BRRP2-326- GOGARI	A 1	RCD Road	Sipahi Singh Basa	2.800	336.536	11.657	348.193	7.881	Gogari
		1			2.800	336.536	11.657	348.193		
		Fango Gaon		Navoliya	3.200	374.897	19.155	394.052		
		1			3.200	374.897	19.155	394.052		
15	MMGSY(AWSESH) -NDB-BRRP2-327- SUPAUL	A 1	Dallu Mandal House	Dhanik Lal Mandal	0.369	40.863	3.570	44.433	11.521	Supaul
		A 2	Hanuman Mandir	Chakla PWD Sima	0.905	93.536	7.348	100.884		
		A 3	Chandani Chowk (Shiv Mandir) on Road No-6	Yadav Tola Dighiya	1.801	201.051	15.746	216.797		
		A 4	NIH-327A (Disko House)	PMGSY Road	1.009	113.186	8.533	121.719		
		A 5	Narayan Pandit House	Kedar Pandit	0.756	86.374	5.848	92.222		
16	MMGSY(AWSESH)	5			4.840	535.010	41.045	576.055	1.908	Supaul
		Total			0.795	87.653	7.739	95.392		

Rameez Raja

Standard Bidding Document for MMGSY(AWSESH)

17	MMGSY(AWSESH) -NDB-BRRP2-329-SUPAUL	A 1	Maha, Dikhan, Yadav House	I	Paswan Tola Ward 5	0.795	87.653	7.739	95.392	Supaul
		A 2	Majhari, Ayodhi Mandal Garden	NH-57	Majhari, Muslim Tola	0.805	91.860	6.823	98.683	16.532
		A 3	Rameshwar Pandit Land	Shop	Sathokhar Tola	1.567	177.722	14.205	191.927	134.917
		A 4	Koshi Bandh, Suraj Yadav	NH-57	Sathokhar Tola	1.099	126.182	8.735	134.917	203.760
		A 5	NH-57 Bhugat Mandal Land	Haripur Jilewi	Mandal House	1.676	190.947	12.813	203.760	97.936
		A 6	Ramkrelawa n Mandal	NH-57	Mandal House	0.824	90.819	7.117	97.936	5280
		Total	6	Veena to Balyas Mushari MMGSY Road	Sundarpur Kumhar Tola	6.831	769.783	56.806	826.589	Supaul
18	MMGSY(AWSESH) -NDB-BRRP2-330-SUPAUL	A 1	Sikandar Rajak (Kushwaha W-11)	I	Nepali Tola	0.900	101.940	7.492	109.432	Trivenig araj
		Total	1	Samda Bhavanpur Road	RWD Road Katia	0.900	101.940	7.492	109.432	Virpur
20	MMGSY(AWSESH) -NDB-BRRP2-332-VIRPUR	A 1	RWD Road	Rajpur Canal	Muslim Tola	2.235	266.138	17.389	283.527	13.193
		A 2	Rajpur Canal	RWD Road	Kamalpur	2.246	181.375	24.861	206.236	659.636
		Total	3	Rajpur Canal	Rajpur Canal	5.871	605.773	53.853	659.636	Virpur
21	MMGSY(AWSESH) -NDB-BRRP2-333-VIRPUR	A 1	Ratnapura	Rajpur Canal	Rajpur Canal	1.927	204.857	15.031	219.888	11.605
		A 2	Koshi Bandh 11 Km	Rajpur Canal	Rajpur Canal	2.134	246.703	15.416	262.119	16.147
		A 3	NH-106	Rajpur Canal	Rajpur Canal	0.803	92.812	5.427	98.239	278.244
		Total	3	Rajpur Canal	Rajpur Canal	4.864	544.372	35.874	580.246	Virpur
22	MMGSY(AWSESH) -NDB-BRRP2-334-VIRPUR	A 1	RWD Road	Rajpur Canal	Rajpur Canal	1.238	141.647	9.826	151.473	16.147
		A 2	Ratnapura	Rajpur Canal	Rajpur Canal	0.506	57.650	4.316	61.966	315.687
		A 3	SH-91	SH-91	SH-91	2.956	283.003	32.684	315.687	278.244
		Total	4	Indo Nepal Road	Indo Nepal Road	2.304	262.965	15.279	278.244	Virpur

Ramesh Ray



3.2024

11

Downloading of Bidding Documents	From 12.10.2023 (0900 Hours) to 02.11.2023 (1500 Hours)
----------------------------------	---

From 12.10.2023 (0900 Hours) to 02.11.2023 (1500 Hours)

Standard Bidding Document for MMGSY(AWSESH)

Online Bid Submission last Date	on 02.11.2023 up to 1500 Hours
Offline Bid Submission last Date	on 02.11.2023 up to 1500 Hours
Online Bid Opening Date	on 02.11.2023 at 1530 Hours
Cost of Bid	Rs. 10000.00 per package (non-refundable) only in form of Demand Draft in favour of concerned Executive Engineer.
Place, date and time of Pre-Bid Meeting	Concerned office of Superintending Engineer on 20.10.2023 from 1100 Hours

\* The Earnest Money will be 2% on the sanction cost of B.O.Q only and as prescribed in clause 16.1 of Appendix to ITB of Bidding Document.

1. All documents submitted by the bidder with an affidavit shall be considered in technical bid evaluation but after award all the documents shall be duly verified.
2. As per notification no.-447(s), dated-16.01.2020 issued by the Road Construction Department, Government of Bihar and RWD letter no.-१०३०-4(गो) बिबि (कत) 23-291/2014-292 (अपे) dated 17.01.2020, it is to amend that in the percentage rate tenders the maximum lower limit of the rate quoted by the tenderer is herewith deleted.
3. The tenderer is liable to submit Additional Performance Guarantee for the unbalanced bid as per notification no.-447(s), dated-16.01.2020 issued by the Road Construction Department, Government of Bihar and in accordance with Clause-26.3 of ITB and Clause-46 Part-1 General Condition of the Standard Bidding Document (SBD).
4. As per letter No.-29 encl. dated: 25.01.2021 issued by Home Department, Government of Bihar and subsequently department letter No.- 489 (e) dated: 29.01.2021, it is mandatory to submit a valid Character certificate by bidders.
5. LoA will be issued after verification of Bid Security Instrument.
6. Details of tender related information can be viewed/downloaded from the website <http://pmgsytendersbih.gov.in> . Interested Bidders will have to register with their DSC (Digital Signature Certificate) in the website <http://pmgsytendersbih.gov.in> .

7. For any queries regarding e-tendering process kindly contact -MMGSY Cell, 6th floor, Vishveshwaraiya Bhawan, Bailey Road, Patna-15. Phone -8986915224 or email at [mmgsyrvd@gmail.com](mailto:mmgsyrvd@gmail.com)
8. As per Department Letter No.-511(E) Patna dated 29.01.2020 it is mandatory to submit the advocates welfare fund of Rupees 25.00 in the affidavit for all Tenders.

*Ramesh Baga*