

# 3rd year mainm. bill

60

Sch. XLV—Form No. 134

| Particulars                            | Details of actual measurement |    |    |    | Contents of area              |
|----------------------------------------|-------------------------------|----|----|----|-------------------------------|
|                                        | No.                           | L. | B. | D. |                               |
| Name of work - maint. of road          |                               |    |    |    |                               |
| From pokhariya chowk to                |                               |    |    |    |                               |
| Paswan Jora                            |                               |    |    |    |                               |
| Agency - Ashutosh Kumar Singh.         |                               |    |    |    |                               |
| Agreement no. 01/SBD/2018-19           |                               |    |    |    |                               |
| Dow - 25/02/2019                       |                               |    |    |    |                               |
| ToC - 28/02/2020                       |                               |    |    |    |                               |
| Actual date of completion - 28/01/2021 |                               |    |    |    |                               |
| (1) Restoration of raincuts /          |                               |    |    |    |                               |
| berms with soil                        |                               |    |    |    |                               |
| 6 x 8.00 x 2.00 x 0.30 =               |                               |    |    |    | 28.8                          |
| 10 x 6.50 x 1.95 x 0.30 =              |                               |    |    |    | 38.02                         |
| 7 x 4.97 x 1.95 x 0.30 =               |                               |    |    |    | 20.35                         |
|                                        |                               |    |    |    | <u>= 87.17 m<sup>3</sup></u>  |
| (2) Making up of berms /               |                               |    |    |    |                               |
| Shoulder etc.                          |                               |    |    |    |                               |
| 10 x 10.10 x 1.70 =                    |                               |    |    |    | 171.7                         |
| 11 x 6.5 x 1.65 =                      |                               |    |    |    | 117.97                        |
| 6 x 8.00 x 1.85 =                      |                               |    |    |    | 88.8                          |
| 8 x 6.61 x 2.00 =                      |                               |    |    |    | 105.76                        |
|                                        |                               |    |    |    | <u>= 484.23 m<sup>2</sup></u> |
| (3) Repair of pot holes                |                               |    |    |    |                               |
| Filled with 75mm etc.                  |                               |    |    |    |                               |

Continuation

| Particulars                                                 | Details of actual measurement |    |    |    | Contents of area |
|-------------------------------------------------------------|-------------------------------|----|----|----|------------------|
|                                                             | No.                           | L. | B. | D. |                  |
| <u>Abstract qty. of Cast</u>                                |                               |    |    |    |                  |
| (1) Restoration of rainwater berms.                         |                               |    |    |    |                  |
| vide qty. page no - 60                                      |                               |    |    |    |                  |
| 87.17 m <sup>3</sup> @ 365.25 / m <sup>3</sup> =            |                               |    |    |    | 31839.00         |
| (2) making of berms/shoulder etc.                           |                               |    |    |    |                  |
| vide qty. page no - 60                                      |                               |    |    |    |                  |
| 484.23 m <sup>2</sup> @ 54.16 / m <sup>2</sup> =            |                               |    |    |    | 26226.00         |
| (3) Repair of pot holes                                     |                               |    |    |    |                  |
| filled 75mm etc.                                            |                               |    |    |    |                  |
| vide qty. page no - 61                                      |                               |    |    |    |                  |
| 63.28 m <sup>2</sup> @ 336.94 / m <sup>2</sup> =            |                               |    |    |    | 21322.00         |
| (4) Patch repair over bituminous w/s surface with 20mm etc. |                               |    |    |    |                  |
| vide qty. page no - 61                                      |                               |    |    |    |                  |
| 63.28 m <sup>2</sup> @ 212.06 / m <sup>2</sup> =            |                               |    |    |    | 13419.00         |
| (5) Maint. of C/D works. (H.P. Culverts)                    |                               |    |    |    |                  |
| vide qty. page no - 61                                      |                               |    |    |    |                  |
| 3.00 nos @ 1131.64 / nos =                                  |                               |    |    |    | 3395.00          |

Continuation

Continuation