

3rd year maintenance

33

Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Work:-	Ganpurvi Barapur, Jharkhand				
	Bhagat Keshav to				
	Yagunay Ke Balthom Tak				
Agency:-	Anjana Kumari				
Agreement :-	11/1/2019/2019-20				
Actual date of completion:-	18/6/21				
① Restoration of	cul.				
	4x5.0x1.0x0.30				6.00m ³
	8x3.0x1.0x0.30				7.20m ³
	8x5.50x0.75x0.30				9.90m ³
	10x3.5x0.75x0.40				10.50m ³
	3x7.0x1.0x0.30				6.30m ³
	18x2.5x0.60x0.30				8.10m ³
	5x8.5x0.60x0.30				7.65m ³
	8x11.0x0.60x0.30				15.84m ³
	2x10.0x0.75x0.30				4.50m ³
	6x4.50x0.90x0.30				7.29m ³
	7x3.5x0.60x0.40				5.88m ³
					89.16m ³
	Lt 88.59m ³				
② maintenance of	earth				
	shredle				
	4x15.0x1.0				60.0m ²
	3x13.0x0.90				48.60m ²
	4x20.0x1.0				80.00m ²
	10x5.50x1.00				55.00m ²

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
⑤ Paving and laying					
hot applied bitum.					
Plastic compound -					
TMSP. 34 - BT. 250.0 m ²					
@ ₹ 735.40/m ² - ₹					183852
C.C. 71.60 m ²					
@ ₹ 820.55/m ² - ₹					58754
⑥ maintenance already					
Planted trees					
TMSP 85 - 80.00					
@ ₹ 61.43/cd - ₹					14917
⑦ maintenance of					
J.H.P. culvert					
TMSP 35 - 1.00 @ ₹ 1102.81/m ² - 11032					
⑧ maintenance of slab					
asphalt					
TMSP. 35 - 1.00 @ ₹ 2273.40/m ² - 22732					
⑨ maintenance of drain					
Stone					
TMSP. 35 - 1.608 km					
@ ₹ 711.43/km - ₹					11452
					₹ 3997572
Add (L.C + GST) @ 13%.					₹ 519842
1% 10%					₹ 4517252
Less 10% below					₹ 4065522
Pr. Sm.					
1110 Continuation					15104

masonry -
 Earth - 162.39 m³
 structure - 5.80 m³
 Bitumen - 490.11 kg.