



बिहार BIHAR

8744 2024 में निष्ठावासी कंसाइसिंग
AV 130282
का. नं. 125/04 पीरो
हारांग विन्दा का. नं.
मुसतार 10

Treasury Officer

AGREEMENT FORM

Agreement No : 13 /M.B.D./M/R -2023-24

This Agreement, made the 29th day FEBRUARY 2024 between The Executive Engineer, Rural Work Department, Works Division Piro (Bhojpur) and Maa Vindhya wasini Construction, At-Power Ganj Near Ganesh Rice Mill, Ara, Bhojpur.

Whereas the Employer is desirous that the Contractor execute Construction of Road From Repair L035 To Basauri, Packg. No-(MR-N/23-24 Piro/12) Tender ID-129812 (and maintenance for five years under M/R for 2023-24 and the Employer has accepted the Bid by Contractor for the execution and completion of such works and the remedying of any defects therein at a cost of Rupees 69,73,087.00 (Rupees Sixty Nine Lacs Seventy Three Thousand Eighty Seven Only).

Amount Of Estimated Cost	:-	Rs. 69,80,067.00
Amount of Agreement Rs	:-	Rs. 69,73,087.00
Construction Value	:-	Rs. 54,59,889.00
Maintenance Amount	:-	Rs. 15,13,198.00
Date of Written order to Commence	:-	<u>29-02-2024</u>
Time of Completion	:-	<u>28-11-2024</u>
Approved Rate of which Payment	:-	Below 0.10 % From Schedule rate will be made.

Maa Vindhya wasini Construction
Surjeet Singh
Proprietor

29/02/24
Executive Engineer
R.W.D Work Division
Piro
29-2-24



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Contractor 'Details

1	Agreement No.	13 /M.B.D./M/R -2023-24
2	Tender ID	129812
3	Name of Road	Construction of Road From Repair L035 To Basauri, Packg. No-(MR-N/23-24 Piro/12) Tender ID-129812
4	Company Name	Maa Vindhya wasini Construction
5	Contractor Name:-	Surjeet Singh
6	Registration No.	2230719
7	Registration Class :-	Class 2
8	Registration Validity :-	21.12.2028
9	Contractor Address :-	At-Power Ganj Near Ganesh Rice Mill, Ara, Bhojpur.
10	District :-	Bhojpur
11	Pan No :-	EKWPS7304M
12	EPF Number :-	BRPAT3165060000
13	GST NUMBER :-	10EKWPS7304M2ZI
14	Bank A/C No :-	
15	Bank Name :-	
16	IFSC Code :-	
17	Mobile No :-	9507773356
18	E-mail ID :-	surjeetsinghrwd@gmail.com

Maa Vindhya wasini Construction
Surjeet Singh
Proprietor
Maa Vindhya wasini Construction
At-Power Ganj Near Ganesh Rice Mill
Ara, Dist-Bhojpur.

Executive Engineer
R. W. D. Piro
EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT
WORKS DIVISION, PIRO

Name of Works:- Construction of Road From Repair L035 To Basauri,
Packg. No-(MR-N/23-24 Piro/12) Tender ID-129812

Agency:

Maa Vindhya wasini Construction,
At-Power Ganj Near Ganesh Rice Mill,
Ara, Bhojpur.

Performance Security

SI No	Detailed	Amount	B.G./F.D.	Date
1.	Earnest Money	1,40,000.00	F.D.	17.02.2024
2.	Initial Security	2,10,000.00	F.D.	17.02.2024
	Total	3,50,000.00		

1. Estimated Cost:- Rs. 69,80,067.00
2. Agreement Value:- Rs. 69,73,087.00
3. Construction Value:- Rs. 54,59,889.00
4. Maintenance Amount:- Rs. 15,13,198.00
5. Performance Security:- Rs. 3,50,000.00
6. Date of Written order to Commence:-
7. Time of Completion:- 09 Months i.e.
8. Rate:- 0.10 % Below from Schedule Rate.

Maa Vindhya wasini Construction
Suresh Singh
Proprietor

Executive Engineer
Rural Works Department
Works Division Piro

[Signature]
Executive Engineer
R.W.D Work Division
Piro
29.2.24
[Signature]
29.02.24

S.T.NO-10EKWPS7304M2Z1

Mob No-9507773356

MAA VINDHYAWASINI CONSTRUCTION

REGT. GOVT CONTRACTOR

Add: Power Ganj Near Ganesh Rice Mill, Ara, Bhojpur, Bihar 802301

ef.....

Date.....

WORK PROGRAM

Sl. No.	Discription of Work	1 st Months	2 st Months	3 st Months	4 st Months	5 st Months	6 st Months	7 st Month	8 st Month	9 st Month
	Site Clearance									
	Earth Work									
	GSB									
	Aproch PCC	-	-	-	-	-	-	-	-	-
	WBM II	-	-	-	-	-	-	-	-	-
	WBM III									
	Primcote									
	Track Cote									
	BM									
	Seal Coat/SDBC									
	Traffic Signal/ Board Instlation									
	Other Finising Work									

ma Vindhyawasini Construction
ma Vindhyawasini Construction
Surya Singh
Proprietor
Proprietor

Executive Engineer
R.W.D Work Division
Piro
29.2.24
29.02.24

ANNEXURE - "B"
GOVERNMENT OF BIHAR
RURAL WORKS DEPARTMENT
CERTIFICATE OF REGISTRATION

Old Registration	New Registration
Registration No :- NA	Registration No : 2230719
Class :- NA	Class : Class 2

Maa Vindhyawasini Construction Prop Surjeet Singh

At Power Ganj Near Ganesh Rice Mill Goma Road Arrah Bhोजपुर Bihar 802301
Pincode: 802301



is hereby registered in Class 2 for the period from date 22-Dec-2023 to 21-Dec-2028 As Contractor of Rural Works Department.
22-12-2023 12:12:00

Signature Of Applicant

Maa Vindhyawasini Construction
Surjeet Singh
Proprietor

This Document is Digitally
Signed, Need no Signature

Maa Vindhyawasini Construction
Surjeet Singh
Proprietor

29/12/23
Executive Engineer
R.W.D Work Division
29-12-23 Piro
29.01.24

Percentage BOQ

Tender Inviting Authority: Engg-In Chief RWD Patna

LENGTH - 1.770KM

BLOCK - SANDESH

Name of Work: L036 TO BASAURI

Contract No: Civil Works

Name of the Bidder/
Bidding Firm
/ Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grasses, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	4	5	6	54	55
1		0.30	Hect	76955.06	23077.82	INR Twenty Three Thousand & Seventy Seven and Paise Eighty Two Only
2	Construction of Subgrade and Earthen Shoulders Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1. (Having CBR not less than 5%)	840.75	Cum	264.72	222563.34	INR Two Lakh Twenty Two Thousand Five Hundred & Sixty Three and Paise Thirty Four Only

Maa Vindhyawasini Construction

Proprietor

Executive Engineer

R.W.D Work Division

Piro

3	<u>Granular Sub-base with Coarse Graded Material</u> (Table 400.1) Construction of granular sub-base by providing Coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	137.70	Cum.	3043.92	419147.78	INR Four Lakh Nineteen Thousand One Hundred & Forty Seven and Paise Seventy Eight Only
4	3) WBM Grading 3 With Stone Screening/ Providing, laying, spreading and compacting mechanically crushed stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding material to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	160.71	Cum.	4789.48	721822.53	INR Seven Lakh Twenty One Thousand Eight Hundred & Twenty Two and Paise Fifty Three Only
5	Prime Coat Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	2015.89	Sqm	57.65	116216.06	INR One Lakh Sixteen Thousand Two Hundred & Sixteen and Paise Six Only
	Tack Coat Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion, distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	6703.88	Sqm	19.76	132468.67	INR One Lakh Thirty Two Thousand Four Hundred & Sixty Eight and Paise Sixty Seven Only

Maa Vindhya wasini Construction

Surjit Singh
Proprietor

Executive Engineer

R.W.D Work Division
Piro

29.2.24

29.2.24

2	Semi-Dense Bituminous Concrete Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	167.60	Cum	13501.02	2262770.95	INR Twenty Two Lakh Sixty Two Thousand Seven Hundred & Seventy and Paise Ninety Five Only
3	Dry Lean Cement Concrete Sub-base Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing.	6.10	Cum	4205.68	34090.31	INR Thirty Four Thousand & Ninety and Paise Thirty One Only
9	Kilometre Stone Reinforced concrete M15 grade kilometre stone/locational stone of standard design as per IRC-8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 (i) Ordinary Kilometre Stone (Precast) (ii) 200 m stone (precast)	3.00	Each	2627.31	8481.93	INR Eight Thousand Four Hundred & Eighty One and Paise Ninety Three Only
		7.00	Each	796.62	5590.34	INR Five Thousand Five Hundred & Ninety and Paise Thirty Four Only

Maa Vindhya wasini Construction

Surjeet Singh
Proprietor

[Signature]
Executive Engineer
R.W.D Work Division
Piro
29.12.24

29.12.24


11	Retro-Reflectors Traffic Signs: Providing and fixing of retro-reflectors cautionary, mandatory and informative sign as per IRC-67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminum sheeting. 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (i) 60 cm equilateral triangle	4.00	Each	4433.19	17932.76	INR Seventeen Thousand Nine Hundred & Thirty Two and Paise Seventy Six Only
12	(i) 60 cm circular	6.00	Each	4279.08	25674.48	INR Twenty Five Thousand Six Hundred & Seventy Four and Paise Forty Eight Only
13	(iii) 600 mm x 450 mm rectangular	4.00	Each	4135.92	16540.08	INR Sixteen Thousand Five Hundred & Forty and Paise Eight Only
14	Road Marking with Hot Applied Thermoplastic Compound with Reflecting Glass Beads on Bituminous Surface & Concrete Surface. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	354.00	Sqm	886.50	313821.00	INR Three Lakh Thirteen Thousand Eight Hundred & Twenty One Only

Maa Vinhyawasini Construction

Surjit Singh
Proprietor

Zubair
Executive Engineer
R.W.D Work Division
29.2.24 Piro
29.02.24

15	Providing and fixing of typical MINGSY Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.5 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be pointed with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1 Citizen Information Board Maintenance Board	4.00	Each	10977.36	45909.40	INR Forty Three Thousand Nine Hundred & Nine and Paise Forty Only
16	Guard stones/boundary stones/guardrails Guard stones/boundary stones/guardrails Painting/guard stones, boundary stones and guardrail	32.00	Each	689.32	22058.24	INR Twenty Two Thousand & Fifty Eight and Paise Twenty Four Only
17	Planting of tree & there maintenance for one Year Planting of tree by the road side (Avenue Tree) in 0.5 m dia holes, 1 m deep dug in the Ground, Mixing the soil with decayed farm yard/ slug manure, planting the saplings back filling the trench, watering, fixing the tree guard & maintain the Plant for One Year.	75.00	Each	1306.10	97882.50	INR Ninety Seven Thousand Eight Hundred & Eighty Two and Paise Fifty Only
18	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications Brick Masonry in C.M.(1:3) in parapet Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4 Painting Two Coats on New Concrete Surfaces Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	40.32	Sqm	199.26	8033.76	INR Eight Thousand & Thirty Three and Paise Seventy Six Only
		5.76	cum	6998.71	40318.33	INR Forty Thousand Three Hundred & Eighteen and Paise Thirty Three Only
		160.80	Cum	139.16	14027.33	INR Fourteen Thousand & Twenty Seven and Paise Thirty Three Only

Wala Vindhya wasini Construction

 Proprietor

Executive Engineer
 R.W.D Work Division
 Piro

 29.2.24

21	GST @ 18% OF TOTAL COST	1.00	RS	818355.42	818355.42	INR Eight Lakh Eighteen Thousand Three Hundred & Fifty Five and Paise Forty Two Only
22	LABOUR CESS @ 1 % OF TOTAL COST	1.00	RS	45464.19	45464.19	INR Forty Five Thousand Four Hundred & Sixty Four and Paise Nineteen Only
23	Seigniorage Fee @ 10 % OF TOTAL COST	1.00	RS	55113.57	55113.57	INR Fifty Five Thousand One Hundred & Thirteen and Paise Fifty Seven Only
24	Five Year Maintenance	20.00	Quarterly	1268710.00	1268710.00	INR Twelve Lakh Sixty Eight Thousand Seven Hundred & Ten Only
25	GST @ 18% OF TOTAL COST	1.00	RS	228367.80	228367.80	INR Two Lakh Twenty Eight Thousand Three Hundred & Sixty Seven and Paise Eighty Only
26	LABOUR CESS @ 1 % OF TOTAL COST	1.00	RS	12687.10	12687.10	INR Twelve Thousand Six Hundred & Eighty Seven and Paise Ten Only
27	Seigniorage Fee @ 10 % OF TOTAL COST	1.00	RS	4941.42	4941.42	INR Four Thousand Nine Hundred & Forty One and Paise Forty Two Only
Total in Figures				6980067.11	6980067.11	Sixty Nine Lakh Eighty Thousand & Sixty Seven and Paise Eleven Only
Quoted Rate in Figures				0.00	0.00	INR Zero Only
Quoted Rate in Words				INR Zero Only		


Maa Vindhyawasini Construction
Proprietor


Executive Engineer
R.W.D Work Division
Piro
 29.1.24
 29.2.24