



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## Contractor 'Details

1	Agreement No.	15/M.B.D./M/R -2023-24
2	Tender ID	129690
3	Name of Road	Construction of Road From Repair L045 Canal Road To Koni, Packg. No-(MR-N/23-24 Piro/07) Tender ID-129690
4	Company Name	M/s Gautam Construction,
5	Contractor Name:-	Gautam Kumar Singh,
6	Registration No.	3210933
7	Registration Class :-	Class 3
8	Registration Validity :-	31.10.2026
9	Contractor Address :-	Vill+Po-Mohadipur, Ps-Jagdishpur, Dist-Bhagalpur.
10	District :-	Bhagalpur
11	Pan No :-	HMEPS8725K
12	EPF Number :-	BRBHA2554652000
13	GST NUMBER :-	10HMEPS8725K1ZN
14	Bank A/C No :-	
15	Bank Name :-	
16	IFSC Code :-	
17	Mobile No :-	7004795094
18	E-mail ID :-	bhagatconstruction7@gmail.com

गौतम-कुमार सिंह  
M/s Gautam Construction,  
Vill+Po-Mohadipur, Ps-Jagdishpur,  
Dist-Bhagalpur

03/11/24  
EXECUTIVE ENGINEER  
RURAL WORKS DEPARTMENT  
WORKS DIVISION, PIRO  
01-3-24



भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

बिहार BIHAR

Treasury Officer

8827 ३६२ मेसर्स जीतम कंस्ट्रक्शंस  
सा. मोहदीपुर भागा जयसिंहपुर  
बिहार

AV 130322

प्रा. नं. ११६/७२ की  
द्वारा विवेक पर  
मुख्यतः

### AGREEMENT FORM

Agreement No : 15/M.B.D./M/R -2023-24

This Agreement made the 01<sup>st</sup> day March 2024 between The Executive Engineer, Rural Works Department, Works Division Piro (Bhojpur) and M/s Gautam Construction, Prop Gautam Kumar Singh, Vill+Po-Mohadipur, Ps-Jagdishpur, Dist-Bhagalpur.

Whereas the Employer is desirous that the Contractor execute Construction of Road From Repair L045 Canal Road To Koni, Packg. No-(MR-N/23-24 Piro/07) Tender ID-129690 [and maintenance for five years under M/R for 2023-24 and the Employer has accepted the Bid by Contractor for the execution and completion of such works and the remedying of any defects therein at a cost of Rupees 45,89,031.00 (Rupees Forty Five Lacs Eighty Nine Thousand Thirty One Only).

Amount Of Estimated Cost	:-	Rs. 45,89,949.00
Amount of Agreement Rs	:-	Rs. 45,89,031.00
Construction Value	:-	Rs. 35,34,939.00
Maintenance Amount:-		Rs. 10,54,092.00
Date of Written order to Commence	:-	01.03.2024
Time of Completion	:-	30.11.2024
Approved Rate of which Payment	:-	Below 0.02 % From Schedule rate will be made.

गौतम कुमार सिंह

Executive Engineer

R.W.D Work Division  
Piro

**ANNEXURE - "B"**  
**GOVERNMENT OF BIHAR**  
**RURAL WORKS DEPARTMENT**  
**CERTIFICATE OF REGISTRATION**

Old Registration	New Registration
Registration No :- NA	Registration No : 3210933
Class :- NA	Class : Class 3



M/S Gautam Construction Prop Gautam Kumar Singh

So Birendra Prasad Singh Vill Mohadiapur Po Mohadiapur Ps Jagdishpur District Bhagalpur Bihar 813105 Pincode: 813105

Is hereby registered in Class 3 for the period from date 01-Nov-2021 to 31-Oct-2026 As Contractor of Rural Works Department.

01-11-2021 12:11:00

**Signature Of Applicant**

*(Handwritten signature in a box)*

This Document is Digitally Signed/Need no Signature

*(Handwritten signature)*


*(Handwritten signature)*  
**Executive Engineer**  
**R.W.D Work Division**  
**Piro**  
*(Handwritten date: 01-3-24)*



<b>आयकर विभाग</b> <b>INCOME TAX DEPARTMENT</b>			<b>भारत सरकार</b> <b>GOVT. OF INDIA</b>
	<b>स्थायी लेखा संख्या कार्ड</b> <b>Permanent Account Number Card</b>		
<b>नाम/ Name</b> <b>GAUTAM KUMAR SINGH</b>		<b>HMEPSB725K</b>	
<b>पिता का नाम/ Father's Name</b> <b>BIRENDRA PRASAD SINGH</b>			
<b>जन्म की तारीख/ Date of Birth</b> <b>10/06/1994</b>		<b>हस्ताक्षर/ Signature</b>	

गौतम कुमार सिंह

गौतम कुमार सिंह

  
**Executive Engineer**  
**R.W.D Work Division**  
**Piro**  
 01-3-25  
 01-3-25



Government of India  
Form GST REG-06  
(See Rule 10(1))

Registration Certificate

Registration Number : ICHMEPS1725K12N

1.	Legal Name	GAUTAM KUMAR SINGH			
2.	Trade Name, if any	M/S GAUTAM CONSTRUCTION			
3.	Constitution of Business	Proprietorship			
4.	Address of Principal Place of Business	MOHADIPUR, S/O-BIRENDRA PRASAD SINGH, MOHADIPUR, MOHUDDINPUR, BHAGALPUR, Bhagalpur, Bihar, 813105			
5.	Date of Liability				
6.	Period of Validity	From	13/06/2021	To	Not Applicable
7.	Type of Registration	Regular			
8.	Particulars of Approving Authority	Bihar			
Signature					
Signature valid Digitally signed by  GOODS AND SERVICES TAX NETWORK Date: 2021.06.13 10:45:15 IST					
Name		Divakar Prasad			
Designation		Joint Commissioner of State Tax			
Jurisdictional Office		Bhagalpur			
9. Date of issue of Certificate		13/06/2021			
Note: The registration certificate is required to be prominently displayed at all places of business in the State.					

This is a system generated digitally signed Registration Certificate issued based on the approval of application granted on 13/06/2021 by the Jurisdictional authority.

Digitally signed by

Digitally signed by

20/07/2021

Executive

R.W.D Work Division

01-3-24

Pirp

01-3-24



# Percentage BOD

For Tendering Authority: Engg-in-Chief RWD Patna

Name of Work: L045-CANAL ROAD TO KONI

BLOCK - SAHAR

LENGTH - 1.250KM

Contract No: Civil Works:

Name of the Bidder/  
Bidding Firm  
/ Company:

(This BOD template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender.

Bidders are allowed to enter the Bidder Name and Values only )

## PRICE SCHEDULE

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
SI No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words	
1	2	4	5	6	54	55	
1	Clearing and Grabbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 360mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.17	Hect	76920.06	13077.43	INR Thirteen Thousand & Seventy Seven and Paise Forty Three Only	

*[Signature]*  
Executive Engineer  
R.W.D Work Division  
Piro

*[Signature]*  
Executive Engineer  
R.W.D Work Division  
Piro

Approved for Contracted  
S.E  
R.W.D Works Circle  
Piro

*[Signature]*

2	Construction of Subgrade and Earthen Shoulders Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 301.1. (Having CBR not less than 0%)	653.75	Cum	261.72	173060.70	MR One Lakh Seventy Three Thousand & Sixty and Paise Seventy Only
3	Granular Sub-base with Coarse Graded Material (Table 409.1) Grading - II Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	48.60	Cum.	2876.31	139760.07	MR One Lakh Thirty Nine Thousand Seven Hundred & Forty and Paise Seven Only
4	Granular Sub-base with Coarse Graded Material (Table 409.1) Construction of granular sub-base by providing Coarse Graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	17.57	Cum.	2331.24	40955.89	MR Forty Thousand Nine Hundred & Fifty Nine and Paise Eighty Nine Only
5	3) WBM Grading 3 With Stone Screening Providing, laying, spreading and compacting mechanically crushed stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/building material to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	80.19	Cum.	4595.56	308517.56	MR Three Lakh Sixty Eight Thousand Five Hundred & Seventeen and Paise Ninety Six Only  Approved for Construction S.E.

3710  
21/11/2024  
21/11/2024

Executive Engineer  
R.W.D Work Division  
Piro  
R.W.D Circle  
A/c



6	<b>Prime Coat</b> Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	1071.35	Sqm	11.71	61859.75	INR Sixty One Thousand Eight Hundred Fifty Nine and Paise Seventy Five Only
7	<b>Tack Coat</b> Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503.	4451.56	Sqm	19.79	88096.77	INR Eighty Eight Thousand & Ninety Six and Paise Seventy Seven Only
8	<b>Semi-Dense Bituminous Concrete</b> Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	111.29	Cum	13360.87	1486931.22	INR Fourteen Lakh Eighty Six Thousand Nine Hundred & Thirty One and Paise Twenty Two Only
9	<b>Dry Lean Cement Concrete Sub-base</b> Construction of dry lean cement concrete Sub-base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 160 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 6-10 tonnes vibratory roller, finishing and curing.	9.76	Cum	4064.45	35669.03	INR Thirty Nine Thousand Six Hundred & Sixty Nine and Paise Three Only

*[Signature]*  
Executive Engineer  
R.W.D Work Division  
Piro

*[Signature]*  
21/07/2017

Executive Engineer  
R.W.D Work Division  
Piro

*[Signature]*  
S E  
P.W.D. Circle

Approved for Corrected



10	<b>Kilometre Stone</b> Reinforced cement concrete M15 grade Kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703	2.00	Each	2790.32	5580.64	INR Five Thousand Five Hundred and Paise Sixty Four Only
11	(i) Ordinary Kilometre Stone (Precast) (ii) 200 mm stone (precast)	5.00	Each	792.04	3960.20	INR Three Thousand Nine Hundred & Sixty and Paise Twenty Only
12	Retro-Reflectorised Traffic Signs: Providing and fixing of retro-reflectorised cautionary, mandatory and informative sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting. 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 601 (i) 60 cm equilateral triangle	2.00	Each	4465.85	8931.76	INR Eight Thousand Nine Hundred & Thirty One and Paise Seventy Six Only
13	(ii) 60 cm circular	6.00	Each	4261.77	25570.62	INR Twenty Five Thousand Five Hundred & Seventy and Paise Sixty Two Only
14	(iii) 600 mm x 450 mm rectangular	6.00	Each	4117.71	24706.26	INR Twenty Four Thousand Seven Hundred & Six and Paise Twenty Six Only
15	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface & Concrete Surface. Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes.	250.00	Sqm	888.50	221625.00	INR Two Lakh Twenty One Thousand Six Hundred & Twenty Five Only

*20/08/23*  
Executive Engineer  
R.W.D Work Division  
Piro

*Orthographic*

Executive Engineer  
R.W.D Work Division  
Piro

Approved & Contracted  
S.E.  
R.W.D Work Division  
Piro



16	<p>crowding and fixing of typical MMSGY informative sign board with Logo as per MORD specifications and drawing. Three MS plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1</p> <p>Citizen Information Board</p> <p>Maintenance Board</p>	4.00	Each	10942.73	43770.92	INR Forty Three Thousand Seven Hundred & Seventy and Paise Ninety Two Only
17	<p>Guard stones/boundary stones/gaurdrails</p> <p>Guard stones/boundary stones/gaurdrails</p> <p>Painting guard stones, boundary stones and guardrail</p>	45.00	Each	686.30	32942.40	INR Thirty Two Thousand Nine Hundred & Forty Two and Paise Forty Only
18	<p>Planting of tree &amp; there maintenance for one Year</p> <p>Planting of tree by the road side (Avenue Tree) in 0.6 m dia holes, 1 m deep dug in the Ground, mixing the soil with decayed farm yard/ slug manure, planting the saplings back filling the trench, watering, fixing the tree guard &amp; maintain the Plant for One Year.</p>	42.50	Each	1305.10	59466.75	INR Fifty Five Thousand Four Hundred & Sixty Six and Paise Seventy Five Only
19	<p>Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications</p>	80.64	Sqm	126.32	15831.24	INR Fifteen Thousand Eight Hundred & Thirty One and Paise Twenty Four Only
20	<p>Brick Masonry in C.M.(1:3) in parapet</p> <p>Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4</p>	11.62	cum	6989.71	80636.66	INR Eighty Thousand Six Hundred & Thirty Six and Paise Sixty Six Only

*Signature*  
 Executive Engineer  
 R.W.D Work Division  
 Piro

Executive Engineer  
 R.W.D Work Division  
*Signature*  
 Piro

Approved & Corrected  
*Signature*  
 S.E.  
 R.W.D Works Circle  
*Signature*



Bidding Documents				For New, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701		
22	GST @ 18% OF TOTAL COST	1.00	RS	528593.12	528593.12	INR Eleven Thousand Two Hundred Sixty One and Paise Eighty Six Only
23	LABOUR CESS @ 1 % OF TOTAL COST	1.00	RS	29421.84	29421.84	INR Twenty Nine Thousand Four Hundred & Twenty One and Paise Eighty Four Only
24	Seigniorage Fee @ 10 % OF TOTAL COST	1.00	RS	34474.65	34474.65	INR Thirty Four Thousand Four Hundred & Seventy Four and Paise Sixty Five Only
25	Five Year Maintenance	20.00	Quarterly	44151.80	683036.00	INR Eight Lakh Eighty Three Thousand & Thirty Six Only
26	GST @ 18% OF TOTAL COST	1.00	RS	158946.48	158946.48	INR One Lakh Fifty Eight Thousand Nine Hundred & Forty Six and Paise Forty Eight Only
27	LABOUR CESS @ 1 % OF TOTAL COST	1.00	RS	8830.36	8830.36	INR Eight Thousand Eight Hundred & Thirty and Paise Thirty Six Only
28	Seigniorage Fee @ 10 % OF TOTAL COST	1.00	RS	3489.70	3489.70	INR Three Thousand Four Hundred & Eighty Nine and Paise Seventy Only
Total in Figures				4589949.28		Forty Five Lakh Eighty Nine Thousand Nine Hundred & Forty Nine and Paise Twenty Eight Only
Quoted Rate in Figures			Select	0.00		INR Zero Only
Quoted Rate in Words		INR Zero Only				

*[Signature]*  
Executive Engineer  
R.W.D Work Division  
Piro

*[Signature]*  
S. Jangamrath

*[Signature]*  
Executive Engineer  
R.W.D Work Division  
Piro

*[Signature]*  
Supplementing Engineer  
R.W.D Work Division  
Piro

Total Quantity approved for Rs 45,89,949.28  
Approx. Forty Five Lakh Eighty Nine  
Thousand Four Hundred and Paise Twenty Eight  
Hundred and Paise Twenty Eight Only