

GOVERNMENT OF BIHAR
DETAILED PROJECT REPORT
FDR-2023



बिहार सरकार
ग्रामीण कार्य विभाग

DISTRICT :	EAST CHAMPARAN	BLOCK :	KESARIYA
NAME OF ROAD	Dekaha Chaparan Tathband to Manjhariya Road		
ESTIMATED COST:	रु :1297107 .00		
SUBMITTED BY			
THE EXECUTIVE ENGINEER, RWD			
WORKS DIVISION, CHAKIA			

FDR
तकनीकी प्रतिवेदन

पथ का नाम :- Dekaha champaran tathband to Manjhariya Road

प्रखण्ड का नाम :- केसरिया


पथ की लम्बाई :- 1.655 KM


प्राक्कलित राशि :- ₹ 1297107.00


प्रस्तुत प्राक्कलन Dekaha champaran tathband to Manjhariya Road पथ में अतिवृष्टि एवं बाढ़ आने से पानी के तेज बहाव के कारण क्षतिग्रस्त पथांशों में यातायात पुनर्स्थापन हेतु तैयार किया गया है। यह प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना का पत्रांक मु. अ. - 4 (मु.) ~~विधि कार्य~~ पत्रांक 3724 दिनांक 19-07-2023 के आदेश के आलोक में तैयार किया गया है।

उपर्युक्त पथ, बाढ़ एवं अतिवृष्टि से क्षतिग्रस्त होने के कारण ग्रामीणों का आवागमन अवरुद्ध हो गया था, जिसके कारण तत्काल Brick Bats भरकर पथ को मोटरेबुल किया गया। कार्य विभागीय रूप से सम्पादित किया गया है।

प्रस्तुत प्राक्कलन वर्तमान अनुसूचित दर पर (संवेदक लाभांश छोड़कर) तैयार किया गया है लोकहित एवं जनहित में प्राक्कलन की भूतलाक्षित प्रभाव (Post facto) स्वीकृति अपेक्षित है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा केसरिया


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल केसरिया


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल चकिया

Estimate for Restoration work of Road from Dekaha Chaparan Tathband to Manjhariya Road for the year 2023-2024 in Keshariya Block

Length-1.655 KM

Sr NO.	Item of Work							
1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)							
Ch	Nos	Length	Width	Height	Quantity	Unit	Rate	Amounts
			(3.75+8.75)/2					
cto	1	30.00	6.25	2.50	468.75			
15	1	20.00	3.75	0.30	22.50			
mtr	1	50.00	3.75	0.30	56.25			
					547.50	Cum	2135.92	1169416.2

Add Seigniorage fee

547.50 - 657 Cum 1696.88 111485.02 64780.2

Say 1297107.00

GST - 18% → 210494.92

Labourers - 11694.16

1456385.36

Say → 1456385.00

Bhandari
25/7/23
JE
RWD
KESARIYA

AB
25/7/23
AE
RWD
KESARIYA

AB
25/7/23
JE
RWD
KESARIYA

POST facto T.A.T.S. is accorded for Rs. 1456385.00

(..... crore) *Four* *hundred* *fifty six* thousand *Three* *hundred* *eighty five* (.....) only

Sharma
16/03/24
S.E. (R.W.D.)
works Circle
Motihari
Sharma
16/03/24

INSPECTION REPORT FOR MOTORABLE WORK

Name of PIUs :- Executive Engineer, R.W.D. (W) div. Chakia.

Name of Block/Road :- Kesariya / Dekha Champaran Tathband to Manjhariga Road

A. For Road

1. Damage Location/Chainage :- 0 to 150 mtr

2. Damage Length :- 100 Mtr

3. Nature of Damage (Length Wise)

(i) Breach :-	<u>30 mtr</u>
(ii) Crust Damage :-	<u>70 mtr</u>
(iii) Only Flank Damage :-	

whether traffic fully/Partialy obstructed :- fully obstructed

4. Details of Restoration :-

(i) Material Being Used in Restoration :- Bricks bat,

(ii) Equipment/Tools Being Used in Restoration Works :- Tractor, Labours, Light hammer

(iii) Restored Length

In open Area :-	<u>100 mtr</u>
In habitation Area :-	

(iv) If Restoration work done in habitation Area give Reason :-

B. For Bridge (Size of Bridge/Culvert)

(1) Damage Location/Chainage :-

(2) No. of Span Damage :-

(3) Length of Span :-

(4) Nature of Damage (Pier/Abuttment/
Wing Wall/Approach Road Damage) :-

(5) Details of Restoration :-

(i) Material Being Used in Restoration :-

(ii) Equipment/Tools Being Used in Restoration Works :-

(iii) Restored Length :-

Overall Grade of Restoration work (Satisfactory/Unsatisfactory) :- Satisfactory.

A. Kumar

Bhandary
J.E.

For inspection
15/5/24
Signature of Inspector
(Official Seal)
Executive Engineer
R.W.D. (W) Division
Motihari