

अधीक्षण अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, मोतिहारी

पत्रांक601.....

मोतिहारी, दिनांक 25/03/2024

प्रेषक:-

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल मोतिहारी

सेवा में,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल पकड़ीदयाल

विषय :-

कार्य प्रमंडल पकड़ीदयाल के अधीन FDR अन्तर्गत पथों के कार्योत्तर तकनीकी स्वीकृति के सम्बन्ध में।

प्रसंग :-

आपका पत्रांक-630 अनु0 दिनांक-21.03.2024


महाशय,

उपर्युक्त विषयक कार्य प्रमंडल पकड़ीदयाल के अधीन FDR अन्तर्गत निम्नलिखित पथों का पुनरीक्षित प्राक्कलन कार्योत्तर तकनीकी स्वीकृति उपरान्त आवश्यक कार्रवाई हेतु वापस किया जाता है।

क्र0 सं0	पथ का नाम	कार्योत्तर तकनीकी स्वीकृति की राशि (लाख में)
1	Barkagav to Parsauni vi Sisahani Parsauni	7.48200
2	Patahi Sugapipar Road to Gonahi Purbi Tola	2.93000
3	Sheohar Kajrahan RCD Road to Delho	2.28000
4	Jihuli to Gonahi	7.72000
5	Gonahi Anusuchit Jati se Sugapipar tak	6.91900
6	Jihuli to Jihuli Sekahi tola	7.66072
7	Mohar Tola to Siraha GP	4.09400
8	Jihuli to Jihuli Ghat	8.15600
9	PWD road Madhuban Tetariya Ghoghwa to Balram Bhagat Avm Devi Sahni	10.60000
10	Patahi to Sugapipar Road Near Kodaria Petrol Pump	19.97400

अनु0- यथोक्त।

विश्वासभाजन


25.03.2024

अधीक्षण अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, मोतिहारी



ग्रामीण कार्य विभाग

Rural Works Department ,Govt.of Bihar

PLAN HEAD-FDR

YEAR 2023-2024

DISTRICT;-EAST CHAMPARAN

BLOCK;- PATAHI

Estimate for Repair of Road breaches (Damaged by Flood)
For Motorability in JIHULI TO GONAH

ESTIMATED COST;-Rs. 1241132.00

LENGTH: KM

Submitted by:

Executive Engineer

RWD WORKS DIVISION

PAKARIDYAL



Name of work :- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in JIHULI TO GONAHU

HEAD:- FDR Length:-

SI No	Name of Item	Unit	QTY	Rate	Amount
			M3	Rs	Rs
1.	Labour for laying dry graded jhama khoa Or stone filter under Brick Pitching in Slope or apron including light ramming Etc. all complete as per approved design. Specification and direction ofE/I	M3	290.24	2135.52	619929.28
2.	Providing and laying RCC NP3 for culaverts On first class bedding of granular material In single/dubal row including fixing collar with CM 1:2 but excluding excavation.....E/I	M	00.00	7297.86	00.00
3.	Sand filling with Appoved Materials Seposited at site from road way cutting and excavation from drain and foundation of other strecture graded and compected as per Technical specification.....E/I	Bag			
Total(in Rs) 973533.52					619929.28
ADD G.S.T @18% Rs. 175236.03					111587.28
ADD LBOUR CESS @1% Rs. 9735.33					6199.28
ADD SIGNIORAGE FEE Rs. 7557.61					3434.9
TOTAL (in Rs.) 1241132.00					7,72,056.00
Say Total Rs 1241132.00					

Say 772000.00

[Signature]
20.12.23
J.E

[Signature]
20.12.23
A.E

[Signature]
20.12.23
E.E

RWD(W)DIV.PAKARIDYAL

Post facto A.T.S is accorded for Rs. 772000.00
Seven hundred and Seventy two thousand
only


[Signature]
25.03.2024
S.E. (R.W.D.)
works Circle
Motihari
25/3/2024

Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for

JIHULI TO GONAH

Appendix -1

Measurement for surfacing the Breach with.....					Filling
Sl.No	Chainage Km	Length(m)	Avg.Width (M)	Avg.Depth (M)	Quantity(m3)
Ch-0.00 to 50.00 m.	30.00	3.75 + 4.00 + 3.75/3	$\frac{1.10 + 1.30 + 1.20}{3}$	$\frac{0.90 + 0.50 + 0.80}{3}$	$\frac{137.85}{3} = 34.47$
	40.00	3.75 + 4.00 + 3.75/3	$\frac{1.10 + 1.20 + 1.00}{3}$	$\frac{0.5 + 1.06 + 0.60}{3}$	$\frac{138.57}{3} = 110.30$
	37.30	3.75 + 4.20 + 3.75/3	$\frac{1.00 + 1.10 + 0.90}{3}$		$\frac{145.47}{3} = 290.24$
TOTAL QTY :-					$\frac{451.87}{3} = 290.24 m^3$


20.12.23
J.E


20.12.23
A.E


20.12.23
E.E

~~I.A./T S is accorded for Rs.....
.....crore.....lacs.....thousand
.....hundred only~~

S.E. (R.W.D.)
works Circle
Motihari

BRICK BATS PITCHING MANUAL MEANS

6.6.1 WRD Bihar	Labour for laying dry graded Jhama Khoa or stone filter under Brick Pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I.				
	Unit :- Per Cum				
	Taking Output = 2.832 Cum				
	Unskilled Mazdoor	Nos.	3	442.40	1327.20
	Rate for 2.832 Cum				1327.20
	Rate per Cum (Rs.) -				468.64
1.	Supplying for Brick Bats (without Seigniorage Fee)				
A.	Brick Bats with Carriage	Per Cum		1696.88	1696.88
B.	Cost of Labour for Pitching and Light Ramming as per WRD SOR 6.6.1				468.64
	Total (A+B) -				2165.52
	Total Cost per Cum			Rs.-	2165.52

कार्यपालक अभियंता का कार्यालय, ग्रामीण कार्य विभाग,
कार्य प्रमण्डल ढाका, पूर्वी चम्पारण।

पत्रांक 411

ढाका दिनांक 21-03-2024

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, ढाका।

सेवा में,

अधीक्षण अभियंता,
ग्रामीण कार्य विभाग,
कार्य अंचल मोतिहारी।

विषय :- वर्ष 2023 के बाढ़ में क्षतिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जाँच के संबंध में।

प्रसंग :- अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक मु0अ0-4 (मु0) विविध (कार्य) -23-291/2019 4589 पटना, दिनांक 13.11.2021 एवं भवदीय कार्यालय आदेश ज्ञापांक 844 दिनांक 04.10.2021

महाशय,


उपर्युक्त विषयक एवं प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल पकड़ीदयाल द्वारा उपलब्ध कराये गये मोटरेबुल पथों की सूची में अंकित पथों का अधोहस्ताक्षरी तथा सहायक अभियंता एवं कनीय अभियंता द्वारा निरीक्षण किया गया है। निरीक्षण के दौरान कार्य प्रमंडल पकड़ीदयाल द्वारा प्रतिवेदित सभी पथों में मोटरेबुल कार्य कराया गया है एवं वर्तमान में यातायात चालु हैं।

सादर सूचनार्थ एवं अग्रेतर कार्रवाई हेतु समर्पित।

अनु0 - निरीक्षण किये गये पथों की सूची।

विश्वासभाजन


21/3/24
कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल ढाका।


21/3/24
सहायक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल ढाका।


21.3.24
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल ढाका।

Inspection Report For Flood Damage Work

Date :-

1. Name of PIUs- Executive Engineer, RWD. (W.D), Pakridayal.
2. Name of Block – Patahi.
3. Name of Road – Jihuli To Gonahi.

(A) For Road

1. Damage Location/Chainage :- 0.000 To 0.500
2. Damage Length :- 107.30 Meter.
3. Cause of Damage :- Due To Flood 2023/ Heavy Rain.
4. Nature of Damage :- Ditches/Breaches
5. Details of Restoration Work :-
 - (i) Material being used in restoration works :- Bricks Bat/Jhamma Metal/ Rabis/Hume Pipe.
 - (ii) Equipment/Tools being used in restoration Works :- J.C.B./Tractor/Trolley/Others
 - (iii) Procedure Taken up in restoration works :- Emergent Repair.
 - (iv) Restored Length :- 107.30 Meter.

পর্যাপ্ত পরিমাণে ব্রিক
ব্যবহার করা হয়েছে।
21/3/24


Signature of Inspecting officer 21.3.24
(Executive Engineer)
R.W.D. (W.D) Dhaka.