

पत्रांक 581 (अगु) /

शेखपुरा, दिनांक 04/04/2024 /

प्रेषक:- ई0 विमल कुमार,
कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, शेखपुरा।

सेवा में,
नोडल पदाधिकारी
राज्य योजना (State Schemes)
ग्रामीण कार्य विभाग, बिहार, पटना।

विषय:- शीर्ष राज्य योजना अन्तर्गत कराये गये पंचवर्षीय अनुसूच्य कार्य के लिए माँग राशि
उपलब्ध कराने के संबंध में।

महाशय,

उपर्युक्त विषय के संदर्भ में कहना है कि सूची में संलग्न विवरणी के अनुसार शीर्ष
नाबार्ड योजनान्तर्गत कराये गए पंचवर्षीय अनुसूच्य कार्य के भुगतान के लिए Rs.42,772/- (बेयालीस
हजार सात सौ बहत्तर रुपये) मात्र राशि की आवश्यकता है।

अतः कार्यहित में अनुरोध है कि उक्त राशि उपलब्ध कराने की कृपा की जाय।
ताकि कराये गये कार्यों के विपत्र भुगतान किया जा सके।

- अनु0:- (1) अधियाचना प्रपत्र।
(2) मापीपुरस्तिका की छायाप्रति।
(3) उपयोगिता प्रमाण-पत्र।
(4) प्रशासनिक स्वीकृति का पत्र।
(5) एकरारनामा की अभिप्रामणित प्रति।

विश्वासभाजन



(ई0 विमल कुमार)

कार्यपालक अभियन्ता
ग्रा.का.वि., कार्य प्रमण्डल,

शेखपुरा
4/4/24

न्याय प्रमाणद्वय का नाम :- ग्रामीण कार्य विभाग, कार्य प्रमाणद्वय, श्रेष्ठपुत्र।

क्र.सं	कार्य प्रस्ताव का नाम	योजना का नाम	एकरचना के अनुसार प्रास्तावित राशि वर्षवार					कुल राशि (लाख में)	व्यय की राशि वर्षवार					कुल राशि (लाख में)	प्रशासनिक स्वीकृति की राशि एवं प्रस्तावित परीक्षण राशि (लाख में)	अनुवर्ष हेतु प्रशासनिक स्वीकृति का पत्रांक/दिनांक	पूरा निर्माण कार्य पूर्ण करने की वास्तविक तिथि	वर्तमान अधिग्रहित राशि					कुल राशि (लाख में)	कुल अधिवर्ष राशि (लाख में)	
			प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)		प्रथम वर्ष राशि (लाख में)	द्वितीय वर्ष राशि (लाख में)	तृतीय वर्ष राशि (लाख में)	चतुर्थ वर्ष राशि (लाख में)	पंचम वर्ष राशि (लाख में)												
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
1	शेखपुरा	एकरस्य पथ से केमरा मुसहरी पथ।	0.213201	0.249723	0.346068	0.389817	0.438444	1.637253	0.20739	0.24318	0.33772	0.38024	0	1.16853	अपर सचिव, प्रा0का0वि0, का पत्रांक- मु0310-4 (मु0)-नाकाई-03-39/2017-5761,	45.0319 4 Lacs	Nil	06.06.2018	.	.	.	.	0.42772	0.42772	0.42772

- 1 कार्य विशिष्टियों के अनुरूप पूर्ण कर लिया गया है।
- 2 बाथ में MQMU/PQM/E से संगठित कोई सुधार प्रतिवेदन लंबित नहीं है।
- 3 अनुमोदित परिमाण विपन्न की कुल राशि प्रशासनिक स्वीकृति की राशि से 20% अधिकताप सीमा के भीतर है साथ ही अनुमोदित परिमाण के भर्तों की मात्रा का विस्तार नहीं किया गया है।
- 4 अनुलग्नक-प्रशासनिक स्वीकृति का पत्र, अनुमोदित परिमाण विपन्न एवं एकरतनामा की अभिप्रमाणित प्रति।

Sheikhpura

R.W.D.(W) Division,
Sheikhpura

Executive Engineer
R.W.D. (W) Division,
Sheikhpura

FORM GFR 19-A

(See Government of India's Decision (I) below Rule- 150)

Form of Utilization Certificate upto the date of **04.04.2024**

Sl. No.	Name of Scheme	Sanction No. & Date with Amount (In lacs Rs.)	Amount Received (In Lacs Rs.)	Particulars
1	Construction of Rural Roads under State Schemes, Maint. Fund.	O/B up to 2022-23	0.000	Certified that out of Rs.0.000 lacs of grants- in- favour of Executive Engineer, R.W.D. (W) Division, Sheikhpura. Bihar a sum of Rs.0.000 lacs has been utilized for the purpose of State Scheme Maintenance Fund schemes as given in the margin for which it was sanctioned and that the balance of Rs. Nil Lacs remaining unutilized at the end of the period under report.

Total =0.000

2. Certified that I have satisfied myself that the conditions on which the grants-in-aid was sanctioned have been duly fulfilled. are being fulfilled and that I have exercised the following checks to see that the money was actually utilized for the purpose for which it was sanctioned.



Kind of Checks exercise:-

- Works have been supervised by Executive Engineer/ Superintending Engineer.
 - Periodical inspection has been conducted by Executive Engineer/ Superintending Engineer.
 - Construction materials have been tested.
 - Measurements have been recorded in the MBs and test check conducted by the Assistant Engineer/ Executive Engineer.
- v) All other codal formalities have been observed.

3. Physical progress achieved:-

- Construction of Road works.
- Construction of CD works.


D.A.O.
R.W.D.(W) Division
Sheikhpura


Executive Engineer
R.W.D. (W) Division.
Sheikhpura


बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक - मु० अ०-६ (गु०)-नाबार्ड-०३-३९/२०१७

/पटना, दिनांक-

प्रेषक,

संजय कुमार, भा० प्र० से०

अपर सचिव।

आंतरिक विनियम सलाहकार द्वारा
अनुमोदित रूप से प्रामाणिक

सेना में,

महालेखाकार, बिहार

वीरचन्द पटेल गद्य, पटना।

विषय:- योजना शीर्ष ४५१५-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-१०३-ग्राम विकास-राज्य

योजना-०१०५-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट-१ के रूप में संलग्न सूची के अनुरूप) कुल ८७ पथ निर्माण योजनाओं पर पथवार प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महाराज,

निदेशानुसार योजना शीर्ष ४५१५-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-१०३-ग्राम विकास-राज्य योजना-उप शीर्ष-०१०५-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उप शीर्ष के अन्तर्गत बिहार राज्य के विभिन्न जिलों में (परिशिष्ट-१ के रूप में संलग्न सूची के अनुरूप) कुल ८७ पथ निर्माण योजनाओं जिसकी लम्बाई ८४.७६६ कि०मी० एवं राशि रु० ५३.३०८५९६७ करोड़ (तिरपन करोड़ तीस लाख पैंसठ हजार नौ सौ सड़सठ रु० मात्र) है-हेतु पथवार प्रशासनिक स्वीकृति प्रदान की जाती है।

परिशिष्ट-१

नाबार्ड संपोषित योजना अन्तर्गत वित्तीय वर्ष २०१७-१८ के लिए प्रशासनिक अनुमोदित योजनाओं की सूची :-

Sl. No.	District	Works Division	Block	MMGSY CNCPL No.	Name of Road	Length (K.M)	TA Amount (In Lacs)	Amount Lac/K.M
1	2	3	4	5	6	7	8	9
1	Patna	Patna	Fatuha	S038	Saidpur Chandasi Path to Yamnagura	0.555	38.482	69.3369369
2	Patna	Patna	Khushrupur	S04	NH-30 to 100m Aage (Nagmausa Taraf) to Harijan Tola	0.515	36.039	69.9786403
3	Patna	Patna	Daniyawar	S06	NH-30A Jodhan Bigha	0.525	34.848	66.3771429
4	Patna	Danapur	Maner	S030	Maner-Haldichapra Road to Dhajawa tola	1.00	69.86850	69.8685
5	Patna	Danapur	Bihta	S042	Bihta Bikram Road to Kanchanpur Yadav Tola	1.10	68.48430	62.2584545
6	Patna	Masaurhi	Punpun	S03	Pothi Bripur Path to Parthu main Road Mahadalit tola.	1.00	59.90840	59.9084
7	Patna	Masaurhi	Masaurhi	S033	Nadani Bhagwananj Path to Nadaura.	0.15	20.92597	59.7884857
8	Patna	Masaurhi	Dhanarua	S024	Sowai Mode to Tadwan	2.10	127.44	60.6857143
9	Patna	Paliganj	Naubatpur	S020	Bari Tairaila to Bedulli	1.06	65.80	62.0754717
10	Patna	Paliganj	Dulhin Bazar	S016	Pali Masaurhi Road to Shihi Takiya (Nawada)	1.10	61.53	55.9363636
11	Patna	Paliganj	Naubatpur	S014	Gouwan Palta Chhitani Road to Navadilhan	0.55	30.90	56.1818182
12	Patna	Paliganj	Bikram	S026	Tiluchak Sundarpur road to Taripur	0.3	22.80250	76.008
13	Lakhisarai	Lakhisarai	Chanan	S024	PMGSY Malva to South Manjhi tola Malva	0.720	40.774	56.6305556

Sl. No.	District	Works Division	Block	PMGSY CNOPL No.	Name of Road	Length (KM)	TA Amount (In Lacs)	Amount Lac/KM
1	2	3	4	5	6	7	8	9
14	Lakhisarai	Lakhisarai	Lakhisarai	S013	T012 ODR to Saaroaro Itarijan Tola	1.125	68.519	60.9057778
15	Lakhisarai	Lakhisarai	Ramgarh Chowk	S015	L033 to Ramnagar	0.790	46.503	58.864557
16	Lakhisarai	Lakhisarai	Suryagarha	S031	L049 Sahur to Jagira	0.620	39.752	64.116129
17	Lakhisarai	Lakhisarai	Halsi	S011	Sehna Salsunta Nahar Road to Banjipur.	1.610	78.99	49.0621118
18	Lakhisarai	Lakhisarai	Pipariya	S01	Middle School Diyna Pipariya to Karari Pipariya	1.865	135.95	72.895442
19	Lakhisarai	Lakhisarai	Ramgarh Chowk	S02	L056 to Bhamariya Manjhi Tola	1.600	93.44	58.40
20	Katihar	Katihar	Hasanganj	S01	Madarsa Chowk to Baghabari	1.05	67.296	64.0914285
21	Katihar	Katihar	Hasanganj	S012	T01 to Naga Tola	0.575	38.608	67.1443478
22	Sheikhpur	Sheikhpur	Barbiga	S005	Barbiga Toy path Terarour more to Saraiya.	0.936	56.075	59.909188
23	Sheikhpur	Sheikhpur	Chewara	S038	Ekray Path to Kemra Mushari	0.745	48.460	65.0469799
24	Sheikhpur	Sheikhpur	Sheikhpur	S010	Melus Chimani par to Manisuri via Nawada	0.730	43.348	59.3808219
25	Supaul	Triveniganj	Triveniganj	S129	PWD Parsahi sadak Kuwar Yadav ke ghar to Parsahi Mehan Yadav Tola tak.	0.846	60.76	71.820331
26	Chapra	Chapra-2	Jalalpur	S016	Bangra to Bangra -4.	1.195	68.713	57.5020921
27	Chapra	Chapra-2	Jalalpur	S054	Dhenki to Devbariya tak.	0.500	28.174	56.348
28	Chapra	Chapra-2	Lahladpur	S049	Purusotampur Sonin PMGSY Kishanpur Lauxar Panchayat Bhawan se Bhagthaliya khas.	0.515	39.073	75.8699029
29	Chapra	Chapra-1	Garkha	S057	Dhanaura High School to Dhanaura Jaggu Singh ke ghar tak.	0.39	31.015	79.525641
30	Chapra	Chapra-1	Sadar Chapra	S036	Middle School Fakuli to Umdha.	1.055	58.328	55.2872038
31	Chapra	Chapra-1	Sadar Chapra	S019	Mathiya Gramin Sadak to Hasanpurva Chhat Talab tak.	0.700	44.519	63.5985714
32	Chapra	Madhaura	Amnaur	S062	Raipura Mura PMGSY Path to Hakuna Paschim Tola.	0.97	68.439	70.5556701
33	Chapra	Madhaura	Taraiya	S034	Yakuchak Pachaur PMGSY to Pekkara tak	0.605	25.623	42.3520661
34	Chapra	Madhaura	Panapur	S036	Ubhawa Bhoia Pandey ke ghar to Masjid tak.	0.445	29.037	65.2516854
35	Chapra	Madhaura	Panapur	S030	Totha PMGSY to Simari Pakki Salak.	0.999	62.17	62.2322322
36	Chapra	Sonpur	Masker	S18	Maker-Mahesh Chapra PMGSY to Purshotimpur Bazar	1.595	104.87	65.7492163

Sl. No.	District	Works Division	Block	MMGSY CNCFI. No.	Name of Road	Length (K.M)	TA Amount (In Lac)	Amount Lac/K.M
1	2	3	4	5	6	7	8	9
37	Chapra	Sompur	Maker	S001	Bishampur Piprahi PMGSY Sadak to Gandak Nahar	3.375	194.45	57.6148148
38	Chapra	Sompur	Dariyapur	S04	Khajauli PMGSY path se Ghanechakra gramin path tak	1.845	120.12	65.1056911
39	Chapra	Chapra-1	Nagra	S011	Chapra-Masrakh PWD Road (Yogendra Singh ke Ghar) to Afsar Purab Tola	2.040	110.32	54.0784314
40	Chapra	Chapra-1	Nagra	S015	T05 Sargatti PMGSY to takiya.	1.685	98.30	58.3382789
41	Chapra	Chapra-2	Baniyapur	S039	Dhobwal Sekhpura PMGSY se Gowa Piparpati Nagdevi Tola hote	1.950	114.43	58.6820513
42	Chapra	Chapra-2	Baniyapur	S054	Harpur Karah PMGSY se Ram Tola tak	1.690	108.43	64.1597633
43	Chapra	Chapra-2	Lahalsapur	S024	Ekma Masrakh PMGSY Sausa Transformer ke pass se Shambhu Chapra Khas tak	1.805	103.22	57.1855956
44	Chapra	Madhaura	Amzaur	S043	Salkhua Marhaura PMGSY Path to Parsa Bhatti PMGSY Road.	2.890	179.18	62.00
45	Chapra	Madhaura	Masrakh	S070	Nirsu dhala Pakki sadak to 40 RD Nahar Pul tak.	3.250	203.10	62.4923077
46	Chapra	Madhaura	Madhaura	S016	Silauri Paharpur PMGSY Path to Mathiya tak	2.550	134.16	52.6117647
47	Chapra	Madhaura	Masrakh	S021	Masrakh Sahajipur road to Sankauli PCC.	2.095	140.89	67.2505967
48	Chapra	Madhaura	Tarniya	S02	Bhataura Primary School to Bhataura Devi Aashan.	1.415	91.98	65.0035336
49	Muzaffarpur	Muzaffarpur East-1	Bandra	S031	Patsara dhobi tola samudaiye bhawan to Baisnathpur.	2.490	170.38	68.4257028
50	Muzaffarpur	Muzaffarpur East-1	Kurhani	S06	PMGSY (Khamuna Dih) to Harijan Dalit Basti	0.850	54.30	63.8788235
51	Muzaffarpur	Muzaffarpur East-1	Bandra	S032	Karmait Kewatsa path to Marha tola	0.650	46.74	71.9076923
52	Muzaffarpur	Muzaffarpur East-1	Kurhani	S05	MMGSY (Paltan Chaudhary ke Ghar) to Jairam Tola (Khamuna Dih)	0.57	45.70	80.1754386
53	Muzaffarpur	Muzaffarpur East-1	Sakra	S030	PMGSY Rasulpur Maniyari to Muslim Tola.	1.125	80.14	71.2355556
54	Muzaffarpur	Muzaffarpur East-1	Saraiya	S051	Karja Jaitpur road Nuwada kedar misra ke ghar to Repura muslim tola tak.	1.782	109.12	61.2345679
55	Muzaffarpur	Muzaffarpur East-1	Saraiya	S098	Nargi Jivnath PMGSY road to Govindpur se Khaira road tak.	2.207	129.410	58.6361577

SL No.	District	Works Division	Block	MMGSY CNCL NO.	Name of Road	Length (K.M)	TA Amount (In Lacs)	Amount Lac/K.M
1	2	3	4	5	6	7	8	9
56	Muzaffarpur	Muzaffarpur East-1	Sakra	S033	Middle school Majhauria to Satpura murali block siman lak.	2.260	154.860	68.5221239
57	Muzaffarpur	Muzaffarpur East-1	Musahari	S046	SI1102 Ramesh Thakur ke Dalun to Patahi Jagannath Late Kalyan Thakur ke ghar tak.	1.00	76.04	76.04
58	Begusarai	Teghara	Bachhwara	S029	Tura to Maranchi	0.51	35.86	70.3137255
59	Samastipur	Samastipur	Samastipur	S026	L073 Chaknoor to Sahni Tola	0.700	47.63	68.0428571
60	Begusarai	Teghara	Bhagwanpur	S049	S048 Mahadalit tola to Larwapur Bandh via house of Murna Mahto (Tolan)	1.340	92.57	69.0820896
61	Begusarai	Teghara	Bhagwanpur	S048	Naula pul to Kharmooli via Jokia Bandh, Khakhara Gusha	4.105	249.01	60.6601705
62	Madhubani	Fulpara	Khutsuna	S060	Malik Arjun Thakur Ghar to Kolhatta	1.901	133.73	70.3471857
63	Siwan	Siwan-1	Hasanpura	S021	Arjal Bazar to Mandrauli Manja Bhediari Tola	1.000	65.736	65.736
64	Siwan	Siwan-1	Siswan	S026	Naya Gao PWD Road to Chhotaki Nawada via Badaki Nawada	0.500	33.568	67.136
65	Siwan	Siwan-1	Siwan	S02	Siwan Lakadi Path ke Orma Uttar Tola Kothi to Bindusar Hamid	1.050	69.866	66.5390476
66	Siwan	Siwan-1	Siswan	S05	Siswan Chapra CMDG Road to Tolapur	0.800	54.443	68.05375
67	Siwan	Siwan-1	Hasanpura	S027	Laheji Bazar to Mandrauli	1.000	67.513	67.513
Total						84.766	5330.65967	

2. इस योजना को दो वित्तीय वर्ष 2017-18 एवं 2018-19 में पूरा किये जाने का लक्ष्य है।

3. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, संबंधित कार्य प्रमंडल, योजना की विस्तृत कार्य योजना तैयार करेंगे तथा उसके अनुरूप कार्यों को समयबद्ध ढंग से पूर्ण करना सुनिश्चित करेंगे।

4. कार्यपालक अभियंता, संबंधित कार्य प्रमंडल सुनिश्चित करेंगे कि स्वीकृत पथ किसी अन्य योजना के अन्तर्गत सम्मिलित नहीं है।

5. कार्यपालक अभियंता, संबंधित कार्य प्रमंडल, योजना के कार्य सम्पादन हेतु निकासी एवं व्ययन पदाधिकारी होंगे।

6. कार्य ई-निविदा के माध्यम से Standard Bidding Document के आधार पर कराया जायेगा।

7. कार्यों की गुणवत्ता सुनिश्चित करने की जिम्मेदारी संबंधित कार्यपालक अभियंता की होगी। किये गये कार्यों का भुगतान भुगतान के जॉचफल के गुण-दोष के आधार पर किया जायेगा।

8. योजना के क्रियान्वयन से पूर्व इस पर स्थायी पदाधिकारी से प्राथमिक स्वीकृति प्राप्त कर ली जायेगी। प्राथमिक स्वीकृति के समय सभी राशियाँ प्राधिकार IRC SP-72 वर्ष 2015 एवं IRC SP-62 वर्ष 2014 के तकनीकी प्रावधानों का अक्षरशः अनुपालन सुनिश्चित करेंगे।

9. इस योजना का व्यय योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर वृज्जीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (गारंटीड ऋण संपोषित योजना)-उपशीर्ष जिसका विपक्ष कोड P-4515001030105 एवं स्कीम कोड-5369 के अन्तर्गत वित्तीय वर्ष 2017-18 में उपबंधित राशि से विकलनीय होगा।

10. योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर वृज्जीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (गारंटीड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत वित्तीय वर्ष 2017-18 में 454.31 लाख रुपये का बजट उपबंध स्वीकृत है।

11. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, संबंधित कार्य प्रमंडल, द्वारा योजना का भौतिक एवं वित्तीय प्रगति प्रतिवेदन प्रत्येक माह के 10 तारीख तक निश्चित रूप से कर्मशः संबंधित अधीक्षण अभियंता एवं संबंधित मुख्य अभियंता, पटना के माध्यम से विभाग को उपलब्ध कराया जायेगा।

12. इन योजनाओं का निर्माण नाबार्ड के तहत करवाये जाने के प्रस्ताव पर माओ मुख्यमंत्री महोदय, बिहार सरकार का अनुमोदन प्राप्त है।

13. इन पथवार योजनाओं के प्रशासनिक स्वीकृति के प्रस्ताव पर सचिका सं०- गु० अ०-४ (गु०) नाबार्ड-०३-३९/२०१७ के पृ० सं०-१२/टि० पर दिनांक ०७.०४.१७ को अनुमोदन प्राप्त है।

14. बिहार कोषागार संहिता में निहित प्रावधानों के आलोक में बजट प्रावधान के अंतर्गत छी राशि की निकासी की जाय।

15. वित्त विभाग के संकल्प संख्या-४-४५/९४-३०१ वि (२) दिनांक ३१.०१.१९९५ एवं वित्त विभाग के पत्रांक स्कीम (५)-११-२००५-५०९० वि (२) दिनांक १५.०९.०५ एवं २९५ दिनांक २४.०३.१५ के आलोक में तथा वित्त विभाग के संकल्प सं० ९५ दिनांक ०३.०१.२००८ में निहित निर्देशों का अक्षरशः पालन किया जाय तथा बिहार वित्त नियमावली के सुसंगत प्रावधानों के आलोक में योजना में उपबंधित राशि की उपलब्धता के आधार पर व्यय की जाय। यह आदेश आंतरिक वित्तिय सलाहकार की सहमति प्राप्त कर निर्गत किया जा रहा है। आंतरिक वित्तिय सलाहकार की सहमति सचिका सं०- गु० अ०-४ (गु०) नाबार्ड-०३-३९/२०१७ के पृष्ठ संख्या-१५/टि० पर दिनांक- २३.०४.१७ को प्राप्त है।

16. यह राशि उसी मद में खर्च की जायेगी, जिसके लिए पुनर्वित्तियोजित की गयी है, अन्य में नहीं।

17. योजना के लिए संबंधित कार्यपालक अभियंता से विस्तृत कार्य योजना मांगी जायेगी एवं प्राक्कलन की विशिष्टताओं के अनुसार निर्धारित समय सीमा के अंदर कार्य पूर्ण कराना सुनिश्चित किया जाय।

18. योजना के कार्यान्वयन के क्रम में इनका निर्धारित निरीक्षण (नियमित अंतराल पर) अनिवार्य रूप से किया जाय तथा प्रतिवेदन अभिलेखबद्ध किया जाय।

19. वित्त विभाग के पत्रांक-७७०, दिनांक २०.०९.११ के द्वारा सूचित किया गया है कि नाबार्ड से RUDF के अंतर्गत नई परियोजनाओं की प्रशासनिक अनुमोदन प्राप्त करने के उपरान्त ही स्वीकृति हेतु नाबार्ड को भेजी जाये।

विश्वात्मनाजन

ह०/-
(संजय कुमार)
अपर सचिव

पत्रांक- गु० अ०-४ (गु०)-नाबार्ड-०३-३९/२०१७

/पटना, दिनांक-

प्रतिलिपि- सभी संबंधित कोषागार पदाधिकारी, जिला कोषागार/उप कोषागार को सूचना एवं आवश्यक कार्यवाई हेतु प्रेषित।

ह०/-
अपर सचिव

पत्रांक- गु० अ०-४ (गु०)-नाबार्ड-०३-३९/२०१७

/पटना, दिनांक- ५/०८/१७

प्रतिलिपि- माननीय मंत्री के आप्त सचिव, ग्रामीण कार्य विभाग/प्रधान सचिव, योजना एवं विकास विभाग/वित्त विभाग (आय-व्यय शाखा)/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/गतिमंडल सचिवालय एवं सभन्वय विभाग/कार्मिक एवं प्रशासनिक सुधार विभाग, सभी संबंधित प्रमण्डलीय आयुक्त/सभी संबंधित जिला पदाधिकारी/सभी संबंधित उप विकास आयुक्त/अभियंता प्रमुख ग्राम का० वि०, बिहार, पटना/सभी संबंधित मुख्य अभियंता, पटना, ग्रामीण कार्य विभाग/गु० अ०-४ (मुख्यालय), ग्राम का० वि०/सभी संबंधित अधीक्षण अभियंता, ग्राम का० वि०, कार्य अंचल/सभी संबंधित कार्यपालक अभियंता, ग्राम का० वि० कार्य प्रमंडल/मुख्य महाप्रबंधक नाबार्ड, बिहार क्षेत्रीय कार्यालय, (पौरा कमलेका, पंचवी मंजिल) डाक बंगला रोड, पटना को सूचना एवं आवश्यक कार्यवाई हेतु प्रेषित। अतिरिक्त नॉडल, ग्रामीण कार्य विभाग को विभाग के वेबसाईट पर अपलोड करने हेतु प्रेषित।

अपर सचिव

**BILL OF QUANTITY FOR
CONSTRUCTION OF ROAD**

James A. Smith

Stacy Hest 9/12
Executive Engineer
R.W.D. (W) DIVISION
James A. Smith 9/12
9/12

BRICS NABARD
(Rural Works Department, Govt. of BIHAR)
BILL OF QUANTITIES (BOQ)

Name of Road : Ekray Path To Kemra Musahari.

Length of Road : 0.745 Km

District : Sheikhpura

L / TR No. :

Block : Ariyari

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
1	Setting Out Setting Out as MORD Specification 100 Item Nos (i), (ii), (iii) & (iv)				
	Construction of Reference & Working Benchmarks	0.745	Km	4089.38	Rupees Four Thousand Eighty Nine & Paise Thirty Eight Only
	Construction of Reference Pillars/Burjees	0.745	Km	1849.52	Rupees One Thousand Eight Hundred Forty Nine & Paise Fifty Two Only
2	Clearing and Grubbing Road Land Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201.	0.45	Hect.	46416.81	Rupees Forty Six Thousand Four Hundred Sixteen & Paise Eighty One Only
3	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5.	130.38	Cum	43.68	Rupees Forty Three & Paise Sixty Eight Only
4	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. a) For 1000 m lead	1685.95	Cum	171.71	Rupees One Hundred Seventy One & Paise Seventy One Only

for and on behalf of

Executive Engineer
R.W.D. (W) DIVISION

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
5	<u>Construction of Subgrade & Earthen Shoulder</u> Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	719.68	Cum	215.19	Rupees Two Hundred Fifteen & Paise Nineteen Only
6	<u>Granular Sub-base with Well Graded Material (Table 400.1) Gr.II</u> Construction of granular sub-base by providing well graded material (Crushed Stone Aggregates and Local Sand), spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401	88.53	Cum	1275.08	Rupees One Thousand Two Hundred Seven Five & Paise Eight Only
7	<u>WBM Grading 3</u> Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	57.00	Cum	1731.99	Rupees One Thousand Seven Hundred Thirty One & Paise Ninety Nine Only

Amarsingh

9/11/12
 Executive Engineer
 R.W.D. (W) DIVISION
9/11/12

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
8	Cement Concrete Pavement M-30 Construction of un-reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M-30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501.	455.94	Cum	6712.78	Rupees Six Thousand Seven Hundred Twelve Paise Seventy Eight Only
9	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703				
	Ordinary Kilometer Stone (Precast)	1	Each	2304.97	Rupees Two Thousand Three Hundred Four & Paise Ninety Seven Only
	200 m stone (precast)	3	Each	619.34	Rupees Six Thousand Nineteen & Paise Thirty Four Only
10	Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	14	Each	509.63	Rupees Five Hundred Eight & Paise Eight Only

[Handwritten Signature]

[Handwritten Signature]
 Executive Engineer
 R.W.D. (W) DIVISION
 JALPAIGURI

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
11	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701 (For culverts)	44.64	Sqm	105.21	Rupees One Hundred Five & Paise Twenty One Only
12	Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	176	Per Cm Ht. Letter	0.50	Rupees Nil and Paise Fifty Only
13	Providing and fixing of typical NABARD informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2	Each	10760.340	Rupees Ten Thousand Seven Hundred Sixty Paise Thirty Four Only
14	Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801				

Sanjay Singh

Executive Engineer

R.W.D.W. DIVISION


20/11/20


Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
	600 mm equilateral triangle	4	Each	3832.61	Rupees Three Thousand Eight Hundred Thirty Two & Paise Sixty C Only
	800 mm x 600 mm rectangular	2	Each	4526.94	Rupees Four Thousand Five Hundred Twenty Six & Paise Ninety Four Only
15	Providing and laying reinforced cement concrete pipe NP3 for culverts for irrigation purpose <u>300mm dia Pipe</u>	22.50	RM	797.11	Rupees Seven Hundred Ninety Seven & Paise Eleven Only
16	Earthwork in excavation of foundation of structures as per drawing and technical specifications Clause 1104, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material.	67.08	Cum	266.58	Rupees Two Hundred Sixty Six & Paise Fifty Eight Only
17	Providing PCC M15 :- Providing PCC M15 (1:2.5:5) concrete for plain/reinforced concrete in Foundation complete as per drawings and technical specifications.	5.30	Cum	5407.44	Rupees Five Thousand Four Hundred Seven & Paise Fourty Four Only
18	Brick masonry work in cement mortar in (1:4) foundation complete excluding pointing and plastering as per drawing and technical specification Clauses 600, 1202 & 1203.	33.22	Cum	5998.61	Rupees Five Thousand Nine Hundred Ninety Eight & Paise Sixty One Only
19	Brick masonry work in cement mortar in (1:4) substructure complete excluding pointing and plastering as per drawing and technical specification Clauses 602, 603, 604, 1202 & 1204.	20.32	Cum	6271.92	Rupees Six Thousand Two Hundred Seventy One & Paise Ninety Two Only
20	Providing & Laying ISI marks* Cement concrete hune pipe (Burried conduits) on first class bedding of granular material including fixing collar with cement sand mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry work in head wall and parapets (* See general notes) <u>1000mm dia pipe</u>	15.00	RM	3977.95	Rupees Three Thousand Nine Hundred Seventy Seven & Paise Ninety Five Only
21	Laying (First Class) bedding on wel compacted sand, moorum or approved granular material as per Clause 1105 (i) Sand Filling (Coarse Sand, Kiu)	9.74	Cum	471.54	Rupees Four Hundred Seventy One & Paise Fifty Four Only

Forwarded

Executive Engineer
DIVISION

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
22	Filling in foundation trenches as per drawing and technical specification clause 305.3.9 (i) Sand Filling (Local Sand)	15.28	Cum	471.54	Rupees Four Hundred Seventy One & Fifty Four Only
23	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4.	5.76	Cum	6257.97	Rupees Six Thousand Two Hundred Fifty Seven & Paise Nine Only
24	Plastering with cement mortar (1:4), 15 mm thick on brickwork in substructure as per technical specification clauses 613.4 & 1204.	40.32	Cum	161.44	Rupees One Hundred Sixty One & Paise Four Only
25	Dismantling of existing structures like culverts, bridges retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lift and lead of 1000m as per Technical Specification Clause 202.	0.60	Cum	434.82	Rupees Four Hundred Thirty Four & Paise Eighty Two Only
26	Dismantling of existing structures like culverts, bridges retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lift and lead of 1000m as per Technical Specification Clause 202.	17.33	Cum	312.65	Rupees Three Hundred Twelve & Paise Sixty Five Only
27	Removing all types of Hume pipes and stacking within alead of 1000m including Earthwork and Dismantling of Masonry works as per Technical Specification Clause 202. <u>Upto 600mm dia Hume Pipe</u>	5.00	RM	158.59	Rupees One Hundred Fifty Eight & Paise Five Nine Only


 Executive Engineer
 R.W.D. DIVISION
 9/12/12


 Engineer

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
<u>Five Year Maintenance</u>					
28	Maintainance for 1st year	0.745	Km	31797.32	Rupees Thirty O Thousand Seve Hundred Ninety Sa & Paise Thirty T Only
29	Maintainance for 2nd year	0.745	Km	37244.30	Rupees Thirty Se Thousand Two Hur Forty Four & Pai Thirty Only
30	Maintainance for 3rd year	0.745	Km	51613.42	Rupees Fifty On Thousand Six Hun Thirteen & Paise F Two Only
31	Maintainance for 4th year	0.745	Km	58138.26	Rupees Fifty Eig Thousand One Hun Thirty Eight & Pa Twenty Six Only
32	Maintainance for 5th year	0.745	Km	65390.60	Rupees Sixty Fiv Thousand Three Hundred Ninety & P Sixty Only

Note :- (i) 10.00% (Ten Percent) Below in all over items.

(ii) N.I.T., A/A, T/S and condition of SBD are part of Agreement.

9/12/12
Executive Engineer
R.W.D.(W) Division,
Sheikhpura
9/12/12

for over R. Bil