

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

Agreement

Agreement No :-

MBD/MR/

of 2020-21

Name of work :-

- (1) Katsari to Bhataha
- (2) Maksudpur Karariya to Tetariya
- (3) Dhankaul to Minapur
- (4) Basahiya shekh to Rasoula via Gadhwala tola
- (5) Basant Bazar to Chandiha Punarwas
- (6) Chiraiya PWD road to Barahi Mohan road
- (7) Basantpath to Piprahi Punarwas
- (8) Sonaul High school to Barahi Jagdishpur

Name of Agency :- M.S. Enterprises, 53 Satyam Apartment, Kaviraman Path Nageshwar Colony, Boring road Patna.

Date of Start :- 07.12.20

Date of Completion :- 06.09.21

SD :- 38,63,500/-

A.P.G :- 48500/-

Total :- 39,12,000/-

This Agreement, made on the 07 Day of December 2020 between Executive Engineer, Rural works Department, Works Division, Sheohar of the one part and M.S. Enterprises, 53 Satyam Apartment, Kaviraman Path Nageshwar Colony, Boring road Patna. Whereas the Employer is desirous that the Contractor execute the work under M/R Construction & CD Work of (1) Katsari to Bhataha (2) Maksudpur Karariya to Tetariya (3) Dhankaul to Minapur (4) Basahiya shekh to Rasoula via Gadhwala tola (5) Basant Bazar to Chandiha Punarwas (6) Chiraiya PWD road to Barahi Mohan road (7) Basantpath to Piprahi Punarwas (8) Sonaul High school to Barahi Jagdishpur, and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein at a cost of Rupess 772,68,067/- (Seven Crore seventy two lakh and eight thousand six hundred and eighty seven only).

M/S M.S. ENTERPRISES

NOW THIS AGREEMENT WITNESSETH as follows.

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of Contract hereinafter referred to and they shall be deemed to form and be read and construed a part of this agreement.
2. In consideration of the payment to be made by the employer to the Contractor as herein after mentioned, the Contractor hereby covenants with employer to execute and complete the work and remedy any defects therein conformity in all aspects with the provision of the Contractor.
3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following document shall be deemed to form and be read and construed as part of this Agreement viz.

- (i) Letter of Acceptance
- (ii) Notice to proceed with the works
- (iii) Contractor's Bid
- (iv) Contract Data
- (v) Special conditions of contract and general conditions of contract.
- (vi) Additional condition
- (vii) Drawings
- (viii) Bill of Quantities and
- (ix) Any other document listed in the contract data as forming part of the contract.

In witness, where of the parties there to have caused this Agreement to be executed the day and year first before written.

The Common seal of

Was hereunto affixed in the presence of

Signed, Sealed and Delivered by the said

In the presence of

Binding Signature of Employer

Binding Signature of Contractor

M/s M.S. ENTERPRISES
Proprietor

10/11/20
10-11-20

Agreement

1. Name of work :- (1) Katsari to Bhataha
(2) Maksudpur Karariya to Tetariya
(3) Dhankaul to Minapur
(4) Basahiya shekh to Rasoula via Gadhma tola
(5) Basant Bazar to Chandiha Punarwas
(6) Chiraiya PWD road to Barahi Mohan road
(7) Basantpath to Piprahi Punarwas
(8) Sonaul High school to Barahi Jagdishpur
2. Agreement No. :- MBD/MR/ 02 of 2020-21
3. Name of Agency :- M.S. Enterprises, 55 Satyam Apartment, Kaviraman Path Nageshwar Colony, Boring road Patna.
4. Construction Cost :- 5,61,99,520 = 00
5. Maintenance Cost :- 2,10,68,547 = 00
- Total :- 7,72,68,067 = 00
6. Security Deposit :- SD :- 38,63,500 = 00
- A.P.G :- 48,500 = 00
- Total :- 39,12,000 = 00
7. Work allotted rate :- 0.25 % Below
8. The Employer shall retain S.D. of 5 % (Five percent) and performance security of 3% of the amount from each payment due to the contractor until completion of the whole of the construction work.
9. Date of written order to commence :- 07.12.2020
10. Time required for the work from date of written order to Commence :- 09 Months. (06.09.21)
11. Total No. items:- (Seventeen)

Note- MBD Rules Terms and Conditions will be applicable

M/s M.S. ENTERPRISES
Mangal Singh
Proprietor
Contractor

02
Executive Engineer
R.W.D. Works Division
Sheohar

114	Providing and fixing of typical MGSY informational sign board with Logo as per MORD specifications and drawing. Three MS plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5mm size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tube posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	4.00	nos	9497.60	37990.40	INR Thirty Seven Thousand Nine Hundred & Ninety and Paise Forty Only
115	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	28.80	Cum	5213.04	150135.55	INR One Lakh Fifty Thousand One Hundred & Thirty Five and Paise Fifty Five Only
116	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	201.60	Cum	175.20	35320.32	INR Thirty Five Thousand Three Hundred & Twenty and Paise Thirty Two Only
117	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	585.60	Sqm	97.19	56944.46	INR Fifty Six Thousand Nine Hundred & Fourteen and Paise Forty Six Only
118	Maintenance for 1st year	1.00	Year	115295.00	115295.00	INR One Lakh Fifteen Thousand Two Hundred & Ninety Five Only
119	Maintenance for 2nd year	1.00	Year	338603.00	338603.00	INR Three Lakh Thirty Eight Thousand Six Hundred & Three Only
120	Maintenance for 3rd year	1.00	Year	795276.00	795276.00	INR Seven Lakh Ninety Five Thousand Two Hundred & Seventy Six Only
121	Maintenance for 4th year	1.00	Year	403765.00	403765.00	INR Four Lakh Three Thousand Seven Hundred & Sixty Five Only
122	Maintenance for 5th year	1.00	Year	875913.00	875913.00	INR Eight Lakh Seventy Five Thousand Nine Hundred & Thirteen Only
123	1% Labour	1.00	RS	94324.83	94324.83	INR Ninety Four Thousand Three Hundred & Twenty Four and Paise Eighty Three Only
124	12% GST	1.00	RS	1131897.96	1131897.96	INR Eleven Lakh Thirty One Thousand Eight Hundred & Ninety Seven and Paise Ninety Six Only
125	Basantpur Bazar To Chandih Punerwas					


 Manoj Singh
 Proprietor

M/s M.S. ENTERPRISES
 Manoj Singh
 Proprietor

126	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.64	ha	51133.76	32725.61	INR Thirty Two Thousand Seven Hundred & Twenty Five and Paise Sixty One Only
127	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and loads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1344.00	Cum	176.86	237699.84	INR Two Lakh Thirty Seven Thousand Six Hundred & Ninety Nine and Paise Eighty Four Only
128	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	46.48	Cum	2144.81	99690.77	INR Ninety Nine Thousand Six Hundred & Ninety and Paise Seventy Seven Only
129	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	43.84	Cum	3869.94	169658.17	INR One Lakh Sixty Nine Thousand Six Hundred & Fifty Eight and Paise Seventeen Only
130	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	164.10	Cum	3573.25	586370.33	INR Five Lakh Eighty Six Thousand Three Hundred & Seventy and Paise Thirty Three Only
131	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	2188.00	Sqm	44.27	96862.76	INR Ninety Six Thousand Eight Hundred & Sixty Two and Paise Seventy Six Only
132	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrifloc broom as per technical specification clause 503.	2188.00	Sqm	14.86	32513.68	INR Thirty Two Thousand Five Hundred & Thirteen and Paise Eighty Eight Only

W/s M...
Moufi Ling
Proprietor

आम का वि. व. प्र.
शिवराम

133	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509.	2188.00	Sqm	220.34	482103.92	INR Four Lakh Eighty Two Thousand One Hundred & Three and Paise Ninety Two Only
134	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.25 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydraulic broom as per technical specification clause 503.	12000.00	Sqm	12.44	149280.00	INR One Lakh Forty Nine Thousand Two Hundred & Eighty Only
135	Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	300.00	Cum	11258.22	3377466.00	INR Thirty Three Lakh Seventy Seven Thousand Four Hundred & Sixty Six Only
136	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. i) km Stone	4.00	nos	2382.27	9529.08	INR Nine Thousand Five Hundred & Twenty Nine and Paise Eight Only
137	iii) 200 m Stone	13.00	nos	632.95	8228.35	INR Eight Thousand Two Hundred & Twenty Eight and Paise Thirty Five Only
138	Retro-reflectORIZED Traffic Signs Providing and erecting direction and place identification retro-reflectORIZED sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	1.92	Sqm	12422.11	23850.45	INR Twenty Three Thousand Eight Hundred & Fifty and Paise Forty Five Only
139	Providing and fixing of retro-reflectORIZED cautionary, mandatory and informative signs as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 i) 600 mm equilateral & triangle	10.00	nos	3707.42	37074.20	INR Thirty Seven Thousand & Seventy Four and Paise Twenty Only
140	600 mm circular	10.00	nos	3503.96	35039.60	INR Thirty Eight Thousand & Thirty Nine and Paise Sixty Only

W/S M.S. EN
Manoj Singh
Proprietor



141	600 mm x 600 mm rectangular		10.00	nos	3674.84	36748.40	INR Thirty Six Thousand Seven Hundred & Forty Eight and Paise Forty Only
142	Reinforced cement concrete M15 grade boundary pillar/local stone of standard design as per IRC-25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704		48.00	nos	503.61	24269.28	INR Twenty Four Thousand Two Hundred & Sixty Nine and Paise Twenty Eight Only
143	Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/silage manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year		160.00	Each	819.92	131187.20	INR One Lakh Thirty One Thousand One Hundred & Eighty Seven and Paise Twenty Only
144	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes.		640.00	Sqm	733.44	470601.60	INR Four Lakh Seventy Thousand Six Hundred & Eighty One and Paise Sixty Only
145	Providing and fixing of typical MMSY Informatory sign board with Logo as per MCHD specifications and drawing. Three MS Plates of 1.5 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1703.1		4.00	nos	9537.31	38149.24	INR Thirty Eight Thousand One Hundred & Forty Nine and Paise Twenty Four Only
146	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1200.4		11.52	Cum	5213.04	60054.22	INR Sixty Thousand & Fifty Four and Paise Twenty Two Only
147	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications		80.64	Cum	184.46	14874.85	INR Fourteen Thousand Eight Hundred & Seventy Four and Paise Eighty Five Only
148	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701		234.24	Sqm	97.19	22765.79	INR Twenty Two Thousand Seven Hundred & Sixty Five and Paise Seventy Nine Only
149	Maintenance for 1st year		1.00	Year	112103.00	112103.00	INR One Lakh Twelve Thousand One Hundred & Three Only
150	Maintenance for 2nd year		1.00	Year	329276.00	329276.00	INR Three Lakh Twenty Nine Thousand Two Hundred & Seventy Six Only

MS M.S. ENTERPRISES
 Managing Director
 Proprietor



151	Maintenance for 3rd year	1.00	Year	832851.00	832851.00	INR Eight Lakh Thirty Two Thousand Eight Hundred & Fifty One Only
152	Maintenance for 4th year	1.00	Year	394301.00	394301.00	INR Three Lakh Ninety Four Thousand Three Hundred & One Only
153	Maintenance for 5th year	1.00	Year	913395.00	913395.00	INR Nine Lakh Thirteen Thousand Three Hundred & Ninety Five Only
154	1% Labour	1.00	RS	87617.49	87617.49	INR Eighty Seven Thousand Six Hundred & Seventeen and Paise Forty Nine Only
155	12% GST	1.00	RS	1051409.92	1051409.92	INR Ten Lakh Fifty One Thousand Four Hundred & Nine and Paise Ninety Two Only
156	Chiraiya PWD Road To Barahi Mohan Road					
157	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	0.19	ha	51133.76	9715.41	INR Nine Thousand Seven Hundred & Fifteen and Paise Forty One Only
158	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	407.40	Cum	176.86	72052.78	INR Seventy Two Thousand & Fifty Two and Paise Seventy Six Only
159	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	6.49	Cum	2104.31	13656.97	INR Thirteen Thousand Six Hundred & Fifty Six and Paise Ninety Seven Only
160	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	14.23	Cum	3783.25	53835.65	INR Fifty Three Thousand Eight Hundred & Thirty Five and Paise Sixty Five Only
161	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	23.86	Cum	3496.99	83438.18	INR Eighty Three Thousand Four Hundred & Thirty Eight and Paise Eighteen Only

M/s M.S. ENT.
Mangli Singh
Proprietor