

कार्यपालक अभियंता, का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ

पत्रांक 566 3-15/ बिहारशरीफ, दिनांक 28-5-2024

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बिहारशरीफ ।

सेवा में,

नोडल पदाधिकारी NABARD MAINTENANCE
ग्रामीण कार्य विभाग बिहार पटना।

विषय:- शीर्ष NABARD मरम्मति/अनुरक्षण योजनान्तर्गत पूर्ण पथों का 5-वर्षीय रूटीन अनुरक्षण कार्य के कार्यान्वयन हेतु अधियाचना पत्र समर्पित करने के संबंध में।

महाशय,


NABARD मरम्मति/अनुरक्षण योजनान्तर्गत पूर्ण पथों का 5-वर्षीय रूटीन अनुरक्षण कार्य संवेदक द्वारा कराये गये पथों में एकरारनामा के अनुसार राशि की अधियाचना पत्र समर्पित की जा रही है।

अनुरोध है कि 5-वर्षीय रूटीन अनुरक्षण कार्य कराने हेतु संलग्न सूची के अनुसार राशि उपलब्ध कराने की कृपा की जाय ताकि संवेदक को भुगतान किया जा सके।

अनु०:- यथोक्त।


28/5/24

विश्वासभाजन


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बिहारशरीफ
28/5/24

FORM GFR 19-A

(See Government of India's Decision (1) below Rule-150)

Form of Utilisation Certificate up to the month of -11.05.2024

(NABARD MAINTENANCE FUND)

PIU- BIHARSHARIF

Year-2024-25

Sl. No.	Name of Scheme	Sanction No. & Date with Amount (in Rs. Lacs)	Amount Received (in Rs. Lacs)	Particulars	Remarks
1	Construction of Rural Roads under NABARD (4515) MAINTENANCE FUND	Order No-8466 Date-30.01.2023	22.48793	Certified that out of Rs 22.48793 received & balance during the years 2024-25 in favour of Ex. Engineer, R.W.D. Works Division Biharsharif, sum of Rs 22.48793 has been utilized for the purpose of NABARD MAINTENANCE FUND scheme as given in the margin for which it was sanctioned and that the balance of Rs 0.0 lacs remaining unutilized at the end of the period under- 11.05.2024	
	Total Rs.		22.48793		

2 Certified that I have satisfied myself that the conditions on which the grants-in-aid was Kind of Checks exercised :-

- Works have been supervised by Executive Engineer/Superintending Engineer.
- Periodical inspection has been conducted by Executive Engineer/Superintending Engineer.
- Construction material have been tested.
- Measurements have been recorded in the MBs and test check conducted by the Assistant .
- All other codal formalities have been observed.

3 Physical Progress achieved:

- Construction of Road Works.
- Construction of CD works


28/5/24
Divisinal Accounts Officer
Rural Works Department
Works Division Biharsharif


28/5/24
Executive Engineer
Rural Works Department
Works Division Biharsharif
28/5/24

राज्य योजना (नाबार्ड) अन्तर्गत पथों में पंचवर्षीय अनुरक्षण अधियाचना प्रपत्र

[illegible]

Total-

2. यह नो MONI/POME से संवर्धित कोई सुधार प्रतिवेदन लखित नहीं है।
3. अनुमोदित परिमाण विपन्न को कुल दसि प्रशासनिक स्वीकृति की दसि से 20% अधिकतन योग के नीतर है साथ ही अनुमोदित परिमाण विपन्न के नदों की गाना का विस्तार का दिक्कती
4. अनुमोदित परिमाण विपन्न का पत्र, अनुमोदित परिमाण विपन्न एवं एकराशाना की अभिप्रायणित प्रति।

प्रमंडलीय लेखा पदाधिकारी
प्रानीन कार्य दिनांक,
कार्य प्रमंडल, विहारराष्ट्रियक

कार्यपालक अभियंता

28/5/24



ग्रामीण कार्य विभाग

Rura Works Department Govt of Bihar

F2 AGREEMENT

HEAD-4515 NABARD

UNDER

RWD WORKS DIVISION BIHARSHARIF

PROJECT NAME:- CONSTRUCTION OF ROAD FROM NH-31
DEEPNAGAR POLICE STATION TO DRCC
BUILDING (SIPAH) (Including 5years Maint.)

C/S Approved By S.E. RWD Work Circle Nalanda Vide Letter 1691 (we) Dated 28.12.16

CONTRACTOR NAME :- ASHOK KUUMAR,

CONTRACTOR ADDRESS:- MOH.-UDANTPURI, GARHPAR, BIHARSHARIF

BLOCK :- BIHARSHARIF.

original work -
Main -

ESTIMATED COST :-

AGREEMENT No

02 F2 2016-2017

ACCEPTED RATE :-

0.03% Below of BOQ Rate.

AGREEMENT Value :-

Rs. 55,31,811.00

EARNEST MONEY :-

TD3446220223 Rs 116000=00

WORK STARTED DATE :-

BG. No. 12551 LG, 000117 Rs 162000=00

INTENDED DATE OF COMPLETION:-

18-01-2017

Nine Month

312113 3111

Executive Engineer
RWD (W) Division

Bihaarsharif

18/1/17

18/1/17

TENDER FOR WORKS

I/We hereby tender for the execution for the Government of Bihar of the work specified in the under write memorandum at the rates specified there in within a period of year month form the date of written order to commence and in accordance in all respects with the specification designs, drawing and other documents referred to rule her of and subject to the annexed conditions of contract with, such conditions so as applicable

- (a) If several sub-works are included they should be detailed in a separate list

- (b) This deposit will be 5% of the estimated cost of the work

- (c) This percentage deduction from bills will be credited to the contractors security deposit

MEMORANDUM

(A) Name of work:- Construction of Road From NH-31 Deepnagar Police Station to DRCC Building (Sipah).

(B) Estimated cost Rs. 55,31,811.00

(C) Earnest money Rs. TD 116000.00

(D) Initial security deposits (including earnest money) to be deposited before the commencement of the work Bih. Rs 162000.00

(E) Percentage to be deducted from bills Rs. 5% (Rupees five percent).....

(F) Time required for the work from date of written order to commence 18.01.17 Month

(G) Date of written other to commence 18.01.17

(H) Total number of item of work tendered for 29

0.03% below in all item.

Item No.	Item of work	RATE TENDERED		Per
		In figures	In words	
1	Clearing and Grubbing Road Land Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm. removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201. (By Manual Means) In area of non-thorny jungle.	39968.78	Rupees Thirty Nine Thousand Nine Hundred Sixty Eight & Paisa Seventy Eight Only.	Per m ²

उत्तर प्रदेश सरकार

Executive Engineer
RWD (W) Division
18/1/17
Harsharif

Schedule XIV - Form No. - 61

2	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. For Grading II Material.	456.96 Cum	1178.39	Rupees One Thousand One Hundred Seventy Eight & Paisa Thirty Nine Only.	Per m ³
3	Water Bound Macadam with crushable screening Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405. (WBM Grading 2) By Manual Means.	186.66 Cum.	2087.38	Rupees Two Thousand Eighty Seven & Paisa Thirty Eight Only	Per m ³
4	Water Bound Macadam with Stone screening Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (WBM Grading 3) (A) By Manual Means	186.66 Cum	2068.17	Rupees Two Thousand Sixty Eight & Paisa Seventeen Only.	Per m ³
5	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 502 & direction of E/L.	2488.80 Sqm.	31.91	Rupees Thirty One & Paisa Ninety One Only.	Per m ²

अनुमोदित

Executive Engineer
RWD (W) Division

Schedule XLV – Form No. – 61

6	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503 2488.80 Sqm.	11.41	Rupees Eleven & Paise Forty One Only.	Per m
7	Providing, laying and rolling of open-graded premix carpet of 20 mm thickness composed of 13.2 mm size @ 0.18 cum per 10 sqm & 11.2 mm size @ 0.09 cum per 10 sqm aggregates using penetration grade/modified bitumen @ 14.6 kg/10sqm to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A as per Technical Specification Clause 508. Bitumen (S-90) Case-I By Manual Means. 2488.80 Sqm.	149.05	Rupees One Hundred Forty Nine & Paise Five Only.	Per m ²
8	Seal Coat Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A as per Technical Specification Clause 510 By Manual Means. 2488.80 Sqm.	40.16	Rupees Forty & Paise Sixteen Only.	Per m ²
9	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000m as per Technical Specification Clause 301.5 10894.78 Cum.	156.17	Rupees One Hundred Fifty Six & Paise Seventeen Only.	Per m ³
10	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 100m as per Technical Specification Clause 301.5 2723.69 Cum.	155.96	Rupees One Hundred Fifty Five & Paise Ninety Six Only.	Per m ³

अधीन काम

Executive Engineer
RWD (W) Division
15/11/12
15/11/12
15/11/12

Schedule XLV - Form No. - 61

11	Providing and fixing of typical informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1				
12	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703	2 Each	9082.88	Rupees Nine Thousand Eighty Two & Paise Eighty Eight Only.	Each
(i)	Ordinary Kilometer Stone (Precast)			Rupees Two Thousand One Hundred Thirty Six & Paise Seventy Eight Only.	Each
(ii)	200 m stone (precast)	1 Each	2136.78		Each
13	Painting lines, Dashes, Arrows etc on Roads in Two Coats on New work (Painting lines, dashes, arrows etc on roads in two coats on new work with ready mixed road marking paint Up to 10 cm in width sqm	2 Each	714.90	Rupees Seven Hundred Fourteen & Paise Ninety Only.	Each
		80 M	806.60	Rupees Eight Hundred Six & Paise Sixty Only	Per M

अतिरिक्त शुल्क

Executive Engineer

14	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material 600.00 Cum.	229.18	Rupees Two Hundred Twenty Nine & Paisa Eighteen Only.	Per m ³
15	Providing and laying boulder apron for bed protection with stone boulders. 108.00 Cum.	1513.03	Rupees One Thousand Five Hundred Thirteen & Paisa Three Only.	Per m ³
16	Providing and laying pitching on slope (Stone/Boulder) 252.00 Cum.	1513.03	Rupees One Thousand Five Hundred Thirteen & Paisa Three Only.	Per m ³
17	Providing and laying filter under earth pitching in slopes complete as per drawing and Technical specification 126.00 Cum.	1525.47	Rupees One Thousand Five Hundred Twenty Five & Paisa Forty Seven Only.	Per m ³
18	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material 41.10 Cum.	229.18	Rupees Two Hundred Twenty Nine & Paisa Eighteen Only.	Per m ³
19	Sand Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 34.48 Cum.	451.09	Rupees Four Hundred Fifty One & Paisa Nine Only.	Per m ³
20	Providing 100A Bricks flat soling in foundation Trenches as per drawing and technical specification Clause 1108 37.14 Sqm.	265.19	Rupees Two Hundred Sixty Five & Paisa Nineteen Only.	Per m ²
21	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-10 5.58 Cum.	4203.54	Rupees Four Thousand Two Hundred Three & Paisa Fifty Four Only.	Per m ³
22	Brick masonry work in cement mortar in foundation complete excluding pointing and plastering as per drawing and technical specifications Clauses 600, 1202 & 1203 C.M.(1:4). 29.64 Cum.	6938.34	Rupees Six Thousand Nine Hundred Thirty Eight & Paisa Thirty Four Only.	Per m ³

3211/5/2018

Executive Engineer
RWD (W) Division
Rashid

Schedule XLV - Form No. - 61

23	Providing & Laying ISI mark* Cement Concrete hume Pipe (buried conduits) on first class bedding of granular material including fixing collar with cement sand mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry work in head wall and parapets (* See general notes).	15.00 RM	4151.90	Rupees Four Thousand One Hundred Fifty One & Paisa Ninety Only.	Per RM
24	Plastering with cement mortar (1:4), 15 mm thick on brickwork in substructure as per technical specification Clauses 613.4 & 1204.	42.38 Sqm.	187.29	Rupees One Hundred Eighty Seven & Paisa Twenty Nine Only.	Per m ²
25	1st Year Maintenance Cost	0.400 Km.	54605.00	Rupees Fifty Four Thousand Six Hundred Five Only.	Km
26	2nd Year Maintenance Cost	0.400 Km.	69455.00	Rupees Sixty Nine Thousand Four Hundred Fifty Five Only.	Km
27	3rd Year Maintenance Cost	0.400 Km.	101157.50	Rupees One Lakh One Thousand One Hundred Fifty Seven & Paisa Fifty Only.	Km
28	4th Year Maintenance Cost	0.400 Km.	121627.50	Rupees One Lakh Twenty One Thousand Six Hundred Twenty Seven & Paisa Fifty Only.	Km
29	5th Year Maintenance Cost	0.400 Km.	142097.50	Rupees One Lakh Forty Two Thousand Ninety Seven & Paisa Fifty Only.	Km.

37211 रु मर

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक-मु0 अ0-4 (मु0)-नाबार्ड-03-185/2016

प्रेषक,

विनय कुमार
सचिव

सेवा में,

महालेखाकार, बिहार
वीरचन्द पटेल पथ, पटना।

/पटना, दिनांक-

आंतरिक वित्तीय सलाहकार द्वारा
अनुपचारिक रूप से परामर्शित

विषय:- योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत राज्य के नालन्दा जिलान्तर्गत कार्य प्रमंडल, बिहारशरीफ के अधीन बिहारशरीफ प्रखंड के दीपनगर थाना एन0एच0-31 के बगल से नये डी0आर0सी0सी0 भवन तक पथ का निर्माण कार्य जिसकी लम्बाई 0.40 कि0 मी0 के निर्माण हेतु रू0 55.77 लाख रुपये (पचपन लाख सतहत्तर हजार रुपये) मात्र की लागत पर प्रशासनिक स्वीकृति प्रदान करने के संबंध में।

महाशय,

निदेशानुसार योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-उप शीर्ष-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उप शीर्ष के अन्तर्गत राज्य के नालन्दा जिलान्तर्गत कार्य प्रमंडल, बिहारशरीफ के अधीन बिहारशरीफ प्रखंड के दीपनगर थाना एन0एच0-31 के बगल से नये डी0आर0सी0सी0 भवन तक पथ का निर्माण कार्य जिसकी लम्बाई 0.40 कि0 मी0 के निर्माण हेतु रू0 55.77 लाख रुपये (पचपन लाख सतहत्तर हजार रुपये) मात्र की लागत पर प्रशासनिक स्वीकृति प्रदान किया जाता है।

1. इस योजना को दो वित्तीय वर्ष 2016-17 एवं 2017-18 में पूरा किये जाने का लक्ष्य है।
2. योजना के लिए कार्यपालक अभियंता, से विस्तृत कार्य योजना मांगी जायेगी और उसके अनुरूप कार्यों के समयबद्ध ढंग से पूर्ण कराया जायेगा।
3. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ द्वारा इस योजना के कार्य सम्पादन हेतु निकासी एवं व्ययन पदाधिकारी होंगे। कार्य निविदा के माध्यम से कराया जाएगा।
4. योजना के क्रियान्वयन से पूर्व इस पर सक्षम पदाधिकारी से प्रावैधिक स्वीकृति प्राप्त कर ली जायेगी।
5. इस योजना का व्यय योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष जिसका विपत्र कोड P-4515001030105 एवं स्कीम कोड-5369 के अन्तर्गत वित्तीय वर्ष 2016-17 में उपबंधित राशि से विकलनीय होगा।
6. योजना शीर्ष 4515-अन्य ग्राम विकास कार्यक्रमों पर पूंजीगत परिव्यय-103-ग्राम विकास-राज्य योजना-0105-ग्राम विकास की परियोजनाएं (नाबार्ड ऋण संपोषित योजना)-उपशीर्ष के अन्तर्गत वित्तीय वर्ष 2016-17 में 454.31 लाख रुपये का बजट उपबंध स्वीकृत है।
7. कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ द्वारा योजना की भौतिक एवं वित्तीय प्रगति प्रतिवेदन प्रत्येक माह के 10 तारीख तक निश्चित रूप से कमशः अधीक्षण अभियंता, नालन्दा एवं मुख्य अभियंता-1, पटना के माध्यम से विभाग को उपलब्ध कराया जाये।
8. इस योजना का चयन मा0 मंत्री, ग्रामीण कार्य विभाग, द्वारा संचिका संख्या- मु0 अ0-4 (मु0)-नाबार्ड-03-185/2016 के पृ0 सं0-03/टि0 पर दिनांक - 31.10.16 को किया गया है।

अनुरोधित

Executive Engineer

RWD (W) Division

पटना

18/11/16

- measured as per Accountancy
payments for
9. इस योजना के प्रशासनिक स्वीकृति के प्रस्ताव पर सचिव, ग्रामीण कार्य विभाग द्वारा सचिका सं-
मु0 अ0-4 (मु0) नाबार्ड-03-185/2016 के पृ0 सं0-06/टि0 पर दिनांक 11.11.16 को अनुमोदन
प्राप्त है।
10. यह आदेश वित्त विभाग के संकल्प संख्या-4-45/94-301 वि (2) दिनांक 31.01.1995 एवं वित्त
विभाग के पत्रांक स्कीम (8)-11-2005-5090 वि (2) दिनांक 15.09.05 के आलोक में आंतरिक
वित्तिय सलाहकार की सहमति प्राप्त कर निग्त किया जा रहा है। आंतरिक वित्तिय सलाहकार की
सहमति सचिका सं- मु0 अ0-4 (मु0) नाबार्ड-03-185/2016 के पृष्ठ संख्या-09/टि0 पर
दिनांक-29.11.16 को प्राप्त है।
11. वित्त विभाग के पत्रांक-770, दिनांक 20.09.11 के द्वारा सूचित किया गया है कि नाबार्ड से RIDF
के अन्तर्गत नई परियोजनाओं की प्रशासनिक अनुमोदन प्राप्त करने के उपरान्त ही स्वीकृति हेतु
नाबार्ड को भेजी जाये।

विश्वासभाजन

ह0/-

(विनय कुमार)

सचिव

/पटना, दिनांक-

ज्ञापांक- मु0 अ0-4 (मु0)-नाबार्ड-03-185/2016

प्रतिलिपि- कोषागार पदाधिकारी, बिहारशरीफ को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

ह0/-

सचिव

/पटना, दिनांक-01/12/16

ज्ञापांक- मु0 अ0-4 (मु0)-नाबार्ड-03-185/2016 4484

प्रतिलिपि- माननीय मंत्री के आप्त सचिव, ग्रामीण कार्य विभाग/प्रधान सचिव, योजना एवं विकास
विभाग/वित्त विभाग (आय-व्यय शाखा)/आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग/मंत्रिमंडल
सचिवालय एवं समन्वय विभाग/कार्मिक एवं प्रशासनिक सुधार विभाग, प्रमण्डलीय आयुक्त,
पटना/जिला पदाधिकारी, नालन्दा/उप विकास आयुक्त, नालन्दा/अभियंता प्रमुख सह-सचिव,
BRRDA, ग्रा0 का0 वि0, बिहार, पटना/मुख्य अभियंता-1, पटना, ग्रामीण कार्य विभाग/मु0 अ0-4
(मुख्यालय), ग्रा0 का0 वि0/अधीक्षण अभियंता, ग्रा0 का0 वि0, कार्य अंचल, नालन्दा/कार्यपालक
अभियंता, ग्रा0 का0 वि0 कार्य प्रमंडल, बिहारशरीफ/मुख्य महाप्रबंधक नाबार्ड, बिहार क्षेत्रीय कार्यालय,
(मौर्या कम्पलेक्स, पॉचवी मंजिल) डाक बंगला रोड, पटना को सूचनार्थ एवं आवश्यक कार्रवाई हेतु
प्रेषित। आई0टी0 नोडल, ग्रामीण कार्य विभाग को विभाग के वेबसाइट पर अपलोड करने हेतु प्रेषित।

सचिव

अशोक कुमार

Executive Engineer
RWD (W) Division