

# ESTIMATE FOR REPAIRING / RESTORATION / MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

HEAD: (FDR)

## YEAR 2024-25

STATE:- BIHAR
DISTRICT:- SUPAUL
BLOCK:- Basantpur

## Main Road to Harizan Tola Tak

#### DETAILED REPORT

TOTAL LENGTH OF ROAD

3.875 KM

TOTAL COST FOR MOTORABLE OF ROAD

15.967 Lacs

SUBMITTED BY: EXECUTIVE ENGINEER, RWD, WORKS DIVISION,

VIRPUR.

#### INSPECTION REPORT FOR MOTARABLE WORK

NA.	ME OF PIU :-		Virpur	
NAME OF BLOCK :- Basantpur		ROAD :-	Repair of road from Main Tola	road to Harijan
	A. FOR ROAD			
1	Damage Location /Chainage		1.10 KM	
2	2 Damage Lenth:- 45M			
3	Nature of Damage (Length wise )	i. Breach	*	
		ii. Crust I	Damage	45M
	iii. Only Fla		lank Damage	
	Whether Traffic fully/partially obstructed		Fully Obstructed	
4	Details of restoration			
	i. Material Being Used in Restoration		Bamboo, EC Bag, L.Sand, Brick Bats	
	ii. Equipment/Tools Being used in Restoration Works		Bamboo Piler, Excavator Bamboo Cutter EC bag Packer	
	iii. Restored Length In Open	Area:-	45M	
	In Habit			
	iv. If Restoration Work Done In Habitation		rea Give Reason	N/A
	B. For Bridge (Size of Bridge / Culvert )			
	Damage Location /Chainage			
	No. Of Span Damage			
	Length of Span			
	Nature of Damage (pier/Abutment/			
	Wing Wall /approch road damage			
5	Details of restoration			
	i. Material Being Used in Restoration			
	ii. Equipment/Tools Being used in Restoration			
	iii. Restored Length			
	Overall Grade of Restoration Work (Satisfactory ( ) Unsatisfactory ( )			

Signature of Inspector (Official Seal) E. E. R. D., Trivenigan पथ का नाम :- प्रेन रोड से हरिजन टोला प्रे अहिपानी भरम्मते नाय में बाढ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 2024 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त में बाढ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 15.967 लांट्य है। उक्त पथ का निर्माण MMUSY (38) योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में हैं। पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदो का दर वर्तमान अनुसुचित दर के अनुरूप है।

कनीय अभियंता,

कनीय अभियंता, ग्रामीण कार्य विभाग, कार्य प्रशाखा, व्यक्तिपुर सहायक अभियता, ग्रामीण कार्य विभाग, कार्य अवर प्रमण्डल,

कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमण्डल, अ